The Far-Infrared Radiation Mobile Observation System for spectral characterisation of the atmospheric emission

Claudio Belotti[1], Flavio Barbara[2], Marco Barucci[1], Giovanni Bianchini[1], Francesco D'Amato[1], Samuele Del Bianco[2], Gianluca Di Natale[1], Marco Gai[2], Alessio Montori[1], Filippo Pratesi[1], Markus Rettinger[3], Christian Rolf[4], Ralf Sussmann[3], Thomas Trickl[3], Silvia Viciani[1], Hannes Vogelmann[3], and Luca Palchetti[1]

[1]National Institute of Optics, National Research Council, Florence, Italy
[2]Institute of Applied Physics "Nello Carrara", National Research Council, Florence, Italy
[3]Karlsruhe Institute of Technology (KIT), IMK-IFU, Garmisch-Partenkirchen, Germany
[4]Forschungszentrum Jülich, IEK-7, Jülich, Germany
Correspondence: Claudio Belotti (claudio.belotti@cnr.it)

Abstract. The Far-Infrared Radiation Mobile Observation System (FIRMOS) is a Fourier transform spectroradiometer developed to support the Far-infrared Outgoing Radiation Understanding and Monitoring (FORUM) satellite mission by validating measurement methods and instrument design concepts, both in the laboratory and in field campaigns. FIRMOS is capable of measuring the downwelling spectral radiance emitted by the atmosphere in the spectral band from 100 to 1000 cm^{-1} (10–100 μm in wavelength), with a maximum spectral resolution of 0.25 cm^{-1}. We describe the instrument design and its characterisation and discuss the geophysical products obtained by inverting the atmospheric spectral radiance measured during a campaign from the high-altitude location of Mount Zugspitze in Germany, beside the Extended-range Atmospheric Emitted Radiance Interferometer (E-AERI), which is permanently installed at the site. Following the selection of clear-sky scenes, using a specific algorithm, the water vapour and temperature profiles were retrieved from the FIRMOS spectra by applying the Kyoto protocol and Informed Management of the Adaptation (KLIMA) code. The profiles were found in very good agreement with those provided by radiosondes and by the Raman lidar operating from the Zugspitze Schneefernerhaus station. In addition, the retrieval products were validated by comparing the retrieved Integrated Water Vapour values with those obtained from the E-AERI spectra.

1 Introduction

The far-infrared (FIR) portion of the Earth's emission spectrum is the subject of a growing research interest because of its important role played in the Earth's radiative balance. This spectral region covers the wavelengths longer than 15 μm (the wavenumbers below 667 cm^{-1}) and is strongly characterised by the pure rotational absorption band of water vapour and the ν_2 carbon dioxide band. Several atmospheric and surface processes contribute to both the outgoing and the incoming radiation at these wavelengths in a complex and entangled manner (for a detailed discussion, see **??**). In this context, spectrally resolved

radiometric observations are a valuable tool that can potentially quantify the role of each of these contributions to the overall radiative balance.

To date, the FIR component of the outgoing longwave radiation has only been measured a few times during balloon campaigns by REFIR-PAD (**?**) and FIRST (**?**), and by the airborne instrument TAFTS (**?**). On the other hand, several ground-based experiments observed the FIR portion of the downwelling longwave radiation (DLR): the Earth Cooling by Water Vapor Radiation (ECOWAR) experiment (**?**), and the Radiative Heating in Underexplored Bands Campaigns (**??**, RHUBC-I and RHUBC-II). Eventually, REFIR-PAD was installed in Antarctica at the Concordia station, where it has been in continuous operation since 2011 (**?**).

FIR spectral measurements of DLR proved valuable for refining the knowledge of water vapour spectroscopy (**?**) and testing the ability to model radiative transfer in the atmosphere (**????**). In addition, ground-based FIR observations were successfully exploited to infer cloud properties (**???**), to retrieve the thermal structure and composition of the atmosphere (**??**), as well as to conduct radiative closure studies (**??**).

The Far-infrared Outgoing Radiation Understanding and Monitoring (**?**, FORUM) project has been selected as the 9th European Space Agency's Earth Explorer Mission, to be launched in 2027. The FORUM core instrument will be a Fourier Transform Spectrometer (FTS) and it will measure the Earth's upwelling spectral radiance from 100 to 1600 cm^{-1} (100–6.25 µm). FORUM will allow for the first time to observe globally the Earth's spectrally resolved emission in the FIR.

During the preparatory phase of FORUM, the Far-Infrared Radiation Mobile Observation System (FIRMOS) was employed to support the mission by validating measurement methods and instrument design concepts, both in the laboratory and in field campaigns. Throughout this activity, the data gathered have been critically employed for the validation of geophysical parameters, retrieval codes, and more generally to expand FIR spectroscopic knowledge.

FIRMOS was built at the Italian National Institute of Optics of the National Research Council (INO-CNR), and it was designed as a laboratory and field campaign flexible instrument. Subsequently it was deployed in the German Alps at the summit station of the Zugspitze Observatory (2962 m a.m.s.l.) for a two-month campaign (**?**) in the winter 2018–19. Some of the measurements collected during that time are presented here to demonstrate the capabilities of the platform. During the campaign at Zugspitze, FIRMOS was jointly operated with an assortment of co-located instruments that characterised the observed atmospheric state. The spectra acquired during the campaign were processed to derive higher level products, namely temperature and water vapour profiles and cloud properties, if applicable.

In this paper we describe the instrument design and its characterisation and discuss the temperature and water vapour products obtained inverting the atmospheric spectral radiance measured during the campaign in clear sky conditions. The retrieval of optical and microphysical cloud properties is the subject of a separate publication (**?**). Section 2 introduces and describes in detail the FIRMOS instrument, its optomechanic design, radiometric calibration, electronics and detection specifics; section 3 presents the Level 1 (L1) and Level 2 (L2) data while in section 4 the results are discussed. Finally, in section 5 the conclusions are drawn.

2 Materials and Methods

FIRMOS was designed and built first as a laboratory prototype and was successively adapted to obtain a versatile instrument that could be quickly deployed in ground-based field campaigns (<80 Kg, 1 day readiness), specifically at high altitude sites, and easily adaptable to stratospheric balloon flights.

The instrument was built during the compressed schedule preceding the Earth Explorer 9 mission selection and deployed for its first campaign at the Zugspitze Observatory in the Bavarian Alps (South Germany, 47.421°N, 10.986°E, 2962 m a.m.s.l, **?**) between the end of 2018 and the beginning of 2019. FIRMOS mostly acquired Atmospheric DLR spectra, in zenith-viewing configuration; at the end of the campaign some days were allocated to surface-looking measurements of a variety of snow samples.

Table 1. Characteristics of the measurements performed at Zugspitze during the FIRMOS campaign (**?**)

Type of measurement	Resolution	Integration	Repetition time	Date	No of spectra measured
DLR spectrum	0.4 cm^{-1}	128 s	256 s	29 November – 18 December 2018	1197
	0.3 cm^{-1}	210 s	420 s	21 January – 15 February 2019	838
Snow and DLR	0.3 cm^{-1}	210 s	420 s	16 – 20 February 19	152 snow + 283 DLR

A set of instruments was operated in conjunction with FIRMOS: E-AERI, an IR commercial FTS at the Zugspitze summit; a lidar instrument at the Schneefernerhaus station (UFS) at 2675 m a.m.s.l., 700 m to the south-west of the summit station; five dedicated radiosonde launches were carried out from Garmisch-Partenkirchen, 8.6 km to the north-east of the summit. More details are given within the sections below.

2.1 The FIRMOS instrument

FIRMOS is a ground-based FTS operating in the far- and mid-infrared range. Its design stems from its predecessor, the Radiation Explorer in the Far InfraRed – Prototype for Applications and Development (**?**, REFIR-PAD). The new design, as described in the following sections, is the result of a rationalisation aimed at a leaner instrumental setup and at reducing deployment times by employing commercial parts for motion control and reflective optics.

2.1.1 Optomechanics

The optical layout of the FIRMOS interferometer is composed by double-input and double-output Mach-Zehnder configuration. The setup allows full tilt compensation by employing a movable unit with roof-top mirrors (RTMU). Additional flat mirrors are used on the right arm of the interferometer to compensate for slit yaw. Parabolic mirrors (45° off-axis) enable light focusing on the detectors, encapsulated with CsI windows. The reference source is a 785.9 nm single-mode thermally stabilised laser (Thorlabs). The latter is driven with a constant current from a controller developed in-house, and already employed within the previous REFIR-PAD instrument. The reference laser follows the same optical path as the infrared beam, with dedicated optics joined to the same mountings as for the main measurement.

Radiometric accuracy is achieved by employing three blackbody source, the hot (HBB) and the cold (CBB) calibration
blackbodies and the reference blackbody (RBB). A rotating mirror (PM0) located at the interferometer first input can select
either the HBB, the CBB or the sample scene (Figure 1), the contribution of this mirror to the instrument response is therefore
accounted for in the calibration procedure (see Section 2.1.3). The RBB, located at the second input, is in thermal equilibrium
with the other optical components. At every measurement cycle, the calibration procedure is performed before and after the
sample scene.

(a)   (b)

Figure 1. FIRMOS: (a) optical layout diagram, the blackbodies (HBB and CBB) are depicted in green, PM0 indicates the scene selection mirror. The roof-top mirrors unit (RTMU) is on the top right, IP is the internal pupil, in the centre BS1 and BS2 indicate the beam splitters. The whole optical path is folded on two levels using mirrors (PMA1, PMA2, PMA3, PM1, PM2). Also shown are the pyroectric detectors (D1 and D2) the reference laser (LS) and its detector (D3), the reference (RBB) (b) picture of the inner structure of the instrument

The FIRMOS setup was designed to maximise the optical throughput by employing 76.2 mm diameter optics while maintaining a field of view of 22 mrad. In addition, the optical system is image-forming at the detector, although the latter is a single pixel (diameter 2 mm). The above features are meant to enhance the observed scene selectivity while maintaining good signal-to-noise ratio, and therefore to facilitate the development of software tools for geophysical parameters retrieval.

The field of view in FIRMOS is defined by the optical path length of the instrument, the internal pupil radius, and the detector area, the latter being the main limiting factor in the current design. The optical specifications of the instrument are listed in Table 2.

To cover the IR spectral range from $100\,\mathrm{cm^{-1}}$ to $1000\,\mathrm{cm^{-1}}$, the instrument adopts wideband Germanium-coated Biaxially-oriented PolyEthylene Terephthalate (BoPET) beam splitters (BS) and room temperature deuterated L-alanine doped Triglycene Sulphate (DLATGS) pyroelectric detectors. The absorption of the BoPET BS substrate causes some degradation in efficiency in some narrow bands around 730, 850, 873 and 973 $\mathrm{cm^{-1}}$, as it can be seen in Figure 2 which shows the typical 4RT efficiency. The instrument spectral range is limited at low wavenumbers by the absorbance of the detector CsI windows and, at high wavenumbers by degradation of the optical performance due to BSs flatness errors (see Fig. 2(b) and Fig. 8).

4

Table 2. Optical collection specifications.

Spectral Coverage	100–1000 cm^{-1}
Maximum Spectral Resolution	0.25 cm^{-1}
Optical throughput	0.0063 cm^2 sr
Beam Aperture (Field of view)	22.4 mrad
Internal pupil at RTMU	45 mm diameter
Internal optical path length	1425 mm

Figure 2. (a) Interferometric efficiency of the beam splitter. (b) Interferometric image of a beam splitter sample.

The BS samples were manufactured at INO-CNR and tested with a Newton interferometer, to select those with maximum flatness. The interferometer is capable of detecting flatness anomalies with 0.1 μm precision by employing a reference surface with a flatness of $\lambda/20$, a monochromatic source and a digital camera. The pattern observed in the case of membranes with a divergence from flatness of a few micrometres is of the saddle or multi-saddle type, especially close to the edge. The saddle peak-valley distance is evaluated through the measurements of the number of fringes on the main saddle along a track (Fig.2(b)). The best two BS samples, with flatness error of less than 2.5 μm peak-valley, were integrated on FIRMOS to guarantee good performance over the 100–1000 cm^{-1}range.

A lightweight and compact linear stage model (Zaber model X-LSM025A, mass <0.5 Kg, height 20 mm, centred load capacity 100N) was used, installed within a notch of the breadboard below the RTMU to perform the interferometric scan. A scanning speed of 0.25 mm/s in a 30–60 s acquisition time for a single scan is used. The typical standard deviation of speed

over a scan was obtained experimentally as 0.043 mm/s at a 0.25 mm/s scan speed, sufficiently stable to be accounted for during the signal analysis.

110   The RTMU was manufactured from a monolithic aluminium piece (see Figure 1(b)). The mirrors are placed in a roof-top configuration and fixed by a system of springs and screws.

    The instrument was designed for easy transportation and deployment. Its size is 85x95x50 cm, it weighs 80 kg, and the power consumption is 60 W. A plastic enclosure was used to protect against environmental conditions, an 8 cm diameter aperture with a motorised shutter was used for observation.

115   The instrument breadboard was realised as a monolithic aluminium slab with a mass of 17.5 Kg, and dimension of 520 x 540 x 45 mm (L x W x H). Rods spacing and tightening points were initially designed balancing dimensions, mass and stiffness of the framework. The final layout was identified through an iterative design process carried out with CAD software that evaluated static loads.

2.1.2   Radiometric Calibration Unit

120 In order to perform a calibrated radiometric measurement, at least two known radiation sources are required. In FIRMOS the HBB and a CBB are located at the instrument entrance. The scene mirror allows the acquisition of the external view of the instrument (Zenith or Nadir) or one of the two BBs. The axial rotation is obtained through a stepper motor (NEMA 17 stepper), that also supports the mirror, surrounded by a plastic guard in order to prevent stray light from other instrument components. The support was assembled out of 3D-printed high strength co-polyester plastic parts.

125   Monte Carlo numerical calculations were performed to optimise the cavity geometry of the BBs, in order to maximise normal emissivity, a 34 ° angle was chosen for both the HBB and CBB inner cones (see Fig. 3) achieving an emissivity > 0.9985.

    The CBB was assembled in a 3D-printed co-polyester plastic shell and the HBB was assembled in a 3D-printed heat resistant carbon fiber reinforced Nylon plastic shell, they were both designed to minimise thermal dispersion. The BBs cavities were fabricated in aluminium, internally coated using NEXTEL-Velvet-Coating 811-21. Some layers of thermal superinsulation

130 foils were placed inside the plastic shells, in order to minimise the thermal exchange between the aluminium structure and its plastic supports.

    The BBs controllers are two modular drivers for temperature reading and stabilisation, developed in-house. The temperature of the RBB is monitored by a supplementary module of the HBB driver. Each BB controller simultaneously records the temperature of four sensors: one high-accuracy (30 mK) resistance temperature detectors (PT100 sensor) for the measurement of the

135 BB temperature, one high-resolution (500 μK) Negative Temperature Coefficient (NTC) sensor for active thermal stabilisation, and two one-wire digital thermometers (Dallas DS18B20). The position of the sensors inside the BBs is shown in Figure 3.

    Due to the sensor high accuracy, the PT100 is employed to measure the BB temperature value used in the L1 data analysis. The PT100 temperature reading by the FIRMOS controller and by a commercial Temperature Monitor (Lakeshore, Model 218, with a temperature equivalent accuracy of 68 mK) were compared to estimate the contribution of the readout electronics to the

140 accuracy of the BB temperature. The comparison showed a maximum positive offset of 200 mK between the two, this value was conservatively assumed as the BB temperature total accuracy.

Figure 3. Scheme of each BB geometry and position of the 4 temperature sensors.

The NTC temperature is used for the thermal stabilisation of the BB. Each stabilisation controller is equipped with a Proportional Integral Derivative (PID) circuitry to maintain the temperature read from the NTC, equal to a selected value. The HBB controller operates in heating-only mode by driving a heater resistor mounted inside the HBB. The CBB controller operates in

145 cooling/heating mode by driving a Peltier element placed inside the CBB.

Two Dallas sensors, located at the opposite extremities of the BB, are used to monitor the BB thermal homogeneity.

For the field campaign, the CBB and the HBB were typically stabilised at a temperature of 15°C and 60°C, respectively. In order to find the precision of the BB thermal stabilisation, the difference between the PT100 reading and the set point (the so-called temperature stabilisation error) was recorded for some hours. Figure 4 shows the PT100 measurements after

150 stabilisation was activated, for the HBB (Fig. 4a), and the CBB (Fig. 4c); Figure 4b and 4d show the temperature stabilisation error after the set point is reached, respectively for the HBB and the CBB. The HBB reached the temperature of 60°C in approximately 2 hours and the CBB reached 15° C in approximately 30 minutes. To infer the precision of the temperature stabilisation, assumed as the standard deviation of the stabilisation error after the set temperature is reached, we calculated the standard deviation of the signals reported in Figure 4b and 4d. The HBB controller provides a stabilisation precision of 8.3

155 mK and the CBB controller provides a stabilisation precision of 1.1 mK.

The BBs temperature homogeneity was estimated from the time evolution of the difference between the readings of the two Dallas thermometers placed at the extremities of the BBs. Figure 5 shows the Dallas1 and Dallas2 measurements after stabilisation was activated for the HBB (Fig. 5a) and the CBB (Fig. 5c), and the temperature difference between the two Dallas sensors after thermal stabilisation was reached, (Fig. 5b for the HBB and 5d for the CBB). After the set temperature was

160 reached, the HBB Dallas thermal difference did not show a significant variation and the thermal gradient remained constant with a mean value of 250 mK. The Dallas thermal difference for CBB showed only a slight decrease of about 30 mK/hour

Figure 4. (a) Time evolution of the PT100 temperature for the HBB since the stabilisation controller is activated. (b) Difference between the HBB PT100 temperature and the target temperature ($70°$C) after the thermal stabilisation is reached. (c) Time evolution of the PT100 temperature for the CBB. (d) Difference between the CBB PT100 temperature and the target temperature ($15°$C), after the thermal stabilisation is reached.

Figure 5. (a) Time evolution of the Dallas1 (orange line) and Dallas2 (blue line) HBB sensors after the stabilisation controller is activated (target temperature: 70°C). (b) Temperature difference between the HBB Dallas sensors, after the thermal stabilisation is reached. (c) Time evolution of the Dallas1 (orange line) and Dallas2 (blue line) CBB sensors after the CBB stabilisation controller is activate (target temperature: 15°C). (d) Temperature difference between the CBB Dallas sensors, after the thermal stabilisation is reached.

and the mean value of the thermal gradient during 4 hours resulted in 300 mK. The mean value of the temperature difference between Dallas2 and Dallas1, after temperature stabilisation was reached, was assumed to be the thermal gradient of the BB. The BB thermal homogeneity was thus conservatively considered of about 300 mK for both.

165   The BB controllers performance is summarised in Table 3.

Table 3. BB temperature control performance

	HBB	CBB
Working Temperature	60 °C	15 °C
Stabilisation Precision	8.3 mK	1.1 mK
PT100 Temperature Accuracy	30 mK	30 mK
Temperature Accuracy (sensor+readout electronics)	200 mK	200 mK
Thermal gradient	300 mK	300 mK

2.1.3   Detectors and Electronics

One of FIRMOS enabling technologies is the adoption of two room-temperature pyroelectric DLATGS detectors covering the mid-infrared as well as the far-infrared region. The detectors are uncooled (model: Selex P5180) and have a noise equivalent power $NEP \equiv \sqrt{A}/D^*$ of 1.4 and 1.6 $10^{-10}W/\sqrt{Hz}$, where A and D^* are, respectively, the detector area (3.14 mm^2) and

170   the detectivity. The pyroelectric preamplifiers were prepared at INO-CNR and the electric scheme follows a classic design, previously tested for the REFIR-PAD instrument (**?**). The original scheme was optimised miniaturising as much as possible the amplifier to reduce the wiring length, in order to increase immunity to electromagnetic interference noise.

The slow response of pyroelectric detectors requires to compensate for the acquired signals with digital processing in order to remove amplitude and phase distortions. For this purpose, the frequency response of the detector and of the pre-amplifier sub-

175   system were characterised, measuring their frequency response to a laser-beam step excitation for both output channels (Fig. 6). An empirical model was successively derived from the measurements with a fitting procedure and then used to digitally compensate for the detector response during the L1a analysis (described in Section 3.1).

The FIRMOS detectors observe signal variations in the range of 5–100 Hz depending on the scanning conditions.

3   Data analysis

180   ### 3.1   Level 1 data analysis (spectral calibration)

The L1 data analysis processes the interferograms acquired by the instrument to obtain calibrated spectra. The procedure follows the one described in more detail in **?** for a double-input/double-output ports interferometer and is divided into 3 steps:

- – L1a performs the signal conditioning (filtering, detector response compensation, path-difference resampling, phase correction, etc.) and the Fourier transform;

Figure 6. Frequency response of the detection system to a laser step excitation.

185   – L1b carries out the radiometric calibration providing the calibration functions and the calibrated spectra for each output channel;

     – L1c calculates the average spectrum for every measurement cycle, composed of sky observations and calibration measurements. L1c provides one average spectrum for each of the two output channels, as well as the average of the two channels together with an estimate of the noise and the calibration error. All the averages are weighted by the respective

190   noise estimate.

Each of the interferometer output signals is proportional to the difference of the two input signals with a wavenumber-dependent complex response function F, that is, in general, different for the two inputs, as well as for the two output channels. As described above, the first input is used to measure the scene, whereas the second input, which corresponds to the instrument self-emission, looks continuously to the RBB source. Under these conditions, the relationship between the uncalibrated complex

195 spectrum $S(\sigma)$, and the calibrated spectrum of the observed scene $L(\sigma)$, for each output channel, is given by the following.

$$S(\sigma) = F_1(\sigma)L(\sigma) - F_2(\sigma)B_r(\sigma) \tag{1}$$

where F_1 and F_2 are the calibration functions and $B_r(\sigma)$ is the radiance from RBB, calculated from its measured temperature using the Planck law.

Calibration is carried out by changing the observed scene with the rotating mirror at the first input. The calibration functions F_1 and F_2 are obtained from a two-point radiometric calibration procedure, measuring sequentially the radiance of the HBB and CBB during each measurement cycle. The calibrated radiance spectrum $L(\sigma)$ is then calculated from the uncalibrated spectrum $S(\sigma)$ and the theoretical expression of $B_r(\sigma)$:

$$L(\sigma) = \Re \left\{ \frac{S(\sigma)}{F_1(\sigma)} + \frac{F_2(\sigma)}{F_1(\sigma)} B_r(\sigma) \right\} \tag{2}$$

As noted in **?**, all the quantities used in the calibration procedure are complex, only in the last expression, Eq. 2, the real part of the result is taken, obtaining the measured spectrum as a real quantity. Furthermore, since the optical layout of the interferometer is equivalent with respect to the two inputs, F_1 and F_2 have almost the same values. Forward and reverse sweeps of the interferometer (optical path difference, $OPD : -OPD_{max} \rightarrow +OPD_{max}$ and $OPD : +OPD_{max} \rightarrow -OPD_{max}$) are treated separately during the calibration, since in general they will have different phase errors, nonetheless, the final spectral radiances can be averaged.

The precision of each measurement is calculated in terms of the noise equivalent spectral radiance (NESR) that has to be associated with the specific observation. This quantity depends on the number of acquisitions of the observed scene and the number of HBB/CBB calibration measurements during each measurement cycle, and it is dominated by the detector noise (random error component) ΔS, which is independent of the observed scene. The NESR is then obtained through error propagation of ΔS on the calibrated spectrum obtaining:

$$NESR = \frac{\Delta S}{F} \sqrt{\frac{1}{N} + \frac{2}{n} \left(\frac{\bar{S}}{\bar{S}_H - \bar{S}_C} \right)^2} \tag{3}$$

where $\bar{S}$ is the average of N scene acquisitions (four in FIRMOS standard acquisition configuration), $\bar{S}_H$, $\bar{S}_C$ are the averages of n HBB and CBB acquisitions (2 in standard configuration), respectively. F_1 and F_2 are considered equal to F for the noise calculation. ΔS is obtained from the standard deviation of a series of uncalibrated measurements of a constant source, such as the CBB. The spectral dependence of all the variables in Eq. 3 is omitted for the sake of brevity.

Figure 7 reports the results for a typical observation of the atmosphere (NESR_atm) and of a reference blackbody source, measured inside the laboratory (NESR_bb). The NESR has sharp spectral features, where the noise increases, due to the absorption of the gases inside the interferometric path, mainly water vapour below $400 \, \mathrm{cm}^{-1}$ and carbon dioxide at $667 \, \mathrm{cm}^{-1}$, and the absorption bands of the BoPET BS, around 730, 850, 873 and $973 \, \mathrm{cm}^{-1}$. Furthermore, the NESR estimate depends on the observed scene because of the error on the calibration source measurements that propagates on the NESR estimate through the calibration functions. If numerous calibration measurements are performed so that n is large enough to neglect the second term in Eq. 3 compared to 1/N, then the NESR estimate does not depend anymore on the observed scene and becomes an instrument specification, see NESR_instr curve in the bottom panel of Fig. 7. The latter approach is typically applied to

specify the instrument performance in terms of the NESR, whereas the second term of Eq. 3 is accounted for in the calibration precision. However, in our case, we perform a calibration for each measurement cycle so that n is comparable with N, therefore, the total NESR estimate of Eq. 3 is a better estimate of the total random error of our single measurement.


Figure 7. NESR of the calibrated spectra calculated from error propagation of Eq.3, in the case of a measurement cycle of $N = 4$ sky measurements and $n = 2$ for each calibration sources. NESR_atm (upper panel) is for the observation of the atmosphere in clear sky condition, NESR_bb (middle panel) is for the observation of a blackbody souces in laboratory, and NESR_instr (lower panel) is the instrumental component equal to $\Delta S/F * \sqrt{(1/N)}$

.

The increase of noise over $600\ \mathrm{cm}^{-1}$ in Figure 7 indicates a performance degradation. Such degradation is mainly caused by the BS flatness error (see Fig. 2), as it can be inferred by Figure 8 that shows the comparison of the measured NESR_instr (the same curves of the bottom panel of Fig. 7) with simulations carried out assuming a simple numerical model of the instrument NESR. The model includes the detector specifications and the optical efficiency of the interferometer, in the simulations the interfering wave fronts were distorted with a spherical shape to approximate the BS flatness error. The results of Fig. 8 demonstrate that measurements are consistent with a BS flatness error of about 2.2 µm in accordance with the results shown Fig. 2.

The calibration error CalErr is spectrally correlated and can be calculated through the error propagation in Eq. 2 assuming as independent the uncertainty on the theoretical Planck emission of each BB (ΔB_H, ΔB_C, and ΔB_R).

13

Figure 8. Comparison of the measured NESR_instr (red and blue curves) with simulated NESR obtained with different values peak-valley of BS flatness errors shown in the legend.

240 $$CalErr = \sqrt{\Delta B_R^2 + \left(\frac{\bar{S}}{\bar{S}_H - \bar{S}_C}\right)^2 (\Delta B_H^2 + \Delta B_C^2)} \qquad (4)$$

The uncertainty ΔB_H, ΔB_C, and ΔB_R are dominated by the uncertainty of the temperature of the BB. The BB temperature error depends on two contributions: the accuracy of PT100 measurements and the BB thermal homogeneity. As the temperature accuracy is lower with respect to the thermal homogeneity, the temperature uncertainty for all BBs can be conservatively assumed to be equal to the thermal gradient of 300 mK. With this temperature error, the uncertainty due to the emissivity

245 deviation from 1 gives a negligible contribution to the calibration error.

As shown in Fig. 9, the calibration error estimate also depends on the observed scenes and is larger for colder scenes when the sky is observed, since the uncalibrated signal S, which depends on the temperature difference between the observed scene and RBB (see Eq. 1), is larger in this case.

Finally, in Fig. 10 is shown an example of the spectrum and error estimates obtained as a weighted mean of the two channels

250 after the L1c analysis. The measurement was acquired in clear sky conditions during the campaign at Mount Zugspitze in measurement cycles, each comprised of four sky and four calibration observations, as described above. The total sky observation

Figure 9. Calibration error calculated from a conservative estimation of 0.3 K uncertainty on the temperature measurement of each reference blackbody. CalErr_atm (upper panel) is for the observation of the atmosphere in clear sky condition, CalErr_bb (lower panel) is for the observation of a blackbody souce in laboratory.

has a duration of 215 s and the total measurement cycle time is eight minutes. The standard deviation (STD in the figure) of the measurement, which is in good agreement with the NESR estimate used in the mean, is also shown in the figure.

3.2 Level 2 data analysis (retrieval)

255 FIRMOS L1 measurements were processed using the Kyoto protocol and Informed Management of the Adaptation (KLIMA) forward and retrieval models (**?????**) to derive geophysical products (L2). Only spectra acquired from the instrument channel one were used since the second channel occasionally showed a degradation that could have a negative impact on the results. The retrieval of water vapour and temperature profiles was carried out on the entire clear sky L1 dataset (as defined in Section 3.3), in the range of 200 cm^{-1} to 1000 cm^{-1}. The targets were retrieved from the surface up to 7 km on seven atmospheric 260 layers for temperature and 6 for water vapour.

The algorithm uses an optimal estimation approach (**?**) and a multi-target retrieval strategy (**?**). Profiles from the National Centers for Environmental Prediction (NCEP) reanalysis (**?**) were used as initial guess and a-priori. The a-priori errors on temperature and water vapour were set to 0.3% and 50% of the averaged a-priori values, respectively. The a-priori covariance

Figure 10. Calibrated spectrum (upper panel) and error estimates (NESR and STD middle, Calibration error lower panel) obtained from the weighted mean of the two output channels in a measurement cycle of four zenith observations in clear sky conditions on 25 January 2019 at 15:55 UTC.

matrix was constructed assuming for both parameters a correlation length equal to 2 km between adjacent levels, while no cross-correlation was imposed between temperature and humidity.

3.3 Clear-sky selection criteria

The KLIMA model can analyse pure clear sky scenes as well as scenes with optically very thin clouds, for this reason a subset of measurements not significantly perturbed by clouds in the FIRMOS band was first selected. The subset is referred to as the *clear-sky cases* subset.

Clear-sky cases were selected by evaluating the transparency and slope (gradient) of the FIRMOS spectra in the Atmospheric Window (AW, 820–980 cm^{-1}). In absence of clouds, the spectrum in the AW is well known and equal to the contribution of the water vapour continuum, which is small in comparison to the measurement noise. Likewise, an ideal noise-free and cloud-free measurement would have a gradient of 0 in the very dry winter conditions at Zugspitze, whereas negative values would correspond to a noise-free cloudy observation with a magnitude depending on the specific cloud.

The transparency of the AW was assessed in the narrow spectral window between 829-839 cm^{-1} by calculating the spectral average of the ratio of the signal with respect to the total noise as follows:

$$\Delta = \frac{1}{\nu_2 - \nu_1} \int_{\nu_1}^{\nu_2} \frac{S(\nu)}{\sqrt{\text{NESR}^2(\nu) + \text{CalErr}^2(\nu)}} d\nu \tag{5}$$

where ν_1 and ν_2 are the extremes of the AW spectral range, S the measured spectral radiance and the quadratic sum of NESR and calibration error constitutes the total noise. The absolute value of Δ for a clear sky observation is expected to be less than one, indicating that the measured signal is only due to noise fluctuations.

The slope was calculated between 786 and 961 cm^{-1} in 6 specific microwindows where gas absorption lines are absent: (786–790, 830–835, 856–863, 893–905, 912–918, 960–961 cm^{-1}). The microwindows were selected from a spectrum simulated by the KLIMA forward model; the gradient was obtained from a linear fit of radiance on the microwindows. The fitted slope lies within the range $[-5 \cdot 10^{-5}, 5 \cdot 10^{-5}]$. The maximum positive values, up to $5 \cdot 10^{-5}$, are not physically consistent, and they can be related to noise fluctuations around zero.

Figure 11. Plot of the Δ ratio, as defined in Eq. 5, versus the normalised slope calculated using the 6 microwindows in the spectral range 786-961 cm^{-1} defined in the text. Blue dashed lines indicate the acceptance values and the green dots and orange crosses denote the spectra analysable and not analysable with KLIMA, respectively.

In Figure 11, slope values, normalised with respect to their maximum, are plotted (abscissa) against Δ. The condition $\Delta < 1$ corresponds to slope values within the range (-1, 1), except for a few negative cases. We assumed that spectra laying between the thresholds, defined by the dashed blue lines, represent the set of measurements which can be analysed by the KLIMA code. This is a reasonable choice since, as long as the signal is lower than the instrumental noise, the normalised slope in the

290   atmospheric window lies in the interval (-1 , 1), with a symmetric distribution around 0. Of a total of 838 spectra, 625 (green dots in Figure 11) fell within the acceptance region (blue dashed lines) and were therefore analysed with KLIMA, 213 spectra (orange crosses) were discarded.

4   Results

4.1   Retrieval of geophysical paramenters

295   The high number of measured spectra (625, clear sky) allowed a statistical analysis of the retrieval results. In particular, it is important to assess the quality of the retrievals by analysing the reduced χ^2 distribution, i.e. the χ^2 divided by the difference between the number of spectral points and the number of retrieved parameters. Figure 12 shows the reduced χ^2 distribution, a clear minimum is found for the value of $\chi^2 = 1.2$ (red line). This threshold was verified being a conservative choice, as it guarantees the exclusion of all problematic L1 FIRMOS measurements, with this criterion, 60 out of 625 measurements of the

300   clear sky selection were excluded.

    The maximum number of occurrences of the distribution lies between 0.6 and 0.7, indicating a probable overestimation of the total error (the quadratic sum of the NESR and calibration error) of the FIRMOS instrument of about 25% on average. The time series of the final reduced χ^2 obtained from the fitting procedure is shown in Figure 13, where the red line indicates the threshold value.


Figure 12. Distribution of the reduced χ^2 using a bin width of 0.05. The red vertical line at 1.2 indicates the threshold corresponding to an evident minimum (close to zero cases) of the distribution.

305   Measurements that satisfy the acceptance criterion χ^2 were used for a statistical analysis of the residuals. The latter are calculated as the difference between the simulated spectrum at the last iteration of the retrieval and the FIRMOS observation. The mean and standard deviation of residuals provide an a-posteriori estimation of the measurements' calibration or forward model error and NESR, respectively.

    Figure 14 compares the standard deviation of the residuals (blue line) to the average NESR (red line). The residuals' stan-

310   dard deviation curve correctly reproduces the shape of the average NESR curve of the FIRMOS measurements. However, as

Figure 13. Time series of the reduced χ^2 obtained from the fitting procedure. Red line indicates the threshold at $\chi^2 = 1.2$ defined in Figure 12.

observed for the reduced χ^2 distribution, the values of the curves indicate a probable overestimation, on average by 25%, of the NESR of the FIRMOS measurements. The same NESR reduced by 25% is also shown in green.

Figure 15 shows the comparison between the average of residuals (blue line) and the averaged calibration error (red line). The grey shading is the average NESR divided by the square root of the number of observations (the standard error of the mean). In this case, both the calibration error and the residual NESR are quantitatively consistent with the average of the residuals.

Figure 14. Comparison between the standard deviation of the residuals (blue line), the averaged NESR (red line), and the averaged NESR reduced by 25% (green line).

The vertical distributions of water vapour and temperature were retrieved from FIRMOS observations for 6 and 7 atmospheric levels, respectively (Figures 18 and 19), from the surface up to 7 km. The time series of the number of the Degrees of freedom (DOFs) (**?**) for water vapour (green points) and temperature (red points) profiles are shown in Figure 16. Within the FIRMOS measurements, we observe strong variability of the information content for water vapour. The temperature also shows some variability in the number of DOFs, although less pronounced than for water vapour. In particular, water vapour shows variations from 2 to 4.5 DOFs and temperature from 1 to 2.5.

19

Figure 15. Comparison between the average of the residuals (blue line) and the averaged calibration error (red line). The grey shading is the residual NESR after the average.


Figure 16. Time series of the number of the DOFs of water vapour (green) and temperature (red) profiles obtained from the FIRMOS observations.

The variation in the number of DOFs for the temperature profile is due to the variation of the FIRMOS NESR, indeed, a perfect correlation between the number of DOFs and the average of the inverse of the FIRMOS NESR was found. In contrast, the variation in the number of DOFs the water vapour profile is associated to the Integrated Water Vapour (IWV) content (**?**).

As an example, we consider two results respectively with high and low number of DOFs for the water vapour profile. In Figure 17 water vapour (left) and temperature (right) retrieved profiles are shown, respectively for the two cases under consideration. The blue curve refers to a high number of DOFs, while the orange curve is for a lower number of the water vapour DOFs. The retrieved IWV content is also indicated in the figure, a higher number of DOFs corresponds to lower IWV and a lower number of DOFs correspond to higher IWV. In contrast, temperature profiles do not show relevant variations.

Figures 18 and 19 show the Averaging Kernel profiles (**?**) for water vapour and temperature, respectively. Retrieved profiles were obtained from two FIRMOS measurements with low (on the left) and high (on the right) IWV content. The vertical resolution profile is also shown (red dashed line). The names of the retrieved species, the total DOFs of the target species, and the number of fitted points are shown in the inset of the figure. High IWV content in the atmosphere reduces the retrieval DOFs, deteriorating the vertical resolution. Instead, the effect of IWV content on temperature retrieval is less significant, both the Averaging Kernel profiles and the vertical resolution show little variation.

20

Figure 17. (a) Retrieved profiles of the water vapour mixing ratio and of the IWV (b) Retrieved profiles of the temperature. Error bars correspond to retrieval errors. The profiles were obtained from two FIRMOS measurements with high (blue curves) and low (orange curves) information content. For water vapour, the DOFs are 4.18 and 2.69 respectively, for temperature 2 and 1.78 as also shown in Figures 18 and 19.

The acquisition of spectra during the campaign experienced some discontinuities, however, during two intervals of the 2019 campaign, between 6:00 pm on 22 January and 6:00 am on 23 January, and successively between 0:00 am on 5 February and 6:00 am on 7 February, FIRMOS observations were sufficiently frequent to create a time-series. In order to gain sufficient 340 density the L2 retrieval results from clear sky scenes were processed together with the cloudy observations analysed in **?** as mixed- and cirrus clouds were identified, mainly, during 5 and 6 February 2019. The single profiles were regridded on a 10 minutes grid, the time-series is presented as a colour-coded map in Fig. 20 to give an overview the water vapour dataset.

4.2 Comparisons

The water vapour and temperature profiles retrieved from FIRMOS spectra were compared with those provided by the ra-345 diosoundings, those retrieved from the Raman lidar (water vapour only).

Figure 18. Averaging Kernel profiles (continuous curves) related to retrieved water vapour profiles as obtained from two FIRMOS measurements with high (a) and low (b) information content. The vertical resolution profile is also reported (red dashed line). (inset) Total DOFs and number of fitted points.

4.2.1 Comparison with radiosonde measurements

Five dedicated balloon launches were carried out by a team from the Forschungszentrum Jülich at the Institut für Meteorologie und Klimaforschung (IMK-IFU, part of the Karlsruher Institut für Technologie, KIT) in Garmisch-Partenkirchen, 8.6 km northeast of the summit. The balloons were launched at 18:03, 19:03, 23:00 CET on 5 February and at 18:33 and 23:33 CET the following day.

Air temperature and water vapour mixing ratio from standard Vaisala RS41-SGP radiosondes were compared to the three individual FIRMOS L2 data nearest in time, in order to evaluate the retrieval products quality. Table 4 lists the measurement time of the FIRMOS data used in the comparison and the corresponding balloon launch.

The RS41 temperature measurement has accuracy 0.3 K and precision 0.15 K, the humidity sensor accuracy is 10%, precision 2%, the quality of the radiosonde water vapour measurements were checked with an accompanied high accurate frostpoint hygrometer (CFH, for details see **?**).

Figure 21 shows the radiosonde flight trajectories while their altitude was between 3 and 10 km. The radiosoundings launched on 6 February were under thin cirrus cloud conditions and much farther from Zugspitze, so they were not included in the

Figure 19. As in Figure 18 for the temperature profiles.

Table 4. Radiosondes launches on 5 February 2019, and corresponding FIRMOS measurements used in the comparison. The central column specifies the time at which the sonde reached the altitude at which FIRMOS was located. All the times are given in CET time.

Launch time	time at 2957 m	FIRMOS measurement time
18:03	18:06	18:13 – 18:21 – 18:29
19:03	19:07	19:09 – 19:32 – 19:40
23:00	23:05	23:14 – 23:30 – 23:46

comparison. The radiosonde profiles have a fine vertical resolution. Therefore, to compare with FIRMOS L2 products, their
360   readings were convolved with the FIRMOS Averaging Kernels (**?**, AK).

Each radio sounding acquired on 5 February was compared to the average of the three profiles of water vapour and temperature retrieved from FIRMOS closest in time (Figures 22 and 23). Each plot refers to a different radiosonde acquisition, the local time is also reported. The retrieved products are the red curves, and radiosonde profiles before and after the convolution with the FIRMOS AK are the orange and green curves, respectively, a-priori profiles are in grey. FIRMOS and a-priori retrieval
365   errors are also reported.

Figure 22 shows how the water vapour profiles retrieved from FIRMOS observations agree with the convolved radiosonde profiles within the retrieval errors. The third radiosound at the surface is an exception that is probably related to the different

Figure 20. Water vapour time series, (left) from 22 January, 6 p.m. to 23 January 6 a.m. and (right) from 5 February, midnight to 7 February, 6 a.m., 2019: profiles retrieved from FIRMOS measurements, the single profiles were regridded on a 10 minutes regular grid.


Figure 21. Radiosonde actual flight routes limited between 3 Km and 10 Km. The launch times of the balloons in local time are also reported.

Figure 22. Comparison between FIRMOS L2 water vapour product (red curves, mixing ratio) and radiosonde profiles (RS, orange curves: raw data, the green curves are convolved with the FIRMOS AK); a-priori profiles are coloured grey. FIRMOS and a-priori retrieval errors are also reported. Each plot refers to a different radiosonde acquisition, the local time of the launch is also reported.


Figure 23. Comparison between the FIRMOS L2 temperature product (red curves, the error bars indicate the retrieval error) and radiosonde profiles (orange curves: raw data, the green curves are convolved with the FIRMOS AK). The profiles are shown as a difference with respect to the a-priori of the retrieval, for an effective interpretation. Each plot refers to a different radiosonde acquisition, the local time of the radiosonde launch is also reported.

boundary conditions experienced by the radiosonde during its trajectory relative to those measured by FIRMOS above the Zugspitze site. Similarly to water vapour, the comparison between the temperature obtained from FIRMOS and the convolved radiosonde profiles shows good agreement within the FIRMOS retrieval errors.

4.2.2 Comparisons with Raman lidar measurements at UFS

On 5 and 6 February 2019, a total of four water vapour measurements was carried out with a high-power Raman lidar at UFS. In this period, the stratospheric aerosol lidar was continuously recording backscatter profiles in order to detect the presence of thin cirrus clouds . The lidar systems are described in detail by **?** (**?**, see also **?** for more technical details). For water vapour the system features a range from 3 to 20 km a.m.s.l. for a measurement time of one hour. The data evaluation procedure was recently refined, yielding a better agreement than described by **?** with the reference measurements of the campaign. A range extension of up to 25 km could be achieved for measurements with minimal background noise.

The water vapour mixing ratios retrieved from the lidar were calibrated by balloon-borne cryogenic sensors (CFH) of the Forschungszentrum Jülich. The agreement of the lidar measurement with the CFH data was outstanding below 5 km and in the upper troposphere and lower stratosphere in the case of the best time overlap. Between 5 and 8 km the water vapour mixing ratio exhibited an increasingly spiky humidity structure that was different for lidar and sonde. This is explained by several spatially confined and highly variable dry layers of stratospheric air, unprecedented in spatial inhomogeneity in our lidar sounding over several decades (e.g., **???**, and references therein) making the instrument comparison particularly difficult (see **??**).

The best agreement can be expected for the vertical measurement on the summit and at UFS since the observation volumes almost match. For the lidar, we assume an uncertainty of the order of 5% on the first two days, given the excellent specifications for the CFH sondes. On the third day the uncertainty can be higher because of the rather distant calibration source.

The lidar acquisitions were compared to water vapour profiles retrieved from FIRMOS coincident measurements. The comparison was performed averaging the profiles from 5 FIRMOS observations for each Raman profile. Given the finer vertical resolution of the Raman profiles they were convolved with the AK to compare them with FIRMOS L2 products.

Figure 24 shows the comparison between the profiles from FIRMOS L2 water vapour and Raman profiles. Each plot refers to one of the FIRMOS–Lidar pairs. The retrieved products are plotted in red, the original Raman profiles in orange, and the green curve is the result of the convolution of the Raman profile with the FIRMOS AK. A-priori profiles are shown in grey. FIRMOS, Raman and a-priori retrieval errors are also reported. From Figure 24 we can conclude that the water vapour profiles retrieved from the FIRMOS observation agreed with the convolved Raman profiles within the retrieval error.

4.2.3 E-AERI radiances comparison

The E-AERI spectrometer at Zugspitze measured in the range 400–1800 cm^{-1} with a resolution of 0.48215 cm^{-1} and was positioned 4 m above FIRMOS. To accurately account for the spectral and geometrical differences, the technique described by **?** was employed to compare the spectra acquired by the two instruments, calculating the residuals between the observed and the calculated spectra of each instrument, the residuals were then convolved by the other's instrument spectral response function (SRF). Equation 6 defines the radiance differences:

Figure 24. Comparison between the FIRMOS L2 water vapour product (red curves) and the raman profiles (with green curves and without orange curves the convolution with the FIRMOS AK). FIRMOS, a-priori and Raman retrieval errors are also reported. Each plot refers to a different Lidar acquisition and the CET time of the acquisition is also reported.

$$R_{DIFF} = (R_{FIRMOS} * SRF_{AERI} - R'_{FIRMOS} * SRF_{AERI}) - (R_{AERI} * SRF_{FIRMOS} - R'_{AERI} * SRF_{FIRMOS}) \quad (6)$$

R_{FIRMOS} and R_{AERI} are the mean radiance spectrum for FIRMOS and AERI, respectively; R'_{FIRMOS} and R'_{AERI} are the mean simulated radiances; the symbol $*$ denotes the spectral convolution. In R_{DIFF} the residuals are reduced to the lowest common spectral resolution; since the radiance calculations were performed using the same atmospheric state, and forward model physics for both instruments, this results in systematic errors that are common to both sets of calculations, and to first order removes the effects of altitude from the comparison (**?**).

Figure 25 shows the radiance differences R_{DIFF}, the spectral quantity calculated as in Eq. 6 over 252 coincident spectra, in the range used for the retrieval of IWV (see Section 4.2.4). The spectrum in the plot starts at 450 as a suitable number of spectral points are needed to avoid wraparound effects when calcultating the convolution. The mean of R_{DIFF} indicates a small positive bias of 0.17 mW m^{-2} sr^{-1} cm and a standard deviation of 1.13 mW m^{-2} sr^{-1} cm, the total NESR shown in red in the figure is the sum in quadrature of the instruments' individual NESR. The analysis of the radiance differences demonstrates the very good agreement of the two instruments.


Figure 25. Differences of FIRMOS and E-AERI obesrved minus calculated residuals, R_{DIFF} (blue) as defined in Eq. 6, and quadrature sum of the NESR of the two instruments (red).

4.2.4 E-AERI products comparison

The KIT algorithm for the retrieval of IWV was applied to both the FIRMOS and E-AERI datasets for comparison. IWV is retrieved by minimising E-AERI (or FIRMOS) versus the Line-By-Line Radiative Transfer Model (LBLRTM, **?**) spectral residuals in the range from 400 cm^{-1} to 600 cm^{-1} (see **?**, for details). The dominant contribution to IWV precision error is the retrieval noise: the higher uncertainty value for FIRMOS precision (0.027 mm) compared to E-AERI (0.020 mm) is related to the higher NESR of FIRMOS compared to E-AERI: $\sim$2 mW m^{-2} sr^{-1} cm and $\sim$0.5 mW m^{-2} sr^{-1} cm, respectively.

Figure 26. IWV values calculated for the two instruments. Red squares: IWV retrieval from AERI spectra and FIRMOS spectra with frequency scale as is. Blue crosses: IWV retrieval from E-AERI and FIRMOS including a joint fit of frequency scale factors (for both instruments independently).

Note that the lower NESR in E-AERI spectra may be explained by E-AERI using a cooled detector (67 K), while FIRMOS uses a room-temperature detector. H_2O continuum and line parameters used in the forward calculation, as well as a-priori assumptions on the shape of the H_2O profile (the NCEP reanalysis as for the FIRMOS L2 data) are factors impacting the accuracy of the IWV retrieval; however, they are common to E-AERI and FIRMOS retrievals and can therefore be disregarded for the IWV intercomparison. Other factors are specific to the instruments and can cause biases between E-AERI and FIRMOS:

– altitude difference of 4 m between the E-AERI and FIRMOS location;

– frequency shifts in either or both E-AERI or FIRMOS spectra;

– calibration errors.

The impact of the altitude difference on IWV (E-AERI 2961 m asl, FIRMOS 2957 m a.m.s.l.) was corrected by calculating IWV at the two altitudes from the NCEP profile used as retrieval a-priori. The resulting difference used for the altitude correction is 0.002 mm for the mean atmospheric state of the campaign, and therefore, the error introduced by this altitude correction should be $\ll 0.002$ mm.

In addition, FTS measurements can show small errors in the frequency scale due to tiny drifts of the calibration laser. As the measured spectrum is fitted to a theoretical spectrum, such frequency errors can propagate to IWV errors in the retrieval process. In fact, direct comparison of coincident FIRMOS and E-AERI spectra ($\Delta t \leq 4$ min) showed evidence of a small

discrepancy in frequency scales. Therefore, we implemented a joint fit of a frequency scale factor = 1 + frequency shift within our IWV retrieval. The resulting mean wavenumber scale factor is 1.0000555 for FIRMOS and 0.9999513 for E-AERI.

The impact from this joint frequency scale retrieval on IWV is shown in Figure 26. The IWV retrievals with the original spectra are displayed as red squares and there is a bias of δIWV(FIRMOS-AERI) = 0.0045 mm. For IWV retrievals with joint frequency scale fit (blue crosses) the bias is practically eliminated to δIWV(FIRMOS-AERI) = 0.0002 mm. This bias of 0.0002 mm is negligible compared to the level of measured atmospheric IWV states (from 0.2 to 2 mmH$_2$O); i.e., there are no indications of significant calibration errors in the spectral domain of the H$_2$O rotational band.

5 Discussion and conclusions

In this paper, we describe the FIRMOS Fourier transform spectroradiometer, and its performance in detecting the downwelling spectral radiance emitted by the atmosphere. FIRMOS is capable of measuring the atmospheric radiance in the spectral band from 100 to 1000 cm^{-1}(10–100 μm wavelength) with a spectral resolution of 0.3 cm^{-1}. Its measurement range, in particular, covers the pure rotational band of water vapour in the FIR region, below 667 cm^{-1}(15 μm), allowing to improve the retrieval performance of water vapour as well as cloud microphysics. The dominant spectral noise on the calibrated spectrum (NESR) is on average equal to 2 mW m^{-2} sr^{-1} cm.

To sound the upper part of the atmosphere, this kind of measurement needs to be performed in extremely dry sites. For this reason, between December 2018 and February 2019, FIRMOS was deployed on the summit of Mount Zugspitze (Germany) at 2957 m a.m.s.l. Out of 838 spectra measured during the campaign a set of 625 were identified as clear-sky and employed to assess the instrument capabilities.

Using the statistical analysis of the difference between the measured spectra and the simulations obtained from the retrieval over the entire clear-sky dataset, we found that the average is comparable with the FIRMOS calibration error indicating the latter is well characterised while the standard deviation suggests a probable overestimation of the NESR.

The radiance measurements were validated with the summit station E-AERI spectroradiometer using the technique described in (?) to accurately account for the instruments different spectral characteristics and slightly different viewing geometry. The radiance differences demonstrate the very good agreement of the two instruments. In addition, the FIRMOS measurements were validated by comparing the retrieved IWV values with those obtained from E-AERI. We found a correlation index equal to 0.9986 and a very low bias between the retrieved IWV estimated about -0.00007 mm. This is another confirmation that the FIRMOS and E-AERI spectral measurements are equivalent in their common spectral range.

The retrieved profiles were also found in very good agreement both with the profiles provided by radiosondes launched from Garmisch-Partenkirchen, and by the Raman lidar measuring from UFS at 2675 m a.m.s.l., 700 m to the south-west of the summit station.

FIRMOS was developed to support the FORUM mission, which will be launched by ESA in 2027. FIRMOS was used to validate the measurement method and preliminary instrument design concepts by providing real measurements acquired during a field campaign, the data were used to support the feasibility studies of the mission (?).

In the future, to provide measurements very similar to those that will be delivered by FORUM, it is planned to adapt FIRMOS to stratospheric balloon platforms, this will require to improve instrument subsystems for near-vacuum operations and to cover the full spectral range from 100 to 1600 cm^{-1} in order to prepare a facility for cal/val activity of the satellite mission.

Author contributions. LP designed the experiment and was chief scientist for the field campaign, RS was responsible for the local de-
475 ployment. MB, GB, FDA, AM, SV and LP designed, built and characterised FIRMOS and carried out the Zugspitze campaign. CB and LP performed the L1 analysis. GDN implemented the clear-sky selection algorithm. SDB, MG, and GDN performed the L2 analysis, FB processed the L2 time-series. CR performed the radio soundings and processed their measurements, and SDB and GDN performed the intercomparison analysis. HV and TT performed and processed the Lidar measurements, and SDB and GDN performed the intercomparison analysis. MG and SDB performed the spectra intercomparison. RS and MR performed and processed the E-AERI measurements and carried
480 out the IWV intercomparison. CB, GDN, FP, and LP prepared the manuscript, CB coordinated the contributions from all co-authors. All authors commented on the manuscript.

Competing interests. One author is member of the editorial board of journal Atmospheric Measurement Techniques. Authors have no other competing interests to declare.