



Extending Ensemble Kalman Filter Algorithms to Assimilate Observations with an Unknown Time Offset

Elia Gorokhovsky^{1,2}, Jeffrey L. Anderson¹

¹National Center for Atmospheric Research, Boulder, CO, USA

5 ²Current affiliation California Institute of Technology, Pasadena, CA, USA

Correspondence to: Elia Gorokhovsky (eliapgorokhovsky@gmail.com), Jeffrey Anderson (jla@ucar.edu)

Abstract. Data assimilation (DA), the statistical combination of computer models with measurements, is applied in a variety of scientific fields involving forecasting of dynamical systems, most prominently in atmospheric and ocean sciences. The existence of misreported or unknown observation times (time error) poses a unique and interesting problem for DA. Mapping observations to incorrect times causes bias in the prior state and affects assimilation. Algorithms that can improve the performance of ensemble Kalman filter DA in the presence of observing time error are described. Algorithms that can estimate the distribution of time error are also developed. These algorithms are then combined to produce extensions to ensemble Kalman filters that can both estimate and correct for observation time errors. A low-order dynamical system is used to evaluate the performance of these methods for a range of magnitudes of observation time error. The most successful algorithms must explicitly account for the nonlinearity in the evolution of the prediction model.

1 Introduction

Ensemble data assimilation (DA) is one of the tools of choice for many earth system prediction applications including numerical weather prediction and ocean prediction. DA is also applied for a variety of other earth system applications like sea ice, space weather, pollution, paleoclimate, and the earth's dynamo. While DA was originally applied to generate initial conditions for weather prediction, it is also used for many related tasks like generating long-term reanalyses (Compo et al., 2011), estimating prediction model error, and evaluating the information content of existing or planned observing systems.

DA can also be used to explore other aspects of observations. An important part of many operational DA prediction systems is estimation and correction of the systematic errors (bias) associated with particular instruments (Dee and Uppala, 2009). Estimating the error variances, comprised of both instrument error and representativeness error (Satterfield et al., 2017), associated with particular observations is also possible (Desroziers et al., 2005) and can be crucial to improving the quality of DA products. DA methods have also been extended to explore problems with the forward operators, the functions used to predict the value of observations given the state variables of the prediction model. These techniques can focus on particular aspects of forward operator deficiencies (Berry and Harlim, 2017) or attempt to do a completely general diagnosis (Hamilton



30 et al., 2019). Here, DA methods for estimating and correcting errors in the time associated with particular observations are explored.

Most observations of the earth system being taken now have precise times associated with them that are a part of the observation metadata. However, this is a relatively recent development for most applications. Even for the radiosonde network
35 which is one of the foundational observing systems for the mature field of numerical weather prediction, precise time metadata has only been universally available for a few decades (Haimberger, 2007). Before the transition to current formats for encoding and transmitting radiosonde observations, many radiosonde data did not include detailed information about ascent time or the time of observations at a particular height. Even the exact launch time was not always available in earlier radiosonde data that are a key part of atmospheric reanalyses for the third quarter of the 20th century (Laroche and Sarrazin, 2013).

40

This lack of time information is also a problem for surface-based observations, especially those taken before the radiosonde era which relied on similarly limited encoding formats. Ascertaining the time of observations becomes increasingly problematic as one goes further into the past. As an example, coordinated time zones were not defined in the Unites States until the 1880s, resulting in local time uncertainty of minutes to hours in extreme cases. In fact, the major push for establishing
45 coordinated time was motivated by the need for consistent atmospheric observing systems (Bartky, 1989). Similar issues were resolved earlier or later in other countries and not resolved globally until the 20th century.

As historic reanalyses extend further back in time (Slivinski et al., 2019), the lack of precise time information associated with observations can become an important issue. There is also a desire to use less quantitative observations taken by amateur
50 observers and recorded in things like logbooks and diaries. An example is the assimilation of total cloud cover observations from personal records in Japan (Toride et al., 2017). While individual observers might have rigorous observing habits, the precise time at which their observations were taken often remains obscure. Curiously, the problem of time error may be less for observations used for historical ocean reanalyses (Giese et al., 2016). This is because a precise knowledge of time was required for navigation purposes. Nevertheless, observations obtained from depth can involve unknown delays and failures to
55 record the exact time associated with observations can remain (Abraham et al., 2013).

Even older observations, for instance those associated with paleoclimate, can have greater time uncertainty. Here, the fundamental relationship between the observations and the physical state of the climate system is poorly known and identifying the appropriate time scales is crucial to improved DA (Amrhein, 2020). Observations related to the evolution of the geosphere
60 can have even more problematic time uncertainty. Initial work on using DA to reconstruct the evolution of the earth's geodynamo highlight the problems associated with specifying the time that should be associated with various observations (Gwirtz et al., 2021).



Failing to account for errors in the time associated with an observation can lead to significantly increased errors in DA results. This is especially true if time errors are correlated for a set of observations since they can result in consistently biased forward operators. Section 2 briefly describes the problem of observation time error while Sect. 3 discusses extensions to ensemble DA algorithms that can explicitly use information about some aspects of time error. Section 4 describes several algorithmic extensions of ensemble DA that can provide estimates of time error distributions. Section 5 describes an idealized test problem while Sect. 6 presents algorithms combining the results of Sects. 3 and 4 to produce a hierarchy of ensemble DA algorithms that both estimate and correct for observation time error. Section 7 presents results of applying these algorithms and Sect. 8 includes discussion of these results and a summary.

2 Statement of the problem

The vector $\chi(t)$ is the time-dependent state of the dynamical system of interest and is defined at a set of discrete times $\{t_i\}$, $i = 0 \dots$ where $t_{i+1} = t_i + \Delta t$. The state χ is assumed to be observed at evenly spaced analysis times with a period of $P\Delta t$, $t_{k+1}^a = t_k^a + P\Delta t$, so that $t_k^a = t_k P$, where P is an integer. However, at each analysis time, the actual observation is taken at an observation time, $t_k^o = t_k^a + \varepsilon_k^t$ where the time offset $\varepsilon_k^t \sim N(0, \sigma_t^2)$ is unknown. The observations have an error $\varepsilon_k^x \sim N(\mathbf{0}, \mathbf{R})$ with the observation error covariance \mathbf{R} diagonal. The observation at the k th analysis time is $\mathbf{y}_k^o \sim N(\chi(t_k^o), \mathbf{R})$ where linear interpolation is used to compute χ between the discrete times $\{t_i\}$.

3 Extending ensemble Kalman filters

Algorithms are described to extend ensemble Kalman filters (Burgers et al., 1998; Tippett et al., 2003) to use information about the time offset of observations. Suppose the time offset at the current analysis time is known to be $\tau \sim N(\mu_\tau, \sigma_\tau^2)$. An ensemble Kalman filter assimilation for this analysis time can make use of this information by adjusting the prior ensemble estimate and the observation error variance. First, the ensemble prior estimate of the observations, \mathbf{y}_n^p , $n = 1 \dots N$, where subscript n indexes the ensemble member and N is the ensemble size, can be selected to simulate observations taken at (or near) time $t_k^a + \mu_\tau$; this time is the maximum likelihood estimate of the observation time. Second, the specified observation error variance \mathbf{R} can be augmented to include contributions from uncertainty due to the variance σ_τ^2 of the estimate of the time offset.

Two methods of obtaining the prior mean and observation error variance are explored in the following subsections.

3.1 Extrapolation

Define \mathbf{v} as the time derivative of the prior ensemble mean at the analysis time,

$$\mathbf{v} = \frac{d\bar{\mathbf{x}}^p}{dt}(t_k^a), \quad (1)$$



where the overbar represents an ensemble mean. The prior state for each ensemble member can then be linearly extrapolated to the most likely observation time,

$$\mathbf{y}_n^p = \mathbf{x}_n^p(t_k^a) + \mu_\tau \mathbf{v}, \quad (2)$$

95 This could also be done with additional cost by using the time derivative of each ensemble member, but that method is not explored here. The uncertainty in the time offset also leads to increased uncertainty in the observations. A linear approximation gives an enhanced observation error covariance of

$$\mathbf{E} = \mathbf{R} + \text{diag}(\sigma_\tau^2 \mathbf{v}^2). \quad (3)$$

3.2 Interpolation

100 Assume that an ensemble of prior estimates of the true state, $\mathbf{x}_n^p(t_i)$ is available at the same discrete times t_i as the truth. A prior estimate of the observations for each ensemble can be obtained by linearly interpolating the values of the state to time $t_k^a + \mu_\tau$. It is convenient to require that this time is not earlier than the previous analysis time or later than the next analysis time, $t_{k-1}^a \leq t_k^a + \mu_\tau \leq t_{k+1}^a$. In order to interpolate to times between those limits, it is necessary to run the prior ensemble forecasts for up to twice as long as for a normal ensemble Kalman filter, out to t_{k+1}^a . This is no more than a doubling of the
105 computation cost of prior forecasts for each analysis. The prior ensemble members must also be stored at all times between the previous and next analysis times to facilitate interpolation. Computing the adjusted observation error variance in a more accurate way than just extrapolating (method 1 above) appears to be costly and complex and is not explored further here.

4 Computing estimates of the time offset

The previous section has presented algorithms to extend ensemble Kalman filters to cases where an estimate of the time offset
110 τ at an analysis time is known. This section presents algorithms for estimating the distribution of τ at an analysis time for use in an ensemble Kalman filter.

4.1 No correction

The distribution is assumed to be $\tau \sim N(0,0)$, so the default ensemble Kalman filter is applied.

4.2 Variance only

115 The distribution from which the time offset is drawn is used, $\tau \sim N(0, \sigma_\tau^2)$. Using this with extrapolation results in no change to the prior mean but an increased observation error variance.



4.3 Impossible linear estimate

This algorithm assumes that the difference between the observation and the truth at the analysis time, $\tilde{\mathbf{d}} = \mathbf{y}_k^o - \boldsymbol{\chi}(t_k^a)$ is known; this is not possible in real systems where the truth is unknown but provides an interesting baseline for practical algorithms. Linearly extrapolating gives the approximation for the distance, $\tilde{\mathbf{d}} = \boldsymbol{\varepsilon}_k^x + \mathbf{v}\boldsymbol{\varepsilon}_k^t$. The relative likelihood of a given value of the offset can then be approximated as

$$p(\tau) = P(\boldsymbol{\varepsilon}_k^x = \boldsymbol{\varepsilon} \cap \boldsymbol{\varepsilon}_k^t = \tau \mid \boldsymbol{\varepsilon} + \tau\mathbf{v} = \tilde{\mathbf{d}}). \quad (4)$$

Since $\boldsymbol{\varepsilon}_k^x$ and $\boldsymbol{\varepsilon}_k^t$ are independent,

$$p(\tau) \propto \exp\left(-\frac{1}{2}(\tilde{\mathbf{d}} - \tau\mathbf{v})^T \mathbf{R}^{-1}(\tilde{\mathbf{d}} - \tau\mathbf{v})\right) \exp\left(-\frac{1}{2}\tau^2\sigma_t^{-2}\right) \quad (5)$$

$$125 \quad p(\tau) \propto \exp\left(-\frac{1}{2}[\tilde{\mathbf{d}}^T \mathbf{R}^{-1} \tilde{\mathbf{d}} - \tau(\tilde{\mathbf{d}}^T \mathbf{R}^{-1} \mathbf{v} + \mathbf{v}^T \mathbf{R}^{-1} \tilde{\mathbf{d}}) + \tau^2 \beta]\right), \quad (6)$$

where $\beta = \mathbf{v}^T \mathbf{R}^{-1} \mathbf{v} + \sigma_t^{-2}$. The constant factor $\exp\left(-\frac{1}{2} \tilde{\mathbf{d}}^T \mathbf{R}^{-1} \tilde{\mathbf{d}}\right)$ can be absorbed into the proportionality and the exponent factored to give

$$p(\tau) \propto \exp\left(-\frac{\beta}{2}\left[\tau^2 - \tau \frac{\tilde{\mathbf{d}}^T \mathbf{R}^{-1} \mathbf{v} + \mathbf{v}^T \mathbf{R}^{-1} \tilde{\mathbf{d}}}{\beta}\right]\right). \quad (7)$$

Now, the constant factor $\exp\left(\frac{\beta}{2}\left[\frac{\tilde{\mathbf{d}}^T \mathbf{R}^{-1} \mathbf{v} + \mathbf{v}^T \mathbf{R}^{-1} \tilde{\mathbf{d}}}{\beta}\right]^2\right)$ can be absorbed to give

$$130 \quad p(\tau) \propto \exp\left(-\frac{\beta}{2}\left[\tau^2 - \tau \frac{\tilde{\mathbf{d}}^T \mathbf{R}^{-1} \mathbf{v} + \mathbf{v}^T \mathbf{R}^{-1} \tilde{\mathbf{d}}}{\beta} + \left(\frac{\tilde{\mathbf{d}}^T \mathbf{R}^{-1} \mathbf{v} + \mathbf{v}^T \mathbf{R}^{-1} \tilde{\mathbf{d}}}{\beta}\right)^2\right]\right). \quad (8)$$

Finally, collecting the squares and reordering exponents gives

$$p(\tau) \propto \exp\left(-\frac{\beta}{2}\left[\tau - \frac{\mathbf{v}^T \mathbf{R}^{-1} \tilde{\mathbf{d}}}{\beta}\right]^2\right). \quad (9)$$

This is the PDF of a normal with mean

$$\mu_\tau = \frac{\mathbf{v}^T \mathbf{R}^{-1} \tilde{\mathbf{d}}}{\beta} = \frac{\mathbf{v}^T \mathbf{R}^{-1} \tilde{\mathbf{d}}}{\mathbf{v}^T \mathbf{R}^{-1} \mathbf{v} + \sigma_t^{-2}} \quad (10)$$

135 and variance

$$\sigma_\tau^2 = \frac{1}{\beta} = \frac{1}{\mathbf{v}^T \mathbf{R}^{-1} \mathbf{v} + \sigma_t^{-2}} \quad (11)$$



4.4 Possible linear estimate

In real applications, the difference between the observation and the truth at the analysis time cannot be computed, but the difference between the observation and the prior ensemble mean, $\mathbf{d} = \mathbf{y}_k^o - \overline{\mathbf{x}^p}(t_k^a)$ can. Linearly extrapolating gives an estimate $\mathbf{d} \approx \boldsymbol{\varepsilon}_k^x + \mathbf{v}\boldsymbol{\varepsilon}_k^t - \boldsymbol{\varepsilon}_k^p$, where $\boldsymbol{\varepsilon}_k^p \sim N(\mathbf{0}, \boldsymbol{\Sigma}^p(t_k^a))$ is a draw from the prior ensemble sample covariance at the analysis time. This assumes that the prior ensemble distribution is consistent with the truth so that the truth over many analysis times is statistically indistinguishable from the prior ensemble members. In real applications, this is never the case. For instance, any practical problem would certainly have model deficiencies so that the prior would be biased and $\boldsymbol{\varepsilon}_k^p$ would have a non-zero mean.

145

Defining the difference of the observation error and the prior ensemble uncertainty as $\boldsymbol{\varepsilon}_k^\delta = \boldsymbol{\varepsilon}_k^x - \boldsymbol{\varepsilon}_k^p$, we have

$\boldsymbol{\varepsilon}_k^\delta \sim N(\mathbf{0}, \mathbf{R} + \boldsymbol{\Sigma}^p(t_k^a))$. The analysis for the impossible linear estimate can be repeated by solving for the probability

$$p(\tau) = P(\boldsymbol{\varepsilon}_k^\delta = \boldsymbol{\varepsilon} \cap \boldsymbol{\varepsilon}_k^t = \tau \mid \boldsymbol{\varepsilon} + \tau\mathbf{v} = \mathbf{d}). \quad (12)$$

in the same fashion. The result is that

$$\mu_\tau = \frac{\mathbf{v}^T [\mathbf{R} + \boldsymbol{\Sigma}^p(t_k^a)]^{-1} \tilde{\mathbf{d}}}{\mathbf{v}^T [\mathbf{R} + \boldsymbol{\Sigma}^p(t_k^a)]^{-1} \mathbf{v} + \sigma_\tau^{-2}} \quad (13)$$

and

$$\sigma_\tau^2 = \frac{1}{\mathbf{v}^T [\mathbf{R} + \boldsymbol{\Sigma}^p(t_k^a)]^{-1} \mathbf{v} + \sigma_\tau^{-2}} \quad (14)$$

It is statistically difficult to distinguish between observation error and error due to time offset. This can lead to time error estimates with a magnitude that is too large. This error can propagate to subsequent analysis times and lead to biased prior estimates that can result in unstable feedback in the assimilation. Sect. 6.3 presents evidence of this problem and describes a solution that works for the test applications explored there.

155

4.5 Nonlinear estimate

As for the interpolation method in Sect. 3.2, assume that an ensemble of prior estimates of the true state, $\mathbf{x}_n^p(t_i)$ is available at the same discrete times as the truth for $t_{k-1}^a \leq t_i \leq t_{k+1}^a$. For each t_i in this range, the relative likelihood that the offset observation was taken at this time is

160

$$P(t_k^o = t_i) = N(\overline{\mathbf{x}^p}(t_i), \boldsymbol{\Sigma}^p(t_i) + \mathbf{R}; \mathbf{y}_k^o) N(t_k^a, \sigma_\tau^2; t_i) \quad (15)$$

The first term is the relative probability that the observation was taken at time t_i while the second term is the relative probability that the time offset is $t_k^a - t_i$. The value of t_i with the largest value in Eq. (15) is assumed to correspond to the maximum likelihood estimate of the time offset, $\mu_\tau = t_k^a - t_i$. It is complex and expensive to compute a nonlinear estimate of the variance



165 of the offset, σ_τ^2 , and that is not explored here. It is also possible to compute the μ_τ in other related ways. For example, the
likelihood weighted average of the $\{t_i\}$, could be used instead. This was found to make only small differences to the results
described in section 7.

5 Low-order model test problems

A set of assimilation methods described in the next section are applied to the 40-variable model described in Lorenz and
170 Emmanuel (1998) with forcing F set to 8, referred to as the L96 model. A fourth-order Runge-Kutta time differencing scheme
is applied with a non-dimensional timestep of $\Delta t = 0.01$ instead of the 0.05 that is more frequently used in previous work.

Results are explored for 5 different simulated observing systems that differ by the analysis period, P , with which observations
are supposed to be taken. The periods are 5, 10, 15, 30 and 60 timesteps corresponding to 0.05, 0.1, 0.15, 0.3 and 0.6 time
175 units. Each experiment performs 1100 analysis steps and the first 100 are always discarded.

For a given analysis period, the L96 model is integrated from an initial condition of 1.0 for the first state variable and zero for
all others to generate truth trajectories. Eleven initial conditions are generated by saving the state every 1100 analysis times.
The first initial condition is used to empirically tune localization and inflation, and the other ten are used for ten trials using
180 the tuned values.

For each observing system, several values of the standard deviation of the observation time offset σ_t are explored. The
combination of σ_t and an analysis period P define a case. Table 1 shows the cases explored. For each method applied to each
case, a set of 49 assimilation experiments is performed using pairs of Gaspari-Cohn (Gaspari and Cohn 1999) localization *half-*
185 *widths* selected from the set $\{0.125, 0.15, 0.175, 0.2, 0.25, 0.4, \infty\}$ and fixed multiplicative *variance* inflation (Anderson
and Anderson 1999) selected from the set $\{1, 1.02, 1.04, 1.08, 1.16, 1.32, 1.64\}$. The pair of halfwidth and inflation that
produces the minimum posterior ensemble mean root mean square error from the truth is used for ten subsequent experiments
for the case that differ only in the initial truth condition.

190 At each analysis time k , all 40 state variables are observed at a time t_k^o that has an offset ε_k^t from the analysis time, $t_k^o = t_k^a +$
 ε_k^t . All observations at a given time share the same time offset which is generated as a random draw from $\varepsilon_k^t \sim N(0, \sigma_t^2)$. If
 $|\varepsilon_k^t|$ is larger than the analysis time period $P\Delta t$, its magnitude is reduced to $\frac{1}{2}P\Delta t$ while its sign is unchanged. This is an
infrequent occurrence by design for most of the cases examined.

195




Table 1: List of observing system cases explored. For each of five analysis periods, a number of different values for the time offset standard deviation were explored.

Analysis Period	σ_t
0.05	0, 0.0125, 0.025, 0.05
0.10	0, 0.0125, 0.025, 0.05, 0.1
0.15	0, 0.0125, 0.025, 0.05, 0.1
0.30	0, 0.0125, 0.025, 0.05, 0.1, 0.2
0.60	0, 0.0125, 0.025, 0.05, 0.1, 0.2

Figure 1 shows a short segment of the trajectory of the truth, $\chi(t_i)$, for a single L96 state variable and the generation of observations for the case with analysis period 0.60 and time error standard deviation 0.2. The true observation values \mathbf{y}_k^{tr} for each state variable are generated by linearly interpolating the true state trajectory $\chi(t_i)$ that is available every 0.01 time units to the offset observing times t_k^o (green circles in Fig. 1). The observation error variance is 1 for all experiments and the actual observations that are assimilated, \mathbf{y}_k^o (red 'X' in Fig. 1) are generated by adding an independent draw from $N(0, 1)$ to \mathbf{y}_k^{tr} for each of the 40 state variables.

Figure 1 also shows the value of the state linearly extrapolated from the analysis time to the observed time as a blue vector and '+' . This is analogous to the extrapolation performed by Eq. (2) using the ensemble mean estimate as a base point and gives a feeling for how nonlinear the time offset problem is at a particular analysis time.





210 **Figure 1:** A short segment of the truth for a state variable and the observation generation process from the case with analysis
period 0.6 and time error standard deviation 0.2. The true trajectory is indicated by the small grey asterisks every 0.01 time
units. The black asterisks indicate the true value at each analysis time. The green asterisks are the truth at the actual observed
time (the analysis time plus the observation time offset for that analysis time). The red asterisk is the actual observation that is
assimilated and is generated by adding a random draw from $N(0, 1)$ to the truth at the actual observed time. The blue asterisk
215 indicates the result of linearly extrapolating the truth at the analysis time to the actual observed time using the time derivative
of the model at the analysis time (v in Eq. (1)); a blue line segment connects the truth to the extrapolated value.

6 Assimilation Methods

Five assimilation methods were tested for each L96 case. All applied a standard ensemble adjustment Kalman filter (EAKF,
220 Anderson 2001) with 80 members using a serial implementation (Anderson 2003) to update the ensemble with observations.
All but the first method made adjustments to the prior observation ensemble and/or the observation error covariance to deal
with the observation time offset.

6.1 No correction (referred to as NOCORRECTION)

225 Observations were assimilated with a standard EAKF. This is consistent with the assumption made in Sect. 4.1 that the time
offset $\tau = 0$.

6.2 Adjust observation error variance only (referred to as VARONLY)

This method assumed time offset $\tau \sim N(0, \sigma_t^2)$ as in Sect. 4.2 and only adjusted the observation error variance using the linear
230 approximation given in Eq. (3).

6.3 Possible linear correction (referred to as LINEAR)

This method used Eq. (13) and Eq. (14) to compute the mean and variance of the time offset. This distribution for τ was then
used with the extrapolation method of Sect. 3.1, using Eq. (2) to compute prior ensemble estimates of each observation and
235 Eq. (3) to compute the observation error variance.

A naive application of this method was not successful in any of the L96 cases. The tuned assimilations worked successfully
for some number of analysis times, but the RMSE of the ensemble mean always began to increase with time before 1100
analysis times and results were worse than for NOCORRECTION. The magnitude of the estimate of the mean value of the
240 time offset $|\mu_\tau|$ would also systematically increase with time.



245 This occurred because of the statistical challenge of separating observation time offset from prior model error. Suppose this method was applied to a model with only a single time varying variable that is observed. The prior ensemble mean will almost always have an error. If, for example, that error has the same sign as the time tendency of the model at the analysis time, the linear correction method will attribute part of that error to a time offset in the observation and will not correct the error as strongly as it would if no time offset were assumed. This means that the forecast at the next analysis time is likely to be consistent with the model state at a time later than the analysis time. Again, the algorithm will attribute some of this error to a time offset in the observation. The net result is that the estimated model state is likely to drift further and further ahead of the true trajectory in time.

250

To avoid this problem, estimates of the time offset that were (nearly) independent of the error for a given state variable were needed. This was accomplished by using a modified version of Eq. (13) to compute a separate value of μ_τ for each observation.

$$\mu_{\tau,m} = \frac{v^T [\mathbf{R} + \Sigma^P(t_k^a)]^{-1} \mathbf{d}^m}{v^T [\mathbf{R} + \Sigma^P(t_k^a)]^{-1} v + \sigma_\tau^{-2}}. \quad m = 1 \dots M \quad (16)$$

255 where M is the number of observations (here, $M = 40$, the size of the model, for all experiments). The vector \mathbf{d}^m is a modification of the original vector \mathbf{d} , the distance between the observations and the prior ensemble mean at the analysis time.

$$\mathbf{d}_i^m = \begin{cases} \mathbf{d}_i, & \|i, m\| > T \\ 0, & \|i, m\| \leq T \end{cases} \quad (17)$$

The subscript i references the vector component for a given scalar observation, T is an integer cutoff threshold, and $\|i, m\|$ is the cyclical distance in units of grid intervals between two variables in the 40-variable L96 model,

$$\|i, m\| = \begin{cases} |i - m|, & |i - m| \leq 20 \\ 40 - |i - m|, & |i - m| > 20 \end{cases} \quad (18)$$

260 A subset of the components of the vector \mathbf{d} that correspond to observed state variables close to the m th state variable were set to 0, effectively eliminating the impact of these state variables on the estimated time offset for the m th observation. All results shown here for the LINEAR method used a threshold T of 10 so that 21 components (out of 40) were set to zero. Larger or smaller values of T increased the RMSE in tuning experiments performed for the case with analysis period $P = 0.3$ and time offset standard deviation $\sigma_\tau = 0.1$. It is likely that improved performance for other cases could result from retuning T , but this was not explored here.

265

6.4 Impossible linear correction (referred to as IMPOSSIBLE)

270 This method used Eq. (10) and Eq. (11) to compute the mean and variance of the time offset. This distribution for τ was then used with the extrapolation method of Sect. 3.1, using Eq. (2) to compute prior ensemble estimates of each observation and Eq. (3) to compute the observation error variance. As noted, computing $\tilde{\mathbf{d}}$ for use in Eq. (10) requires knowledge of the true state so this is not a practical algorithm. Knowledge of the truth prevents the drift away from the truth that necessitated the use of Eq. (16) for LINEAR.



6.5 Nonlinear correction (referred to as NONLINEAR)

275 The nonlinear algorithm in Sect. 4.5 was used to estimate the most likely value of the time offset μ_τ and the interpolation method in Sect. 3.2 was used to adjust the prior estimates of each observation.

In addition to estimating the model state, each of the 5 methods also estimated the value of the time offset, μ_τ at each analysis times. Methods NOCORRECTION, VARONLY and LINEAR used the possible estimate from Eq. (13), IMPOSSIBLE used
280 the estimate from Eq. (10), and NONLINEAR used the estimate from Sect. 4.5.

7 Results

Figure 2 shows the results for the five methods applied to all cases. For each case, the RMSE of the prior ensemble mean is plotted for each of the ten trials made with each assimilation method. The results for different methods are distinguished by the color of the markers and the horizontal offset of the plot columns. Note that ranges of both axes vary across the figures and
285 that the horizontal axis is logarithmic (with the exception of the value for no time offset).

The green markers (leftmost) are the results of the NOCORRECTION method which ignores the time offset and does a standard ensemble adjustment Kalman filter using $N(0, 1)$ as the observation error. The VARONLY method, shown in red (second from left), accounts for the added uncertainty in the observation values due to the unknown time offset. VARONLY
290 is better than NOCORRECTION for longer analysis periods and larger time error standard deviations. There are no cases for which VARONLY is obviously worse than NOCORRECTION.

The LINEAR method is shown in blue (middle). For almost all cases, it generally produces smaller RMSE than NOCORRECTION with the relative improvement being largest for analysis period 0.1 and 0.15 and larger time error standard
295 deviation. LINEAR produces larger RMSE than NOCORRECTION for all cases with analysis period 0.6. The poor performance for the cases with time error standard deviation greater than 0.15 is due to errors in the linear tangent approximation for the evolution of the L96 state trajectories (see examples for the 0.6 analysis period in Fig. 1). LINEAR applies the same increment to the observational error variance as VARONLY. It performs better than VARONLY for most cases. However, VARONLY is better than LINEAR for cases with period 0.6, showing that the additional linear correction to
300 the prior ensemble is clearly inappropriate for these cases.

Additional insight into the performance of LINEAR can be gained from the results for IMPOSSIBLE, shown in black (second from right) in the figure. Not surprisingly, since it has access to the truth when estimating the offset, it always produces smaller RMSE than LINEAR (except for cases with no time error). For the 0.05, 0.1 and 0.15 analysis period cases, the RMSE for



305 IMPOSSIBLE is nearly independent of the time error standard deviation. This is not the case for analysis periods 0.3 and 0.6
 where the error increases as the time error standard deviation increases. The cause of this error increase is that the linear tangent
 approximation becomes inaccurate as the time error increases. However, especially for analysis period 0.6, IMPOSSIBLE does
 not produce significantly better RMSE than NOCORRECTION, even for smaller time error standard deviation where the
 linear tangent approximation should normally be accurate. Apparently, the larger prior error resulting from infrequent
 310 observations dominates the errors introduced by the time error in these cases.

The NONLINEAR method plotted in magenta (rightmost) has additional information about the distribution of the time offset
 and almost always performs significantly better than NOCORRECTION. The relative importance of nonlinearity in the prior
 truth trajectories is revealed by comparing the RMSE for IMPOSSIBLE and NONLINEAR. For time error standard deviations
 315 smaller than 0.1, IMPOSSIBLE is almost always significantly better, but for time error standard deviation of 0.1 and 0.2,
 NONLINEAR is always better.

All methods also produce an estimate, μ_τ , of the true time offset, ε_k^t , at each analysis time, t_k^a . The RMSE of the estimate for
 each method for cases with analysis periods 0.1 and 0.3 are shown in Fig. 3 with the same color/position scheme as in Fig. 2.
 320 For NOCORRECTION, the offset is estimated using Eq. (13) even though the offset is not used in the algorithm. For LINEAR,
 the estimate is the estimate using all state variables from Eq. (13), not the revised estimates using Eq. (16). For IMPOSSIBLE,
 the offset is computed using Eq. (10).





Figure 2: RMSE of the ensemble mean over 1000 analysis time steps for cases with analysis period 0.05 time units. Ten experiments were run for each of 5 methods with each method indicated by a different color. The horizontal axis is logarithmic except for the 0 value.



325 For analysis period of 0.1 (Fig. 3A), the estimates from all methods are always less than the specified time error standard deviation and become smaller fractions of the specified value as the value increases. This is because it is easier to detect time error when that error is relatively larger compared to the observation error. LINEAR and VARONLY have smaller RMSE than NOCORRECTION for larger time error standard deviations with LINEAR being slightly better than VARONLY. The RMSE for NONLINEAR is much larger than for NOCORRECTION for smaller time error standard deviations. This is because

330 the possible offset estimates are selected from the discrete set of times for which the truth and prior ensemble are computed (see Eq. (15)) which are spaced 0.01 time units apart. The time offset estimates for all other methods can take on any real value. For the case with time error standard deviation 0.1, the nonlinearity is large enough that the NONLINEAR estimate of the offset is comparable to that produced by VARONLY and is better than NOCORRECTION.

335 For larger analysis period of 0.3 (Fig. 3B), the estimate from LINEAR is not better than NOCORRECTION, while VARONLY is better than LINEAR for larger time error standard deviations. In this case, NONLINEAR still has the largest RMSE for cases with time error standard deviation of 0.025 and 0.05, but has by far the smallest RMSE for cases with 0.1 and 0.2.



340 **Figure 3:** The RMSE of the estimate of the time offset for cases with analysis period (A) 0.1 time units and (B) 0.3 time units. Ten experiments were run for each of 5 methods with each method indicated by a different color. The horizontal axis is logarithmic except for the 0 value.

8 Discussion and summary

A number of simplifying assumptions were made in the algorithms described here. These include assuming that every state

345 variable is observed directly, that all observations share the same time offset, that the observation error covariance matrix \mathbf{R} is diagonal, and that the time offset variance, σ_t^2 , is known a priori.

It is straightforward to deal with some of these issues. The assimilation problem can be recast in terms of a joint phase space, where an extended model state vector is defined as the union of the model state variables and prior estimates of all observations



350 (Anderson 2003). Then, all observed quantities are model state variables by definition. However, for methods that use linear
extrapolation via Eq. (1), the model equations are no longer sufficient. One can either develop equations for the time tendency
of observations, or simply use finite difference approximations to compute \mathbf{v} for the extended state. It is even more
straightforward to extend the method to cases where not all (extended) state variables are observed. Both the methods for using
(Sect. 3) and computing (Sect. 4) information about the time offset at the current analysis time can be applied just to the
355 variables that are observed.

Since a serial ensemble filter is being used for the actual assimilation, it is possible to partition the observations into subsets
that are themselves assimilated serially. All observations that share a time offset can be assimilated as a subset, including a
subset for those observations with no time offset.

360

All of the methods for estimating the offset at a given analysis time except NOCORRECTION make explicit use of σ_t^2 , the
variance of the distribution from which the offsets are drawn. If this is not known accurately, the performance of all the
algorithms is expected to degrade. However, tests in which the value used in the assimilation was either 4 or 16 times larger
than the actual value of σ_t^2 led to only limited increases in the RMSE of the various methods. It is also possible to refine the
365 estimate of this variance by starting with a large value and examining the estimated values of the time offset that result.

The methods also assume that \mathbf{R} is diagonal, which simplifies the derivation of the equations in Sects. 4.3 and 4.4 and allows
the serial implementation. Removing this simplifying assumption requires computing and inverting matrices of size $M \times M$,
where M is the number of observations with mutually correlated errors. The increase in cost is the same as for algorithms that
370 do not estimate time offset.

The methods described have a range of computational costs. The VARONLY method only requires a single evaluation of Eqs.
(2) and (3) at each analysis time step and has an incremental cost that is a tiny fraction of the NOCORRECTION base filter.
The LINEAR method requires an evaluation of Eq. (16) for every observation, and Eq. (16) requires the computation, storage,
375 and inversion of a prior ensemble covariance matrix. However, this matrix could be reduced in size to only include the subset
of observations that is used to compute the offset for each observation. It would be application specific to determine this size.
For example, a radiosonde would make a large number of observations, e.g., temperature and wind at a number of levels, but
many of these are correlated in time. We can capture most of the information about time offset from a smaller subset of the
observations, and just do the inversion on those to make the matrix small compared to the total model size.

380

The NONLINEAR method involves a large amount of additional computation. The prior ensemble needs to be available over
a range of times covering the possible offsets. In the idealized cases here, that meant that ensemble forecasts were required to
extend to the second analysis time in the future, doubling the forecast model cost. Then Eq. (15) must be evaluated for each of



the available times. The dominant cost in Eq. (15) is computing the prior covariance matrix for the observations that share an
385 offset. This requires $O(M^2)$ computations, where M is the number of observations. Again, the relative cost would be highly
application specific, but this method is the most expensive of the five.

The importance of accounting for observation time errors in many earth system DA applications remains unexplored. The
range of methods discussed here have varying cost, but all could be applied for at least short tests in any application for which
390 ensemble DA is already applicable. In particular, applications to atmospheric reanalyses for periods well before the radiosonde
era seem to be especially good candidates for improvement. Future work will assess the algorithms presented here in both
observing system simulation and real observation experiments with global atmospheric models and observing networks from
previous centuries.

Code and data availability

395 All code used to generate the data for this study, the generated data, code for creating the figures and figure files are available
at https://github.com/jlaucar/npg_gorokhovsky

Author contributions

EG proposed the study, developed the mathematical methods, and implemented initial test code. JA solved the problems with
the possible linear method, ran final tests and implemented figures. Both wrote the final report.

400 **Competing interests**

The authors declare they have no competing interests.

Acknowledgements

The authors would like to thank Peter Teasdale and Valerie Keeney of Summit Middle School and Paul Strode and Emily
Silverman of Fairview High School for their commitment to science education and providing the authors with an opportunity
405 to collaborate. The authors are indebted to NCAR's Data Assimilation Research Section team for providing guidance in
developing the software used for this work.



Financial support

This material is based upon work supported by the National Center for Atmospheric Research, which is a major facility sponsored by the National Science Foundation under Cooperative Agreement No. 1852977.

410

References

Abraham, J. P., et al.: A review of global ocean temperature observations: Implications for ocean heat content estimates and climate change, *Rev. Geophys.*, 51, 450–483, <https://doi.org/10.1002/rog.20022>, 2013.

415 Amrhein, D. E: How large are temporal representativeness errors in paleoclimatology?, *Clim. Past*, 16, 325–340, <https://doi.org/10.5194/cp-16-325-2020>, 2020.

Anderson, J. L., and Anderson, S. L.: A Monte Carlo implementation of the nonlinear filtering problem to produce ensemble assimilations and forecasts, *Mon. Weather Rev.*, 127, 2741-2758, [https://doi.org/10.1175/1520-0493\(1999\)127<2741:AMCIOT>2.0.CO;2](https://doi.org/10.1175/1520-0493(1999)127<2741:AMCIOT>2.0.CO;2), 1999.

420 Anderson, J. L.: An ensemble adjustment Kalman filter for data assimilation, *Mon. Weather Rev.*, 129, 2884–2903, [https://doi.org/10.1175/1520-0493\(2001\)129<2884:Aeakff>2.0.Co;2](https://doi.org/10.1175/1520-0493(2001)129<2884:Aeakff>2.0.Co;2), 2001.

425 Anderson, J. L.: A local least squares framework for ensemble filtering, *Mon. Weather Rev.*, 131, 634–642, [https://doi.org/10.1175/1520-0493\(2003\)131<0634:Allsff>2.0.Co;2](https://doi.org/10.1175/1520-0493(2003)131<0634:Allsff>2.0.Co;2), 2003.

Bartky, I. R.: The adoption of standard time, technology and culture, 30, 25-56, <https://doi.org/10.2307/3105430>, 1989.

Berry, T., and Harlim, J.: Correcting biased observation model error in data assimilation, *Mon. Weather Rev.*, 145, 2833-2853, <https://doi.org/10.1175/MWR-D-16-0428.1>, 2017.

Burgers, G., Van Leeuwen, P. J., and Evensen, G.: Analysis scheme in the ensemble Kalman filter. *Mon. Weather Rev.*, 126, 1719-1724, [https://doi.org/10.1175/1520-0493\(1998\)126<1719:ASITEK>2.0.CO;2](https://doi.org/10.1175/1520-0493(1998)126<1719:ASITEK>2.0.CO;2), 1998.

435 Compo, G. P., et al.: The twentieth century reanalysis project. *Quart. J. Roy. Meteor. Soc.*, 137, 1–28, <https://doi.org/10.1002/qj.776>, 2011.

Dee, D. P., and Uppala, S.: Variational bias correction of satellite radiance data in the ERA-Interim reanalysis. *Quart. J. Roy.*



- Meteor. Soc., 135, 1830-1841, <https://doi.org/10.1002/qj.493>, 2009.
- 440
- Desroziers, G. L., Berre, L., Chapnik, B. and Poli, P.: Diagnosis of observation, background and analysis-error statistics in observation space, *Quart. J. Roy. Meteor. Soc.*, 131, 3385 - 3396. <https://doi.org/10.1256/qj.05.108>, 2005.
- Gaspari, G., and Cohn, S. E.: Construction of correlation functions in two and three dimensions. *Quart. J. Roy. Meteor. Soc.*, 445 125, 723-757, <https://doi.org/10.1002/qj.49712555417>, 1999.
- Giese, B.S., Seidel, H. F., Compo, G. P. and Sardeshmukh, P. D.: An ensemble of ocean reanalyses for 1815-2013 with sparse observational input. *J. Geophys. Res. Oceans*, 121, 6891-6910, <https://doi.org/10.1002/2016JC012079>, 2016.
- 450 Gwirtz, K., Morzfeld, M., Kuang, W., and Tangborn, A.: A testbed for geomagnetic data assimilation, *Geophysical Journal International*, 227, 2180-2203, <https://doi.org/10.1093/gji/ggab327>, 2021.
- Haimberger, L. (2007): Homogenization of radiosonde temperature time series using innovation statistics, *Journal of Climate*, 20, 1377-1403, <https://doi.org/10.1175/JCLI4050.1>, 2007.
- 455
- Hamilton, F., Berry, T., and Sauer, T.: Correcting observation model error in data assimilation, *Chaos*, 29, 053102, <https://doi.org/10.1063/1.5087151>, 2019.
- Laroche, S. and Sarrazin, R.: Impact of radiosonde balloon drift on numerical weather prediction and verification, *Weather and Forecasting*, 28, 772-782, <https://doi.org/10.1175/WAF-D-12-00114.1>, 2013.
- 460
- Lorenz, E. N. and Emanuel, K. A.: 1998: Optimal sites for supplementary weather observations: Simulation with a small model, *J. Atmos. Sci.*, 55, 399-414, [https://doi.org/10.1175/1520-0469\(1998\)055<0399:OSFSWO>2.0.CO;2](https://doi.org/10.1175/1520-0469(1998)055<0399:OSFSWO>2.0.CO;2), 1998.
- 465
- Slivinski, L. C., et al: Towards a more reliable historical reanalysis: Improvements for version 3 of the Twentieth Century Reanalysis system, *Quart. J. of the Roy. Meteor. Soc.*, 145, 2876-2908, <https://doi.org/10.1002/qj.3598>, 2019
- Satterfield, E., Hodyss, D., Kuhl, D. D., and Bishop, C. H.: Investigating the use of ensemble variance to predict observation error of representation, *Mon. Weather Rev.*, 145, 653-667, <https://doi.org/10.1175/MWR-D-16-0299.1>, 2017.
- 470
- Tippett, M. K., Anderson, J. L., Bishop, C. H., Hamill, T. M., and Whitaker, J. S.: Ensemble square root filters, *Mon. Weather Rev.*, 131, 1485-1490, [https://doi.org/10.1175/1520-0493\(2003\)131<1485:ESRF>2.0.CO;2](https://doi.org/10.1175/1520-0493(2003)131<1485:ESRF>2.0.CO;2), 2003.

<https://doi.org/10.5194/egusphere-2022-536>

Preprint. Discussion started: 12 July 2022

© Author(s) 2022. CC BY 4.0 License.



475 Toride, K., Neluwala, P., Kim, H., and Yoshimura, K.: Feasibility study of the reconstruction of historical weather with data assimilation, *Mon. Weather Rev.*, 145, 3563-3580, <https://doi.org/10.1175/MWR-D-16-0288.1>, 2017.