Toward coherent space-time mapping of seagrass cover from satellite data: example of a Mediterranean lagoon

Guillaume Goodwin[1], Marco Marani[2], Sonia Silvestri[3], Luca Carniello[2], and Andrea D'Alpaos[4]

[1]Fish-Pass Environnement, 18, rue de la Plaine, 35830 Laillé, France
[2]DICEA, Universita di Padova, via Marzolo, 9, Padova, Italy
[3]Dipartimento di Scienze Biologiche, Geologiche e Ambientali, Alma Mater Studiorum Università di Bologna, Via S. Alberto 163, Ravenna, Italy
[4]Dipartimento di Geoscienze, Universita di Padova, via Gradenigo, 6, Padova, Italy

Correspondence: Guillaume Goodwin (willgoodwin1201@gmail.com)

Abstract. Seagrass meadows are a highly productive and economically important shallow coastal habitat. Their sensitivity to natural and anthropogenic disturbances, combined with their importance for local biodiversity, carbon stocks and sediment dynamics, motivate a frequent monitoring of their distribution. However, generating time-series of seagrass cover from field observations is costly, and mapping methods based on remote sensing require restrictive conditions on seabed visibility, lim-
5 iting the frequency of observations. In this contribution, we examine the effect of accounting for environmental factors such as the bathymetry and median grain size (D_{50}) of the substrate, as well as the coordinates of known seagrass patches, on the performance of a Random Forest (RF) classifier used to determine seagrass cover. Using 148 Landsat images of the Venice Lagoon (Italy) between 1999 and 2020, we trained a RF classifier with only spectral features from Landsat images and sea-grass surveys, respectively from 2002 and 2017. Then, by adding the features above and applying a time-based correction on
10 predictions, we created multiple RF models with different feature combinations. We tested the quality of the resulting seagrass cover predictions from each model against field surveys, showing that bathymetry, D_{50} and coordinates of known patches exert an influence that is dependant on the training Landsat image and seagrass survey chosen. In models trained on a survey from 2017, where using only spectral features causes predictions to overestimate seagrass surface area, no significant change in model performance was observed. Conversely, in models trained on a survey from 2002, the addition of the out-of-image
15 features and particularly coordinates of known vegetated patches greatly improves the predictive capacity of the model, while still allowing the detection of seagrass beds absent in the reference field survey. Applying a time-based correction eliminates small temporal variations in predictions, improving predictions that performed well before correction. We conclude that accounting for the coordinates of known seagrass patches, together with applying a time-based correction, has the most potential to produce reliable frequent predictions of seagrass cover. While this case study alone is insufficient to explain how geographic
20 location information influences the classification process, we suggest that it is linked to the inherent spatial auto-correlation of seagrass meadow distribution. In the interest of improving remote sensing classification and particularly to develop our capacity to map vegetation across time, we identify this phenomenon as warranting further research.

1 Introduction

Seagrass meadows are emblematic shallow water ecosystems, well-known for their diverse wildlife (Sfriso et al., 2001) and
capacity to sequester carbon and nutrients (Greiner et al., 2013; Russell et al., 2013; Johnson et al., 2017): early landmark
valuations of ecosystem services estimated the benefits generated by seagrass and algae beds at over $19,000\,USD(1997)\cdot ha^{-1}\cdot yr^{-1}$, second only to forested wetlands such as swamps and floodplains (Costanza et al., 1997). Furthermore, seagrass meadows
modify velocity and turbulence regimes (Hendriks et al., 2008; Ganthy et al., 2015; Carniello et al., 2016), resuspension
(Widdows et al., 2008; Volpe et al., 2011; Hansen and Reidenbach, 2013; Carniello et al., 2014; Venier et al., 2011), and
sediment trapping (Hendriks et al., 2010), influencing sediment dynamics in estuaries and lagoons. Hence, in the current
context of rising sea levels (Nicholls et al., 2021) and sediment deprivation (Syvitski and Kettner, 2011), understanding their
role in shaping coastal landforms is crucial: reliable and reproducible observations of space-time seagrass presence and change
are a key missing element towards a complete understanding of tidal environment dynamics, now largely focusing on salt
marsh eco-geomorphodynamics (D'Alpaos et al., 2007; Marani et al., 2007, 2011, 2010; Yousefi Lalimi et al., 2020).

Table 1. Compilation of published works on seagrass detection from satellite data. Numbered references are referenced in Table A1.

Sensor	Pixel size	Scenes	Area [km^2]	Method	Performance	Ref
Landsat 5	30 m	1	200	Minimum-distance-to-means	UA:11-55%, OA:35%	1
	30 m	1	105	Maximum Likelihood	UA:83-99%, OA:92%	2
Landsat 4,5,7	30 m	60	200	Multi resolution Segmentation	OA:52-80%	3
Landsat 5,7	30 m	4	94	Maximum Likelihood	OA:54-100%	4
	30 m	40	$> 10^6$	Maximum Likelihood	UA:0-88%, OA:45-85%	5
Landsat 5,7,8	30 m	49	6	ROI growth	UA:84-92% OA:91-96%	6
Landsat 5, 8	30 m	2	42.6	Maximum Likelihood	A:89-93%, OA:85%	7
Landsat 8 OLI	30 m	2	33,000	(Lyons et al., 2012)	UA:13-95%, OA:29-99%	8
	30 m	1	100	(Roelfsema et al., 2014)	UA:22-73%, OA:59%	9
Landsat 8, Sentinel-2	10-30 m	6	140	Maximum Likelihood	UA:13-95%, OA:65-75%	10
ALI	30 m	1	105	Maximum Likelihood	UA:86-99%, OA:95%	11
Hyperion	30 m	1	105	Maximum Likelihood	UA:89-99%, OA:96%	12
Sentinel-2	10 m	1	100	(Roelfsema et al., 2014)	UA:21-81%, OA:57%	13
	10 m	1-2	340	Empirical	RMSE:14% of area	14
	10 m	1	41,000	Support Vector Machines	UA:up to 99%, OA:72%	15
Ziyuan-3A	5 m	1	100	(Roelfsema et al., 2014)	UA:28-67%, OA:54%	16
CASI-2	4 m	1	200	Minimum-distance-to-means	UA:16-68%, OA:46%	17
IKONOS, WV2, QB2	2.4-4 m	9	142	hierarchical OBIA	UA:10-57%, OA:52+-4%	18
QuickBird	2.4 m	1	200	Minimum-distance-to-means	UA:9-52%, OA:31%	19
WorldView-2	2.4 m	1	8.6	SVM /Random Forest	OA:72-94%	20
WorldView-3	2 m	1	100	(Roelfsema et al., 2014)	UA:29-76 %, OA:59%	21
IKONOS	2 m	1	1.78	KM/MD/ML/LSU	UA:65-85%, OA:40-67%	22
GeoEye1	1.65 m	1	20	ML	UA:78-90%, OA:85.7%	23

35 Multiple monitoring campaigns, at several different sites and using diverse methods, have been conducted over the years to map seagrass cover, leading to the recent compilation of a global seagrass distribution assessment (McKenzie et al., 2020). Field mapping is widely employed to determine vegetation characteristics such as stem density, biomass, metabolism, etc. (e.g. (Smith et al., 1988; Caffrey and Kemp, 1991; Kutser et al., 2007)), but high costs and long completion times prevent frequent surveys of the state and extent of submerged vegetation. And yet timeliness is particularly important in understanding the

40 response of seagrass meadows to environmental stressors. In favourable conditions and in the growing season, seagrass can recover from heat waves (Pedersen et al., 2016; Gamain et al., 2018) or shallow scouring within just a few months (Collier and Waycott, 2014), making the effect of such disturbances invisible to infrequent observations. Remote sensing using multi- and

hyper-spectral sensors constitutes an attractive alternative and complements field mapping, provided that detection methods can reliably classify the seabed. Such methods have been applied successfully to satellite data for salt marsh vegetation in the Venice Lagoon (Wang et al., 2007; Yang et al., 2020) as well as for the quantification of suspended sediment concentration (Volpe et al., 2011; Zhou et al., 2017); detecting seagrass using the same data sources remains challenging, due to to highly variable water depth and constituents, but would allow for consistent environmental monitoring. Satellite-born sensors also provide up to daily observations, and are cost-efficient, making them an ideal support for high-frequency and spatially-extended monitoring.

Table 1 reviews 16 publications concerning seagrass mapping from satellite imagery, ordered by decreasing pixel footprint of the image product. These studies classify seagrass density in steps of 25% pixel surface cover, using various methods such as the Maximum Likelihood method (Cam, 1990), trained Support Vector Machines (Noble, 2006), and Random Forest (Biau and Scornet, 2016) methods. Landsat data, with 30 m pixels that can be larger than some seagrass patches and few spectral bands, do not perform significantly worse than commercially-available data with higher resolution and a larger number of bands, such as IKONOS. The wider range of performances for Landsat over other products may be a result of the greater number of studies that use this support. Overall, trained machine learning methods perform marginally better than more traditional classifiers on remote sensing data of the same resolution. However, a systematic comparison among different classifiers can hardly be inferred from the literature, because of the widely different resolutions explored in the existing studies. Indeed, the Maximum Likelihood classifier is used primarily on Landsat products. The wide variety of performances shown in such applications suggests a strong dependence of classification results on the quality of the data and the conditions in which the data were acquired. Indeed, atmospheric conditions, water depth, the presence of waves, as well as chlorophyll and sediment concentrations, all affect reflectance at the water surface, and thus the visibility of the seabed. As a result, acquisitions to be classified must be subject to a strict selection process, making frequent and regular monitoring difficult.

An inconsistent classification performance, and the consequent irregular monitoring frequency (e.g. see Table 1), poses significant limitations to seagrass cover monitoring: the high primary productivity of seagrass implies that meadow density and canopy characteristics, and therefore spectral reflectance, greatly vary seasonally, with growth stages, and stochastically, with storm-induced thinning or scouring (Sfriso and Francesco Ghetti, 1998). This high rate of variation in density and extent also implies that seagrass maps separated by more than a few months cannot capture seasonal, and much less stochastic, variations in seagrass cover. Yet few of the studies listed in Table 1 classify more than one image (Lyons et al., 2012; Dekker et al., 2005; Wabnitz et al., 2008; Hossain et al., 2015; Kohlus et al., 2020; Roelfsema et al., 2014), while most limit the analyses to single illustrative data acquisitions.

The observations made from Table 1 highlight those drawn by the extensive review of Hossain et al. (2014) in that while seagrass detection through remote sensing is imperfect, applications such as Machine Learning used on extended time-series of multispectral satellite images. For instance, Landsat products show potential to improve greatly with more advanced pro-cessing, amongst which are the integration of ecological data or models. Here we contribute apply a Random Forest (RF) classifier (Bakirman and Gumusay, 2020) to map seagrass cover in approximately 150 Landsat scenes between 1999 and 2020 from the Venice Lagoon, Italy. Based on 9 field surveys performed between 2002 and 2017 a well as remote digitizations on

images between 2000 and 2019, we investigate the influence of environmental conditions, known seagrass coordinates, and temporal persistence of detected features on the performance of the classifier. By adding these features and corrections in the classification process, we take a step toward the integration of ecological data in classification models.

2   Materials and method

With a surface area of $550\ km^2$, the Venice Lagoon is the largest lagoon in the Mediterranean Sea. Due to its socio-economic and environmental importance, and to a significant erosional trend (Carniello et al., 2009), the ecological and morphological state of the lagoon has been systematically monitored for decades. Historic and modern bathymetric information complemented by a long record of tidal data provide the opportunity of quantitatively describing, also via numerical modeling, the detailed hydrodynamic circulation throughout the lagoon (Tommasini et al., 2019). Numerous sampling campaigns of sediment composition on the lagoon bed (Amos et al., 2004; Guerzoni and Tagliapietra, 2006; Carniello et al., 2012) are used to infer the preferred habitat of seagrass meadows, and multiple submerged vegetation surveys conducted throughout the 21st century provide a reference for classification testing.

Figure 1. Out-of-image data used as features for seagrass detection. Background image: gridded bathymetry of the Venice Lagoon, collected in 2003 and updated only for the inlets in 2012; data points: gridded median grain size. Triangles indicate the locations of tide and wind gauges. The greyed area represents a zone in the lagoon where no seagrass was found during field surveys. The coordinate system used is in the local Monte Mario projection (EPSG: 3003). Inset image: ©Google Earth

With this wealth of data, the Venice Lagoon is a prime candidate to test new approaches of submerged vegetation detection. In this section, we first describe the collection and processing of local data as well as satellite images from Landsat 7 ETM and Landsat 8 OLI repositories, used as input and for validation. Then, we describe the structure of the Random Forest model developed to classify the images, and explain how local environmental data, as well as data pertaining to the coordinates of known seagrass patches, are added to improve the skill of the classifier. We also describe a simple process used to correct initial predictions, based on the analysis of the predicted seagrass cover time-series. Finally, we define the metrics used to assess the classifier's performance.

2.1 Local data collection and processing

A full lagoon bathymetric survey was performed in 2003 by the Venice Water Authority (Nuova-Technital, 2007) and subsequently updated to account for engineering works that modified the bathymetry within the inlets of Chioggia, Malamocco, and Lido (Carniello et al., 2009) (Figure 1). Furthermore, samples of bed sediment composition have been collected over the years, resulting in a dataset of more than 900 estimates of median grain size (D_{50}) (Carniello et al., 2012) (Figure 1). A network of tidal and wind speed gauges records hourly water surface elevation, wind speed, and direction in key locations of the lagoon since before 2000: among these, we chose stations close to Chioggia in the South and the Saline station in the North (red triangles in Figure 1, source data: (https://www.comune.venezia.it/content/dati-dalle-stazioni-rilevamento). Those stations were chosen as they have the most consistent record over the 1999-2020 period. The station in Saline records both wind velocities and tidal elevation, whereas these data are recorded by two separate stations, located $500m$ apart, in Chioggia.

In addition to physical data, we used field surveys detailing the extent of seagrass cover, species composition, and stem density, hosted on the Atlante della Laguna website (cigno.atlantedellalaguna.it/maps/6/view).

These surveys were performed by SELC (https://www.selc.it/) by delineating seagrass cover, both using a GNSS on the field and by having an operator digitize patches of seagrass from aerial images. Species identified during those surveys were principally Zostera noltii, Cymodocea nodosa, with Zostera marina and Ruppia maritima being found locally. The surveys were conducted and the images acquired to cover the entire lagoon in late summer 2002, 2004, 2009, 2010 and 2017.

However, given the extent of the lagoon, field surveys took place over periods of several months, such that they do not represent the state of the lagoon at a single moment in time. Furthermore, the criteria used to estimate seagrass cover may have varied over time or as a result of different observers. Additional surveys were conducted in the late summer of every year between 2006 and 2015, focusing on the inlets of Lido, Malamocco and Chioggia (footprints appear in Figure A1), mapping seagrass cover according to density classes derived from field, satellite and aerial image observations. In this study, we do not use these density classes and instead consider all density classes that are not bare as vegetated. Indeed, this classification was likely performed by different operators over the years and introduces a source of uncertainty in reference maps. Finally, an operator digitised seagrass patches from 25 Landsat images between 2000 and 2020 on a specific tidal flat near Chioggia with a wide range of bathymetry and where visual inspection revealed multiple changes in seagrass cover (Figure A1). This digitisation, conducted by visually distinguishing bare and vegetated areas, complemented existing reference maps to produce more frequent references and enable comparisons of vegetated surface area.

2.2 Satellite data collection and processing

We downloaded 164 cloud-free Level 2 multispectral acquisitions from the Landsat 7 ETM and Landsat 8 OLI data repository, covering the entire Venice Lagoon between 1999 and 2020. Landsat 5 data were not considered due to inconsistent results in the studies examined in Table 1. Level 2 products are atmospherically corrected using the LEDAPS (Schmidt et al., 2013) and LaSRC algorithms (Ilori et al., 2019), and yield surface reflectance values corrected for the scattering and absorbing effects of gas, vapour, and aerosols. In May 2003, the Scan Line Correction (SLC) system on the Landsat 7 ETM sensor failed, causing all subsequent ETM scenes to contain strips of empty data. Nevertheless, we did not disregard these acquisitions, and take this into account when interpreting our results. From July 2013 onward, Landsat 8 OLI data were brought online, effectively resolving the issue for the purposes of our study. We selected a number of images among those downloaded according to two criteria (Figure 2): a) the tidal elevation at the full hour closest to overpass time is less than $0.75\ m$ above the national datum (Rete Altimetrica dello Stato ,1897). This value was chosen to cut off specific stormy events during which sediment load increased water column absorption and masked the lagoon bed; this approach was not complemented by the implementation of a correction for sediment suspended load to emulate situations where such models cannot be calibrated; b) the third quartile of the series of wind speeds up to three days prior to overpass time does not exceed $8\ m \cdot s^{-1}$ and the 90-th percentile does not exceed $15\ m \cdot s^{-1}$. This criterion limits the probability of inorganic suspended sediment and wind-waves impacting visibility of the seabed. Applying these criteria leaves 148 scenes that are *a priori* fit for the detection of seagrass meadows on the lagoon bed.

Landsat scenes corresponding to field surveys are listed in Table A2, while those associated with digitised reference information are shown in Table A3.

Bathymetric (Carniello et al., 2009) and sediment grain size data (Carniello et al., 2012), excluding channels and salt marshes, were gridded with the Geospatial Data Abstraction Library (GDAL) (GDAL/OGR contributors, 2021) at a pixel size of $30\ m$ according to the nearest neighbour method. All surveyed and digitised seagrass meadows, initially in vector format, were also rasterised using GDAL at a pixel size of $30\ m$, to match bathymetry and sediment size data. Seagrass cover vector data were gridded by considering pixels covered by a seagrass polygon by more than 50% as vegetated (coded as "1"). The remaining pixels were considered bare soil (coded as "0").

2.3 Description of the Random Forest model

We used a Random Forest (RF) classifier designed to detect the presence of seagrass meadows on the lagoon bed based both on spectral and non-spectral information. Random Forest modelling is an ensemble learning algorithm that uses the results of a large number of decision trees (Ho, 1995). This class of algorithms is being used more frequently in remote sensing classification problems in general (Pal, 2005; Belgiu and Drăgu, 2016) and in seagrass detection in particular (Table 1). RF classifiers are trained to predict a set of target properties based on the values of a set of several features. Here, we train multiple classifiers to predict the absence (0) or presence (1) of seagrass in a given pixel, each with a different set of features, and using different training target values.

Figure 2. Tide and wind conditions used to select Landsat scenes at the stations of (a) Chioggia and (b) Saline. The red dotted line shows the high limit for tidal elevation relative to station datum: scenes where water level exceeds this elevation were not selected and are shown in red. Scenes where wind speed exceeded the limit condition are also shown in red.

Common features used to determine seagrass cover are the atmospherically corrected spectral reflectance values in the blue, red, green and sometimes near-infrared bands (see references in Table 1). When the seagrass is submerged, these reflectances at the water surface are not linearly connected to the reflectance of the bed. Indeed, water depth, organic and inorganic suspended sediment concentrations, water surface roughness, all contribute to define a complex relation between intrinsic seagrass reflectance and remote sensing at-water-surface reflectance. These parameters are rarely simultaneously measured or acquired to be used in a radiative transfer model (Lee et al., 1998; Lee and Carder, 2002) to infer the bed reflectance. In this contribution, we retrieve Red, Green, Blue and Near-Infrared band data from selected Landsat and Sentinel images without applying a water column correction: instead, we test how the Random Forest performs under unknown water column influence, simulating conditions where calibration of inversion methods is problematic. We further note that the band width for the NIR band is different for Landsat and Sentinel images: consequently, when interpreting the model's performance on test data, we separate the performance of the model on images sourced from Landsat or Sentinel images.

Given the uncertainties affecting the spectral reflectance properties that may be retrieved from remote sensing, it is reasonable to leverage all available information with the aim to reliably perform seagrass mapping across multiple acquisitions.

Figure 3. 2D frequency distribution of seagrass according to bathymetry relative to IGM reference and median sediment grain size (D_{50}). (a) seagrass distribution for the 2002 survey; (b) seagrass distribution for the 2017 survey.

Figure 3 shows the frequency distribution of seagrass meadows across bathymetry and median sediment grain size (D_{50}) for full-lagoon field surveys performed in 2002 (a) and 2017 (b). We notice that seagrass meadows in the Venice Lagoon occupy a quite characteristic range of bed elevations, mostly between $-2.1m$ and $-0.5m$ above datum, much narrower than the overall bathymetric range. Furthermore, the peak seagrass occurrence frequency does not correspond with the mode of the bathymetry (horizontal red lines), i.e. it is not located at the most commonly occurring bottom depth. This indicates that seagrass occurs within a preferential range of water depths, dictated by their need of access to light and by preferred flooding frequencies (Carruthers et al., 2002). Even more evidently, seagrass is preferentially found on fine sandy seabeds, where D_{50} ranges between $60\mu m$ and $150\mu m$, even though these are not the most common sediment sizes in the lagoon (visualised by vertical red lines). Whether such ranges of bathymetry and sediment size are purely the expression of preferred habitat or the product of self-organisation and eco-geomorphic feedbacks is not debated in this contribution. However, the existence of a

180 relationship between environmental parameters, such as bathymetry and D_{50}, and seagrass distribution may be of assistance to the developing effective algorithms for the detection of seagrass meadows.

A habitat constraint invariably translates into a constraint in geographical distribution. Figure 4 shows the geographical distribution of seagrass meadows across available field surveys described above, where each pixel expresses the cross-product Π_N in Equation 1:

$$\Pi_N = \frac{\sum_{i=0}^{N}\sum_{j\neq i}^{N} V_i \cdot V_j}{N*(N-1)} \tag{1}$$

185

where N is the number of surveys considered, and V_i is the array representing seagrass cover, with values comprised between 0 and 1. In both the full-lagoon and inlet surveys, large swathes of seagrass meadows harbour $\Pi = 1$ or $\Pi = 0$ (shown as empty data in Figure 4).

Figure 4. Map of Π calculated for (a) 5 full-lagoon surveys; (b-d) 6 inlet surveys, respectively at the inlets of Lido (b), Malamocco (c), and Chioggia (d). Additionally, the area appearing blurred in (d) represents the map of Π for all surveys plus 25 manually classified images.

Figure 4 corroborates the notion that preferred habitats, shown simply in Figure 3, constrain the geographical range of sea-grass meadows in the Venice Lagoon. The North and Central lagoon host patchy, disconnected, meadows, while the Southern lagoon hosts large interconnected meadows separated by navigation canals. This observation implies a degree of spatial auto-correlation in the presence of seagrass meadows, which may be explained by mechanisms of seagrass patch development: these are in general driven by environmental factors, such as differences in depth, nutrient fluxes, and salinity (Ghezzo et al., 2011; Sfriso et al., 2003), while clonal reproduction is the primary mechanism through which seagrass plants become established after an initial colonisation (McMahon et al., 2014) and sexual reproduction allows their spread over large distances.

The global Moran Index provides additional evidence of spatial autocorrelation in seagrass distributions. This index represents the degree of spatial auto-correlation (SAC) for a dataset, varying between -1 and 1, with -1 corresponding to evenly spaced patches, 0 being the value approached by a random distribution of elements, and 1 being attained if a space is divided in two halves of contiguous elements of the same value (Fan and Myint, 2014). This further indicates a strong positive auto-correlation that suggests a zonation of the lagoon in areas, with some being favourable to seagrass development and others not. Here, all full-lagoon surveys present a global Moran's Index greater than 0.8. As a result, the value of pixel coordinates, expressed as row and columns in the array, may represent a useful feature in seagrass detection. Because such a feature carries the risk of introducing confirmation bias in the results, its influence on prediction variability will be examined closely.

Figures 3 and 4 show that features other than spectral reflectance have potential to improve the performance of a classifier seeking to determine seagrass presence. To assess the impact of their inclusion among predictors on classification uncertainty, we train RF classifiers with a combination of features comprising of spectral, environmental, and location-based features, as shown in Figure 5. In order to be used simultaneously in the RF classifier, all features used were first normalised relative to the $5th$ and $95th$ percentile of their value in their respective zone (instead of the minimum and maximum). Because seagrass patches in the North and Central lagoon show different sizes and density than in the Southern lagoon, we divided the lagoon in two geographic zones at the Malamocco Inlet channel (see Figure 4) and adopted a different RF classifier in each zone. The predictors (features) used are spectral reflectances, bed elevation, and D_{50}. The RF classifiers, implemented in the Scikit-Learn package (Pedregosa et al., 2011), include 100 trees, each considering 3 input features with a maximum depth of 30 nodes. This RF classifier structure was chosen to avoid overfitting, which would limit the model's capacity to classify seagrass in the presence of a variable spectral response (caused by the presence of algae, local chlorophyll hotspots, etc.). The RF classifiers are trained using Landsat scenes taken on 14/09/2002 and 30/08/2017, with a split of training/validation/test ratio of 0.2/0.6/0.2, corresponding to field surveys conducted in the summers of 2002 and 2017. The ratio of bare/vegetated pixels in the 2002 survey is 16.1/1 in 1.1/1 in the Southern Lagoon; for the 2017 survey, it is 3.1/1 and 1/4.3 respectively. Hence, the 2002 survey provides a balanced training dataset in the Southern Lagoon; other surveys and zones are imbalanced in favour of bare ground in the North and Central Lagoon, and in favour of vegetation in the Southern Lagoon in 2017. In the discussion of our results, we examine how this imbalance may affect model predictions.

These survey dates were chosen over the remaining ones because the corresponding remote sensing acquisitions are not affected by the Landsat 7 Scan Line Correction (SLC) failure. For each survey, we train one model per each northern/southern

geographical zone, and per each combination of features, resulting in 8 RF models being trained in total. We then use these models to predict seagrass cover in 148 selected Landsat images (see Figure 2).

2.4 Time-based correction

Seagrass cover predictions are liable to instability due to variations in data quality, water absorption and scattering properties. The failure of the Landsat7 ETM scan line corrector on 31/05/2003 caused all subsequent Landsat7 ETM data to contain no-data strips, the position of which varies between images. To account for this discrepancy in data, we gave any no-data pixel at a given classification date t the classification it had in its previous classification $t-1$ and the following classification $t+1$, provided these were identical. If not, the pixel remains as no-data. Further instability in the predictions may be caused by classifications switching from bare to vegetated (or inversely) for a single image, for instance because of changes in seagrass or seabed reflectance caused by the intermittent presence of macroalgae or fishing activities. For instance, a pixel may appear bare for a set of contiguous scenes, then be classified as vegetated for one scene only, to return to a bare classification thereafter. Given the frequency of the scenes acquired, we consider it unreasonable to assume for seagrass patches to appear or disappear in isolated scenes. Indeed, we considered it unlikely for both a scouring event and subsequent full recovery to occur within less than 5 months, which corresponds to the largest gap between images. Instead, these abrupt changes in seagrass classifications may be caused by the apparition or disappearance of algal patches, which appear similar to seagrass in the visible and infrared bands but, lacking a rooted anchor to the seabed, are more mobile than seagrass. Consequently, we applied the following post-processing correction rule: any pixel being classified in a scene at time t differently from classifications in scenes $t-2$, $t-1$, $t+1$, and $t+2$ (provided these are identical), is given the opposite classification. Finally, given the resolution of Landsat images, isolated patches of less than 4 pixels in surface area, whether they be bare or vegetated, are switched to the dominant classification around them. These corrected sets of predictions represent another set of 8 predictions to validate (see Figure 5).

Figure 5. Workflow of the study, depicting the different features used (top), the target surveys and the year in which they were performed (centre); at the bottom, the successive training, prediction, correction and validation steps of the models are described.

2.5 Definition of model performance

For binary classifications such as the one performed here, model performance is quantified by use of the numbers of True

245 Positives (TP), True Negatives (TN), False Positives (FP) and False Negative (FN).

A global accuracy metric is defined as the ratio of true classifications ($TP + TN$) over the total number of pixels, a ratio often referred to as Overall Accuracy in non-binary classification problems (OA, see Table 1). In the Venice Lagoon, the presence of large areas of bare tidal flat relative to seagrass meadow area implies that OA is biased toward the correct prediction of bare tidal flats, rather than toward the correct prediction of seagrass meadows (having a much smaller total area). Hence, Sensitivity

250 (S) (Equation 2), and Precision (P)(Equation 3), give a measure of the model's performance that better fits our purpose, by eliminating TN:

$$S = \frac{TP}{TP + FN} \tag{2}$$

$$P = \frac{TP}{TP + FP} \tag{3}$$

S can be construed as a measure of the model's capacity to identify existing seagrass meadows. In non-binary problems such as those described in Table 1, S becomes User's Accuracy (UA) and is specific to each class. Conversely, P reflects the model's capacity not to include bare seafloor in the detected seagrass meadows, and becomes Producer's Accuracy (PA) in non-binary problems. These metrics may be combined through their harmonic mean $F1$ (Dice, 1945; Sorensen, 1948), defined in Equation 4:

$$F1 = 2 \cdot \frac{S \cdot P}{S + P} \tag{4}$$

The F1 score increases non-linearly but symmetrically with S and P, allowing us to measure the model's performance through a single metric. Contrary to the OA accuracy, F1 does not include the term TN, and is therefore not affected by the presence of extensive areas unequivocally classified as tidal flats: as such, this metric is more sensitive to changes in the detection of positives. The F1 score is used in the results section to describe the performance of the classifier, which we test on full-lagoon and inlet surveys as shown in Figure 4.

3 RESULTS

3.1 Effect of added features

In this section, we describe the performance of the RF classifiers in all 8 training scenarios before applying the time-based correction. Figure 6 shows this performance expressed as the F1 score.

Figure 6. F1 score of all models trained, tested on lagoon (full circles) and inlet (empty circles) surveys performed on the years indicated on the x-axis. Black markers indicate models trained only with spectral features. The models tested were trained in the North-Central zone for the 2002 (a) and 2017 (b) surveys, and in the Southern zone for the 2002 (c) and 2017 (d) surveys.

Figure 6 highlights the different behaviours of models trained with the 2002 survey (a,c) with respect to those trained with the 2017 survey (b,d). We first examine the differences in performance between models using only spectral features, all trained on full-lagoon data and tested on either full lagoon data (full circles) or inlet surveys (empty circles). Tests on full-lagoon data have generally lower F1 scores than tests on inlet surveys, particularly in 2017-trained models. This decreased performance on larger training datasets can be explained by slightly lower sensitivity values (Figure A3) and significantly lower precision values (Figure A2): this means that on test datasets including the full lagoon, models tended to more consistently classify bare ground as vegetated. This is a natural effect of testing on the full lagoon, where large areas, specifically in the North-Central area, are bare and leave an opportunity for error in the prediction.

Models using only spectral features (black) perform very differently than those including either environmental (blue, red) or spatial (green, red) features when trained on a 2002 survey. This is not the case if trained on the 2017 survey. Indeed, the addition of extra features to a 2002-trained model has a positive effect on the F1 score for most test instances (with exceptions in the North-Central zone), with the addition of location features having the greater effect; in contrast it has a slightly negative influence on most 2017-trained models. Tests where full lagoon surveys are less likely to over-identify vegetated areas (2002-trained models), are therefore more positively affected by the additional features. This indicates that the inclusion among the features of spatial position and environmental features produces large potential benefits, without generating significant negative effects on performance. Such advantages seem consistent as the same model formulation is tested across different images.

Decomposing this influence into the effects of Sensitivity and Precision (Figures A2 and A3), we note that improvements occur mostly on the former, while the increase in precision is small (for 2002-trained models) or even negative (for 2017-trained models). In general, Figures A2 and A3 show that 2002-trained models generally have higher precision but lower sensitivity values than 2017-trained models, indicating a tendency of the former to 'miss' vegetated areas while the latter will tend to overestimate the extent of seagrass meadows. In the Southern zone, where most seagrass meadows are located, 2017-trained models using only spectral features perform significantly better than 2002-trained models. 2017-trained models also perform consistently better when tested on inlet surveys rather than lagoon surveys, suggesting that false predictions lie outside the inlet areas. Conversely, 2002-trained models in the Southern zone benefit the most from the addition of environment and coordinate features, improving F1 scores from under 0.5 to up to 0.9. Because the North-Central zone harbours much less extensive seagrass than the Southern zone, F1 scores are more difficult to evaluate in this region.

Figure 7. Proportion of correct predictions of a 2002-trained model using spectral features only, tested on all surveys (lagoon, inlets and digitised meadows).

Figure 8. Proportion of correct predictions of a 2002-trained model all described features, tested on all surveys (lagoon, inlets and digitised meadows).

295   Figures 7 and 8 demonstrate visually the effect of location features on model behaviour, providing an overview of the performances of a 2002-trained model on all other training data combined. Each figure maps, for each pixel of the full lagoon and in more detail for the 3 inlets, the proportion of test surveys for which a given pixel is correctly classified, whether bare or vegetated. Because not all pixels are associated with the same number of surveys, color contrast is variable, with starker contrast appearing in areas where fewer surveys exist. Figure 7 shows the performance of a model using only spectral

features, whereas Figure 8 shows that of a model using both environmental and location features. The comparison of these two figures, with Figure 4 as a reference, reveals several points of interest regarding the effect of the additional features on model performance. In both maps, some areas are consistently and correctly classified as bare: for example, in the north-westernmost area of the lagoon, correct prediction rates are equal to 1 over large surfaces. Such areas are spectrally unambiguous, with a relatively high seabed and light sediment which is never mistaken for seagrass by the model. Conversely, areas that are vegetated in at least one survey are rarely correctly classified as such in all tests (i.e. the proportion of correct predictions is below 1), particularly when using only spectral features: from this we deduce that seagrass, if confused by the model with those of bare ground, exhibits low separation between its spectral properties and that of bare ground in the bands used. This is particularly true in the Southern Lagoon, where the water column is generally thicker. Furthermore, when using only spectral features, maps of correct prediction rates appear "grainy": this reflects irregularities in reflectance on the seabed or in seagrass patches, irregularities which cause local misclassifications. Irregularities are significantly reduced when adding environmental and location features. With fewer local misclassifications, models using these additional features generate more cohesive seagrass meadows: consequently, applying these models to monitor seagrass meadow evolution in time are less likely to erroneously predict changes inside the meadows, thus reducing errors in surface area change. The reduction in prediction "grain" also enhances, in Figure 8, wide swathes of lower correct prediction rates: these swathes are an artifact of the ETM Scan Line Correction failure, and are unclassified in some images. It is interesting to compare Figures 7 and 8, obtained with a 2002-trained model with a relatively well balanced training data, to Figures A4 and A5, which use less balanced training data. In these figures, large areas are consistently misclassified regardless of features used, attesting to an inadequate training dataset. In such a case, the addition of features has very little effect on model performance, as previously shown in Figure 6.

3.2 Effect of time-based correction

Figure 9 demonstrates the effect of the time-based correction process described in Section 2.4 on correct prediction rates, complementing Figures 7 and 8. It showcases the increase in the rates of correct prediction at almost all points of the map brought by this correction, with the notable exception of areas for which correct prediction rates were already below 50%. This is a direct consequence of the method of the time-based correction, which confirms classifications through time even if they are incorrect. Such an effect is unfavorable for models that perform poorly before correction, as showcased by Figure A6, where large areas where correct predictions occurred in less than 50% of tests dropped to 0. This further highlights the fact that models trained on imbalanced training data are ill-suited for the modifications proposed in this contribution. It also shows the elimination of swathes of lower rates through unclassified data, as it assumes continuity of classification between scenes.

Figure 9. Proportion of correct predictions of a 2002-trained model using all described features and after time-based correction, tested on all surveys (lagoon, inlets and digitised meadows).

Figure 10 examines the effect of the time-based correction process described in Section 2.4 on the F1 score of all tested models.

Figure 10. Comparison of F1 scores before and after time-based correction (respectively left and right of vertical bars), tested on lagoon (full circles) and inlet (empty circles) surveys. The models tested were trained in the North-Central zone for the 2002 (a) and 2017 (b) surveys, and in the Southern zone for the 2002 (c) and 2017 (d) surveys.

In the North-Central zone (a, b), no obvious pattern in the the change in F1 after correction is detected. In the Southern zone (c, d), however, both 2002-trained models and 2017-trained models respond in a discernible pattern to the application of the time-based correction: in 2002-trained models (c), models using only spectral or spectral and environmental features, which have a lower F1 score initially, generally see a decrease in F1 after correction, whether they are tested on the full lagoon or at the inlets. This coincides with the lower F1 scores for these models predictions. Conversely, models including known seagrass location as features, for which predictions initially have a higher F1 score, mostly see an increase of F1 scores. For these models, it appears that the F1 score after time-based correction has a stronger positive effect the higher the initial F1 score. For 2017-trained models (d), the addition of features having little effect, the time-based correction has a uniform effect regardless of features . Notably, whether for lagoon or inlet surveys, tests conducted during the period of the Landsat 7 SLC

failure display lower F1 values (see Figure 6(d)) as well as the largest positive change in F1 score after correction: this suggests

340   that the proportion of true positives reinstated through the time-based correction outweighs the proportion of false predictions added in the process.

4   Discussion

Several key issues pertaining to the reliability of seagrass detection arise from the examination of the performance of the models in Section 3: first, the strong disparity in performance, expressed through the F1 score, between models trained using

345   data from 2002 and 2017; then, the significant difference in the influence of environmental and, particularly, spatial features on F1 scores; finally, the opposing effects of time-based correction on the performance of different models. The behaviour of RF models being non-linear, we do not presume to identify a general relationship between the observations made in a single case study and the performance of seagrass cover predictions using a RF classifier. Nevertheless, we attempt to break down the influence of additional features and time-based corrections, using the Southern zone, where most seagrass is found,

350   as a testing ground. Figure 11 shows the relative importance of features used in each RF classifier used, where location features dominate, when present, for both 2002-trained and 2017-trained models. In all scenarios, the red band is the most important spectral band for 2017-trained models. As this band is particularly sensitive to suspended sediment concentration, we may surmise that its high importance could impede classification performance, particularly if turbidity is not accounted for in the classification. Conversely, the near-infrared band shares the highest importance among spectral features with the

355   green band.Given the sensitivity of the NIR band to suspended chlorophyll concentrations, the importance of this band may be conceived as a potential hindrance to the performance of the RF. We note however that in previous iterations of the RF using only the RGB bands, performance was not only lower after adding positional and environmental features and time-based corrections, but also before the applications of these modifications, despite the difference in band width between Landsat7 and Landsat8; This disparity may contribute to the diverging behaviours of the models trained on 2002 or 2017 data.

Figure 11. Relative importance of each feature used in models trained with 2002 and 2017 data

360   In Section 1, we mentioned the difficulty of producing consistent seagrass cover predictions at a high frequency. Figure 12 showcases the potential use of location and environmental features to improve the reliability of seagrass cover predictions, demonstrated on a 2002-trained model. Panels (a-d) are each a map of the success rate of seagrass cover predictions for each pixel near Chioggia Inlet, shown in yellow in Figure A1, tested on 36 reference datasets from surveyed and digitised seagrass

cover. In each panel, R represents the average success rate. In dark red, panels (a-d) show the outlines of vegetated patches in
365   the summer 2002 survey. In panels (a,b), where only spectral features were used, we observe that pixels with lower prediction
success rates overlap with those with higher occurrence rates, but not necessarily with the presence of seagrass in the summer
2002 survey. Panels (c,d), both of which include location features as well as environmental features, experience notable increase
in prediction success rates in these regions. Notably, increases in success rate match areas of high Π value (see Figure 4(d)),
suggesting that where spectral features only did not detect the presence of seagrass, models with all features did. Furthermore,
370   we note that the implementation of the time-based correction shown has little effect on R when using only spectral features
(b) but causes an increase when other features are used. This is consistent with our previous observation that the time-based
correction mostly improves predictions of higher initial quality.

Figure 12. (a-d) Map of the proportion of surveys correctly identified for 36 surveys and digitisations combined. R represents the average
value across all mapped pixels. Red outlines show the extent of seagrass patches in the summer 2002 survey; (e) Surface area of seagrass
predicted by surveys framed in (c,d), filled with the RMSE value. Black dots indicate surveyed or digitised surface area value.

In panel (e), we further note that seagrass surface area predictions decrease by up to a factor of 2 in the year 2000, suggesting that location features are not demonstrably impeding the model's capacity to predict seagrass surface area change. The root mean square error (RMSE) after implementing the time-based correction is 28.89ha, a 7.5% decrease in RMSE respective to predictions without the time-based correction, and amounts to 22% of the average seagrass surface area in the examined pixels. This value matches and exceeds half of the variation in seagrass surface area between most dates where vegetation cover is predicted. While the error in surface area prediction remains high for the purposes of monitoring high frequency changes in seagrass cover, it represents a significant improvement over models using only spectral features and no time-based corrections.

While the error in surface area prediction remains high for the purposes of monitoring high frequency changes in seagrass cover, the improvements made over models using only spectral features and without time-based corrections are significant. This result points to future research avenues in seagrass monitoring. First, performance increases achieved through incorporating coordinates as features validate the notion that observed seagrass meadows are a good proxy for favorable habitat. Second, performance improvements achieved through time-based corrections show that real-world dynamics that bound the growth and degradation of seagrass meadows positively influence remote sensing results. Together, these observations indicate that remote sensing methods would benefit from being coupled with habitat and ecological models. Ultimately, such coupled classification models may be able to detect the intra-and inter-annual variability observed in digitised seagrass cover: in large habitats such as the Venice Lagoon, these models would allow the identification of seagrass degradation events and quantify regrowth and colonisation at scales that are impractical to observe through fieldwork.

5   Conclusions

In this contribution, we implemented several random forest classifiers using various sets of features, supplemented by time-based corrections, to detect the spatial and temporal dynamics of seagrass meadows in the Venice Lagoon. We trained 8 such models using a combination of spectral data, bathymetry, median sediment grain size, and coordinates of known seagrass extent as features. 4 models were trained using data taken from field surveys and Landsat images of summer 2002, and 4 others with data taken in 2017.

We found that 2002-trained models and 2017- trained models responded differently to both the addition of out-of-image features and to the time-based correction. Adding location information was shown to significantly improve the $F1$ score without preventing the model from detecting variations in seagrass cover, but only for 2002-trained models. Examining the importance of different features in each of the models, we observed that 2002-trained models and 2017-trained models were under the dominating influence of seagrass location, when used, but otherwise did not share the same most important spectral features. This may be a reason for their discordant behaviour. Furthermore, the vote count, which expresses the probability of a given pixel to be seagrass according to a RF model, was generally more polarised toward extreme values in 2017-trained models. While not a root cause of the difference between the sets of models, it revealed the effect of using geographic location features on tree voting. This shows that true change in seagrass meadows can be detected by location-dependant models when

taking into account prior knowledge of seagrass location. Ultimately, accurately accounting for spatial auto-correlation will require the examination of more cases as well as a generally applicable formulation of its influence.

This contribution demonstrated the potential of mixing spatial auto-correlation patterns and time-series analysis with commonly used spatial detection methods, such as Random Forest classifiers to increase the performance of submerged vegetation detection methods. The positive effects of these modifications to standard methods have been shown to outweigh their potential "side-effects", although further research is required to generalize their influence. The resulting increased confidence in each seagrass cover map allows the generation of dense sequences of maps, through which the space-time dynamics of seagrass meadows may be described and connected to their governing environmental drivers. This, in turn, can inform ecological models, sediment transport simulations and ultimately feed into predictions of tidal basin response to environmental change.

Data availability. The satellite data used in this contribution are openly available on multiple platforms, including NASA's EarthExplorer (https://earthexplorer.usgs.gov/). The data concerning seagrass cover surveys, bathymetry and median sediment grain size are openly available via the Atlante della Laguna at http://cigno.atlantedellalaguna.it/maps. Tide and wind gauge data are openly available at https://www.comune.venezia.it/content/dati-dalle-stazioni-rilevamento.

Figure A1. Footprint of the inlet surveys of Lido, Malamocco and Chioggia (blues) and of the digitised patch (yellow). The coordinate system used is EPSG: 3003. Inset image: ©Google Earth

Figure A2. Precision score of all models trained, tested on lagoon (full circles) and inlet (empty circles) surveys performed on the years indicated on the x-axis. Black markers indicate models trained only with spectral features. The models tested were trained in the North-Central zone for the 2002 (a) and 2017 (b) surveys, and in the Southern zone for the 2002 (c) and 2017 (d) surveys.

Figure A3. Sensitivity score of all models trained, tested on lagoon (full circles) and inlet (empty circles) surveys performed on the years indicated on the x-axis. Black markers indicate models trained only with spectral features. The models tested were trained in the North-Central zone for the 2002 (a) and 2017 (b) surveys, and in the Southern zone for the 2002 (c) and 2017 (d) surveys.

Figure A4. Percentage of correct predictions of a 2017-trained model using only spectral features tested on all images (lagoon, inlets and additional digitisations combined).

Figure A5. Percentage of correct predictions of a 2017-trained model using all considered features tested on all images (lagoon, inlets and additional digitisations combined).

Figure A6. Percentage of correct predictions of a 2017-trained model using all features and the time-based correction tested on all images (lagoon, inlets and additional digitisations combined).

Table A1. Compilation of published works on seagrass detection from satellite data

Reference number	Reference
1	(Phinn et al., 2008)
2	(Pu et al., 2012)
3	(Lyons et al., 2012)
4	(Dekker et al., 2005)
5	(Wabnitz et al., 2008)
6	(Hossain et al., 2015)
7	(Misbari and Hashim, 2016)
8	(Topouzelis et al., 2018)
9	(Kovacs et al., 2018)
10	(Kohlus et al., 2020)
11	(Pu et al., 2012)
12	(Pu et al., 2012)
13	(Kovacs et al., 2018)
14	(Zoffoli et al., 2020)
15	(Traganos et al., 2018; Traganos and Reinartz, 2018)
16	(Kovacs et al., 2018)
17	(Phinn et al., 2008)
18	(Roelfsema et al., 2014)
19	(Phinn et al., 2008)
20	(Bakirman and Gumusay, 2020)
21	(Kovacs et al., 2018)
22	(O'Neill and Costa, 2013)
23	(Amran, 2017)

Table A2. Selected Landsat scenes with full-lagoon or inlet surveys

Lagoon surveys	LE07_L1TP_192028_20020914_20170128_01_T1
	LE07_L1TP_192028_20040903_20170119_01_T1
	LE07_L1TP_192028_20090901_20161218_01_T1
	LE07_L1TP_192028_20100904_20161212_01_T1
	LC08_L1TP_192028_20170830_20170914_01_T1
Inlet surveys	LE07_L1TP_192028_20080610_20161228_01_T1
	LE07_L1TP_192028_20090901_20161218_01_T1
	LE07_L1TP_192028_20100904_20161212_01_T1
	LE07_L1TP_192028_20111009_20161206_01_T1
	LE07_L1TP_192028_20120909_20161129_01_T1
	LC08_L1TP_192028_20130904_20170502_01_T1
	LC08_L1TP_192028_20140806_20170420_01_T1
	LC08_L1TP_192028_20150809_20170406_01_T1

Table A3. Selected Landsat scenes with digitised areas

Digitised scenes	LE07_L1TP_192028_19990906_20170217_01_T1
	LE07_L1TP_192028_20000316_20170213_01_T1
	LE07_L1TP_192028_20001127_20170209_01_T1
	LE07_L1TP_192028_20010911_20170203_01_T1
	LE07_L1TP_192028_20020117_20170201_01_T1
	LE07_L1TP_192028_20020322_20191106_01_T1
	LE07_L1TP_192028_20020914_20170128_01_T1
	LE07_L1TP_192028_20030325_20170214_01_T1
	LE07_L1TP_192028_20040428_20170121_01_T1
	LE07_L1TP_192028_20050720_20170113_01_T1
	LE07_L1TP_192028_20060213_20170110_01_T1
	LE07_L1TP_192028_20070216_20170104_01_T1
	LE07_L1TP_192028_20090104_20161223_01_T1
	LE07_L1TP_192028_20100328_20161215_01_T1
	LE07_L1TP_192028_20110502_20161210_01_T1
	LE07_L1TP_192028_20120214_20161203_01_T1
	LE07_L1TP_192028_20130216_20161126_01_T1
	LC08_L1TP_192028_20140331_20170424_01_T1
	LC08_L1TP_192028_20150113_20170414_01_T1
	LC08_L1TP_192028_20160116_20170405_01_T1
	LC08_L1TP_192028_20160928_20170321_01_T1
	LC08_L1TP_192028_20170408_20180523_01_T1
	LC08_L1TP_192028_20170830_20170914_01_T1
	LC08_L1TP_192028_20180326_20180404_01_T1
	LC08_L1TP_192028_20180630_20180716_01_T1
	LC08_L1TP_192028_20190225_20190309_01_T1
	LC08_L1TP_192028_20190905_20190917_01_T1

Author contributions. Conceptualization, G. Goodwin, L. Carniello, A. D'Alpaos, M. Marani and S. Silvestri; methodology, G. Goodwin, L. Carniello, A. D'Alpaos, M. Marani and S. Silvestri; software, G. Goodwin.; validation, G. Goodwin, L. Carniello, A. D'Alpaos, M. Marani and S. Silvestri; formal analysis, G. Goodwin; investigation, G. Goodwin; resources, M. Marani; data curation, G. Goodwin; writing— original draft preparation, G. Goodwin; writing—review and editing, G. Goodwin, L. Carniello, A. D'Alpaos, M. Marani and S. Silvestri;

420

visualization, G. Goodwin.; supervision, L. Carniello, A. D'Alpaos, M. Marani and S. Silvestri; project administration, M. Marani; funding acquisition, M. Marani. All authors have read and agreed to the published version of the manuscript.

425 *Competing interests.* Some authors are members of the editorial board of the current special issue "Monitoring coastal wetlands and the seashore with a multi-sensor approach". The peer-review process was guided by an independent editor, and the authors have also no other competing interests to declare.

Acknowledgements. This research was funded by CORILA under the project Venezia 2021 (grant CUP D51B02000050001).

References

430   Amos, C., Bergamasco, A., Umgiesser, G., Cappucci, S., CLoutier, D., DeNat, L., Flindt, M., Bonardi, M., and Cristante, S.: The stability of tidal flats in Venice Lagoon – the results of in-situ measurements using two benthic, annular flumes, Journal of Marine Systems, 51, https://doi.org/10.1002/esp.4599, 2004.

Amran, M. A.: Mapping seagrass condition using google earth imagery, Journal of Engineering Science and Technology Review, 10, 18–23, https://doi.org/10.25103/jestr.101.03, 2017.

435   Bakirman, T. and Gumusay, M. U.: Assessment of machine learning methods for seagrass classification in the mediterranean, Baltic Journal of Modern Computing, 8, 315–326, https://doi.org/10.22364/BJMC.2020.8.2.07, 2020.

Belgiu, M. and Drăgu, L.: Random forest in remote sensing: A review of applications and future directions, ISPRS Journal of Photogrammetry and Remote Sensing, 114, 24–31, https://doi.org/10.1016/j.isprsjprs.2016.01.011, 2016.

Biau, G. and Scornet, E.: A random forest guided tour, Test, 25, 197–227, https://doi.org/10.1007/s11749-016-0481-7, 2016.

440   Caffrey, J. M. and Kemp, W. M.: Seasonal and spatial patterns of oxygen production, respiration and root-rhizome release in Potamogeton perfoliatus L. and Zostera marina L., Aquatic Botany, 40, 109–128, https://doi.org/10.1016/0304-3770(91)90090-R, 1991.

Cam, L. L.: Maximum Likelihood: An Introduction, International Statistical Review / Revue Internationale de Statistique, 58, 153, https://doi.org/10.2307/1403464, 1990.

Carniello, L., Defina, A., and D'Alpaos, L.: Morphological evolution of the Venice lagoon: Evidence from the past and trend for the future,
445   Journal of Geophysical Research: Earth Surface, 114, 1–10, https://doi.org/10.1029/2008JF001157, 2009.

Carniello, L., Defina, A., and D'Alpaos, A.: Modeling sand-mud transport induced by tidal currents and wind waves in shallow microtidal basins: Application to the Venice Lagoon (Italy), Estuarine, Coastal and Shelf Science, https://doi.org/10.1016/j.ecss.2012.03.01, 2012.

Carniello, L., Silvestri, S., Marani, M., V, V., and Defina, A.: Sediment dynamics in shallow tidal basins: In situ observations, satellite retrievals, and numerical modeling in the Venice Lagoon, J. Geophys. Res. Earth Surf., 119, https://doi.org/10.1002/2013JF003015, 2014.

450   Carniello, L., D'Alpaos, A., Botter, G., and Rinaldo, A.: Statistical characterization of spatiotemporal sediment dynamics in the Venice lagoon, Journal of Geophysical Research F: Earth Surface, 121, 1049–1064, https://doi.org/10.1002/2015JF003793, 2016.

Carruthers, T., Dennison, W., Longstaff, B., Waycott, M., Abal, E., L, M., and Lee Long, W.: SEAGRASS HABITATS OF NORTHEAST AUSTRALIA: MODELS OF KEY PROCESSES AND CONTROLS, Bulletin of Marine Science, 71, 2002.

Collier, C. J. and Waycott, M.: Temperature extremes reduce seagrass growth and induce mortality, Marine Pollution Bulletin, 83, 483–490,
455   https://doi.org/10.1016/j.marpolbul.2014.03.050, 2014.

Costanza, R., D'Arge, R., de Groot, R., Farber, S., Grasso, M., Hannon, B., Limburg, K., Naeem, S., O'Neill, R. V., Paruelo, J., Raskin, R. G., Sutton, P., and van den Belt, M.: The value of the world's ecosystem services and natural capital, Nature, 387, 253–260, https://www-nature-com.ezproxy.royalroads.ca/articles/387253a0.pdf, 1997.

D'Alpaos, A., Lanzoni, S., Marani, M., and Rinaldo, A.: Landscape evolution in tidal embayments: Modeling the interplay of erosion,
460   sedimentation,and vegetation dynamics, Journal of Geophysical research, 112, https://doi.org/10.1029/2006JF000537, 2007.

Dekker, A. G., Brando, V. E., and Anstee, J. M.: Retrospective seagrass change detection in a shallow coastal tidal Australian lake, Remote Sensing of Environment, 97, 415–433, https://doi.org/10.1016/j.rse.2005.02.017, 2005.

Dice, L. R.: Measures of the amount of ecologic association between species ecology, Ecology, 26, 297–302, 1945.

Fan, C. and Myint, S.: A comparison of spatial autocorrelation indices and landscape metrics in measuring urban landscape fragmentation,
465   Landscape and Urban Planning, 121, 117–128, https://doi.org/10.1016/j.landurbplan.2013.10.002, 2014.

Gamain, P., Feurtet-Mazel, A., Maury-Brachet, R., Auby, I., Pierron, F., Belles, A., Budzinski, H., Daffe, G., and Gonzalez, P.: Can pesticides, copper and seasonal water temperature explain the seagrass Zostera noltei decline in the Arcachon bay?, Marine Pollution Bulletin, 134, 66–74, https://doi.org/10.1016/j.marpolbul.2017.10.024, 2018.

Ganthy, F., Soissons, L., Sauriau, P. G., Verney, R., and Sottolichio, A.: Effects of short flexible seagrass Zostera noltei on flow, erosion and deposition processes determined using flume experiments, Sedimentology, 62, 997–1023, https://doi.org/10.1111/sed.12170, 2015.

GDAL/OGR contributors: GDAL/OGR Geospatial Data Abstraction software Library, Open Source Geospatial Foundation, https://gdal.org, 2021.

Ghezzo, M., Sarretta, A., Sigovini, M., Guerzoni, S., Tagliapietra, D., and Umgiesser, G.: Modeling the inter-annual variability of salinity in the lagoon of Venice in relation to the water framework directive typologies, Ocean and Coastal Management, 54, 706–719, https://doi.org/10.1016/j.ocecoaman.2011.06.007, 2011.

Greiner, J. T., McGlathery, K. J., Gunnell, J., and McKee, B. A.: Seagrass Restoration Enhances "Blue Carbon" Sequestration in Coastal Waters, PLoS ONE, 8, 1–8, https://doi.org/10.1371/journal.pone.0072469, 2013.

Guerzoni, S. and Tagliapietra, D.: Atlante della laguna, Venezia tra terra e mare, https://doi.org/10.1002/esp.4599, 2006.

Hansen, J. C. and Reidenbach, M. A.: Seasonal Growth and Senescence of a Zostera marina Seagrass Meadow Alters Wave-Dominated Flow and Sediment Suspension Within a Coastal Bay, Estuaries and Coasts, 36, 1099–1114, https://doi.org/10.1007/s12237-013-9620-5, 2013.

Hendriks, I. E., Sintes, T., Bouma, T. J., and Duarte, C. M.: Experimental assessment and modeling evaluation of the effects of the seagrass Posidonia oceanica on flow and particle trapping, Marine Ecology Progress Series, 356, 163–173, https://doi.org/10.3354/meps07316, 2008.

Hendriks, I. E., Bouma, T. J., Morris, E. P., and Duarte, C. M.: Effects of seagrasses and algae of the Caulerpa family on hydrodynamics and particle-trapping rates, Marine Biology, 157, 473–481, https://doi.org/10.1007/s00227-009-1333-8, 2010.

Ho, T. K.: Random Decision Forests Tin Kam Ho Perceptron training, Proceedings of 3rd International Conference on Document Analysis and Recognition, 1, 278–282, https://ieeexplore.ieee.org/abstract/document/598994/, 1995.

Hossain, M. S., Bujang, J. S., Zakaria, M. H., and Hashim, M.: The application of remote sensing to seagrass ecosystems: an overview and future research prospects, International Journal of Remote Sensing, 36, 61–113, https://doi.org/10.1080/01431161.2014.990649, 2014.

Hossain, M. S., Bujang, J. S., Zakaria, M. H., and Hashim, M.: Application of Landsat images to seagrass areal cover change analysis for Lawas, Terengganu and Kelantan of Malaysia, Continental Shelf Research, 110, 124–148, https://doi.org/10.1016/j.csr.2015.10.009, 2015.

Ilori, C. O., Pahlevan, N., and Knudby, A.: Analyzing performances of different atmospheric correction techniques for Landsat 8: Application for coastal remote sensing, Remote Sensing, 11, 1–20, https://doi.org/10.3390/rs11040469, 2019.

Johnson, R. A., Gulick, A. G., Bolten, A. B., and Bjorndal, K. A.: Blue carbon stores in tropical seagrass meadows maintained under green turtle grazing, Scientific Reports, 7, 1–11, https://doi.org/10.1038/s41598-017-13142-4, 2017.

Kohlus, J., Stelzer, K., Müller, G., and Smollich, S.: Mapping seagrass (Zostera) by remote sensing in the Schleswig-Holstein Wadden Sea, Estuarine, Coastal and Shelf Science, 238, https://doi.org/10.1016/j.ecss.2020.106699, 2020.

Kovacs, E., Roelfsema, C., Lyons, M., Zhao, S., and Phinn, S.: Seagrass habitat mapping: How do landsat 8 OLI, sentinel-2, ZY-3A, and worldview-3 perform?, Remote Sensing Letters, 9, 686–695, https://doi.org/10.1080/2150704X.2018.1468101, 2018.

Kutser, T., Vahtmäe, E., Roelfsema, C. M., and Metsamaa, L.: Photo-library method for mapping seagrass biomass, Estuarine, Coastal and Shelf Science, 75, 559–563, https://doi.org/10.1016/j.ecss.2007.05.043, 2007.

Lee, Z. and Carder, K. L.: Effect of spectral band numbers on the retrieval of water column and bottom properties from ocean color data, Applied Optics, 41, 2191, https://doi.org/10.1364/ao.41.002191, 2002.

Lee, Z., Carder, K. L., Mobley, C. D., Steward, R. G., and Patch, J. S.: Hyperspectral remote sensing for shallow waters I A semianalytical model, Applied Optics, 37, 6329, https://doi.org/10.1364/ao.37.006329, 1998.

Lyons, M. B., Phinn, S. R., and Roelfsema, C. M.: Long term land cover and seagrass mapping using Landsat and object-based image analysis from 1972 to 2010 in the coastal environment of South East Queensland, Australia, ISPRS Journal of Photogrammetry and Remote Sensing, 71, 34–46, https://doi.org/10.1016/j.isprsjprs.2012.05.002, 2012.

Marani, M an D'Alpaos, A., Lanzoni, S., Carniello, L., and Rinaldo, A.: The importance of being coupled: Stable states and catastrophic shifts in tidal biomorphodynamics, Journal of Geophysical research, 115, https://doi.org/10.1029/2009JF001600, 2010.

Marani, M., D'Alpaos, A., Lanzoni, S., Carniello, L., and Rinaldo, A.: Biologically-controlled multiple equilibria of tidal landforms and the fate of the Venice lagoon, Journal of machine learning research, 34, https://doi.org/10.1029/2007GL030178, 2007.

Marani, M., Da Lio, C., and D'Alpaos, A.: Vegetation engineers marsh morphology through multiple competing stable states, Proceedings of the National Academy of Science, 110, 3259–3263, https://doi.org/10.1016/j.rse.2006.10.007, 2011.

McKenzie, L., Nordlund, L. M., Jones, B. L., Cullen-Unsworth, L. C., Roelfsema, C. M., and Unsworth, R.: The global distribution of seagrass meadows, Environmental Research Letters, https://doi.org/10.1088/1748-9326/ab7d06, 2020.

McMahon, K., van Dijk, K. J., Ruiz-Montoya, L., Kendrick, G. A., Krauss, S. L., Waycott, M., Verduin, J., Lowe, R., Statton, J., Brown, E., and Duarte, C.: The movement ecology of seagrasses, Proceedings of the Royal Society B: Biological Sciences, 281, https://doi.org/10.1098/rspb.2014.0878, 2014.

Misbari, S. and Hashim, M.: Change detection of submerged seagrass biomass in shallow coastalwater, Remote Sensing, 8, https://doi.org/10.3390/rs8030200, 2016.

Nicholls, R. J., Hanson, S. E., Lowe, J. A., Slangen, A. B., Wahl, T., Hinkel, J., and Long, A. J.: Integrating new sea-level scenarios into coastal risk and adaptation assessments: An ongoing process, Wiley Interdisciplinary Reviews: Climate Change, 12, 1–27, https://doi.org/10.1002/wcc.706, 2021.

Noble, W. S.: What is a support vector machine?, Nature Biotechnology, 24, 1565–1567, https://doi.org/10.1038/nbt1206-1565, 2006.

Nuova-Technital, C. V.: Attività di aggiornamento del piano degli interventi per il recupero morfologico in applicazione della delibera del Consiglio dei Ministri del 15.03.01, Studi integrative, Rapporto finale—Modello morfologico a maglia curvilinear: Relazione di sintesi, 2007.

O'Neill, J. D. and Costa, M.: Mapping eelgrass (Zostera marina) in the Gulf Islands National Park Reserve of Canada using high spatial resolution satellite and airborne imagery, Remote Sensing of Environment, 133, 152–167, https://doi.org/10.1016/j.rse.2013.02.010, 2013.

Pal, M.: Random forest classifier for remote sensing classification, International Journal of Remote Sensing, 26, 217–222, https://doi.org/10.1080/01431160412331269698, 2005.

Pedersen, O., Colmer, T. D., Borum, J., Zavala-Perez, A., and Kendrick, G. A.: Heat stress of two tropical seagrass species during low tides - impact on underwater net photosynthesis, dark respiration and diel in situ internal aeration, New Phytologist, 210, 1207–1218, https://doi.org/10.1111/nph.13900, 2016.

Pedregosa, F., Varoquaux, G., Gramfort, A., Michel, V., Thirion, B., Grisel, O., Blondel, M., Prettenhofer, P., Weiss, R., Dubourg, V., et al.: Scikit-learn: Machine learning in Python, Journal of machine learning research, 12, 2825–2830, 2011.

Phinn, S., Roelfsema, C., Dekker, A., Brando, V., and Anstee, J.: Mapping seagrass species, cover and biomass in shallow waters: An assessment of satellite multi-spectral and airborne hyper-spectral imaging systems in Moreton Bay (Australia), Remote Sensing of Environment, 112, 3413–3425, https://doi.org/10.1016/j.rse.2007.09.017, 2008.

Pu, R., Bell, S., Meyer, C., Baggett, L., and Zhao, Y.: Mapping and assessing seagrass along the western coast of Florida using Landsat TM and EO-1 ALI/Hyperion imagery, Estuarine, Coastal and Shelf Science, 115, 234–245, https://doi.org/10.1016/j.ecss.2012.09.006, 2012.

Roelfsema, C. M., Lyons, M., Kovacs, E. M., Maxwell, P., Saunders, M. I., Samper-Villarreal, J., and Phinn, S. R.: Multi-temporal mapping of seagrass cover, species and biomass: A semi-automated object based image analysis approach, Remote Sensing of Environment, 150, 172–187, https://doi.org/10.1016/j.rse.2014.05.001, 2014.

Russell, B. D., Connell, S. D., Uthicke, S., Muehllehner, N., Fabricius, K. E., and Hall-Spencer, J. M.: Future seagrass beds: Can increased productivity lead to increased carbon storage?, Marine Pollution Bulletin, 73, 463–469, https://doi.org/10.1016/j.marpolbul.2013.01.031, 2013.

Schmidt, G., Jenkerson, C., Masek, J., Vermote, E., and Gao, F.: Landsat Ecosystem Disturbance Adaptive Processing System (LEDAPS) algorithm description, Tech. rep., 2013.

Sfriso, A. and Francesco Ghetti, P.: Seasonal variation in biomass, morphometric parameters and production of seagrasses in the lagoon of Venice, Aquatic Botany, 61, 207–223, https://doi.org/10.1016/S0304-3770(98)00064-3, 1998.

Sfriso, A., Birkemeyer, T., and Ghetti, P. F.: Benthic macrofauna changes in areas of Venice lagoon populated by seagrasses or seaweeds, Marine Environmental Research, 52, 323–349, https://doi.org/10.1016/S0141-1136(01)00089-7, 2001.

Sfriso, A., Facca, C., Ceoldo, S., Silvestri, S., and Ghetti, P. F.: Role of macroalgal biomass and clam fishing on spatial and temporal changes in N and P sedimentary pools in the central part of the Venice lagoon, Oceanologica Acta, 26, 3–13, https://doi.org/10.1016/S0399-1784(02)00008-7, 2003.

Smith, R. D., Pregnall, A. M., and Alberte, R. S.: Effects of anaerobiosis on root metabolism of Zostera marina (eelgrass): implications for survival in reducing sediments, Marine Biology, 141, 131–141, 1988.

Sorensen, T. A.: A method of establishing groups of equal amplitude in plant sociology based on similarity of species and its application to analyses of the vegetation on Danish commons, Biol. Skar, 5, 1–34, 1948.

Syvitski, J. P. and Kettner, A.: Sediment flux and the anthropocene, Philosophical Transactions of the Royal Society A: Mathematical, Physical and Engineering Sciences, 369, 957–975, https://doi.org/10.1098/rsta.2010.0329, 2011.

Tommasini, L., Carniello, L., Ghinassi, M., Roner, M., and D'Alpaos, A.: Changes in the wind-wave field and related saltmarsh lateral erosion: inferences from the evolution of the Venice Lagoon in the last four centuries, Earth Surf. Process. Landforms, https://doi.org/10.1002/esp.4599, 2019.

Topouzelis, K., Makri, D., Stoupas, N., Papakonstantinou, A., and Katsanevakis, S.: Seagrass mapping in Greek territorial waters using Landsat-8 satellite images, International Journal of Applied Earth Observation and Geoinformation, 67, 98–113, https://doi.org/10.1016/j.jag.2017.12.013, 2018.

Traganos, D. and Reinartz, P.: Machine learning-based retrieval of benthic reflectance and Posidonia oceanica seagrass extent using a semi-analytical inversion of Sentinel-2 satellite data, International Journal of Remote Sensing, 39, 9428–9452, https://doi.org/10.1080/01431161.2018.1519289, 2018.

Traganos, D., Aggarwal, B., Poursanidis, D., Topouzelis, K., Chrysoulakis, N., and Reinartz, P.: Towards global-scale seagrass mapping and monitoring using Sentinel-2 on Google Earth Engine: The case study of the Aegean and Ionian Seas, Remote Sensing, 10, 1–14, https://doi.org/10.3390/rs10081227, 2018.

Venier, C., D'Alpaos, A., and Marani, M.: Evaluation of sediment properties using wind and turbidity observations in the shallow tidal areas of the Venice Lagoon, Journal of Geophysical Research: Earth Surface, 119, 1604–1616, https://doi.org/10.1002/2013JF003019, 2011.

Volpe, V., Silvestri, S., and Marani, M.: Remote sensing retrieval of suspended sediment concentration in shallow waters, Remote Sensing of Environment, 115, 44–54, https://doi.org/10.1016/j.rse.2010.07.013, 2011.

580   Wabnitz, C. C., Andréfouët, S., Torres-Pulliza, D., Müller-Karger, F. E., and Kramer, P. A.: Regional-scale seagrass habitat mapping in the Wider Caribbean region using Landsat sensors: Applications to conservation and ecology, Remote Sensing of Environment, 112, 3455–3467, https://doi.org/10.1016/j.rse.2008.01.020, 2008.

Wang, C., Menenti, M., Stoll, M.-P., Belluco, E., and Marani, M.: Mapping mixed vegetation communities in salt marshes using airborne spectral data, Remote Sensing of Environment, 107, 559–570, https://doi.org/10.1016/j.rse.2006.10.007, 2007.

585   Widdows, J., Pope, N. D., Brinsley, M. D., Asmus, H., and Asmus, R. M.: Effects of seagrass beds (Zostera noltii and Z. marina) on near-bed hydrodynamics and sediment resuspension, Marine Ecology Progress Series, 358, 125–136, https://doi.org/10.3354/meps07338, 2008.

Yang, Z., D'Alpaos, A., Marani, M., and Silvestri, S.: Assessing the Fractional Abundance of Highly Mixed Salt-Marsh Vegetation Using Random Forest Soft Classification, Remote Sensing, 12, https://doi.org/10.3390/rs12193224, 2020.

Yousefi Lalimi, F., Marani, M., Hefferman, J., D'Alpaos, A., and Murray, B.: Watershed and ocean controls of salt marsh extent and resilience,
590   Earth Surface Processes and Landforms, 45, 2825–2830, https://doi.org/10.1002/esp.4817, 2020.

Zhou, X., Marani, M., Albertson, J., and Silvestri, S.: Hyperspectral and Multispectral Retrieval of Suspended Sediment in Shallow Coastal Waters Using Semi-Analytical and Empirical Methods, Remote Sensing, 9, https://doi.org/10.3390/rs9040393, 2017.

Zoffoli, M. L., Gernez, P., Rosa, P., Le Bris, A., Brando, V. E., Barillé, A. L., Harin, N., Peters, S., Poser, K., Spaias, L., Peralta, G., and Barillé, L.: Sentinel-2 remote sensing of Zostera noltei-dominated intertidal seagrass meadows, Remote Sensing of Environment, 251,
595   112 020, https://doi.org/10.1016/j.rse.2020.112020, 2020.