

Impact of urbanization on fine particulate matter concentrations over central Europe

Peter Huszar, Alvaro Patricio Prieto Perez, Lukáš Bartík, Jan Karlický, and Anahi Villalba-Pradas

Department of Atmospheric Physics, Faculty of Mathematics and Physics, Charles University, Prague, V Holešovičkách 2, 18000, Prague 8, Czech Republic

Correspondence: P. Huszar (peter.huszar@matfyz.cuni.cz)

Abstract. The rural-to-urban transformation (RUT) is the process of turning rural or natural land-surface into urban one which brings important modifications in the surface causing well know effects like the urban heat island (UHI), reduced wind-speeds, increased boundary layer heights and so on. Moreover, with concentrated human activities RUT introduces new emission source which greatly perturbs the local and regional air-pollution. Particulate matter (PM) is one of key pollutants responsible for deterioration of urban air-quality and is still a major issue in European cities with frequent exceedances of limit values. Here we introduce a regional chemistry-climate model (regional climate model RegCM coupled offline to chemistry transport model CAMx) study which quantifies how the process of RUT modified the PM concentrations over central Europe including the underlying controlling mechanisms that contribute to the final PM pollution. Apart from the two most studied ones, i) the urban emissions and ii) the urban canopy meteorological forcing (UCMF, i.e. the impact of modified meteorological conditions on air-quality) we analyze also two less studied contributors to the RUT's impact on air-quality: iii) the impact of modified dry-deposition velocities (DV) due to urbanized land-use and iv) the impact of modified biogenic emissions due to urbanization induced vegetation modifications and changes in meteorological conditions which affect these emissions. To calculate the magnitude of each of these RUT contributors, we perform a cascade of simulations where each contributor is added one-by-one to the reference state while focus is given on PM_{2.5} (particulate matter with diameter less than 2.5 μm). Its primary and secondary components, namely primary elemental carbon (PEC), sulphates (PSO₄), nitrates (PNO₃), ammonium (PNH₄) and secondary organic aerosol (SOA) are analyzed too.

The validation using surface measurements showed a systematic negative bias for the total PM_{2.5} which is probably caused by underestimated organic aerosol and partly by the negative bias in sulphates and elemental carbon. For ammonium and nitrates, the underestimation is limited to the warm season while for winter, the model tends to overestimate their concentrations. However, in each case, the annual cycle is reasonably captured.

We evaluated the RUT impact on PM_{2.5} over a sample of 19 central European cities and found that the total impact of urbanization is about 2-3 and 1-1.5 $\mu\text{g m}^{-3}$ in winter and summer, respectively. This is mainly driven by the impact of emissions alone causing a slightly higher impact (1.5-3.5 and 1.2-2 $\mu\text{g m}^{-3}$ in winter and summer), while the effect of UCMF was a decrease at about 0.2-0.5 $\mu\text{g m}^{-3}$ (in both seasons) which was mainly controlled by enhanced vertical eddy-diffusion while increases were modelled over rural areas. The transformation of rural land-use into urban one caused an increase of dry-deposition velocities by around 30-50% which alone resulted in a decrease of PM_{2.5} by 0.1-0.25 $\mu\text{g m}^{-3}$ in both seasons.

Finally, the impact of biogenic emission modifications due to modified land-use and meteorological conditions caused a decrease of summer PM_{2.5} of about 0.1 μgm^{-3} while the winter effects were negligible. The total impact of urbanization on aerosol components is modelled to be (values indicate winter and summer averages) 0.4 and 0.3 μgm^{-3} for PEC, 0.05 and 0.02 μgm^{-3} for PSO₄, 0.1 and 0.08 μgm^{-3} for PNO₃, 0.04 and 0.03 μgm^{-3} for PNH₄ and 0 and 0.05 μgm^{-3} for SOA. The main contributor of each of these components was the impact of emissions which was usually larger than the total impact due to the fact that UCMF counteracted with a decrease. For each aerosol component the impact of modified DV was a clear decrease of concentration and finally, the modifications of biogenic emissions impacted predominantly SOA causing a summer decrease while a very small secondary effect of secondary inorganic aerosol was modelled too (they increased).

In summary, we showed that when analyzing the impact of urbanization on PM pollution, apart from the impact of emissions and the urban canopy meteorological forcing, one has to consider also the effect of modified land-use and its impact on dry-deposition. These were shown to be important in both seasons. For the effect of modified biogenic emissions, our calculations showed that it acts on PM_{2.5} predominantly through SOA modifications which turned to be important only during summer.

1 Introduction

In the upcoming years, more than 60% of Earth's population will live in cities (UN, 2018) while urban areas in general represent only a tiny fraction of the habitable land. Moreover, the process of urbanization is predicted to continue by the end-of-the 21st century under all SSPs (Shared-Socioeconomic-Pathways) (Gao et al., 2020). It is thus a great desire to quantify the environmental footprints of urbanization, or more precisely, the rural-to-urban transformation (RUT) causes.

The RUT acts via two primary pathways: a) with the human activities concentrated in urban areas a great amount of emissions are introduced (both green-house-gas and short-lived pollutants) which affect the local but also the regional and global air pollution (Im and Kanakidou, 2012; Markakis et al., 2015; Timothy and Lawrence, 2009; Butler and Lawrence, 2009; Stock et al., 2013; Huszar et al., 2021), b) urban land-surface differs greatly from rural one by introducing artificial objects and surfaces in specific geometries (e.g. street canyons, buildings etc.) which affect the surface-air fluxes of energy, momentum and material with strong consequences on meteorological conditions (Oke, 1982; Oke et al., 2017; Karlický et al., 2020) and at the same time, in long-term, they modify the regional climate (Huszar et al., 2014; Karlický et al., 2018). In other words, cities have strong impact on the whole atmospheric environment (Folberth et al., 2015).

Regarding the first pathway, it is clear that urban emissions alone substantially deteriorate the local air-pollution (Thunis et al., 2021). They are composed of a mixture of different gases like oxides of nitrogen (NO_x) originating mainly from road transportation (Huszar et al., 2016a, 2021) along with the volatile organic compounds (VOC), carbon monoxide (CO) and sulphur dioxide (SO₂) or ammonia (NH₃). Further, urban emissions contain also primary aerosol in the form of elemental carbon (PEC), primary organic aerosol (POA) and other primary material like metals (Freney et al., 2014; Allan et al., 2010; Rivellini et al., 2020; Yang et al., 2023). By introducing urban emissions, large quantities of these primary pollutants are added to their background levels. Moreover, they are potentially responsible – as precursors – for the formation of secondary pollutants too. NO_x together with VOC (partly supported by CO) leads to formation of ozone (O₃) while the ratio of NO_x-

60 to-VOC determines the amount of O_3 formed or destroyed (Beekmann and Vautard, 2010; Xue et al., 2014). Emissions of gaseous pollutants further lead to formation of secondary aerosol. NO_x , SO_2 and NH_3 are absorbed by water droplets leading to formation of secondary inorganic aerosol (SIA). These include sulphates (PSO_4), nitrates (PNO_3) and ammonium (PNH_4). The main precursor for PSO_4 is SO_2 which although exhibits decreasing global emissions (Zhong et al., 2020), many urban areas are still marked with significant perturbation of aerosol burden due to this pollutant (Guttikunda et al., 2003; Yang et al., 65 2011). It has to be further noted that sulfates can be emitted directly too and thus contribute to total particulate matter (PM) pollution (Li et al., 2018). Nitrogen oxides are the main precursors for nitrate aerosol via forming nitric acid (HNO_3) which is easily absorbed by water (Seinfeld and Pandis, 1998) and it is well known that urban NO_x can significantly contribute to total PM pollution via the formation of PNO_3 (e.g. Lin et al., 2010). Ammonia (NH_3), while constitutes relatively a small fraction of urban emissions (although there is an indication that transport emits much more ammonia than previously thought (e.g. 70 Walters et al., 2022)), efficiently helps forming sulfate and nitrate aerosol by reacting to ammonium-sulfates and ammonium-nitrates and is found to be very important in connection with urban emissions (e.g. Behera and Sharma, 2010, and references therein). The thermodynamical equilibrium of the ammonium-sulfate-nitrate-water solution is, in general, rather complicated and highly dependent on ratio of emissions of SO_2 - NO_x - NH_3 as well as on the prevailing meteorological conditions (Martin et al., 2004). This gives a potential to high variability of the contribution of different cities to total aerosol burden.

75 There is a large number of studies that investigates the perturbation of the atmospheric composition due to the urban emissions: Lawrence et al. (2007), Butler and Lawrence (2009) or Stock et al. (2013) investigated the global impact of emissions from large urban agglomerations. On regional scale, Im et al. (2011a, b); Im and Kanakidou (2012); Finardi et al. (2014); Skyllakou et al. (2014); Markakis et al. (2015); Hodnebrog et al. (2011); Huszar et al. (2016a); Hood et al. (2018) looked at European cities (e.g. Paris, London, Istanbul, Athens) but the regional fingerprint of Asian megacity emissions has been also 80 of great interest (Guttikunda et al., 2003, 2005; Tie et al., 2013). They all showed that the concentrations of primary pollutants (both gaseous and primary aerosol) are substantially increased locally but also on regional scales. On the other hand, secondary pollutants like ozone can respond differently: e.g. for these cities often decreases in urban cores are modelled due to emissions caused by high NO_x -to-VOC ratio (e.g. Huszar et al., 2016a, 2021). Further, it was found that air pollution in cities is determined mainly by the local sources, however a considerable part of the total concentration is associated to rural ones (Panagi et al., 85 et al., 2020; Thunis et al., 2021; Huszar et al., 2021).

Besides the direct impact of urban emissions, urbanization influences air chemistry also via the so called “urban canopy meteorological forcing” (UCMF) as introduced by Huszar et al. (2020a). Urban land-surface brings higher temperatures (urban heat island or UHI; (Oke, 1982; Karlický et al., 2020; Sokhi et al., 2022)), drag-induced wind-speed reductions (Huszar et al., 2018b; Zha et al., 2019) and enhanced vertical turbulent diffusion along with elevated planetary boundary layer height (Ren 90 et al., 2019; Wang et al., 2021). Further it has clear impact on the hydrological cycle by removing the precipitated water via drainage and decreasing thus the humidity over cities (Richard, 2004; Huszar et al., 2018b). UCMF then propagates to modifications in transport, deposition and chemical transformation of the emitted pollutants leading to modifications of their concentrations linking the urban meteorological conditions to urban pollution very tightly (Ulpiani, 2021). The impact of UCMF on air-quality in and around cities (or also rural areas) was a focus of many modelling studies that found that the

95 most important components of UCMF are temperature, wind-speed and turbulence (Struzewska and Kaminski, 2012; Liao
et al., 2014; Kim et al., 2015; Jacobson et al., 2015; Zhu et al., 2017; Zhong et al., 2018; Li et al., 2019a; Huszar et al.,
2018a, 2020a, b; Wei et al., 2018). Due to UCMF, primary gas-phase pollutants and PM are decreased over cities (driven
mainly by urban land-surface induced vertical eddy diffusion increase). In case of secondary pollutant the situation is more
difficult as the total impact of UCMF is a combination of the direct impact on the secondary pollutant and the impact on its
100 precursors; e.g. for ozone the resulting effect is an increase over the surface (Janssen et al., 2017; Yim et al., 2019; Li et al.,
2019a; Kim et al., 2021; Kang et al., 2022; Huszar et al., 2022).

Apart from the impact of urban emissions and the impact of UCMF, RUT influences the final air-pollution via two other less-
studied pathways too. The first is the impact of urbanization induced land-surface change on the dry-deposition of pollutants
and the second is the modification of biogenic emissions due to change (decrease) of vegetation distribution due to urbanization.
105 The land-surface type determines the resistances of that surface (and the canopy layer) which in turn determines the dry
deposition velocities (DV) (Zhang et al., 2003; Cherin et al., 2015; Hardacre et al., 2021). It has been shown by many that
by urbanization and the consequent reduction of vegetation in urban areas, the deposition velocities are greatly reduced for
some gaseous pollutants (e.g. NO₂, O₃) leading to their increased concentrations (Nowak and Dwyer, 2007; Mcdonald-Buller
et al., 2001; Song et al., 2008; Tao et al., 2015), for others due to higher reactivity on solid surfaces (compared to vegetated
110 ones) the DVs are increased leading to concentration increase (Zhang et al., 2003). For aerosol, DVs are determined mainly
by the sedimentation of the particles and by aerodynamic and boundary resistances (Zhang et al., 2001). While sedimentation
is determined by particle size and shape, surface resistances are a function of the roughness length and friction velocities
(Wesely, 1989) which are enhanced over urbanized land-surface compared to rural ones. This alone would lead to decrease of
PM concentration bearing larger DVs. However, this is modulated also by the modifications of precursor concentrations as a
115 result of the land-surface changes associated with RUT. For example, Huszar et al. (2022) modelled decreases of NO₂ and SO₂
concentration due to land-surface change (and hence dry deposition modifications) alone which would imply an amplification
of the land-surface induced decrease of nitrates and sulphates. Further, it can be assumed that ammonia (NH₃) concentrations
are also modified by modified dry-deposition velocities which in turn has impacts on the amount of ammonium salts formed.

Regarding the influence of the modified biogenic emissions (BVOC; biogenic volatile organic compounds) as a result of
120 urbanization, one has to realize that the urbanization i) reduces the amount of vegetation (e.g. turning crop land into urban built-
up) which alone reduces the emission of biogenic substances (Song et al., 2008) and ii) it was detailed above that urban areas
exhibit higher-temperature and moreover it seems that cloudiness is somewhat reduced above cities too (w.r.t rural regions)
meaning higher solar incident radiation at the surface (Karlický et al., 2020) – both promoting the vegetation metabolism
resulting in higher fluxes of BVOC (Guenther et al., 2006). These two effects (i and ii) counteract but the dominant one is
125 probably the vegetation effect (Li et al., 2019a; Huszar et al., 2022), i.e. due to urbanization, BVOC emissions are reduced.
As for the effect of such reduction, it is expected that near surface ozone concentration will be decreased as urban areas are
usually VOC-limited (Song et al., 2008). In case of PM, this will act via modification of the formation of secondary organic
aerosol (SOA). It has been shown by many, that BVOC are an important precursors of SOA and responsible for the formation
of biogenic secondary organic aerosol (BSOA; (Gao et al., 2022)). Couvidat et al. (2013) showed that almost one third of the

130 organic material in the Paris region originates from biogenic VOCs. The great importance of BVOC in urban SOA formation was confirmed also by Sartelet et al. (2012); Hu et al. (2017); Nagori et al. (2019); Ma et al. (2023) but of course, anthropogenic precursors remain also very important (Zhang et al., 2015; Guo et al., 2022). While it is clear that most of the BVOC emissions originates from rural and natural land-surfaces (i.e. “non-urban” areas Lin et al., 2016), it is expected that any change in urban BVOC emissions as a result of urban expansion will have immediate effect on SOA concentrations too, and hence, the total
135 PM.

To summarize, urbanization (RUT) greatly modifies the air composition over both the cities themselves but also over surrounding rural areas while this modification is the result of four impacts or contributors that add-up to the background air pollution level (i.e. that without urbanization): namely, i) the effect of urban emissions (“DEMIS”), ii) the effect of the urban canopy meteorological forcing (UCMF) on transport and chemical transformations (“DMET”), iii) the effect of modified
140 dry-deposition velocities as a result of modified (urbanized) land-surface (“DLU_D”) and, finally, iv) the effect of modified emissions of BVOC due to modified vegetation-cover and meteorology (“DBVOC”). They together constitute the total RUT impact (“DTOT”).

These four impacts had been formulated also in our previous paper Huszar et al. (2022) where we looked, using regional chemistry-transport models coupled to regional climate models, at their effect on gas-phase chemistry, however most of the
145 other studies mentioned above focused either at the total impact of the urbanization or at some of the individual impacts without a detailed analysis of the contribution of each of them. The mentioned Huszar et al. (2022) study indeed aimed at the quantification of each individual impact as well as the total impact as one of the first studies of such kind analysing central European domain at moderate horizontal resolution. Here, as a follow-up study, we extend our analysis conducted there to particulate matter and will investigate, how the total PM (as PM_{2.5}, particles of diameter less than 2.5 μm) as well as their
150 primary and secondary components respond to these impacts. To fulfill this goal, a background or reference state has to be defined to which these impacts will be gradually added: for our purpose that reference state will be the non-urbanized land-surface without any urban emissions (only rural ones) and without the effect of UCMF. The analysis will focus on present day conditions which includes present day driving climate, emissions and land-use. The four listed impacts will be then gradually added to this reference (i.e. non-urbanized) state in a cascading manner. To consider the uncertainty arising from different
155 background climate, size and emissions from different cities, we conduct our analysis on a larger selection of 19 cities from central Europe.

As mentioned, our analysis will focus on PM_{2.5} and its components. Despite notable improvements in European PM pollution, EEA (2022) reports that in 2020, 96 % of the urban population in the European Union was exposed to high levels of PM_{2.5}. This makes the investigation of the components and contributors to urban PM pollution very important. It has to be
160 also noted that urban air-quality is influenced not only by the local effects. Im and Kanakidou (2012); Huszar et al. (2016a) e.g. showed that emissions from other areas (rural or other, even distant cities) represent a major fraction of urban pollution burdens. Also the urban canopy meteorological forcing can act not only locally over cities but over regional scales too and the UCMF triggered by one city can have impact on other one too, as shown by Huszar et al. (2014). Here we however will

be interested in the local effects only without looking at the inter-urban influences (i.e. the effect different cities pose on each other mutually).
165

The study is structured in the following way: the Introduction is followed by the presentation of experimental tools (models), their configuration and the data used. Next, the experiments performed are described and the results summarized in the Result section. Finally, these are discussed and conclusions are drawn.

2 Methodology

170 2.1 Models used

The study uses the same models, model settings and same input data as Huszar et al. (2022). Here we will therefor summarize only the most relevant information about the model setup stressing the eventual differences.

The chemistry transport model (CTM) simulations were carried out by the CAMx version 7.10 model (Ramboll, 2020) using the Carbon Bond 6 revision 5 (CB6r5) scheme (Cao et al., 2021). Aerosol physics and chemistry were treated with the a static two mode approach and the ISORROPIA thermodynamic equilibrium model (Nenes and Pandis, 1998) was applied for the secondary inorganic aerosol formation. For secondary organic aerosol (SOA), the SOAP equilibrium scheme (Strader et al., 1999) was used. For wet and dry deposition treatment, the Seinfeld and Pandis (1998) and Zhang et al. (2001, 2003) methods were invoked.
175

CAMx was driven by the regional climate model (RCM) RegCM version 4.7 (Giorgi et al., 2012) using non-hydrostatic dynamics. PBL physics, cloud and rain microphysics, convection and radiation are treated following Holtslag et al. (1990); Hong et al. (2004); Tiedtke et al. (1989). The atmosphere-biosphere-surface coupling was treated with the Community Land Model (CLM) version 4.5 (Oleson et al., 2013) land-surface scheme and to account for the urban scale processes, the CLMU module within CLM4.5 was used (Oleson et al., 2008, 2010). CLMU adopts the classical canyon geometry approach, i.e. cities are represented as networks of street-canyons with specified geometry and surface parameters (Oke et al., 2017) while anthropogenic heat (AH) from heating and waste heat from air-conditioning is accounted for. AH from traffic is not calculated which might result in some underestimation of temperature due to this missing heat source. RegCM was offline coupled to CAMx using the RegCM2CAMx interface developed by Huszar et al. (2012). The vertical eddy diffusion coefficients (K_v) are diagnosed using the CMAQ approach (Byun, 1999). Because of the offline character of the coupling, no feedback between the RegCM's radiation scheme and chemistry is considered. Based on 10yr long simulations, Huszar et al. (2016b) concluded that the radiative effects of urban pollutant emissions and secondarily formed pollutants are minor which justified the offline coupling (which is not true for short term effects that can be considerable, e.g. (Prieto Perez et al., 2022)). On the other hand, all urban effects on meteorology, i.e. urban heat island, moisture island (and others, like increased vertical turbulence, lower over wind speeds over cities) are included in the meteorological data that is offline fed into CAMx having thus direct impact on chemistry in our simulations.
185
190

Model simulations with RegCM and CAMx were conducted over 9 km x 9 km resolution domain covering “larger” central Europe (from France to Ukraine and from northern Italy to Denmark) with 189×165 gridboxes, centered over the Czech capital, Prague (50.075° N, 14.44° E; Lambert Conic Conformal projection). In vertical, the model grid spawns 40 layers in RegCM up to 5 hPa, while CAMx uses the lowermost 18 layers up to about 12 km. The simulated years are DEC 2014 to DEC 2016 with the first month serving as spin-up. Fenech et al. (2018) showed that the difference between the coarse and fine resolution PM_{2.5} concentrations is rather small and our resolution is comparable to the resolution of the emissions (see below). The requirement of Tie et al. (2010) that the size of the city to resolution should be 6:1 means that preferably, a resolution 6 km or finer should be used, however we rely on the fact that land-use is represented as fractional land-use so even the smallest cities are resolved within the surface model in our RCM. Markakis et al. (2015) showed that the modelled PM_{2.5} concentrations for Paris are more sensitive to the emissions inventory resolution than on the resolution at which the meteorology is resolved in the driving RCM.

RegCM simulations are forced with the ERA-Interim reanalysis (Simmons et al., 2010). Chemical boundary conditions are taken from the CAM-chem global climate-chemistry model (Buchholz et al., 2019; Emmons et al., 2020). Land-use for RegCM and for the CAMx dry-deposition calculations are based on the 100 m resolution CORINE CLC 2012 landcover data (<https://land.copernicus.eu/pan-european/corine-land-cover>, last access May 16, 2023) except a small area over Belarus, where CORINE is not available, so the United States Geological Survey (USGS) data is used.

Anthropogenic emissions are taken from the European CAMS (Copernicus Atmosphere Monitoring Service) version CAMS-REG-APv1.1 inventory (Regional Atmospheric Pollutants; (Granier et al., 2019)) for year 2015 combined with the Czech national emission data, the Register of Emissions and Air Pollution Sources (REZZO) dataset issued by the Czech Hydrometeorological Institute (www.chmi.cz, last access May 16, 2023) and the ATEM Traffic Emissions dataset provided by ATEM (Ateliér ekologických modelů – Studio of ecological models; www.atem.cz, last access May 16, 2023). These annual sector based emission totals are decomposed to hourly speciated emissions fluxes using the Flexible Universal Processor for Modeling Emissions (FUME) emission model (<http://fume-ep.org/>; Benešová et al., 2018) using speciation and time-disaggregation factors of Passant (2002) and van der Gon et al. (2011). To account for the SOA formation from intermediate VOC (IVOC) which are normally not included in emission inventories, we proceeded following Ciarelli et al. (2017); Giani et al. (2019) to calculate IVOC based on the known non-methane VOC and POA (primary organic aerosol) emissions from gasoline and diesel vehicles, and emissions from biomass burning. This emission adjustment was not implemented in Huszar et al. (2022) but there we looked at gas-phase chemistry impacts only. It has been shown that a major contributors to urban SOA precursors in urban environment are asphalt-based vehicular emissions (Khare et al., 2020). These are strongly dependent on solar radiation and temperature and the currently used anthropogenic emission model does not include them. Thus our estimates of the impact of urban emissions to SOA might be somehow underestimated especially during hot sunny days (the winter error by not including these emissions will be however probably much smaller). On the other hand, road dust re-suspension (Rienda and Alves, 2021) is partly included in our study, as the Czech ATEM traffic emissions consider these type of emissions. They are

however not included in the European CAMS emissions thus their effect is included only for Prague implying further potential
230 underestimation of the urbanization impact on total fine PM loads.

Biogenic emissions are computed offline using MEGANv2.1 (Model of Emissions of Gases and Aerosols from Nature version 2.1) with the algorithm described by Guenther et al. (2012) driven by RegCM meteorological fields (short-wave radiation, temperature, soil moisture, humidity). The necessary input for MEGAN were not part of the CORINE land-use information and were compiled based on Lawrence and Chase (2007); Sindelarova et al. (2014, 2022). These include leaf-area index data
235 (weekly data), plant functional types (PFT) and emission potentials of different plant types. Besides BVOC, MEGAN also calculates the fluxes of soil-biogenic NO (nitrogen monoxide) emissions from bacterial activity (Yienger and Levy, 1995). As these emissions are a function of LAI and meteorological conditions, a fraction of the “DBVOC” impact will be composed of soil-NO_x emissions modifications. Not presented here, in our experiments the soil-NO_x emissions were about two orders of magnitude smaller compared to the BVOC emissions and their effect is expected to be much smaller including the effect of
240 their urbanization induced modulations. BVOC emission fluxes are strongly temperature dependent, i.e. higher temperatures result in enhanced emissions. In this regard, it is expected that urbanization induced temperature increase will lead to higher BVOC fluxes. It has to be noted that PFT data are fractional meaning that even the smallest fraction of a particular plant type is represented in the BVOC emissions, which allows us to account for the very small but not zero amount of urban vegetation. On the other hand, the PFT input is relatively old (year 2007) and some inaccuracies might be present in the vegetation fraction
245 given the urban development that took place for the chosen cities since 2007.

For the purpose of the study, we had to isolate the emissions originating from selected urban areas from rural emissions. To achieve this, we used the masking capability of the emissions model used (FUME) while we used the administrative boundaries of the chosen cities based on the GADM public database (<https://gadm.org>, last visit May 16 2023) which provide geographic shape-files of these boundaries. Cities selected in the analysis are Berlin, Brussels, Budapest, Cluj-Napoca, Cologne, Frankfurt, Hamburg, Krakow, Lodz, Lyon, Milan, Munich, Prague, Torino, Vienna, Warsaw, Wroclaw, Zagreb, Zurich. The choice
250 considered the same criteria as in Huszar et al. (2021, 2022): the diameter of the city larger than 9 km (the gridcell size in our model), minimal orographic variability to reduce orographic effects (see e.g. Ganbat et al., 2015), sufficiently large distance between cities eliminating mutual influences and, finally, no coastal cities to eliminate the effect of asymmetric land-use effects, like e.g. the sea-breeze effect (e.g. Ribeiro et al., 2018). Despite strict emission control policies, these cities are still often
255 burdened with high air pollution due to PM (Khomeenko et al., 2021; Sokhi et al., 2022; Balamurugan et al., 2022; Putaud et al., 2023).

The mutual interaction between the regional climate and chemistry transport model, as well as the emissions models (for biogenic and anthropogenic emissions) is depicted in Fig. 1. It shows as detailed above that meteorological conditions generated by the regional climate model (RegCM) drive both the biogenic emissions model (MEGAN) as well as the chemistry transport
260 model (CAMx). The emissions fluxes calculated as the sum of anthropogenic and biogenic emissions are then fed into CAMx.

2.3 Model simulations

In a similar fashion that in (Huszar et al., 2022), we decomposed the total impact of urbanization (RUT) into the individual impacts or contributors (i.e. “DEMIS”, “DMET”, “DLU_D”, “DBOC”) listed in the introduction. This required to carry out a series of model simulations with each contributor added gradually one-by-one to the reference simulation arriving to the full urbanization case.

First, we carried out a pair of model simulations with RegCM: ”Urban“ and ”Nourban“ with former accounting for urban land-surface treated with the RegCM’s urban canopy module while in the later, land-use was replaced by “crops” as the most common rural land-use type in the region analyzed. We performed 5 simulations with CAMx that differ in the in-/exclusion of urbanized land-surface, the UCMF (acting on both atmospheric chemistry in general and on biogenic emissions) and urban emissions. These simulations are summarized in Tab. 1. The first simulation called “ENNNN” represents the hypothetical reference (background) state without urban emissions and with the urban land-surface replaced by rural land-surface in RegCM and CAMx as well as in the BVOC calculations (with MEGAN). In the 2nd experiment, “ENYNN”, the urban emissions are turned on. In the 3rd experiment, “ENYUN”, the urban land-use was “switched-on” for the dry-deposition scheme in CAMx. In the 4th experiment, “ENYUU”, urban land-use and the UCMF (i.e. “Urban” meteorology) is accounted for the biogenic emissions model and finally, in the 5th experiment, “EUYUU”, all the urbanization-related effects are considered, representing the most realistic full case.

In the first experiment where urban emissions are disregarded, we removed urban emissions only for the 19 cities selected. For the effect of rural-urban land-use transformation on meteorological conditions, dry-deposition and biogenic emissions, we replaced the urban land by rural one over the entire domain (i.e. not only for the cities selected). It is clear that this has effect on the background level of air pollutants and not only on local urban levels, but the effect is probably much smaller than local effects as 1) emissions from these areas were still considered, 2) the urban meteorological effects from these (minor) urban areas have rather small influence on air pollutants as the UCMF over them is also small (see e.g. Huszar et al. (2014)).

Similar as in Huszar et al. (2022), we can express mathematically the concentrations c_i of a pollutant i in a selected city with respect to RUT in a following way:

$$c_i = c_{i,rural} + \Delta c_{i,RUT}, \quad (1)$$

where $c_{i,rural}$ is the reference (background) concentration before RUT and $\Delta c_{i,RUT}$ is the total impact of urbanization.

In this study, we are concerned about the contributors to $\Delta c_{i,RUT}$ (regardless of their sign), i.e.:

$$\Delta c_{i,RUT} = \Delta c_{i,EMIS} + \Delta c_{i,MET} + \Delta c_{i,LU_D} + \Delta c_{i,BVOC}, \quad (2)$$

where $\Delta c_{i,EMIS}$, $\Delta c_{i,MET}$, $\Delta c_{i,LU_D}$ and $\Delta c_{i,BVOC}$ are the impacts of urban emissions, the impact of the urban canopy meteorological forcing, the impact of modified land-use on dry-deposition and the impact of modifications of BVOC emissions, denoted above as “DEMIS”, “DMET”, “DLU_D” and “DBVOC”.

These impacts will be calculated from the experiments listed in Tab. 1 as indicated below (the experiment number is shown in parenthesis):

$$\begin{aligned}
 \Delta c_{i,RUT} &= EUYUU(5) - ENNNN(1) \\
 \Delta c_{i,EMIS} &= ENYNN(2) - ENNNN(1) \\
 \Delta c_{i,MET} &= EUYUU(5) - ENYUU(4) \\
 \Delta c_{i,LU_D} &= ENYUN(3) - ENYNN(2) \\
 \Delta c_{i,BVOC} &= ENYUU(4) - ENYUN(3)
 \end{aligned} \tag{3}$$

295 It has to be realized that, in fact, the contributors above act simultaneously and feedbacks are present between them so their impacts are not additive. The way how we calculated them however allow us to consider them to be additive meaning that their sum is the total impact of urbanization. This is also a consequence of Eq. 3. Also the impact of the order of application of the four contributors has to be discussed. The choice of starting with the “DEMIS“ was motivated by ”filling“ the atmosphere with pollutants before any other contributor is ”turned on“. We assumed with this choice the other contributors act on a more
300 realistic base state (see the Discussion section for more details).

Our analysis will focus on near surface PM_{2.5} concentrations as well as their secondary components, i.e. secondary inorganic aerosol (SIA) composed of sulphates (PSO_4), nitrates (PNO_3) and ammonium (PNH_3) and secondary organic aerosol. Moreover, we will also focus on primary elemental carbon (PEC) which is an important fraction of urban emission loads. As the emissions of primary organic aerosol have very similar magnitude in our emission data compared to PEC and it has the
305 same deposition velocity (which is determined only by size), we will not explicitly analyze POA concentrations as we assume that the impacts of urbanization on POA will be very similar to impact on PEC.

3 Results

This section presents the results and only a brief, rather general discussion is provided. A more detailed interpretation of the results is given by the Discussion section including a comparison with existing studies.

310 3.1 Validation

Here we compare the modelled concentrations of PM_{2.5} and their components (PSO_4 , PNO_3 , PNH_4 , SOA and PEC) to observations. The measured data for PM_{2.5} are taken from the AirBase European air quality data (<http://www.eea.europa.eu/data-and-maps/data/aqereporting-1>, last access 16 May 2023) while for PM components data are taken from EBAS database (<https://ebas-data.nilu.no/>, last access May 16 2023) from EMEP background sites. AirBase data are taken from all available
315 rural and urban background stations in order to distinguish between model performances above both type of stations.

Fig. 2 shows the average annual cycle of monthly means for urban and rural stations including the corresponding model values. Over urban stations, CAMx exhibits a strong underestimation around 5-10 $\mu\text{g m}^{-3}$ and the underestimation is stronger in winter. CAMx performs slightly better over rural stations with smaller negative bias. In both cases, the annual cycle is

reasonably captured. We also compared the analysed components (sulphates, nitrates, ammonium and elemental carbon) with
320 measurements. In this case the EMEP background station data acquired from EBAS (<https://ebas.nilu.no/data-access/>, last
access 5 May 2023) was used. Fig. 3 shows that the model underestimates PSO4 by about 0.5-1 $\mu\text{g m}^{-3}$, especially during
summer when the model predicts minimum values while in measurements, the values show more or less uniform distribution
during the year. PNO3 is overestimated during winter by about 2 $\mu\text{g m}^{-3}$ and the model well matches the summer values. In case
of PNH4, an 0.5 $\mu\text{g m}^{-3}$ overestimation of winter values and a similar underestimation of summer values is encountered. Thus,
325 for both PNO3 and PNH4, the amplitude of the annual cycle is overestimated. For PEC, the match is very satisfactory with an
uniform model bias of -0.25 $\mu\text{g m}^{-3}$ throughout the year meaning that the annual cycle is very well captured by the model. The
presented underestimation of fine PM is caused most probably by underestimation of the organic aerosol fraction which is an
important component of the urban PM. The strong underestimation of sulphates may be connected to overestimation of other
inorganic aerosol components, e.g., overestimated nitrates can consume the the available ammonia and suppress the formation
330 of PSO4. See the Discussion for more details.

3.2 The impact of individual contributors to RUT

Here we present the total impact of RUT as well as its individual contributors on PM2.5 concentrations as 2015-2016 DJF and
JJA averages, averaged across the selected cities. Values from model gridboxes that cover the city centres are selected. The
results are shown as boxplots in Fig. 4; they show the 1st and 3rd quartiles and the median values along with the minimum and
335 maximum value across all the cities.

As expected, the highest impact is attributed to the effect of emission only causing an increase of urban concentrations
by around 1.5 to 3.4 $\mu\text{g m}^{-3}$ in DJF and by about 1.2 to 2 $\mu\text{g m}^{-3}$ in JJA. The effect of UCMF on concentration is usually
a decrease up to -1 and -0.4 $\mu\text{g m}^{-3}$ in winter and summer, respectively. The impact of minor contributors associated with
modified land-use and deposition velocities and modified BVOC emissions are a decrease for “DLU_C” for both seasons by
340 -0.2 to -0.3 $\mu\text{g m}^{-3}$ in DJF and -0.08 to -0.15 $\mu\text{g m}^{-3}$ in JJA, while for the effect of BVOC modifications is very small, around
-0.05 $\mu\text{g m}^{-3}$ in summer and almost zero in DJF. The total impact of urbanization on PM2.5 is 1.2 to 3 $\mu\text{g m}^{-3}$ increase in DJF
and a smaller increase, from 1 to 1.6 $\mu\text{g m}^{-3}$ in JJA, while of course, the impact of emissions dominates.

To examine the contribution of the most important aerosol components to these changes, we plotted a similar figure as above
but individually for PSO4, PNO3, PNH4, PEC and SOA presented in Fig. 5. Sulphates respond to urban emissions alone by
345 an increase by about 0.05-0.15 $\mu\text{g m}^{-3}$ and up to 0.05 $\mu\text{g m}^{-3}$ in DJF and JJA, respectively. The urban canopy meteorological
forcing results in a decrease of sulphates in DJF by up to -0.05 $\mu\text{g m}^{-3}$ while increases are modelled for JJA up to 0.025 $\mu\text{g m}^{-3}$.
The impact of dry-deposition change on PSO4 is a decrease: up to -0.025 $\mu\text{g m}^{-3}$ in DJF and -0.01 $\mu\text{g m}^{-3}$ in JJA. The BVOC
effect on PSO4 is a slight increase in JJA and virtually zero in DJF. The total impact of RUT on PSO4 is an increase up to 0.15
and 0.05 $\mu\text{g m}^{-3}$ in DJF and JJA, respectively.

350 In case of nitrates, the urban emissions alone increase urban concentrations by about 0.1 to 0.2 $\mu\text{g m}^{-3}$ in both seasons
(somewhat more in DJF). The effect of UCMF is an increase in DJF by about 0.05 $\mu\text{g m}^{-3}$ while in JJA, decreases dominate up
to -0.15 $\mu\text{g m}^{-3}$. The impact of modified dry-deposition is a decrease by about -0.08 to -0.11 $\mu\text{g m}^{-3}$ in DJF and -0.03 to -0.06

μgm^{-3} in JJA. The impact of modified BVOC emissions are negligible and the total impact of RUT on PNO₃ is an increase up to about 0.16 and 0.12 μgm^{-3} in DJF and JJA, respectively.

355 For ammonium, urban emissions cause increase by 0.04 to 0.09 μgm^{-3} and by 0.04 to 0.05 μgm^{-3} in DJF and JJA, respectively. The sign of the UCMF impact can be positive and negative in both seasons with values between -0.01 to 0.025 μgm^{-3} in DJF and between -0.03 to 0.02 μgm^{-3} in JJA. The impact of dry-deposition modifications is negative in both seasons with -0.03 to -0.04 μgm^{-3} and -0.01 to -0.02 μgm^{-3} decrease in winter and summer, respectively. The impact of modified BVOC emissions are again negligible. Finally, the total impact of RUT on PNH₄ is an increase up to about 0.04 and 0.03 μgm^{-3} in
360 DJF and JJA, respectively.

The impact on elemental carbon which is a primary component chemically inert in CAMx (with no chemical decay or reactions) is as follows: urban emissions cause increase of PEC by around 0.2 to 0.5 μgm^{-3} in DJF and around 0.2 to 0.4 μgm^{-3} in JJA. The UCMF causes a slight decrease of PEC by around -0.05 to -0.1 μgm^{-3} in both seasons. The increased deposition velocities caused decreased concentrations of PEC by about -0.01 to -0.015 μgm^{-3} in DJF and around -0.005
365 μgm^{-3} in JJA. Being an inert PM component in CAMx, no impacts of BVOC modifications on PEC are modelled. The total impact of RUT on PEC is again dominated by urban emissions and reached 0.6 μgm^{-3} and 0.3 μgm^{-3} in DJF and JJA, respectively.

Finally, the impact secondary organic aerosol has considerable values only during JJA when dominantly the oxidation of primary VOC to semivolatile precursors of SOA take place. The impact of urban emissions is an increase of SOA by up to 0.05
370 to 0.1 μgm^{-3} while urban meteorological changes cause SOA modifications usually between zero and 0.05 μgm^{-3} . Due to land-use modifications and associated deposition velocity increases, SOA responds with a decrease up to -0.02 μgm^{-3} while due to urbanization induced BVOC modifications, SOA decreases by around -0.04 to -0.06 μgm^{-3} . The total impact of RUT on SOA is an increase by 0.07 μgm^{-3} in JJA and a very tiny increase by up to 0.01 μgm^{-3} in DJF.

These results confirm that urban PM_{2.5} levels are a result of mainly the local input represented by urban emissions but gets
375 smaller if the urban meteorological characteristics are taken into account (in the form of UCMF). It is also seen that urban land-surface exhibits a stronger depositional sink to PM causing the landuse impact to be negative and finally, urbanization-induced decrease of BVOC emissions leads, as expected, to suppressed SOA formation negatively contributing to the over RUT impact.

3.3 The spatial distribution of the impacts

To obtain a spatially resolved information about the impact of individual contributors to RUT, we plot here their 2-D distribution
380 as DJF and JJA averages. We start with presenting the distribution of absolute modelled concentrations for comparison of the changes with absolute values in order to resolve the relative magnitude of these contributors.

Fig. 6 shows the absolute modelled near surface concentrations of DJF and JJA PM_{2.5} and its analyzed components from the experiment with all urban effects considered (“EUYUU”). The PM_{2.5} concentrations reach 30-40 μgm^{-3} in winter while rural areas are often over 8 μgm^{-3} . In summer, concentrations are, as expected, smaller, reaching 10 μgm^{-3} being above
385 4 μgm^{-3} over rural areas. In DJF, the highest contribution is made by nitrates reaching 20 μgm^{-3} over northern Italy and being about 4-6 μgm^{-3} over central Europe. The concentrations of sulphates are large especially over Poland, reaching 2-3

μgm^{-3} while ammonium is largest over northern Italy reaching $4\text{-}6\ \mu\text{gm}^{-3}$ while other areas exhibit concentrations around $1\text{-}2\ \mu\text{gm}^{-3}$. Elemental carbon contributes to total PM_{2.5} by values around $2\text{-}4\ \mu\text{gm}^{-3}$ over northern Italy while the contribution is clearly limited to urban areas over other regions within the domain (e.g. $1\text{-}2\ \mu\text{gm}^{-3}$ over urban areas in eastern Europe).
390 The SOA concentrations in JJA are usually between $0.2\text{-}1\ \mu\text{gm}^{-3}$ reaching maxima again over Italy ($2\text{-}3\ \mu\text{gm}^{-3}$). In summer, the secondary inorganic aerosol concentrations are somewhat smaller, especially for ammonium (less than $0.6\ \mu\text{gm}^{-3}$) while nitrates are largest over western Europe reaching $2\text{-}3\ \mu\text{gm}^{-3}$ and sulphates largest over southern Europe, reaching also around $2\text{-}3\ \mu\text{gm}^{-3}$. The PEC concentrations in JJA are small, usually around 0.1 to $0.4\ \mu\text{gm}^{-3}$. SOA is larger in summer than in winter reaching concentration up to $2\ \mu\text{gm}^{-3}$ and being usually around $0.4\text{-}1.5\ \mu\text{gm}^{-3}$.

395 **3.3.1 The impact of urban emissions (DEMIS)**

In Fig. 7 the DJF and JJA average spatial impact of urban emissions (“DEMIS”) on the near-surface concentrations of PM_{2.5} and its five analysed components are presented. Urban emission impact is in general higher in winter expect for SOA. In DJF, PM_{2.5} are increased over urban areas by up to $4\ \mu\text{gm}^{-3}$ and the contribution to rural concentrations can also reach $0.5\ \mu\text{gm}^{-3}$. In JJA, urban emissions contribute to total PM_{2.5} by about $1\text{-}3\ \mu\text{gm}^{-3}$ over cities while the rural contribution is small, reaching
400 $0.02\ \mu\text{gm}^{-3}$. The impact of urban emissions on PEC reaches 1 and $0.5\ \mu\text{gm}^{-3}$ in city centres in DJF and JJA, respectively, while the impact over rural areas is less than $0.02\ \mu\text{gm}^{-3}$. For sulphates, urban emissions impact urban concentrations up to $0.5\ \mu\text{gm}^{-3}$ in winter while the summer impact is smaller reaching $0.1\ \mu\text{gm}^{-3}$. The impact over rural areas is again less than $0.02\ \mu\text{gm}^{-3}$ in both seasons. Much larger impact is modelled for nitrates reaching $1\ \mu\text{gm}^{-3}$ over Italy and exceeding 0.2 over most of central Europe in winter. In summer, the impact on PNO₃ is smaller reaching $0.5\ \mu\text{gm}^{-3}$ over urban- and $0.2\ \mu\text{gm}^{-3}$
405 over rural areas. The impact of urban emissions on ammonium reaches $0.5\ \mu\text{gm}^{-3}$ and is usually around $0.05\ \mu\text{gm}^{-3}$ in DJF while JJA concentrations are smaller reaching 0.05 but usually less than $0.02\ \mu\text{gm}^{-3}$. Finally, the impact on SOA is negligible in winter reaching $0.02\ \mu\text{gm}^{-3}$ over city centres while in summer, it can reach $0.2\ \mu\text{gm}^{-3}$ and the contributions over rural areas can exceed $0.02\ \mu\text{gm}^{-3}$. These result clearly show that emission act mainly locally, but a large fraction of urban pollution is caused also by rural emissions or emissions from nearby cities. Further it is clear that the impact on primary pollutants is more
410 localized than the one on secondary components which are formed during aging of the urban aerosol plume impacting distant areas.

3.3.2 The impact of modified meteorological conditions (DMET)

In Fig. 8 the DJF and JJA average spatial impact of the urban canopy meteorological forcing (“DMET”) is presented. For PM_{2.5}, it is characterized by decreases located above urban areas reaching $-2\ \mu\text{gm}^{-3}$ in both seasons. Elsewhere, i.e. above
415 rural areas, PM_{2.5} increases by up to $1\text{-}1.5\ \mu\text{gm}^{-3}$. In case of PEC, the decrease over urban areas are evident and reaches $-0.2\ \mu\text{gm}^{-3}$, especially during DJF, while some minor increases are modelled over rural land reaching $0.05\ \mu\text{gm}^{-3}$. The impact for secondary aerosol components is more complicated as apart from the direct impact, UCMF impacts also their precursors. Sulphates decrease above urban areas by about 0.2 to $0.5\ \mu\text{gm}^{-3}$ in DJF and by $0.1\ \mu\text{gm}^{-3}$ in JJA. Large rural regions show, on the other hand, increases of PSO₄ by up to $0.1\text{-}0.2\ \mu\text{gm}^{-3}$, mainly in winter. In case of nitrates, some urban areas exhibit

420 decreases in DJF (e.g. Berlin, the Ruhr area) but also large increases are modelled over rural areas and even urban ones, especially over northern Italy along the Po river reaching $0.5 \mu\text{gm}^{-3}$. In summer, the decrease over urban areas is seen for most of the cities, however, over other areas, a strong increase of PNO₃ is modelled reaching $0.5 \mu\text{gm}^{-3}$. The UCMF's impact on PNH₄ is somewhat smaller and is, again, characterized by decreases above cities up to $-0.2 \mu\text{gm}^{-3}$ in both seasons, while increases are modelled over rural areas and also some urban ones reaching $0.3 \mu\text{gm}^{-3}$ in winter and $0.2 \mu\text{gm}^{-3}$ in summer. In
425 case of SOA, some urban areas over western and southern Europe exhibit decreases in JJA up to $-0.05 \mu\text{gm}^{-3}$ but increases dominate reaching $0.2 \mu\text{gm}^{-3}$. In DJF, the impact is very small with some minor increase over rural areas up to $0.05 \mu\text{gm}^{-3}$. The simulated impact of UCMF on fine PM is most probably the result of enhanced vertical eddy-diffusion caused by the urban canopy. This leads to decreases of PM concentrations by transporting material into higher levels. However, this can lead to elevated concentrations further from the sources (cities) when this material is deposited back to lower model levels.

430 3.3.3 The impact of dry-deposition modifications (DLUC_D)

Fig. 9 depicts the DJF and JJA average spatial impact of the modified dry-deposition velocities due to urban land-use. In both seasons, a clear decrease of concentrations is modelled indicating that dry deposition velocities increased, as it was expected. The total PM_{2.5} concentrations decreased by up to $-1.5 \mu\text{gm}^{-3}$ in winter over cities while large rural areas exhibit a decrease up to $-0.5 \mu\text{gm}^{-3}$. In summer, the decreases have smaller magnitude, reaching $-0.5 \mu\text{gm}^{-3}$ over urban areas while over rural ones
435 they reach $-0.2 \mu\text{gm}^{-3}$. For PEC, decreases are limited mostly to urban areas reaching $-0.05 \mu\text{gm}^{-3}$ in DJF and $-0.01 \mu\text{gm}^{-3}$ in JJA. Larger impacts are modelled for secondary aerosol, probably due to the fact that their precursors are also impacted. Sulphates decreased in winter by about $0.05 \mu\text{gm}^{-3}$ and by about $0.02 \mu\text{gm}^{-3}$ in summer, mainly over urban areas. Among SIA, the largest impacts are modelled for nitrates, exceeding $-0.1 \mu\text{gm}^{-3}$ decrease in DJF over northern Italy but being large over rural areas too (about $-0.05 \mu\text{gm}^{-3}$). In summer, PNO₃ decreases by around 0.02 to $0.05 \mu\text{gm}^{-3}$, mainly over cities. In
440 case of PNH₄ the decreases are, again, largest above cities reaching $-0.05 \mu\text{gm}^{-3}$ in both seasons (slightly stronger decrease in DJF). Over rural areas, the decrease is about $-0.02 \mu\text{gm}^{-3}$ and $-0.01 \mu\text{gm}^{-3}$ in DJF and JJA, respectively. SOA decreased due to modified dry-deposition velocities by around $0.02 \mu\text{gm}^{-3}$ above cities in both season, while over rural areas, it reaches about $-0.01 \mu\text{gm}^{-3}$, slightly higher in JJA.

The decreases above are the result of increased deposition velocities, which are depicted in Fig. 10 for PEC for both winter
445 and summer. As the DVs in the model used (CAMx) are a function only of the size, all aerosol within the 0-2.5 micron size range (where all the secondary aerosols belong) have the same DV values, we present here the modification of DV only for this component (for others the figure would be the same). DVs increased clearly above urban areas while the increase reaches 0.1 cms^{-1} in DJF for some cities. For JJA, the increases are slightly smaller, usually between 0.02 and 0.1 cms^{-1} . It has to be noted here that the used deposition model considered a spatially uniform surface parameters relevant for deposition, however
450 cities are covered by a very high variety of different materials and the deposition velocities can vary from place-to-place with a great magnitude so the results are rather a rough estimate.

3.3.4 The impact of biogenic emissions (DBVOC)

Fig. 11 presents the impact of modified biogenic emissions due to RUT on PM concentrations. It is clear that BVOC emissions are important mainly during the warm season and that is why the impacts during DJF are much smaller than during JJA. Moreover, during summer BVOC can more readily oxidize to semi-volatile hydrocarbons forming SOA so the impact on PM_{2.5} act predominantly via impacting secondary organics concentrations. However due to feedback on the overall gas-phase chemistry and thus SIA precursors, SIA are also slightly modified. In winter the impact on PM_{2.5} is considerable only above northern Italy reaching $-0.05 \mu\text{g m}^{-3}$ while mainly SOA and nitrates contribute to these PM modifications. In case of PNO₃, they decrease above the same region by around $0.01\text{-}0.02 \mu\text{g m}^{-3}$ while SOA decreased by a similar magnitude (and slightly increased over other areas). Sulphates responded to BVOC changes by a slight decrease up to $-0.01 \mu\text{g m}^{-3}$. In JJA, the impacts are in general much larger (as expected) and are mainly determined by the decreased SOA but also modulated by increases in SIA. The PM_{2.5} JJA decrease reaches $-0.1 \mu\text{g m}^{-3}$ (again mainly over northern Italy) but is between -0.02 to $-0.05 \mu\text{g m}^{-3}$ over large areas all over the domain. Regarding SIA, all of them increased: by up to $0.02 \mu\text{g m}^{-3}$ for PNO₃ and up to $0.01 \mu\text{g m}^{-3}$ in case of PSO₄ and PNH₄. For SOA there is a clear decrease during JJA up to $-0.1 \mu\text{g m}^{-3}$ over northern Italy and being between -0.02 and $-0.05 \mu\text{g m}^{-3}$ over large regions across the domain. As PEC is not affected by either gas-phase and aerosol chemistry, no modifications due to biogenic emission changes are modelled.

3.4 The diurnal variation of the impacts

Human activities change during the day causing a typical diurnal cycle of urban emissions. Moreover, the urban canopy meteorological forcing has also a distinct diurnal pattern, e.g. the modification of temperature is strongest during night, the impacts on wind and turbulence are the strongest during day-time and so on (Huszar et al., 2018a). It is thus expected that the individual contributors to the total impact of RUT analyzed here will have also a distinct diurnal cycle.

In Fig. 12 and 13 we present the diurnal cycles for the four contributors' impact on PM_{2.5} and its components during winter and summer averaged over all urban centres (we took the model gridbox covering the city centre, in a similar way as in Fig 4). In case of PM_{2.5} in winter, "DEMIS" causes a typical diurnal variation resembling the diurnal cycle of urban emissions (varying between 1.5 and $4 \mu\text{g m}^{-3}$), this is also seen for PEC, when maxima occur during morning and evening rush hours. A similar diurnal pattern is seen also for sulphates varying between 0.1 and $0.2 \mu\text{g m}^{-3}$. For other secondary aerosol components the diurnal cycles are characterized by only one maximum: for nitrates, the maximum occurs during noon time reaching $0.25 \mu\text{g m}^{-3}$, while for ammonium, the maximum emission impact is reached during morning reaching $0.1 \mu\text{g m}^{-3}$. SOA are increased due to emission at most during early afternoon by up to $0.015 \mu\text{g m}^{-3}$. In case of the impact of UCMF ("DMET"), it is usually negative for PM_{2.5} being lowest during afternoon reaching around $-1 \mu\text{g m}^{-3}$. For PEC and PSO₄, the maximum decrease is about -0.2 and $-0.1 \mu\text{g m}^{-3}$, respectively. For PNO₃ and PNH₄ and SOA, it is again negative during afternoon hours reaching -0.2 , -0.07 and $-0.02 \mu\text{g m}^{-3}$, respectively. The impact of increased deposition velocities is negative in all cases and throughout the whole day in winter. However, the diurnal patterns indicate that the maximum decrease is modelled for early afternoon hours, reaching $-0.3 \mu\text{g m}^{-3}$ for PM_{2.5}. For PEC, PSO₄, PNO₃ and PNH₄, it reaches -0.02 , -0.02 , -0.01

485 and $-0.04 \mu\text{gm}^{-3}$, respectively. For SOA, the maximum decrease reaches $-0.016 \mu\text{gm}^{-3}$. As expected, the impact of modified BVOC emissions is almost negligible with weak maximum decrease during afternoon and evening hours for SOA (around $-0.002 \mu\text{gm}^{-3}$).

The JJA diurnal cycles of the impacts are similar to DJF in case of “DEMIS” with two maxima for PM_{2.5}, PEC and PSO₄, while a single maximum due to emissions is modelled for the other components. For the “DMET”, again an early evening decrease is modelled reaching -0.5 and $-0.1 \mu\text{gm}^{-3}$ for PM_{2.5} and PEC. The impact on PSO₄ is very small reaching $-0.01 \mu\text{gm}^{-3}$, while for PNO₃, PNH₄ and SOA, the maximum decrease is about -0.15 , -0.04 and $-0.05 \mu\text{gm}^{-3}$, respectively. The summer “DLU_D” impact on PM_{2.5} and its components has a distinct cycle compared to DJF with usually a morning maximum decrease. This reaches $-0.16 \mu\text{gm}^{-3}$ for PM_{2.5}. It is further very small for PEC. For PSO₄, PNO₃, PNH₄ and SOA reaching -0.02 , -0.15 , -0.03 and $-0.025 \mu\text{gm}^{-3}$, respectively. In contrary to DJF, the impact of biogenic emissions changes due to urbanization show a clear diurnal cycle for all PM components except PEC, which does not interact with gas-phase species. For PM_{2.5}, concentrations decrease and this decrease is at its maximum during evening hours reaching $-0.08 \mu\text{gm}^{-3}$. For PSO₄, increases are modelled reaching their maximum during noon time ($0.005 \mu\text{gm}^{-3}$), while for PNO₃ and PNH₄, increase is modelled too, but during afternoon there is a slight decrease of nitrate concentrations. In case of SOA, a strong decrease is modelled during evening hours reaching $-0.075 \mu\text{gm}^{-3}$ which clearly determines the overall cycle for total PM_{2.5}. For other hours, the decrease of SOA in JJA is around $-0.05 \mu\text{gm}^{-3}$.

The presented diurnal variations are in close relation to diurnal pattern of emissions, both anthropogenic (in case of “DEMIS”) and biogenic (in case of “DBVOC”) and also to the diurnal cycle of UCMF (in case of “DMET”). While for emissions, these are more or less well known (maximum during daytime for BVOC and two daytime maxima in case of anthropogenic emissions), for UCMF the underlying causes are hidden in the diurnal pattern of individual components in UCMF (temperature, wind, planetary boundary layer height, turbulence etc.) and these have been modelled and well described in our previous studies (Huszar et al., 2018a, b, 2020a). However, the diurnal pattern of deposition velocities for PM and their urbanization-induced modifications have not yet been evaluated. Therefore here, to accompany the diurnal variation of concentrations, we plot the diurnal variation of the changes of DV due to urban land-surface as well as the absolute values (corresponding to non-urbanized land-surface). We chose PEC as a representative PM component (note, that DV are a function of PM size only and we consider only fine aerosol in this study). The results are depicted in Fig. 14. The absolute DVs range between 0.8 and 1.2 mms^{-1} and 0.8 and 1.5 mms^{-1} in DJF and JJA, respectively. The maximum values are reached during noontime. The changes due to the introduction of urban land-surface follow a very similar pattern with the highest impact during noon-time reaching 0.8 and 0.5 mms^{-1} in DJF and JJA, respectively and being about 0.5 - 0.6 and 0.3 mms^{-1} during night-time for both seasons.

4 Discussion and conclusions

515 In this study, an analysis of the different contributors to the overall impact of urbanization (called rural-urban-transformation; RUT) on fine particulate matter concentrations over central Europe was presented. It focused on the four most important contributors to RUT: the impact of urban emissions only (“DEMIS”), the impact of the UCMF (urban canopy meteorological

forcing) on PM transport and chemistry (“DMET”), the impact of modified dry-deposition velocities due to the urbanized land-cover (“DLU_D”) and the impact of modified biogenic emissions due to modified land-cover (and associated vegetation change) and modified meteorological conditions (“DBVOC”). They were quantified by performing a set of model simulations where each of the contributors were added one-by-one starting with the reference state corresponding to non-urbanized land-surface with no urban emissions.

The model biases identified for PM_{2.5} show that some of the PM_{2.5} components are strongly underestimated in CAMx (Fig. 2). Very similar underestimation was encountered previously by Huszar et al. (2021) for selected European cities, using the same resolution and same emission data (they used however an older version of the models). Ďoubalová et al. (2020) too using CAMx reported a comparable negative bias. From the analysed aerosol components, sulphates were underestimated but this along with the model performance for nitrates and ammonia (Fig. 3) does not explain the strong negative bias for PM_{2.5}. Most probably, the organic aerosol fraction was strongly underestimated in our model, which is a general problem in CTMs and has been encountered previously by many authors (Jiang et al., 2019; Ciarelli et al., 2017), while, at the same time, it is considered as often the largest fraction of fine particulates in urban environments (Allan et al., 2010; Lanz et al., 2010). It is also probable that the bias is partly caused by the fact that the local wind-blown dust sources are not considered in our emissions model while this dust source can significantly contribute to overall PM_{2.5} over central Europe as shown recently by Liaskoni et al. (2023). The modelled negative bias for sulphates is similar to Bartik et al. (2021) who applied CAMx over a similar European domain using slightly newer emission data. Sulphates were moreover underestimated over Europe by the majority of the models used in the AQMEII phase 2 model inter-comparison (Im et al., 2015) and can be connected to overestimation of other secondary inorganic components, i.e. ammonium preferably neutralizes nitrates instead of sulphates leading to less ammonium sulphate formation (Im et al., 2015).

Due to the overall underestimated PM_{2.5} concentrations, it is expected that the impacts presented here for PM_{2.5} are underestimated too. This is true especially for the impact of emissions but as the effect of UCMF and deposition velocity change is also proportional to the concentrations they act on, the impacts presented below are underestimated most probably in these cases too.

The total impact of urbanization on PM_{2.5} over central European cities was calculated to be 1-1.5 $\mu\text{g m}^{-3}$ in average in summer while in winter, urbanization increased air pollution even more, by around 2-3 $\mu\text{g m}^{-3}$ (Fig. 4). When comparing these results to other similar studies one has to remember that this includes not only the impact of urban emissions but also the counteracting effect of UCMF and increased dry-deposition, and, in a minor way also the impact of biogenic emissions changes. Indeed, urban emissions alone increased PM_{2.5} concentration by 1.2-2 $\mu\text{g m}^{-3}$ and 1.5-3.5 $\mu\text{g m}^{-3}$ in winter and summer. These numbers are close to what was modelled in Huszar et al. (2016a) who looked only at the effect of emissions. The reason we got slightly smaller numbers is that they used 2005 emissions which were higher compared to our 2015 emissions used in this study. Our PM_{2.5} increases due to urban emissions only are also much lower than in Im and Kanakidou (2012) but they modelled Istanbul and Athens which are large megacities, much larger than the average of our central European selection. Previously, Skyllakou et al. (2014) showed for Paris that the contribution of local sources to PM is smaller, around 1 $\mu\text{g m}^{-3}$ however they used much coarser resolution and could not thus capture the city core contributions. Indeed, the contributions of

urban emissions to urban air-pollution over the urban core is much larger if higher resolutions are applied, as seen in Huszar et al. (2021) as the largest contributions occur over city centres (Thunis et al., 2021). Finardi et al. (2014) made estimates on the impact of Po valley, a highly urbanized region in Northern Italy on PM_{2.5} concentration and they found that local emissions contribute to local concentration by up to 10-20 $\mu\text{g m}^{-3}$ which is much larger contribution than our 4 $\mu\text{g m}^{-3}$ simulated for Milan (as city belonging to this region) however, they simulated the contribution from a much larger, regional emission source and not only one city.

As already seen, the total urban impact is lower if other contributors besides the urban emissions are considered. From these, the impact of UCMF showed a clear decrease of PM_{2.5} concentrations by around 0.5 $\mu\text{g m}^{-3}$ counteracting the increase due to urban emissions. Indeed, many showed that the most important component of UCMF is the enhanced vertical eddy-transport which removes pollutants from the surface layer (where they are emitted) causing decreased concentrations (Kim et al., 2015; Huszar et al., 2018b, 2020a; Zhu et al., 2017; Wei et al., 2018). Moreover, our spatial results showed that PM_{2.5} increases due to UCMF over rural areas, which was also seen in (Huszar et al., 2018b) and is probably the result of the fact that the removed PM by increased turbulence is deposited to lower model levels over other regions further from the sources (cities). However, as seen in Huszar et al. (2018a), the strong reduction of wind-speed over and around urban areas can be sometimes very strong resulting in counteracting the turbulence decrease. This in turn causes increase of urban PM_{2.5} concentrations. This probably also contributed to the modelled increases of PM_{2.5} (e.g. over the Benelux states in JJA, similar to Huszar et al. (2018b)).

Regarding the impact of urbanized land-surface on PM deposition, the results are in-line with the expectations that increased DV over cities (by 30-50%) result in decreased concentrations of PM_{2.5} (by around -0.12 $\mu\text{g m}^{-3}$ and -0.23 $\mu\text{g m}^{-3}$ in summer vs. winter). This is an although minor decrease but is seen over the whole domain with maxima, as expected, over cities. Moreover, the decrease of DV is same across all the PM_{2.5} components as in the used CTM, DV is a function of aerosol size only. Here we have to note however, that the dry-deposition parameterization used here (Zhang et al., 2001) considers urban areas as flat surfaces with prescribed roughness length and other parameters relevant for the dry-deposition. This certainly differs from reality, where the urban canopy is formed of individual objects with different surface materials, and also vegetation fraction while in each of these cases the parameters controlling the dry-deposition are different. E.g. Cherin et al. (2015) showed that “dry deposition velocities can vary by a factor of 24 between two surface types in urban areas”. Our results on the impact on urban land-surface on PM_{2.5} dry deposition are therefore a very rough estimate.

Regarding the impact of modified biogenic emissions on PM_{2.5}, these are of course acting predominantly via modifying SOA concentrations. As BVOC are a main precursor of biogenic SOA, a decrease of biogenic emissions result in decrease of SOA formation. This is more pronounced during summer, of course, when BVOC emissions are at their peak. We also modelled some secondary effects on PNO₃ (and to a smaller extent to sulphates and ammonia), which is related to influencing OH radical which in turn influences the oxidation of nitrates and also ammonium causing them to decrease (Aksoyoglu et al., 2017).

We further discuss the modelled RUT-induced modifications of the analysed PM_{2.5} components. Looking at elemental carbon, it is an inert aerosol in CAMx without chemical decay, so it is influenced via direct pathways along with changes of emissions, meteorological conditions and deposition. Indeed, urbanization increased PEC by about 0.2-0.6 $\mu\text{g m}^{-3}$ in winter

and by about $0.2\text{-}0.3\ \mu\text{g m}^{-3}$ in summer (Fig. 5), which is mainly influenced by the urban emissions alone causing slightly higher increases and the increase is predominately limited to urban areas. Indeed, e.g. Skyllakou et al. (2014) showed for Paris, that almost 60% of PEC originates from local sources although they calculated somehow stronger contributions of urban emissions to the total PEC (around $0.3\text{-}0.4\ \mu\text{g m}^{-3}$). However, Paris is at the high-end of the size distribution of cities we selected so its urban emissions will be also very large compared to the average in our selection. The total urbanization impact on PEC is again smaller than that of emission only, which is caused partly due to the effect of UCMF on PEC. Similarly to the total PM_{2.5}, PEC also responds to higher vertical eddy-diffusion above cities by decreases. A similar decrease of PEC due to UCMF as in our study was modelled in Huszar et al. (2018b) who showed that this decrease is a counteraction of a large decrease due to turbulence enhancement and a smaller increase due to reduced wind-speeds. Our results further showed that the decrease is largest during afternoon hours which is in line with Huszar et al. (2018b) and Huszar et al. (2020a). They showed that the impact of turbulence enhancement is largest during these hours of the day when the strongest mixing in- and above urban canopy occurs. The impact of enhanced deposition velocities is again expected and exhibits a clear decrease of PEC concentrations above urban areas. The impact is larger in winter in line with the larger winter absolute PEC concentration compared to summer ones. Further we showed (and this was seen for PM_{2.5} too) that the strongest decrease of PEC due to increased DV occurs during daytime, which can be clearly explained by the peaking DV values during day and thus strongest influence of urban land-surface (as shown in Fig. 14). This is a known behaviour of particle deposition velocities which are modelled to peak during early afternoon hours (e.g. Nho-Kim et al., 2004). Finally, as PEC is chemically inert, it does not respond to modification of biogenic emissions.

As a result of urbanization, sulphates increased by about $0.05\ \mu\text{g m}^{-3}$ in winter and $0.03\text{-}0.04\ \mu\text{g m}^{-3}$ in summer while urban emissions alone caused a slightly larger increase in winter (around $0.1\ \mu\text{g m}^{-3}$) and a similar one in summer (Fig. 5). These are almost 10 times smaller values compared to PEC and in general show the low sulphur fraction of urban emissions in Europe. Indeed, sulphates are emitted mainly as a result of combustion however strong reduction policies were implemented during the 80s and 90s which substantially reduced the sulphur content of combustion products (Vestreng et al., 2007). Sulphur emissions and thus sulphate formation is larger in eastern Europe (Fig. 7), especially in Poland, where coal combustion is still a significant energy producing method. This is reflected also in the emission data we used and consequently, the largest urban contribution to regional sulphate levels are above eastern Europe where often coal combustion facilities are located even within the cities outskirts or coal is used for domestic combustion. For this reason, winter sulphate increases due to urban emission are much larger than during summer. Previously, Skyllakou et al. (2014) showed a very small contribution of local sources to PSO₄ concentrations (on the case of Paris) reaching less than $0.1\ \mu\text{g m}^{-3}$ during summer, which is in line with the largest contributions in our case (e.g. over Hamburg due to shipping SO₂ emissions or over Polish cities). Due to the urban canopy meteorological forcing, sulphates decreased over cities and increased over rural areas (Fig. 8). This is expected (similarly to PM_{2.5}) as the main component acting within UCMF is the enhanced vertical eddy diffusion which removes material from the surface model layer and is deposited further from the sources causing increase elsewhere. This behavior was seen also in Huszar et al. (2018b) who have seen an decrease of sulphates of about up to $-0.5\ \mu\text{g m}^{-3}$, similar to our results. Moreover, sulphates decreased also due to decreases of its precursors, SO₂ and NH₃ driven by the same mechanism. Indeed, we showed

in Huszar et al. (2022) too that SO₂ usually decreases above cities by about 0.5 ppbv. NH₃ also decreases as seen in Fig. 15 by about up to 1 ppbv in both seasons, limiting the formation of ammonium sulphate. Also Kang et al. (2022) showed that near the surface, sulphates decrease due to the enhanced urban mixing (an increase in the free troposphere above). It has to be noted however, that the UCMF induced modifications are a trade-off between the wind-speed decreases which increase the urban concentrations and the turbulence-induced decreases. In some studies, e.g. Huszar et al. (2018b) the wind speed decrease is more important and can cause that they have higher urban concentrations due to UCMF. As expected, sulphates decreased as a result of increased dry-deposition velocities (Fig. 9) and this is amplified also by the increased dry-deposition of SO₂ due to urbanization as shown in Huszar et al. (2022). Finally, the impact of reduced urban BVOC emissions on PSO₄ is negligible, only some very small increases during summer are modelled. This may be explained by the less OH radical reacting to oxidize biogenic hydrocarbons which thus can oxidize more SO₂ (Aksoyoglu et al., 2017).

Urbanization increased nitrates and ammonium by about 0.1 µgm⁻³ and 0.25 µgm⁻³ respectively with higher numbers in winter (Fig. 5), which is clear as the absolute concentrations of these secondary aerosols are also higher in winter. The impact of emissions alone is also clearly higher in winter, which is caused by stronger NO_x emissions (mainly combustion and transport) and by usually higher ammonia emissions too during the colder part of the year (although these can have a smaller late summer peak too; e.g. Drugé et al., 2019) (see Fig. 7). Again, the emission impact is higher than the one from total urbanization and this is caused (similarly to PM_{2.5}, PEC or sulphates) to the effect of UCMF, which is dominated by increased vertical eddy-diffusion. This reduces the near surface concentrations of both aerosol as well as of their precursors (NO_x and NH₃). Previously, Huszar et al. (2018b) showed decreases of PNO₃ and PNH₄ over central European cities due to the UCMF by about 0.02-0.04 and 0.02 µgm⁻³ in summer (they did not look on winter) which is slightly smaller for nitrates than our numbers and is comparable to ammonium modification presented in this work. The decrease of PNO₃ and PNH₄ is also caused by the decreases of nitrogen oxides and ammonia as seen on Fig. 15 or previously in Huszar et al. (2018b, 2022). Recently, also Kang et al. (2022) reported higher nitrate and ammonium values above a large Chinese agglomeration if the urban land-surface and the associated UCMF was not considered. Similar to sulphates, PNO₃ and PNH₄ responded to urbanization induced land-surface changes by increased dry-deposition velocities resulting in their decrease. In winter, this was partly caused also by the reduced NH₃ due to increased dry-deposition, however for JJA, we modelled increased ammonia concentration due to dry-deposition changes due to urbanization (see Fig.15). Indeed, the used dry-deposition model (Zhang et al., 2003) predicts for NH₃ in case of dry-canopies (i.e. summer conditions) smaller dry-deposition velocities for urban areas compared to rural ones (e.g, crops). Finally, as a result of decreased urban BVOC emissions, some increases of nitrates and ammonium are modelled which can be connected to more OH available to oxidize NO_x (Aksoyoglu et al., 2017) but also less NO_x is reacting with organic molecules to create organic nitrates (Fischer et al., 2014). E.g. Jiang et al. (2019) showed that smaller biogenic emissions fluxes result in increased PNO₃ and PNH₄ concentrations over central Europe, while the impact on PNO₃ is larger, which is in line with our results.

The impact of urbanization on secondary organic aerosol concentration is notable only during summer (Fig. 5) owing to the suppressed oxidation of VOC in winter and small BVOC emissions responsible for biogenic SOA formation during the cold part of the year (Gao et al., 2022; Zhai et al., 2023). The total summer impact of urbanization is about 0.03-0.05 µgm⁻³ (reaching

0.1 μgm^{-3}) while the emission impact alone is again larger often exceeding 0.1 μgm^{-3} . A very similar summer contribution of urban emissions from Paris was modelled earlier by Skyllakou et al. (2014) who pointed out that the contribution of SOA to the total urban impact is about 5-10%. Freney et al. (2014) arrived to similar results and argued that contribution of SOA gets larger as the urban plume ages. Regarding the impact of UCMF on SOA in summer (Fig. 8), it is characterized by both increases and decreases, depending on the city with an average slightly below zero (around $-0.01 \mu\text{gm}^{-3}$). The reason for this is probably in the inter-play between the reduction caused by the increased vertical eddy diffusion and increase caused by the decreased urban wind-speeds, while increased urban temperatures shift the partitioning between the gas-phase and particulate-phase towards the gas-phase (Huszar et al., 2018b; Wang et al., 2009). This means the impact over a particular city depends on relative magnitude of these three components of UCMF and how they act on SOA. The UCMF caused also a relatively large impact over rural areas, which can be explained also by the fact that SOA is formed more readily in an aged urban plume (Ortega et al., 2016), so probably the removed SOA precursors by the increased vertical eddy diffusion were transported over rural areas while oxidized and condensed into SOA. Regarding the impact of increased PM deposition velocities due to urbanization, the impact follows those for secondary inorganic aerosol or PEC, i.e. the urban concentrations decreased (by around $-0.02 \mu\text{gm}^{-3}$). Here again, one must realize that the the modified DVs impacted also the precursor species which oxidize to semi-volatile compounds. In CAMx in the Zhang deposition model for gases (Zhang et al., 2003), the deposition velocities for SOA precursors (and most of VOCs) are smaller for urban canopies which means their concentration are larger for urban areas. Hence more SOA formation is favored because higher precursors abundances. This consequently means that the final impact on SOA is a counteract between the decrease due to direct impact of urbanization induced land-use change on SOA deposition velocities and increase due to higher precursor concentrations. In our simulation the former was the dominating effect as SOA decreased above all urban areas. Finally, the urbanization induced decrease of BVOC emissions resulted in a reduction of SOA concentrations (by about $0.04-0.06 \mu\text{gm}^{-3}$) and this decrease is modelled not only over urban areas but over large rural regions while the largest decrease is above Milan which has also the warmest climate among the selected cities (Fig. 5 and 11). Indeed, SOA of biogenic origin is an important contributor to urban SOA levels so the modelled decreases were expected (Couvidat et al., 2013; Hu et al., 2017). Ghirardo et al. (2016) also calculated strong influence of local BVOC emissions from urban trees in a Chinese megacity (although the anthropogenic influences were much larger). Again, the impact affected also rural areas which can be explained by the repeated fact that in aged urban plumes, SOA forms more effectively.

In summary, we evaluated over a sample of 19 Central European cities the impact of rural-to-urban transformation and its four contributors on PM urban (and rural) concentrations including the impact on its primary and secondary components. We found that the two main controlling drivers are the impact of urban emissions themselves (increases the concentrations for PM_{2.5} and all of its analyzed components) and the urban canopy meteorological forcing (usually decreases over urban areas, increases over rural ones). We showed however that two additional controlling mechanisms can play important role within the process of urbanization although smaller by an order of magnitude than the effect of emissions and UCMF: the impact of dry-deposition velocity changes due to urbanization of land-surface and the reduction of biogenic emissions by turning rural/natural land-surface into urban built-up. The former results in decreases of concentrations due to increased deposition velocities, the later acts predominantly via modification of secondary organic aerosols and results in decrease of PM_{2.5} concentrations (by

reducing SOA). In summary, when the impact of urbanization on PM air-pollution is analyzed, all four contributors have to be accounted for.

695 It has to be also discussed what impact has the order of application of the contributors on their magnitude. The experiment design started with addition of the urban emission (DEMIS) to the reference (non-urbanized) state as this impact was assumed (and proven) to be the dominant. With this choice, the urban atmosphere was already filled with pollutants serving as base state for the other impacts. The impact of the order of addition of the two further contributors, DLU and DBVOC is probably small as their effect is also small. However, if they were applied before DEMIS, their magnitude would be probably even smaller: the deposition flux depends on the absolute concentrations (Zhang et al., 2003) while adding BVOC to a high-NOx air can have mixed effects leading to both increases and decreases of secondary organic aerosol (Li et al., 2019b; Pullinen et al., 2020). Further, in our previous paper Huszar et al. (2022) which had the same goal and modelling design as this paper but looked at the gas-phase chemistry, we analysed in detail the effect of the order of the two sub-contributors of DBVOC, which are the impact of reduced vegetation (DBVOC_L; see Huszar et al. (2022)) and impact of changed meteorological conditions that drive the MEGAN model impacting BVOC fluxes (DBVOC_M). We found that 1) with regard to DBVOC, the changes of vegetation cover play a much more important role than the changed meteorological conditions 2) the partial impact of changed meteorological conditions is smaller if applied after DBVOC_L. As for the DMET impact, this is in general the second strongest contributor and one gets different magnitude of the impacts if DMET is applied before DEMIS. Let's suppose that first the DMET contributor has been applied. This means that the meteorological conditions that drive the impact of emissions consider the urban canopy meteorological forcing (UCMF). Huszar et al. (2021) however showed that the impact of urban emissions is considerably (almost by 50%) smaller if UCMF is accounted for. On the other hand, DMET applied as the first contributor would be very small as UCMF would act on a much less polluted air (with missing urban emissions). So in conclusion, the DLU, DBVOC and DMET impacts would be smaller if applied before DEMIS and somehow decoupled from the reality motivating us to start the addition of the different components of urbanization by the emissions themselves. The choice of the order of the other three contributors has rather much smaller effect.

715 We must also stress that that the cities selected in this study are from a relatively small region meaning that they do not exhibit a substantially different background climate. Moreover the typical "rural" vegetation was assumed to be crop which might not be the case if cities over other parts of the world were considered (e.g. tropical areas) meaning that the impact of modified biogenic emissions could be much stronger. Further, some secondary effect of PM concentration changes can play role too via the direct and indirect radiative effect. E.g. photolysis rates and temperatures are altered via the direct effect of aerosol that in turn influences air chemistry (Han et al., 2020; Wang et al., 2022) or the vertical structure of urban boundary layer can be altered by the aerosol emitted that modifies the overall stability and convection (Miao et al., 2020; Slater et al., 2022; Fan et al., 2020; Yu et al., 2020; López-Romero et al., 2021) which in turn can modify the vertical mixing and precipitation with feedbacks on species concentration. Consequently, to obtain a more accurate quantification of the impact of rural-to-urban transformation on PM, these effect has to be included in modelling studies.

Code and data availability. The RegCM4.7 model is freely available for public use at <https://github.com/ICTP/RegCM> (last access May 16, 2023) (Giuliani, 2021). CAMx version 7.10 is available at <http://www.camx.com/download/default.aspx> (last access May 16, 2023) (Ramboll, 2020). The RegCM2CAMx meteorological preprocessor used to convert RegCM outputs to CAMx inputs and the MEGAN v2.10 code as used by the authors is available upon request from the main author. The complete model configuration and all the simulated data
730 (3-dimensional hourly data) used for the analysis are stored at the Dept. of Atmospheric Physics of the Charles University data storage facilities (about 5TB) and are available upon request from the main author.

Author contributions. PH created the concept and designed the experiments, PH and JK performed the model simulations, APPP, LB and AVP contributed to input data preparation, model configuration and analysis of the outputs, ALL authors contributed to the manuscript text.

Competing interests. The authors declare that they have no conflict of interest.

735 *Acknowledgements.* This work has been funded by the Czech Science Foundation (GACR) project No. 19-10747Y, by the Czech Technological Agency (TACR) grant No.SS02030031 ARAMIS (Air Quality Research Assessment and Monitoring Integrated System) and by project – Programmes of Charles University. We further acknowledge the CAMS-REG-APv1.1 emissions dataset provided by the Copernicus Atmosphere Monitoring Service, the Air Pollution Sources Register (REZZO) dataset provided by the Czech Hydrometeorological Institute and the ATEM Traffic Emissions dataset provided by ATEM (Studio of ecological models). We also acknowledge the providers of AirBase
740 European Air Quality data (<http://www.eea.europa.eu/data-and-maps/data/aqereporting-1>).

References

- Allan, J. D., Williams, P. I., Morgan, W. T., Martin, C. L., Flynn, M. J., Lee, J., Nemitz, E., Phillips, G. J., Gallagher, M. W., and Coe, H.: Contributions from transport, solid fuel burning and cooking to primary organic aerosols in two UK cities, *Atmos. Chem. Phys.*, 10, 647–668, <https://doi.org/10.5194/acp-10-647-2010>, 2010.
- 745 Aksoyoglu, S., Ciarelli, G., El-Haddad, I., Baltensperger, U., and Prévôt, A. S. H.: Secondary inorganic aerosols in Europe: sources and the significant influence of biogenic VOC emissions, especially on ammonium nitrate, *Atmos. Chem. Phys.*, 17, 7757–7773, <https://doi.org/10.5194/acp-17-7757-2017>, 2017.
- Balamurugan, V., Chen, J., Qu, Z., Bi, X., and Keutsch, F. N.: Secondary PM_{2.5} decreases significantly less than NO₂ emission reductions during COVID lockdown in Germany, *Atmos. Chem. Phys.*, 22, 7105–7129, <https://doi.org/10.5194/acp-22-7105-2022>, 2022.
- 750 Bartík, L., Huszár, P., Vlček, O. and K. Eben, Sensitivity of Secondary Inorganic Aerosol Concentrations to Precursor Emissions and Inorganic Aerosol Modules in CAMx over Central Europe, in WDS'21 Proceedings of Contributed Papers – Physics (eds. J. Šafránková and J. Pavlů), Prague, Matfyzpress, 77–84, https://www.mff.cuni.cz/veda/konference/wds/proc/pdf21/WDS21_10_f8_Bartik.pdf (last access 5 May 2023), 2021.
- Beekmann, M. and Vautard, R.: A modelling study of photochemical regimes over Europe: robustness and variability, *Atmos. Chem. Phys.*, 10, 10067–10084, doi:10.5194/acp-10-10067-2010, 2010.
- 755 Behera, N. S. and Sharma, M.: Investigating the potential role of ammonia in ion chemistry of fine particulate matter formation for an urban environment, *Sci. Total Environ.*, 408, 3569–3575, 2010.
- Benešová, N., Belda, M., Eben, K., Geletič, J., Huszár, P., Juruš, P., Krč, P., Resler, J. and Vlček, O.: New open source emission processor for air quality models, In Sokhi, R., Tiwari, P. R., Gállego, M. J., Cravioito Arnau, J. M., Castells Guiu, C. and Singh, V. (eds) Proceedings of Abstracts 11th International Conference on Air Quality Science and Application, doi: 10.18745/PB.19829. (pp. 27). Published by University of Hertfordshire. Paper presented at Air Quality 2018 conference, Barcelona, 12-16 March, 2018.
- 760 Butler, T. M. and Lawrence, M. G.: The influence of megacities on global atmospheric chemistry: a modelling study, *Environ. Chem.*, 6, 219–225, doi:10.1071/EN08110, 2009.
- Buchholz, R. R., Emmons, L. K., Tilmes, S. and The CESM2 Development Team: CESM2.1/CAM-chem Instantaneous Output for Boundary Conditions. UCAR/NCAR - Atmospheric Chemistry Observations and Modeling Laboratory. Subset used Lat: 10 to 80, Lon: -20 to 50, December 2014 - January 2017, Accessed: 19/09/2019, <https://doi.org/10.5065/NMP7-EP60>, 2019.
- 765 Byun, D. W. and Ching, J. K. S.: Science Algorithms of the EPA Model-3 Community Multiscale Air Quality (CMAQ) Modeling System. Office of Research and Development, U.S. EPA, North Carolina, 1999.
- Cao, L., Li, S., and Sun, L.: Study of different Carbon Bond 6 (CB6) mechanisms by using a concentration sensitivity analysis, *Atmos. Chem. Phys.*, 21, 12687–12714, <https://doi.org/10.5194/acp-21-12687-2021>, 2021.
- 770 Ciarelli, G., Aksoyoglu, S., El Haddad, I., Bruns, E. A., Crippa, M., Poulain, L., Äijälä, M., Carbone, S., Freney, E., O'Dowd, C., Baltensperger, U., and Prévôt, A. S. H.: Modelling winter organic aerosol at the European scale with CAMx: evaluation and source apportionment with a VBS parameterization based on novel wood burning smog chamber experiments, *Atmos. Chem. Phys.*, 17, 7653–7669, <https://doi.org/10.5194/acp-17-7653-2017>, 2017.
- 775 Couvidat, F., Kim, Y., Sartelet, K., Seigneur, C., Marchand, N., and Sciare, J.: Modeling secondary organic aerosol in an urban area: application to Paris, France, *Atmos. Chem. Phys.*, 13, 983–996, <https://doi.org/10.5194/acp-13-983-2013>, 2013.

- Cherin, N., Roustan, Y., Musson-Genon, L., and Seigneur, C.: Modelling atmospheric dry deposition in urban areas using an urban canopy approach, *Geosci. Model Dev.*, 8, 893–910, <https://doi.org/10.5194/gmd-8-893-2015>, 2015.
- 780 Ďoubalová, J.; Huszár, P.; Eben, K.; Benešová, N.; Belda, M.; Vlček, O.; Karlický, J.; Geletič, J.; Halenka, T.: High Resolution Air Quality Forecasting Over Prague within the URBI PRAGENSI Project: Model Performance During the Winter Period and the Effect of Urban Parameterization on PM, *Atmosphere*, 11, 625, 2020.
- Drugé, T., Nabat, P., Mallet, M., and Somot, S.: Model simulation of ammonium and nitrate aerosols distribution in the Euro-Mediterranean region and their radiative and climatic effects over 1979–2016, *Atmos. Chem. Phys.*, 19, 3707–3731, <https://doi.org/10.5194/acp-19-3707-2019>, 2019.
- 785 EEA: Air quality in Europe 2022, Report no. 05/2022, <https://www.eea.europa.eu/publications/air-quality-in-europe-2022>, last access: 25 January 2023, 2022.
- Emmons, L. K., Schwantes, R. H., Orlando, J. J., Tyndall, G., Kinnison, D., Lamarque, J.-F., et al.: The Chemistry Mechanism in the Community Earth System Model version 2 (CESM2), *J. Adv. Model. Earth Sys.*, 12, e2019MS001882. <https://doi.org/10.1029/2019MS001882>, 2020.
- 790 Ramboll, CAMx User’s Guide, Comprehensive Air Quality model with Extentions, version 7.10, www.camx.com, Novato, California, 2020.
- Fan, J., Zhang, Y., Li, Z., Hu, J., and Rosenfeld, D.: Urbanization-induced land and aerosol impacts on sea-breeze circulation and convective precipitation, *Atmos. Chem. Phys.*, 20, 14163–14182, <https://doi.org/10.5194/acp-20-14163-2020>, 2020.
- Fenech, S., Doherty, R. M., Heaviside, C., Vardoulakis, S., Macintyre, H. L., and O’Connor, F. M.: The influence of model spatial resolution on simulated ozone and fine particulate matter for Europe: implications for health impact assessments, *Atmos. Chem. Phys.*, 18, 5765–5784, <https://doi.org/10.5194/acp-18-5765-2018>, 2018.
- 795 Finardi, S., Silibello, C., D’Allura, A., and Radice, P.: Analysis of pollutants exchange between the Po Valley and the surrounding European region, *Urban Climate*, 10, 682–702, doi:10.1016/j.uclim.2014.02.002, 2014.
- Fischer, E. V., Jacob, D. J., Yantosca, R. M., Sulprizio, M. P., Millet, D. B., Mao, J., Paulot, F., Singh, H. B., Roiger, A., Ries, L., Talbot, R. W., Dzepina, K., and Pandey Deolal, S.: Atmospheric peroxyacetyl nitrate (PAN): a global budget and source attribution, *Atmos. Chem. Phys.*, 14, 2679–2698, <https://doi.org/10.5194/acp-14-2679-2014>, 2014.
- 800 Folberth, G. A., Butler, T. M., Collins, W. J., and Rumbold, S. T.: Megacities and climate change – A brief overview, *Environ. Pollut.*, 203, 235–242, <http://dx.doi.org/10.1016/j.envpol.2014.09.004>, 2015.
- Freney, E. J., Sellegri, K., Canonaco, F., Colomb, A., Borbon, A., Michoud, V., Doussin, J.-F., Crumeyrolle, S., Amarouche, N., Pichon, J.-M., Bourianne, T., Gomes, L., Prevot, A. S. H., Beekmann, M., and Schwarzenböeck, A.: Characterizing the impact of urban emissions on regional aerosol particles: airborne measurements during the MEGAPOLI experiment, *Atmos. Chem. Phys.*, 14, 1397–1412, [10.5194/acp-14-1397-2014](https://doi.org/10.5194/acp-14-1397-2014), 2014.
- 805 Ganbat, G., Baik, J. J. and Ryu, Y. H.: A numerical study of the interactions of urban breeze circulation with mountain slope winds, *Theor. App. Clim.*, 120(1-2), 123–135, 2015.
- Gao, J. and O’Neill B. C.: Mapping global urban land for the 21st century with data-driven simulations and Shared Socioeconomic Pathways, *Nature Com.*, 11, 2302, <https://doi.org/10.1038/s41467-020-15788-7>, 2020.
- 810 Gao, Y., Mingchen Ma, Feifan Yan, Hang Su, Shuxiao Wang, Hong Liao, Bin Zhao, Xuemei Wang, Yele Sun, James R. Hopkins, Qi Chen, Pingqing Fu, Alastair C. Lewis, Qionghui Qiu, Xiaohong Yao, Huiwang Gao, Impacts of biogenic emissions from urban landscapes on summer ozone and secondary organic aerosol formation in megacities, *Sci. Tot. Environ.*, 814, 152654, <https://doi.org/10.1016/j.scitotenv.2021.152654>, 2022.

- 815 Ghirardo, A., Xie, J., Zheng, X., Wang, Y., Grote, R., Block, K., Wildt, J., Mentel, T., Kiendler-Scharr, A., Hallquist, M., Butterbach-Bahl, K., and Schnitzler, J.-P.: Urban stress-induced biogenic VOC emissions and SOA-forming potentials in Beijing, *Atmos. Chem. Phys.*, 16, 2901–2920, <https://doi.org/10.5194/acp-16-2901-2016>, 2016.
- Giani, P., Balzarini, A., Pirovano, G., Gilardoni, S., Paglione, M., Colombi, C., Gianelle, V. L., Belis, C. A., Poluzzi, V., and Lonati, G.: Influence of semi- and intermediate-volatile organic compounds (S/IVOC) parameterizations, volatility distributions and aging schemes
820 on organic aerosol modelling in winter conditions, *Atmos. Environ.*, 213, 11–24, <https://doi.org/10.1016/j.atmosenv.2019.05.061>, 2019.
- Giorgi, F., Coppola, E., Solmon, F., Mariotti, L., Sylla, M., Bi, X., Elguindi, N., Diro, G. T., Nair, V., Giuliani, G., Cozzini, S., Guettler, I., O'Brien, T. A., Tawfi, A. B., Shalaby, A., Zakey, A., Steiner, A., Stordal, F., Sloan, L., and Brankovic, C.: RegCM4: model description and preliminary tests over multiple CORDEX domains, *Clim. Res.*, 52, 7–29, 2012.
- ICTP: The Regional Climate Model version 4.7 source code (provided by Graziano Giuliani), <https://github.com/ictp-esp/RegCM/releases?after=4.7.9> (last access 2021/03/31), 2021.
825
- van der Gon, H. D., Hendriks, C., Kuenen, J., Segers, A. and Visschedijk, A.: Description of current temporal emission patterns and sensitivity of predicted AQ for temporal emission patterns. EU FP7 MACC deliverable report D_D-EMIS_1.3, http://www.gmes-atmosphere.eu/documents/deliverables/d-emis/MACC_TNO_del_1_3_v2.pdf, 2011.
- Granier, C.S., Darras, H., Denier van der Gon, J., Doubalova, N., Elguindi, B., Galle, M., Gauss, M., Guevara, J.-P., Jalkanen, J. and Kuenen, C.: The Copernicus Atmosphere Monitoring Service Global and Regional Emissions; Report April 2019 version [Research Report]; ECMWF: Reading, UK, doi:10.24380/d0bn-kx16, 2019.
830
- Guenther, A., Karl, T., Harley, P., Wiedinmyer, C., Palmer, P. I., and Geron, C.: Estimates of global terrestrial isoprene emissions using MEGAN (Model of Emissions of Gases and Aerosols from Nature), *Atmos. Chem. Phys.*, 6, 3181–3210, <https://doi.org/10.5194/acp-6-3181-2006>, 2006.
- 835 Guenther, A. B., Jiang, X., Heald, C. L., Sakulyanontvittaya, T., Duhl, T., Emmons, L. K., and Wang, X.: The Model of Emissions of Gases and Aerosols from Nature version 2.1 (MEGAN2.1): an extended and updated framework for modeling biogenic emissions, *Geosci. Model Dev.*, 5, 1471–1492, <https://doi.org/10.5194/gmd-5-1471-2012>, 2012.
- Guo, Y., Yan, C., Liu, Y., Qiao, X., Zheng, F., Zhang, Y., Zhou, Y., Li, C., Fan, X., Lin, Z., Feng, Z., Zhang, Y., Zheng, P., Tian, L., Nie, W., Wang, Z., Huang, D., Daellenbach, K. R., Yao, L., Dada, L., Bianchi, F., Jiang, J., Liu, Y., Kerminen, V.-M., and Kulmala, M.: Seasonal
840 variation in oxygenated organic molecules in urban Beijing and their contribution to secondary organic aerosol, *Atmos. Chem. Phys.*, 22, 10077–10097, <https://doi.org/10.5194/acp-22-10077-2022>, 2022.
- Guttikunda, K. S., Carmichael, G. R., Calori, G., Eck, C., and Woo, J.-H.: The contribution of megacities to regional sulfur pollution in Asia, *Atmos. Environ.*, 37, 11–22, doi:10.1016/S1352-2310(02)00821-X, 2003.
- Guttikunda, S. K., Tang, Y., Carmichael, G. R., Kurata, G., Pan, L., Streets, D. G., Woo, J.-H., Thongboonchoo, N., and Fried, A.: Impacts of
845 Asian megacity emissions on regional air quality during spring 2001, *J. Geophys. Res.*, 110, D20301, doi:10.1029/2004JD004921, 2005.
- Han, W., Li, Z., Wu, F., Zhang, Y., Guo, J., Su, T., Cribb, M., Fan, J., Chen, T., Wei, J., and Lee, S.-S.: The mechanisms and seasonal differences of the impact of aerosols on daytime surface urban heat island effect, *Atmos. Chem. Phys.*, 20, 6479–6493, <https://doi.org/10.5194/acp-20-6479-2020>, 2020.
- Hardacre, C., Mulcahy, J. P., Pope, R. J., Jones, C. G., Rumbold, S. T., Li, C., Johnson, C., and Turnock, S. T.: Evaluation of SO₂, SO₄²⁻ and an updated SO₂ dry deposition parameterization in the United Kingdom Earth System Model, *Atmos. Chem. Phys.*, 21, 18465–18497,
850 <https://doi.org/10.5194/acp-21-18465-2021>, 2021.

- Hodnebrog, Ö., Stordal, F., and Berntsen, T. K.: Does the resolution of megacity emissions impact large scale ozone?, *Atmos. Environ.*, 45, 6852–6862, 2011.
- 855 Holtslag, A. A. M., de Bruijn, E. I. F., and Pan, H.-L.: A high resolution air mass transformation model for shortrange weather forecasting, *Mon. Wea. Rev.*, 118, 1561–1575, 1990.
- Hong, S.-Y., Dudhia, J. and Chen, S.-H.: A Revised Approach to Ice Microphysical Processes for the Bulk Parameterization of Clouds and Precipitation, *Month. Weather Rev.*, 132, 103-120., [http://dx.doi.org/10.1175/1520-0493\(2004\)132<0103:ARATIM>2.0.CO;2](http://dx.doi.org/10.1175/1520-0493(2004)132<0103:ARATIM>2.0.CO;2), 2004.
- Hood, C., MacKenzie, I., Stocker, J., Johnson, K., Carruthers, D., Vieno, M., and Doherty, R.: Air quality simulations for London using a coupled regional-to-local modelling system, *Atmos. Chem. Phys.*, 18, 11221–11245, <https://doi.org/10.5194/acp-18-11221-2018>, 2018.
- 860 Hu, J., Wang, P., Ying, Q., Zhang, H., Chen, J., Ge, X., Li, X., Jiang, J., Wang, S., Zhang, J., Zhao, Y., and Zhang, Y.: Modeling biogenic and anthropogenic secondary organic aerosol in China, *Atmos. Chem. Phys.*, 17, 77–92, <https://doi.org/10.5194/acp-17-77-2017>, 2017.
- Huszar, P., Miksovsky, J., Pisoft, P., Belda, M., and Halenka, T.: Interactive coupling of a regional climate model and a chemistry transport model: evaluation and preliminary results on ozone and aerosol feedback, *Clim. Res.*, 51, 59–88, doi:10.3354/cr01054, 2012.
- Huszar, P., Halenka, T., Belda, M., Zak, M., Sindelarova, K., and Miksovsky, J.: Regional climate model assessment of the urban land-surface forcing over central Europe, *Atmos. Chem. Phys.*, 14, 12393-12413, doi:10.5194/acp-14-12393-2014, 2014.
- 865 Huszar, P., Belda, M., and Halenka, T.: On the long-term impact of emissions from central European cities on regional air quality, *Atmos. Chem. Phys.*, 16, 1331–1352, doi:10.5194/acp-16-1331-2016, 2016a.
- Huszár, P., Belda, M., Karlický, J., Pišoft, P., and Halenka, T.: The regional impact of urban emissions on climate over central Europe: present and future emission perspectives, *Atmos. Chem. Phys.*, 16, 12993-13013, doi:10.5194/acp-16-12993-2016, 2016b.
- 870 Huszar, P., Karlický, J., Belda, M., Halenka, T. and Pisoft, P.: The impact of urban canopy meteorological forcing on summer photochemistry, *Atmos. Environ.*, 176, 209-228, <https://doi.org/10.1016/j.atmosenv.2017.12.037>, 2018a.
- Huszar, P., Belda, M., Karlický, J., Bardachova, T., Halenka, T., and Pisoft, P.: Impact of urban canopy meteorological forcing on aerosol concentrations, *Atmos. Chem. Phys.*, 18, 14059-14078, <https://doi.org/10.5194/acp-18-14059-2018>, 2018b.
- 875 Huszar, P., Karlický, J., Ďoubalová, J., Šindelářová, K., Nováková, T., Belda, M., Halenka, T., Žák, M., and Pišoft, P.: Urban canopy meteorological forcing and its impact on ozone and PM2.5: role of vertical turbulent transport, *Atmos. Chem. Phys.*, 20, 1977-2016, <https://doi.org/10.5194/acp-20-11977-2020>, 2020a.
- Huszar, P., Karlický, J., Ďoubalová, J., Nováková, T., Šindelářová, K., Švábik, F., Belda, M., Halenka, T., and Žák, M.: The impact of urban land-surface on extreme air pollution over central Europe, *Atmos. Chem. Phys.*, 20, 11655–11681, <https://doi.org/10.5194/acp-20-11655-2020>, 2020b.
- 880 Huszar, P., Karlický, J., Marková, J., Nováková, T., Liaskoni, M., and Bartík, L.: The regional impact of urban emissions on air quality in Europe: the role of the urban canopy effects, *Atmos. Chem. Phys.*, 21, 14309–14332, <https://doi.org/10.5194/acp-21-14309-2021>, 2021.
- Huszar, P., Karlický, J., Bartík, L., Liaskoni, M., Prieto Perez, A. P., and Šindelářová, K.: Impact of urbanization on gas-phase pollutant concentrations: a regional-scale, model-based analysis of the contributing factors, *Atmos. Chem. Phys.*, 22, 12647–12674, <https://doi.org/10.5194/acp-22-12647-2022>, 2022.
- 885 Im, U., Poupkou, A., Incecik, S., Markakis, K., Kindap, T., Unal, A., Melas, D., Yenigun, O., Topcu, O., Odman, M. T., Tayanc, M., and Guler, M.: The impact of anthropogenic and biogenic emissions on surface ozone concentrations in Istanbul, *Sci. Total Environ.*, 409, 1255–1265, doi:10.1016/j.scitotenv.2010.12.026, 2011a.

- 890 Im, U., Markakis, K., Poupkou, A., Melas, D., Unal, A., Gerasopoulos, E., Daskalakis, N., Kindap, T., and Kanakidou, M.: The impact of temperature changes on summer time ozone and its precursors in the Eastern Mediterranean, *Atmos. Chem. Phys.*, 11, 3847–3864, doi:10.5194/acp-11-3847-2011, 2011b.
- Im, U. and Kanakidou, M.: Impacts of East Mediterranean megacity emissions on air quality, *Atmos. Chem. Phys.*, 12, 6335–6355, doi:10.5194/acp-12-6335-2012, 2012.
- 895 Im, U., Bianconi, R., Solazzo, E., Kioutsioukis, I., Badia, A., Balzarini, A., Baro, R., Bellasio, R., Brunner, D., Chemel, C., Curci, G., Denier van der Gon, H., Flemming, J., Forkel, R., Giordano, L., Jimenez-Guerrero, P., Hirtl, M., Hodzic, A., Honzak, L., Jorba, O., Knote, C., Makar, P. A., Manders-Groot, A., Neal, L., Perez, J. L., Pirovano, G., Pouliot, G., San Jose, R., Savage, N., Schroder, W., Sokhi, R. S., Syrakov, D., Torian, A., Tuccella, P., Wang, K., Werhahn, J., Wolke, R., Zabkar, R., Zhang, Y., Zhang, J., Hogrefe, C., and Galmarini, S.: Evaluation of operational online coupled regional air quality models over Europe and North America in the context of AQMEII phase 2, Part II: particulate matter, *Atmos. Environ.*, 115, 421–441, 2015.
- 900 Jacobson, M. Z., Nghiem, S. V., Sorichetta, A., and Whitney, N.: Ring of impact from the mega-urbanization of Beijing between 2000 and 2009, *J. Geophys. Res.*, 120(12), 5740–5756, <https://doi.org/10.1002/2014JD023008>, 2015.
- Janssen, R. H. H., Tsimpidi, A. P., Karydis, V. A., Pozzer, A., Lelieveld, J., Crippa, M., Prévôt, A. S. H., Ait-Helal, W., Borbon, A., Sauvage, S. and Locoge, N.: Influence of local production and vertical transport on the organic aerosol budget over Paris, *J. Geophys. Res.*, 122(15), 8276–8296, <https://doi.org/10.1002/2016JD026402>, 2017.
- 905 Jiang, J., Aksoyoglu, S., El-Haddad, I., Ciarelli, G., Denier van der Gon, H. A. C., Canonaco, F., Gilardoni, S., Paglione, M., Minguillón, M. C., Favez, O., Zhang, Y., Marchand, N., Hao, L., Virtanen, A., Florou, K., O’Dowd, C., Ovadnevaite, J., Baltensperger, U., and Prévôt, A. S. H.: Sources of organic aerosols in Europe: a modeling study using CAMx with modified volatility basis set scheme, *Atmos. Chem. Phys.*, 19, 15247–15270, <https://doi.org/10.5194/acp-19-15247-2019>, 2019.
- Kang, H., Zhu, B., de Leeuw, G., Yu, B., van der A, R. J., and Lu, W.: Impact of urban heat island on inorganic aerosol in the lower free troposphere: a case study in Hangzhou, China, *Atmos. Chem. Phys.*, 22, 10623–10634, <https://doi.org/10.5194/acp-22-10623-2022>, 2022.
- 910 Karlický, J., Huszár, P., Halenka, T., Belda, M., Žák, M., Pišoft, P., and Mikšovský, J.: Multi-model comparison of urban heat island modelling approaches, *Atmos. Chem. Phys.*, 18, 10655–10674, doi:10.5194/acp-18-10655-2018, 2018.
- Karlický, J., Huszár, P., Nováková, T., Belda, M., Švábik, F., Ďoubalová, J., and Halenka, T.: The “urban meteorology island”: a multi-model ensemble analysis, *Atmos. Chem. Phys.*, 20, 15061–15077, <https://doi.org/10.5194/acp-20-15061-2020>, 2020.
- 915 Kim, Y., Sartelet, K., Raut, J.-Ch., and Chazette, P.: Influence of an urban canopy model and PBL schemes on vertical mixing for air quality modeling over Greater Paris, *Atmos. Environ.*, 107, 289–306, doi:10.1016/j.atmosenv.2015.02.011, 2015
- Kim, G., Lee, J., Lee, M-I and Kim, D.: Impacts of urbanization on atmospheric circulation and aerosol transport in a coastal environment simulated by the WRF-Chem coupled with urban canopy model, *Atmos. Environ.*, 249, 118253, <https://doi.org/10.1016/j.atmosenv.2021.118253>, 2021.
- 920 Khare, P., Machesky, J., Soto, R., He, M., Presto, A. A. and Gentner, D. R.: Asphalt-related emissions are a major missing nontraditional source of secondary organic aerosol precursors, *Science Adv.*, 6(36), <https://doi.org/10.1126/sciadv.abb9785>, 2020.
- Khomenko, S., Cirach, M., Pereira-Barboza, E., Mueller, N., Barrera-Gómez, J., Rojas-Rueda, D., de Hoogh, K., Hoek, G., and Nieuwenhuijsen, M.: Premature mortality due to air pollution in European cities: a health impact assessment, *Lancet Planetary Health*, 3, S2542519620302722, [https://doi.org/10.1016/S2542-5196\(20\)30272-2](https://doi.org/10.1016/S2542-5196(20)30272-2), 2021.

- Lanz, V. A., Prévôt, A. S. H., Alfarra, M. R., Weimer, S., Mohr, C., DeCarlo, P. F., Gianini, M. F. D., Hueglin, C., Schneider, J., Favez,
925 O., D'Anna, B., George, C., and Baltensperger, U.: Characterization of aerosol chemical composition with aerosol mass spectrometry in
Central Europe: an overview, *Atmos. Chem. Phys.*, 10, 10453–10471, <https://doi.org/10.5194/acp-10-10453-2010>, 2010.
- Lawrence, P. J. and Chase, T. N.: Representing a new MODIS consistent land surface in the Community Land Model (CLM 3.0), *J. Geophys.
Res.-Biogeo.*, 112, G01023, <https://doi.org/10.1029/2006JG000168>, 2007.
- Lawrence, M. G., Butler, T. M., Steinkamp, J., Gurjar, B. R., and Lelieveld, J.: Regional pollution potentials of megacities and other major
930 population centers, *Atmos. Chem. Phys.*, 7, 3969–3987, doi:10.5194/acp-7-3969-2007, 2007.
- Li, X., Wu, J., Elser, M., Feng, T., Cao, J., El-Haddad, I., Huang, R., Tie, X., Prévôt, A. S. H., and Li, G.: Contributions of residen-
tial coal combustion to the air quality in Beijing–Tianjin–Hebei (BTH), China: a case study, *Atmos. Chem. Phys.*, 18, 10675–10691,
<https://doi.org/10.5194/acp-18-10675-2018>, 2018.
- Li, Y., Zhang, J., Sailor, D. J., and Ban-Weiss, G. A.: Effects of urbanization on regional meteorology and air quality in Southern California,
935 *Atmos. Chem. Phys.*, 19, 4439–4457, <https://doi.org/10.5194/acp-19-4439-2019>, 2019a.
- Li, K., Liggio*, J., Han, Ch., Liu, Q., Moussa, S. G., Lee, P. and Li, S.-M.: Understanding the Impact of High-NO_x Conditions on the
Formation of Secondary Organic Aerosol in the Photooxidation of Oil Sand-Related Precursors, *Environ. Sci. Technol.*, 53, 24, 14420–
14429, <https://doi.org/10.1021/acs.est.9b05404>, 2019b.
- Liao, J., Wang, T., Wang, X., Xie, M., Jiang, Z., Huang, X. and Zhu, J.: Impacts of different urban canopy schemes in WRF/Chem on regional
940 climate and air quality in Yangtze River Delta, China, *Atmos. Res.*, 145–146, 226–243, <https://doi.org/10.1016/j.atmosres.2014.04.005>,
2014.
- Liaskoni, M., Huszar, P., Bartfk, L., Prieto Perez, A. P., Karlický, J., and Vlček, O.: Modelling the European wind-blown dust emissions and
their impact on particulate matter (PM) concentrations, *Atmos. Chem. Phys.*, 23, 3629–3654, <https://doi.org/10.5194/acp-23-3629-2023>,
2023.
- 945 Lin, J., Junling An, Yu Qu, Yong Chen, Ying Li, Yujia Tang, Feng Wang, Weiling Xiang, Local and distant source contributions
to secondary organic aerosol in the Beijing urban area in summer, *Atmospheric Environment*, Volume 124, Part B, 176–185,
<https://doi.org/10.1016/j.atmosenv.2015.08.098>., 2016.
- Lin, Y.-C., Cheng, M.-T., Lin, W.-H., Lan, Y.-Y., and Tsuang, B.-J.: Causes of the elevated nitrate aerosol levels during episodic days in
Taichung urban area, Taiwan, *Atmos. Environ.*, 44, 1632–1640, doi:10.1016/j.atmosenv.2010.01.039, 2010.
- 950 López-Romero, J. M., Montávez, J. P., Jerez, S., Lorente-Plazas, R., Palacios-Peña, L., and Jiménez-Guerrero, P.: Precipitation response
to aerosol–radiation and aerosol–cloud interactions in regional climate simulations over Europe, *Atmos. Chem. Phys.*, 21, 415–430,
<https://doi.org/10.5194/acp-21-415-2021>, 2021.
- Ma, J., Zhu, S., Wang, S., Wang, P., Chen, J., and Zhang, H.: Impacts of land cover changes on biogenic emission and its contribution to
ozone and secondary organic aerosol in China, *Atmos. Chem. Phys.*, 23, 4311–4325, <https://doi.org/10.5194/acp-23-4311-2023>, 2023.
- 955 Markakis, K., Valari, M., Perrussel, O., Sanchez, O., and Honore, C.: Climate-forced air-quality modeling at the urban scale: sensitivity to
model resolution, emissions and meteorology, *Atmos. Chem. Phys.*, 15, 7703–7723, <https://doi.org/10.5194/acp-15-7703-2015>, 2015.
- Martin, S. T., Hung, H.-M., Park, R. J., Jacob, D. J., Spurr, R. J. D., Chance, K. V., and Chin, M.: Effects of the physical state of tropospheric
ammonium-sulfate-nitrate particles on global aerosol direct radiative forcing, *Atmos. Chem. Phys.*, 4, 183–214, doi:10.5194/acp-4-183-
2004, 2004.
- 960 McDonald-Buller, E., Wiedinmyer, C., Kimura, Y. and Allen, D.: Effects of land use data on dry deposition in a regional photochemical
model for eastern Texas, *J. Air Waste Manage. Assoc.*, 51, 1211–1218, <https://doi.org/10.1080/10473289.2001.10464340>, 2001.

- Miao, Y., Che, H., Zhang, X., and Liu, S.: Integrated impacts of synoptic forcing and aerosol radiative effect on boundary layer and pollution in the Beijing–Tianjin–Hebei region, China, *Atmos. Chem. Phys.*, 20, 5899–5909, <https://doi.org/10.5194/acp-20-5899-2020>, 2020.
- 965 Nagori, J., Janssen, R. H. H., Fry, J. L., Krol, M., Jimenez, J. L., Hu, W., and Vilà-Guerau de Arellano, J.: Biogenic emissions and land–atmosphere interactions as drivers of the daytime evolution of secondary organic aerosol in the southeastern US, *Atmos. Chem. Phys.*, 19, 701–729, <https://doi.org/10.5194/acp-19-701-2019>, 2019.
- Nenes, A., Pandis, S. N., and Pilinis, C.: ISORROPIA: a new thermodynamic equilibrium model for multiphase multicomponent inorganic aerosols, *Aquat. Geochem.*, 4, 123–152, 1998.
- Nho-Kim, E.-Y., Michou, M. and Peuch, V.-H.: Parameterization of size-dependent particle dry deposition velocities for global modeling, *Atmos. Environ.*, 38(13), 1933–1942, <https://doi.org/10.1016/j.atmosenv.2004.01.002>, 2004.
- 970 Nowak, D. J. and Dwyer, J. F.: Understanding the Benefits and Costs of Urban Forest Ecosystems, In: *Urban and Community Forestry in the Northeast*, Kuser, J.E. (ed.), Springer Netherlands, 25–46, 2007.
- Oke, T. R.: The energetic basis of the urban heat island, *Q. J. Roy. Meteor. Soc.*, 108, 1–24, <https://doi.org/10.1002/qj.49710845502>, 1982.
- Oke, T., Mills, G., Christen, A., and Voogt, J.: *Urban Climates*, Cambridge University Press, <https://doi.org/10.1017/9781139016476>, 2017.
- 975 Oleson, K. W., Bonan, G. B., Feddema, J., Vertenstein, M., and Grimmond, C. S. B.: An urban parameterization for a global climate model. 1. Formulation and evaluation for two cities. *J. Appl. Meteor. Clim.*, 47, 1038–1060, 2008.
- Oleson, K.W., Bonan, G.B., Feddema, J., Vertenstein, M., and Kluzek, E.: Technical Description of an Urban Parameterization for the Community Land Model (CLMU), NCAR TECHNICAL NOTE NCAR/TN-480+STR, National Center for Atmospheric Research, Boulder, Co, USA, pp. 61–88, 2010.
- 980 Oleson, K., Lawrence, D. M., Bonan, G. B., Drewniak, B., Huang, M., Koven, C. D., Levis, S., Li, F., Riley, W. J., Subin, Z. M., Swenson, S. C., Thornton, P. E., Bozbiyik, A., Fisher, R., Heald, C. L., Kluzek, E., Lamarque, J.-F., Lawrence, P. J., Leung, L. R., Lipscomb, W., Muszala, S., Ricciuto, D. M., Sacks, W., Sun, Y., Tang, J., and Yang, Z.-L.: Technical Description of version 4.5 of the Community Land Model (CLM), NCAR Technical Note NCAR/TN-503+STR, Boulder, Colorado, 420 pp., 2013.
- Ortega, A. M., Hayes, P. L., Peng, Z., Palm, B. B., Hu, W., Day, D. A., Li, R., Cubison, M. J., Brune, W. H., Graus, M., Warneke, C., 985 Gilman, J. B., Kuster, W. C., de Gouw, J., Gutiérrez-Montes, C., and Jimenez, J. L.: Real-time measurements of secondary organic aerosol formation and aging from ambient air in an oxidation flow reactor in the Los Angeles area, *Atmos. Chem. Phys.*, 16, 7411–7433, <https://doi.org/10.5194/acp-16-7411-2016>, 2016.
- Panagi, M., Fleming, Z. L., Monks, P. S., Ashfold, M. J., Wild, O., Hollaway, M., Zhang, Q., Squires, F. A., and Vande Hey, J. D.: Investigating the regional contributions to air pollution in Beijing: a dispersion modelling study using CO as a tracer, *Atmos. Chem. Phys.*, 20, 2825–2838, <https://doi.org/10.5194/acp-20-2825-2020>, 2020.
- 990 Passant, N.: Speciation of UK Emissions of Non-methane Volatile Organic Compounds, DEFRA, Oxon, UK, 2002.
- Prieto Pérez, A. P., Huszár, P. and Karlický, J.: Extreme PM and Ozone Pollution over Central Europe: Interactions of the Urban Canopy Meteorological Forcing and Radiative Effects of Urban Emissions in WDS’22 Proceedings of Contributed Papers — Physics (eds. J. Šafránková and J. Pavlů), Prague, Matfyzpress, pp. 204–210, ISBN 978-80-7378-477-5, 2022.
- 995 Pullinen, I., Schmitt, S., Kang, S., Sarrafzadeh, M., Schlag, P., Andres, S., Kleist, E., Mentel, T. F., Rohrer, F., Springer, M., Tillmann, R., Wildt, J., Wu, C., Zhao, D., Wahner, A., and Kiendler-Scharr, A.: Impact of NO_x on secondary organic aerosol (SOA) formation from α -pinene and β -pinene photooxidation: the role of highly oxygenated organic nitrates, *Atmos. Chem. Phys.*, 20, 10125–10147, <https://doi.org/10.5194/acp-20-10125-2020>, 2020.

- Putaud, J.-P., Pisoni, E., Mangold, A., Hueglin, C., Sciare, J., Pikridas, M., Savvides, C., Ondracek, J., Mbengue, S., Wiedensohler, A.,
1000 Weinhold, K., Merkel, M., Poulain, L., van Pinxteren, D., Herrmann, H., Massling, A., Nordstroem, C., Alastuey, A., Reche, C., Pérez,
N., Castillo, S., Sorribas, M., Adame, J. A., Petaja, T., Lehtipalo, K., Niemi, J., Riffault, V., de Brito, J. F., Colette, A., Favez, O., Petit,
J.-E., Gros, V., Gini, M. I., Vratolis, S., Eleftheriadis, K., Diapouli, E., Denier van der Gon, H., Yttri, K. E., and Aas, W.: Impact of 2020
COVID-19 lockdowns on particulate air pollution across Europe, *EGUsphere* [preprint], <https://doi.org/10.5194/egusphere-2023-434>,
2023.
- 1005 Ren, Y., Zhang, H., Wei, W., Wu, B., Cai, X., and Song, Y.: Effects of turbulence structure and urbanization on the heavy haze pollution
process, *Atmos. Chem. Phys.*, 19, 1041-1057, <https://doi.org/10.5194/acp-19-1041-2019>, 2019.
- Ribeiro, F. N. D., Amauri P. de Oliveira, Jacyra Soares, Regina M. de Miranda, Michael Barlage, Fei Chen: Effect of sea
breeze propagation on the urban boundary layer of the metropolitan region of Sao Paulo, Brazil, *Atmos. Res.*, 214, 174-188,
<https://doi.org/10.1016/j.atmosres.2018.07.015>, 2018.
- 1010 Richards, K.: Observation and simulation of dew in rural and urban environments, *Prog. Phys. Geogr.*, 28, 76–94, 2004.
- Rienda, I. C. and Alves, C. A.: Road dust resuspension: A review, *Atmos. Res.*, 261, 105740, <https://doi.org/10.1016/j.atmosres.2021.105740>,
2021.
- Rivellini, L.-H., Adam, M. G., Kasthuriarachchi, N., and Lee, A. K. Y.: Characterization of carbonaceous aerosols in Singapore: insight from
black carbon fragments and trace metal ions detected by a soot particle aerosol mass spectrometer, *Atmos. Chem. Phys.*, 20, 5977–5993,
1015 <https://doi.org/10.5194/acp-20-5977-2020>, 2020.
- Sartelet, K. N., Florian Couvidat, Christian Seigneur, Yelva Roustan, Impact of biogenic emissions on air quality over Europe and North
America, *Atmospheric Environment*, Volume 53, 131-141, <https://doi.org/10.1016/j.atmosenv.2011.10.046>, 2012.
- Seinfeld, J. H. and Pandis, S. N.: *Atmospheric Chemistry and Physics: From Air Pollution to Climate Change*, J. Wiley, New York, 1998.
- Simmons, A. J., Willett, K. M., Jones, P. D., Thorne, P. W., and Dee, D. P.: Low-frequency variations in surface atmospheric humidity,
1020 temperature and precipitation: inferences from reanalyses and monthly gridded observational datasets, *J. Geophys. Res.*, 115, D01110,
[doi:10.1029/2009JD012442](https://doi.org/10.1029/2009JD012442), 2010.
- Sindelarova, K., Granier, C., Bouarar, I., Guenther, A., Tilmes, S., Stavroukou, T., Müller, J.-F., Kuhn, U., Stefani, P., and Knorr, W.: Global
data set of biogenic VOC emissions calculated by the MEGAN model over the last 30 years, *Atmos. Chem. Phys.*, 14, 9317–9341,
<https://doi.org/10.5194/acp-14-9317-2014>, 2014.
- 1025 Sindelarova, K., Markova, J., Simpson, D., Huszar, P., Karlicky, J., Darras, S., and Granier, C.: High-resolution biogenic global emission
inventory for the time period 2000–2019 for air quality modelling, *Earth Syst. Sci. Data*, 14, 251–270, <https://doi.org/10.5194/essd-14-251-2022>, 2022.
- Skyllakou, K., Murphy, B. N., Megaritis, A. G., Fountoukis, C., and Pandis, S. N.: Contributions of local and regional sources to fine PM in
the megacity of Paris, *Atmos. Chem. Phys.*, 14, 2343–2352, [doi:10.5194/acp-14-2343-2014](https://doi.org/10.5194/acp-14-2343-2014), 2014.
- 1030 Slater, J., Coe, H., McFiggans, G., Tonttila, J., and Romakkaniemi, S.: The effect of BC on aerosol–boundary layer feedback: potential
implications for urban pollution episodes, *Atmos. Chem. Phys.*, 22, 2937–2953, <https://doi.org/10.5194/acp-22-2937-2022>, 2022.
- Sokhi, R. S., Moussiopoulos, N., Baklanov, A., Bartzis, J., Coll, I., Finardi, S., Friedrich, R., Geels, C., Grönholm, T., Halenka, T., Ketzler,
M., Maragkidou, A., Matthias, V., Moldanova, J., Ntziachristos, L., Schäfer, K., Suppan, P., Tsegas, G., Carmichael, G., Franco, V., Hanna,
S., Jalkanen, J.-P., Velders, G. J. M., and Kukkonen, J.: Advances in air quality research – current and emerging challenges, *Atmos. Chem.*
1035 *Phys.*, 22, 4615–4703, <https://doi.org/10.5194/acp-22-4615-2022>, 2022.

- Song, J., Webb, A., Parmenter, B. Allen, D. T. and McDonald-Buller, E.: *Environmental Sci. Tech.*, 42(19), 7294-7300 DOI: 10.1021/es800645j, 2008.
- Stock, Z. S., Russo, M. R., Butler, T. M., Archibald, A. T., Lawrence, M. G., Telford, P. J., Abraham, N. L., and Pyle, J. A.: Modelling the impact of megacities on local, regional and global tropospheric ozone and the deposition of nitrogen species, *Atmos. Chem. Phys.*, 13, 12215–12231, <https://doi.org/10.5194/acp-13-12215-2013>, 2013.
- 1040 Strader, R. Lurmann, F. and Pandis, S. N.: Evaluation of secondary organic aerosol formation in winter, *Atmos. Environ.*, 33., 4849-4863, 1999.
- Struzewska, J. and Kaminski, J. W.: Impact of urban parameterization on high resolution air quality forecast with the GEM – AQ model, *Atmos. Chem. Phys.*, 12, 10387–10404, <https://doi.org/10.5194/acp-12-10387-2012>, 2012.
- 1045 Tao, W., Liu, J., Ban-Weiss, G. A., Hauglustaine, D. A., Zhang, L., Zhang, Q., Cheng, Y., Yu, Y., and Tao, S.: Effects of urban land expansion on the regional meteorology and air quality of eastern China, *Atmos. Chem. Phys.*, 15, 8597–8614, <https://doi.org/10.5194/acp-15-8597-2015>, 2015.
- Thunis, P., Clappier, A., de Meij, A., Pisoni, E., Bessagnet, B., and Tarrason, L.: Why is the city’s responsibility for its air pollution often underestimated? A focus on PM_{2.5}, *Atmos. Chem. Phys.*, 21, 18195–18212, <https://doi.org/10.5194/acp-21-18195-2021>, 2021.
- 1050 Tie, X., Brasseur, G., and Ying, Z.: Impact of model resolution on chemical ozone formation in Mexico City: application of the WRF-Chem model, *Atmos. Chem. Phys.*, 10, 8983-8995, <https://doi.org/10.5194/acp-10-8983-2010>, 2010.
- Tie, X., Geng, F., Guenther, A., Cao, J., Greenberg, J., Zhang, R., Apel, E., Li, G., Weinheimer, A., Chen, J., and Cai, C.: Megacity impacts on regional ozone formation: observations and WRF-Chem modeling for the MIRAGE-Shanghai field campaign, *Atmos. Chem. Phys.*, 13, 5655–5669, <https://doi.org/10.5194/acp-13-5655-2013>, 2013.
- 1055 Tiedtke, M.: A Comprehensive Mass Flux Scheme for Cumulus Parameterization in Large-Scale Models, *Mon. Weather Rev.*, 117, 1779-1800, [https://doi.org/10.1175/1520-0493\(1989\)117](https://doi.org/10.1175/1520-0493(1989)117), 1989.
- Timothy, M. and Lawrence, M. G.: The influence of megacities on global atmospheric chemistry: a modeling study, *Environ. Chem.*, 6, 219–225, doi:10.1071/EN08110, 2009.
- Ulpiani, G.: On the linkage between urban heat island and urban pollution island: Three-decade literature review towards a conceptual framework, *Sci. Total Environ.*, 751, 141727, <https://doi.org/10.1016/j.scitotenv.2020.141727>, 2021.
- 1060 UN2018: The World’s Cities in 2018 – Data Booklet (ST/ESA/SER.A/417), United Nations, Department of Economic and Social Affairs, Population Division, New York, USA, 2018.
- Vestreng, V., Myhre, G., Fagerli, H., Reis, S., and Tarrasón, L.: Twenty-five years of continuous sulphur dioxide emission reduction in Europe, *Atmos. Chem. Phys.*, 7, 3663–3681, <https://doi.org/10.5194/acp-7-3663-2007>, 2007.
- 1065 Walters, W. W., Karod, M., Willcocks, E., Baek, B. H., Blum, D. E., and Hastings, M. G.: Quantifying the importance of vehicle ammonia emissions in an urban area of northeastern USA utilizing nitrogen isotopes, *Atmos. Chem. Phys.*, 22, 13431–13448, <https://doi.org/10.5194/acp-22-13431-2022>, 2022.
- Wang, X., Wu, Z., Liang, G.: WRF/CHEM modeling of impacts of weather conditions modified by urban expansion on secondary organic aerosol formation over Pearl River Delta, *Particuology*, 7(5), 384-391, <https://doi.org/10.1016/j.partic.2009.04.007>, 2009.
- 1070 Wang, M., Tang, G., Liu, Y., Ma, M., Yu, M., Hu, B., Zhang, Y., Wang, Y. and Wang, Y.: The difference in the boundary layer height between urban and suburban areas in Beijing and its implications for air pollution, *Atmos. Environ.*, 260, 118552, <https://doi.org/10.1016/j.atmosenv.2021.118552>, 2021.

- Wang, J., Xing, J., Wang, S., Mathur, R., Wang, J., Zhang, Y., Liu, C., Pleim, J., Ding, D., Chang, X., Jiang, J., Zhao, P., Sahu, S. K., Jin, Y., Wong, D. C., and Hao, J.: The pathway of impacts of aerosol direct effects on secondary inorganic aerosol formation, *Atmos. Chem. Phys.*, 22, 5147–5156, <https://doi.org/10.5194/acp-22-5147-2022>, 2022.
- 1075
- Wesely, M. L.: Parameterization of Surface Resistances to Gaseous Dry Deposition in Regional-Scale Numerical Models. *Atmos. Environ.*, 23, 1293–1304, 1989.
- Wei, W., Zhang, H., Wu, B., Huang, Y., Cai, X., Song, Y., and Li, J.: Intermittent turbulence contributes to vertical dispersion of PM 2.5 in the North China Plain: cases from Tianjin, *Atmos. Chem. Phys.*, 18, 12953–12967, <https://doi.org/10.5194/acp-18-12953-2018>, 2018.
- 1080
- Xue, L. K., Wang, T., Gao, J., Ding, A. J., Zhou, X. H., Blake, D. R., Wang, X. F., Saunders, S. M., Fan, S. J., Zuo, H. C., Zhang, Q. Z., and Wang, W. X.: Ground-level ozone in four Chinese cities: precursors, regional transport and heterogeneous processes, *Atmos. Chem. Phys.*, 14, 13175–13188, [doi:10.5194/acp-14-13175-2014](https://doi.org/10.5194/acp-14-13175-2014), 2014.
- Yang, F., Tan, J., Zhao, Q., Du, Z., He, K., Ma, Y., Duan, F., Chen, G., and Zhao, Q.: Characteristics of PM_{2.5} speciation in representative megacities and across China, *Atmos. Chem. Phys.*, 11, 5207–5219, <https://doi.org/10.5194/acp-11-5207-2011>, 2011.
- 1085
- Yang, J., Ma, L., He, X., Au, W. C., Miao, Y., Wang, W.-X., and Nah, T.: Measurement report: Abundance and fractional solubilities of aerosol metals in urban Hong Kong – insights into factors that control aerosol metal dissolution in an urban site in South China, *Atmos. Chem. Phys.*, 23, 1403–1419, <https://doi.org/10.5194/acp-23-1403-2023>, 2023.
- Yienger, J. J. and Levy, H.: Empirical model of global soil-biogenic NO_x emissions, *J. Geophys. Res. Atmos.*, 100 (D6), 11447–11464, <https://doi.org/10.1029/95JD00370>, 1995.
- 1090
- Yim, S. H. L., Wang, M., Gu, Y., Yang, Y., Dong, G., and Li, Q.: Effect of urbanization on ozone and resultant health effects in the Pearl River Delta region of China, *J. Geophys. Res. Atmos.*, 124, 11568–11579, <https://doi.org/10.1029/2019JD030562>, 2019.
- Yu, M., Tang, G., Yang, Y., Li, Q., Wang, Y., Miao, S., Zhang, Y., and Wang, Y.: The interaction between urbanization and aerosols during a typical winter haze event in Beijing, *Atmos. Chem. Phys.*, 20, 9855–9870, <https://doi.org/10.5194/acp-20-9855-2020>, 2020.
- Zha, J., Zhao, D., Wu, J. and Zhang, P.: Numerical simulation of the effects of land use and cover change on the near-surface wind speed over Eastern China, *Clim. Dyn.*, <https://doi.org/10.1007/s00382-019-04737-w>, 2019.
- 1095
- Zhai, M., Kuang, Y., Liu, L., He, Y., Luo, B., Xu, W., Tao, J., Zou, Y., Li, F., Yin, C., Li, C., Xu, H., and Deng, X.: Insights into characteristics and formation mechanisms of secondary organic aerosols in the Guangzhou urban area, *Atmos. Chem. Phys.*, 23, 5119–5133, <https://doi.org/10.5194/acp-23-5119-2023>, 2023.
- Zhang, L., Gong, S., Padro, J. and Barrie, L.: A size-segregated particle dry deposition scheme for an atmospheric aerosol module. *Atmos. Environ.*, 35, 549–560, 2001.
- 1100
- Zhang, L., Brook, J. R., and Vet, R.: A revised parameterization for gaseous dry deposition in air-quality models, *Atmos. Chem. Phys.*, 3, 2067–2082, <https://doi.org/10.5194/acp-3-2067-2003>, 2003.
- Zhang, Q. J., Beekmann, M., Freney, E., Sellegri, K., Pichon, J. M., Schwarzenboeck, A., Colomb, A., Bourriane, T., Michoud, V., and Borbon, A.: Formation of secondary organic aerosol in the Paris pollution plume and its impact on surrounding regions, *Atmos. Chem. Phys.*, 15, 13973–13992, <https://doi.org/10.5194/acp-15-13973-2015>, 2015.
- 1105
- Zhong, S., Qian, Y., Sarangi, C., Zhao, C., Leung, R., Wang, H., et al.: Urbanization effect on winter haze in the Yangtze River Delta region of China, *Geophys. Res. Letters*, 45., <https://doi.org/10.1029/2018GL077239>, 2018.
- Zhong, Q., Huizhong Shen, Xiao Yun, Yilin Chen, Yu'ang Ren, Haoran Xu, Guofeng Shen, Wei Du, Jing Meng, Wei Li, Jianmin Ma, and Shu Tao: Global Sulfur Dioxide Emissions and the Driving Forces, *Environ. Sci. Tech.*, 54 (11), 6508–6517, DOI: 10.1021/acs.est.9b07696,
- 1110 2020.

Zhu, K., Xie, M., Wang, T., Cai, J., Li, S., and Feng, W.: A modeling study on the effect of urban land surface forcing to regional meteorology and air quality over South China, *Atmos. Environ.*, 152, 389–404, <http://dx.doi.org/10.1016/j.atmosenv.2016.12.053>, 2017.

Table 1. The list of CAMx simulations performed with the information of the effects considered.

Regional Chemistry Transport Model (CAMx) simulations					
	Experiment	Driving meteorology	Urban emissions	Land-use (deposition)	BVOC emissions
1	ENNNN (Reference)	Nourban	No	Nourban	Nourban
2	ENYNN	Nourban	Yes	Nourban	Nourban
3	ENYUN	Nourban	Yes	Urban	Nourban
4	ENYUU	Nourban	Yes	Urban	Urban
5	EUYUU	Urban	Yes	Urban	Urban




Figure 1. The models used in the study including their mutual interaction (the flow of the meteorological and emission data).




Figure 2. Comparison of modelled (red) and observed (blue) PM_{2.5} monthly concentrations over rural (left) and urban (right) AirBase stations as 2015-2016 mean. Shaded areas represent the standard deviation across all the stations. Units are in $\mu\text{g m}^{-3}$.




Figure 3. Comparison of modelled (red) and observed (blue) PSO₄, PNO₃, PNH₄ and PEC monthly concentrations over available EMEP stations as 2015-2016 mean. Shaded areas represent the standard deviation across all the stations. Units are in $\mu\text{g m}^{-3}$.




Figure 4. The 2015-2016 DJF and JJA averaged total impact of urbanization as well as of each contributor to the urban concentrations of PM2.5 averaged over all chosen city. The boxplots show the 25% to 75% quantiles including the minimum and maximum value across all cities. The red line shows the median value. Values are taken from model grid-cell that covers the city center. The upper sub-figures show the two main contributors including the total impact ("DEMIS", "DMET" and "DTOT") while the lower one the minor contributors ("DLU_D" and "DBVOC"). Units are in μgm^{-3} .




Figure 5. Same as Fig. 4 but for PM_{2.5} components: PSO₄, PNO₃, PNH₄ (upper row), PEC and SOA (lower row).




Figure 6. The absolute DJF (left panel) and JJA (right panel) concentrations of modelled PM_{2.5} and its components (PEC, PSO₄, PNO₃, PNH₄ and SOA) from the "EUYUU" experiment (all urban effects considered) averaged over 2015-2016 in μgm^{-3} .




Figure 7. The spatial distribution of the 2015-2016 DJF (left panel) and JJA (right panel) average urban emission impact "DEMIS" on PM2.5 and its components. Units in $\mu\text{g m}^{-3}$. Note that PM2.5 has separate colorbar.




Figure 8. The spatial distribution of the 2015-2016 DJF (left panel) and JJA (right panel) average UCMF impact "DMET" on PM2.5 and its components. Units in $\mu\text{g}/\text{m}^3$. Note that PM2.5 has separate colorbar.




Figure 9. The spatial distribution of the 2015-2016 DJF (left panel) and JJA (right panel) average impact of modified dry-deposition velocities due to land-use change "DLU_D" on PM_{2.5} and its components. Units in $\mu\text{g m}^{-3}$. Note that PM_{2.5} has separate colorbar.




Figure 10. The spatial distribution of the 2015-2016 DJF (left panel) and JJA (right panel) average impact of urban land-use on dry-deposition velocities for PEC. Units in cm s^{-1} .




Figure 11. The spatial distribution of the 2015-2016 DJF (left panel) and JJA (right panel) average impact of modified biogenic emissions "DBVOC" on PM2.5 and its components. Units in $\mu\text{g m}^{-3}$.

Diurnal cycle of impact of urbanization on PM2.5 and its components 2015-2016 DJF




Figure 12. Diurnal cycles of the impact of individual contributors to RUT averaged over 2015-2016 DJF for PM2.5, PEC, PSO4, PNO3, PNH4 and SOA. Colors stand for: brown – DEMIS, blue – DMET, red – DLU_D and green – DBVOC. Left y-axis is for the two major contributors: DEMIS and DMET, while the right y-axis belongs to the two smaller contributors (DLU_D and DBVOC). Units are in μgm^{-3} .

Diurnal cycle of impact of urbanization on PM2.5 and its components 2015-2016 JJA




Figure 13. Same as Fig 12 but for JJA.




Figure 14. Diurnal cycle of the DJF (left) and JJA (right) DV of PEC: solid lines denote absolute values, dashed lines mean the change caused by the urban land-surface. Units in mms^{-1} .




Figure 15. The DJF (upper row) and JJA (lower row) impact of "DEMIS", "DMET" and "DL_U" on near surface NH_3 concentrations in ppbv.