Gas-particle partitioning of toluene oxidation products: an experimental and modeling study

Victor Lannuque[1], Barbara D'Anna[2], Evangelia Kostenidou[2,a], Florian Couvidat[3], Alvaro Martinez-Valiente[2], Philipp Eichler[4,b], Armin Wisthaler[4,5], Markus Müller[6], Brice Temime-Roussel[2], Richard Valorso[7] and Karine Sartelet[1]

[1] CEREA, École des Ponts ParisTech, EDF R&D, IPSL, 77455 Marne-la-Vallée, France
[2] Aix-Marseille University, UMR 7673 CNRS, LCE, Marseille, France
[3] National Institute for Industrial Environment and Risks (INERIS), Verneuil-en-Halatte, France
[4] Institute for Ion and Applied Physics, University of Innsbruck, Innsbruck, 6020, Austria
[5] Department of Chemistry, University of Oslo, Oslo, 0315, Norway
[6] Ionicon Analytik GmbH, Innsbruck, 6020, Austria
[7] Univ Paris Est Creteil and Université ~~de~~ Paris Cité, CNRS, LISA, F-94010 Créteil, France
[a] Now at: Department of Environmental Engineering, Democritus University of Thrace, 67100 Xanthi, Greece
[b] Now at: German Environment Agency, Dessau, Germany

Correspondence to: Victor Lannuque (victor.lannuque@enpc.fr) and Barbara D'Anna (barbara.danna@univ-amu.fr)

Keywords: SOA, toluene, volatility, temperature dependence, modelling, gas-particle partitioning processes, oxidation mechanisms, reaction products, molecular identification

Abstract. Toluene represents a large fraction of anthropogenic emissions and significantly contributes to tropospheric ozone and secondary organic aerosol (SOA) formation. Despite the fact that toluene is one of the most studied aromatic compounds, detailed chemical mechanisms still fail to correctly reproduce the speciation of toluene gaseous and condensed oxidation products. This study aims to elucidate the role of initial experimental conditions on toluene SOA mass loadings and to investigate gas-particle partitioning of its reaction products at different relevant temperatures. Gaseous and particulate reaction products were identified and quantified using a proton transfer reaction time-of-flight mass spectrometer (PTR-ToF-MS) coupled to a CHemical Analysis of aeRosol ONline (CHARON) inlet. The chemical system exhibited a volatility distribution mostly in the semi-volatile regime. Temperature decrease caused a shift of saturation concentration towards lower values. The CHARON/PTR-ToF-MS instrument identified and quantified approximately 60–80% of the total organic mass measured by an aerosol mass spectrometer. A detailed mechanism for toluene gaseous oxidation was developed based on the MCM and GECKO-A deterministic mechanisms, modified following the literature. The new mechanism showed improvements in modeling of oxidation products speciation with more observed species represented and more representative concentrations compared to the MCM/GECKO-A reference. Tests on partitioning processes, non-ideality and wall losses highlighted the high dependency of SOA formation to the considered processes. Our results underline that volatility is not

sufficient to explain the gas-particle partitioning: the organic and the aqueous phases need to be considered as well as the interactions between compounds in the particle phase.

Aromatic hydrocarbons represent a large fraction of anthropogenic volatile organic compounds and significantly contribute to tropospheric ozone and secondary organic aerosol (SOA) formation. Toluene photooxidation experiments were carried out in an oxidation flow reactor (OFR). We identified and quantified the gaseous and particulate reaction products at 280, 285 and 295 K using a proton-transfer-reaction time-of-flight mass spectrometer (PTR-ToF-MS) coupled to a CHemical Analysis of aeRosol ONline (CHARON) inlet. The reaction products accounted for both ring retaining compounds such as cresols, benzaldehyde, nitrophenols, nitrotoluene, bicyclic intermediate compounds, as well as ring scission products such as dicarbonyls, cyclic anhydrides, small aldehydes and acids. The chemical system exhibited a volatility distribution mostly in the semi-volatile (SVOCs – semi-volatile organic compounds) regime. The saturation concentration (C_i^*) values of the identified compounds were mapped onto the two-dimensional volatility basis set (2D-VBS). Temperature decrease caused a shift of C_i^* towards lower values while there was no clear relationship between C_i^* and oxidation state. The CHARON PTR-ToF-MS instrument identified and quantified approximately 70-80% of the total organic mass measured by an aerosol mass spectrometer (AMS). The experiments were reproduced by simulating SOA formation with the SSH-aerosol box model. A semi-detailed mechanism for toluene gaseous oxidation was developed. It is based on the MCM and GECKO-A deterministic mechanisms modified following the literature in particular to update cresols and ring scission chemistry. The new mechanism improved secondary species representation with an increment of the major identified species (+35% in number). Light compounds formation (i.e. m/z < 100) is enhanced and accumulation of heavy compounds (i.e. $m/z \geq$ 100) is reduced, especially in the gas phase. Additional tests on (i) partitioning processes such as condensation into aqueous phase, (ii) interactions of organic compounds between themselves and with inorganics and (iii) wall losses were also performed. When all these processes were taken into account the simulated SOA mass concentration showed a much better agreement with the experimental results. Finally, an irreversible partitioning pathway for methylglyoxal was introduced and considerably improved the model results, opening a way to further developments of partitioning in models. Our results underline that the volatility itself is not sufficient to explain the partitioning between gas and particle phase: the organic and the aqueous phases need to be taken into account as well as interactions between compounds in the particle phase.

1 Introduction

Aromatic compounds represent an important fraction of hydrocarbons emitted in the urban atmosphere (Calvert et al., 2002). Their photochemical oxidation is a source of ozone and secondary organic gas-phase compounds which can lead to the formation of secondary organic aerosol (SOA) (Seigneur, 2019). SOA represents a significant fraction of the total fine particles (Gelencsér et al., 2007; Jimenez et al., 2009) which are key components of the Earth's atmospheric system, significantly impacting visibility (Han et al., 2012), human health (Lim et al., 2018, 2012; Malley et al., 2017), and the Earth's climate (Boucher et al., 2013).

Toluene is the most abundant alkyl-aromatic compound especially in urban areas (Lee et al., 2002; Yan et al., 2019; Zhang et al., 2015a). It is emitted by vehicle exhausts but also from biomass burning, fuel evaporation, solvent usage and industrial processes (Singh et al., 1992; Skorokhod et al., 2017). It is classified as a toxic compound as it affects the central nervous system (US Environmental Protection Agency, 2012). The gas-phase products from toluene-OH radical reaction have been widely studied in the last 20 years, both via experimental or modeling approaches (Baltaretu et al., 2009; Bohn, 2001; Jang and Kamens, 2001; Klotz et al., 1998; Sato et al., 2007; Schwantes et al., 2017; Suh et al., 2002; Wagner et al., 2003; Xu et al., 2015; Zaytsev et al., 2019). Toluene photo-oxidation leads to the formation of gas-phase products of low volatility that can easily condense on the pre-existing aerosol particles to form SOA (Ng et al., 2007; Seigneur, 2019; White et al., 2014). Despite the amount of work devoted to the degradation of toluene, many uncertainties remain regarding the oxidation mechanisms (species and reactions involved) and the physicochemical processes leading to the formation of SOA from toluene (Calvert et al., 2002; Jang and Kamens, 2001; Schwantes et al., 2017; Zaytsev et al., 2019). Moreover, properties of the formed compounds (and thus their ability to condense and form SOA) strongly depend on environmental parameters such as temperature, NO_X, humidity, pre-existing particle surface, toluene concentration, OH radical concentration, etc. (Kamens et al., 2011; Kim et al. 2011 ; Lannuque et al., 2018; Ng et al., 2007; Sato et al., 2007; Takekawa et al., 2003; Xu et al., 2015). In order to well reproduce the observed SOA variations with modeling and to interpret experimental measurements, detailed and representative oxidation mechanisms and partitioning processes are required.

The reference explicit chemical mechanism for toluene oxidation is the Master Chemical Mechanism (MCM) (Bloss et al., 2005; Jenkin et al., 2003). The MCM is a detailed mechanism that describes the chemical evolution of organic matter from toluene through 270 secondary species and 814 reactions. The main reaction pathways of toluene are (i) addition of an OH function on the aromatic ring and the formation of an RO_2 radical leading to the formation of bicyclic compounds with an O-O bridge (65%), (ii) addition of an OH function on the ring and the formation of cresol and HO_2 (18%), (iii) addition of an OH function on the aromatic ring leading to the formation of epoxides and the ring opening (10%) and (iv) hydrogen abstraction from the methyl group (7%). Based on recent experiments in atmospheric simulation chambers, the cresol formation pathway and the successive addition of alcohol function on the aromatic ring seem to be underestimated or neglected in the MCM (Schwantes et al., 2017) and ~~this new~~ branching ratios should be revised (Zaytsev et al., 2019). These changes necessarily affect ~~the estimation of~~ SOA formation ~~from toluene oxidation. SOA formation~~which is favored by the formation of (i) low-volatility oxygenated compounds ~~with low volatility~~ (Molteni et al., 2018; Ng et al., 2007; Schwantes et al., 2017; Wang et al., 2020, 2017) ~~but also by the formation of more volatile compounds such as~~ and of (ii) volatile organic acids and dicarbonyls such as methylglyoxal and glyoxal, which oligomerize, hydrate or oxidize in aqueous phase (De Haan et al., 2018; Hu et al., 2022; Li et al., 2021b, a; Marrero-Ortiz et al., 2019). Nonetheless,~~The~~ partitioning processes toward an aqueous phase and particle-phase chemistry (such as oligomerization or oxidation) remain ~~however little~~poorly represented in models.

The recent development of soft-ionization analytical tools for particles as the CHemical Analysis of aeRosol ONline (CHARON) coupled to a Proton-Transfer-Reaction Time-of-Flight Mass Spectrometer (PTR-ToF-MS) allows for direct

100 characterization of organic aerosol on a molecular composition level (Eichler et al., 2015). At the same time the molecular gas-phase characterization is provided by a separate PTR-ToF-MS. The above instruments were deployed in an effort to better understand the chemistry of toluene and the formation of SOA at different temperatures using a thermostated oxidation flow reactor (OFR). Then these experiments were numerically reproduced using detailed chemical mechanisms based on a combination of the MCM and the Generator for Explicit Chemistry and Kinetics of Organics in the Atmosphere

105 (GECKO-A) (Aumont et al., 2005) modified according to recents studies.

The main goals of this study are~~were~~ (1) the chemical identification of the gaseous and particulate phase products, (2) the determination of the partition coefficient of the individual SOA products ~~under different experimental conditions~~at different temperatures, (3) the development of a new detailed oxidation mechanism for toluene to better reproduce~~d~~ the experimental speciation and (4) the exploration and impact analysis of the different processes influencing the partitioning (hydrophilic

110 partitioning, non-ideality, wall losses and methylglyoxal irreversible partitioning) on the modeling of experimental SOA. To our knowledge this is the first time that partitioning and volatility data of individual toluene SOA components are provided at relevant ambient temperatures.

2 Methods

2.1 Experimental conditions and instrumentation

115 #### 2.1.1 Oxidation experiments

Toluene photo-oxidation experiments were carried out at atmospheric pressure in a horizontal cylindrical OFR made of Pyrex (12 cm internal diameter, 152 cm length) surrounded by seven fluorescent lamps (Philips CLEO) with a continuous emission spectrum in the 300–420 nm range and a total irradiance of 3×10^{16} photons cm^{-2} s^{-1}. Temperature was controlled using a circulating water bath with the outer jacket (Huber CC 405)~~.;~~ T~~t~~he experiments were conducted at 280, 285 and 295

120 K~~elvin~~. The total flow varied from 1.3 to 1.8 l/min and the residence time also was of 10–13 minutes. The relative humidity (RH) was adjusted by bubbling pure ~~N_2~~nitrogen though ultrapure distilled and deionized water and ranged from ~~24~~23 to ~~41~~50%. Monodisperse ammonium sulphate (AS) particles were nebulized using a TSI atomizer (Model 3076), then dried using a silica diffusion drier and then passed through a Differential Mobility Analyser (DMA, TSI model 3081) to generate monodisperse aerosol ranging from ~~120~~113 and ~~169~~150 nm (mobility diameter). Toluene (99.8% purity, Sigma Aldrich)

125 was constantly introduced in the OFR via a permeation tube kept at 353 K and purged with pure nitrogen and its concentration inside the OFR varied from 8 to 162 ppbv~~(N_2)~~. Isopropyl nitrite (IPN) was used as a hydroxyl radical precursor and was prepared from the corresponding alcohol following the procedure reported by Johnson (1939). The IPN was constantly introduced in the OFR using a permeation tube kept at 308-313 K and flushed with pure nitrogen. During IPN photolysis NO and HO_2 are produced and can further react producing OH and NO_2 radicals (Raff and Finlayson-Pitts,

130 2010). The average oxidant concentration during the experiment was calculated from the toluene decay ($k_{OH} \approx 6 \times 10^{-12}$ cm^3

molecules^{-1} s^{-1}) and ranged from 7.4 to 13 × 10^7 molecules cm^{-3} corresponding approximately to 10 and 20 hours of atmospheric OH-radical exposure, taking into account a diurnal average hydroxyl radical concentration of 1.5 × 10^6 molecules cm^{-3} (Mao et al., 2009). High amounts of acetone, a side-product of IPN photolysis, inhibit the detection of glyoxal, a major gas phase product. 24 photooxidation experiments have been carried out. A detailed list of the experimental conditions is provided in Table S1 in the supplementary information (SI). A subset of six experiences is reported here for detailed analysis at molecular level of the gaseous and particulate phases, these experiments are indicated by the red color in Table S1.

2.1.2 Instrumentation

A high-resolution Time-of-Flight Aerosol mass spectrometer (HR-ToF-AMS, Tofwerk AG, Aerodyne Inc., USA) (DeCarlo et al., 2006), a scanning mobility particle sizer (SMPS, TSI Classifier model 3081, DMA, TSI CPC 3776) and a "Chemical CHemical Analysis of Aerosol AeRosol OnlineONline" (CHARON) inlet coupled to a commercial PTR-TOF-ToF-MS 8000 analyzer (Ionicon Analytik GmbH, Innsbruck, Austria) were used to measure aerosol mass, aerosol chemical composition and size distribution. The AMS operating principles, calibration procedures and analysis protocols are described in Drewnick et al. (2005, 2009). Uncertainties from the HR-ToF-AMS are typically of the order of ± 30%.

The PTR-TOF-ToF-MS 8000 instrument and methods of data analysis are described in Jordan et al. (2009), Graus et al. (2010) and Müller et al. (2013). Data analysis was performed using the standard PTR data analysis toolkits (Tofwerk Inc, Switzerland) version 2.5.10 with Igor Pro 6.37 version (Wavemetrics, Inc.) and PTR-ToF-MSPTR TOF Data Analyzer toolbox (version 4.46) (Müller et al., 2013). Calibration and quantification procedures are described in the supplementary information (SI) of the article. A detailed description of the CHARON inlet has been provided elsewhere by Eichler et al. (2015), Müller et al. (2017) and Leglise et al. (2019) therefore only a brief description is provided here. The CHARON inlet used in these experiments was a non-commercial prototype almost identical to that described by Eichler et al. (2015). The air sample is drawn through an activated carbon monolith denuder which removes gaseous organics. An aerodynamic lens is used for enriching the particle concentration by a factor of ~8-25 depending on the particle size. Enrichment factor calibration has been repeated several times during the campaign using ammonium nitrate monodispersed particles (see figFig. S1 in the SI section). Finally, a thermodesorption unit vaporizes the particles at 413 K. The instrumental background is determined by periodically diverting the sampling flow through a High-Efficiency Particulate Air filter (HC01-5N-B miniature HEPA capsule filter) placed upstream of the CHARON inlet. Operational and software details, routines are given in the SI. An additional NO$_X$ detector (Thermo 42C chemiluminescent analyzer) was also used at the exit of the OFR during some experiments.

2.1.3 Experimental partitioning and volatility distribution

The experimental partitioning coefficient $K_{p,i}$ (in µg^{-1} m^3) is calculated for the experimental data applying the partitioning theory (Yamasaki et al., 1982):

$$K_{p,i} = \frac{C_{p,i}}{C_{g,i} \, TSP},$$ (1)

where, $C_{p,i}$ and $C_{g,i}$ are the particle and gas phase concentrations measured by CHARON/PTR-ToF-MS and PTR-ToF-MS of the species i (in µg m^{-3}) and TSP is the total suspended particulate matter (in µg m^{-3}). The saturation concentration C_i^* (in µg m^{-3}), commonly used to define the volatility of different chemical species (Donahue et al., 2011), is linked to the $K_{p,i}$ through the equation:

$$C_i^* = \frac{1}{K_{p,i}},$$ (2)

The saturation concentration of the major particle components is calculated for experiments at 295 and 280 K. For species having concentrations close to the detection limits, the C_i^* -was not evaluated because of high uncertainty associated with it.

2.2 Model setup and chemical mechanisms

2.2.1 Toluene oxidation mechanisms

Three versions of a detailed chemical mechanism are used in this study to reproduce the experimental oxidation of toluene and the formation of condensable species. All three are based on a detailed mechanism coupling MCM and GECKO-A to which additions and modifications are successively made. All the chemical mechanisms of toluene oxidation as well as the chemical compounds are presented in the SI with the details of the modifications made (tab. Tables S4 to S8 in the SI) and the first oxidation step is illustrated in Fig. S11.

The MCM/GECKO base mechanism

The first oxidation mechanism is generated with GECKO-A (Aumont et al., 2005). The GECKO-A tool is a computer program that automatically generates explicit chemical mechanisms following an established writing protocol. It integrates the elementary kinetic and mechanistic data available in the literature and estimates the missing ones using structure/activity relationships (SAR). The version of GECKO-A used in this study is based on the protocol presented in Aumont et al. (2005) and includes updates described in Valorso et al. (2011), Aumont et al. (2012, 2013) and La et al. (2016). In this version, the MCM v3.3.1 is used to describe the chemistry of compounds possessing an aromatic ring (Bloss et al., 2005; Jenkin et al., 2003) and GECKO-A then generates the oxidation mechanism for non-aromatic compounds.

Because the explicit description of toluene oxidation involves thousands of species and reactions, simplifications are made during generation to limit the size of the mechanism. Gaseous compounds with a saturating vapor pressure (P^{sat}) below 10^{-13} atm are considered non-reactive. Positional isomers are lumped together if their production yield is less than 10^{-3} (Valorso et al., 2011). RO$_2$ from the stepwise oxidation of toluene can only react with NO, HO$_2$, and CH$_3$O$_2$. The other RO$_2$ + RO$_2$ reactions which represent less than 10% of RO$_2$ reactivity under atmospheric conditions (Lannuque et al., 2018) are not generated. The writing of the oxidation mechanism stops after the formation of the 6th generation of stable compounds. The reaction pathways thereby simplified or eliminated concern minor fraction of matter. These simplifications do not

significantly impact ~~either the~~the simulated SOA mass.~~-~~ neither the major simulated species. ~~simulated or the simulations of the observed species.~~

~~In order to limit the number of compounds and reactions and to focus on the reproduction of measured compounds and SOA concentrations, other reductions have been realized after the generation of the chemical mechanism.~~ Only the reaction pathways leading to the formation of the main gaseous and/or condensed compounds experimentally identified ~~experimentally~~ (i.e. at the measured mass-charge ratio *m/z*) as well as to the formation of the major contributors to SOA identified by the ~~modelling~~modeling (i.e. representing more than 1% of the simulated SOA mass under the experimental conditions) are here considered. One of the major gaseous compounds formed during the toluene oxidation is methylglyoxal. It is produced by more than one hundred reactions and belongs to all the six generations of the chemical mechanism. The simplifications made reduced the number of these reactions to about fifteen major reaction pathways that represent about 85% of the simulated production of methylglyoxal. The resulting chemical mechanism is hereafter noted MG (for MCM/GECKO-A) and is composed of 125 species and 366 reactions (277 reactions leading to the formation of new species and 89 losses reactions to avoid the accumulation of final products).

Modification of the cresol chemistry

The second chemical mechanism of toluene oxidation studied is based on the MG mechanism with the addition of the chemistry of cresols and in particular, the successive addition of alcohol functions -OH on the aromatic ring, the fragmentation of the formed compounds into two aliphatic compounds and the associated kinetics as described in Schwantes et al. (2017). Additional modifications were made to the mechanism proposed in Schwantes et al. (2017) based on MCM and GECKO-A. For example, the first ~~2~~two products of reaction B2-017 (see Table~~tab.~~ S5) are from MCM, while the others are from Schwantes et al. (2017) and the branching ratios are estimated using GECKO-A. The products of reactions B2-078, B2-084 and B2-090 (see Table~~tab.~~ S5) are those proposed in Schwantes et al. (2017) and the same branching ratios are taken for each pair of formed compounds due to the lack of more accurate estimations. Hydrogen abstraction of an -OH group and then organic nitrate or peroxyl formation reactions (by addition of NO_2 or reaction with O_3 and then HO_2 respectively) at each oxidation step are added to the mechanism of Schwantes et al. (2017) following kinetics estimated by the SAR implemented in GECKO-A (Jenkin et al., 2019; Platz et al 1998; Tao et al.,1999) and branching ratios similar to MCM cresol oxidation reaction (see reactions B2-059 to B2-074 in Table ~~tab.~~ S5). Finally, loss reactions are added for all end products of new reaction pathway. This chemical mechanism is hereafter denoted MG-Cr and has 168 species and 422 reactions (including 110 loss reactions).

Modification of the aliphatic chemistry and other modifications

The third chemical mechanism studied is similar to MG-Cr, with the addition of a new ring-opening reaction pathway for toluene and new pathways for the formation of furan-like compounds based on the work of Jang and Kamens (2001). The new aromatic ring-opening pathway is added to the first oxidation step (reactions B5-001 to B5-024 in Table~~tab.~~ S5). It is

different from the one leading to the formation of MG mechanism epoxides. In ~~the study in~~ Jang and Kamens (2001) study,

no kinetics and branching ratios are proposed. These are therefore estimated using the SAR implemented in GECKO-A

230 (Jenkin et al., 2018, 2019; Vereecken and Peeters, 2009). Reaction pathways for the formation of 5-atom ring compounds (4

carbon and one oxygen) are therefore added ~~for the major compounds of the study of Jang and Kamens (2001)~~ with kinetics

estimated by GECKO-A. Some branching ratios are adjusted in order to reproduce the measurements as well as possible (for

the B3-010 reaction in particular).

In parallel to the addition of this reaction pathway, other modifications are ~~made~~considered. A simplified formation of nitro

235 toluene, an abundant gaseous first-generation ~~-~~product,~~compound in the gas phase,~~ is added following the parameterization

proposed by Atkinson et al. (1989). A formation pathway of highly oxygenated matter (HOM) is added following Wang et

al. (2017) (reactions B3-004 to B3-009 in Table~~tab.~~ S5). The kinetics of the first reaction of the pathway (B3-004) is

estimated by taking into account the fraction of biperoxy radicals leading to HOM formation (Wu et al., 2014). In absence of

experimental or theoretical values, the kinetics of the second successive autoxidation reaction (B3-005) is set to 0.5 s^{-1}

240 (similar to the value proposed in Ehn et al. (2014) for autoxidation during α-pinene oxidation). These additions also lead to

the modification of the branching ratios of the first oxidation step of toluene (B0-001). The branching ratios are modified to

incorporate the new reaction pathways,~~ and~~ to be closer to those proposed in Zaytsev et al. (2019) and to better reproduce the

experimental observations. The latter chemical mechanism is denoted MG-Cr-Al hereafter and has 210 species and 493

reactions (including 136 loss).

245 **2.2.2 Partitioning Modeling with SSH-aerosol**

The chemical mechanisms are implemented in the SSH-aerosol box model (Sartelet et al., 2020). SSH-aerosol is a modular

model that represents the formation and evolution of the mass, number and mixing state of primary and secondary particles

with different levels of complexity. It results from the coupling of three models: the Size-Composition Resolved Aerosol

Model (SCRAM) (Zhu et al., 2015) for aerosol dynamics, the Secondary Organic Aerosol Processor (SOAP) (Couvidat and

250 Sartelet, 2015) for organic gas/particle partitioning and the Hydrophobic/Hydrophilic Organics mechanism (H^2O) (Couvidat

et al., 2012) for the gas-phase chemical mechanism that represent the formation of condensable species. SSH-aerosol models

the physicochemical processes driving the evolution of atmospheric particles such as: (i) nucleation and coagulation; and (ii)

partitioning of inorganic and organic compounds dynamically or assuming thermodynamic equilibrium. For organics,

compounds can partition towards the organic or aqueous phases. The influence of hygroscopicity, viscosity and non-ideality

255 of condensed phases can be taken into account.

SSH-aerosol is here used to represent the partitioning of organic compounds formed following the different chemical

mechanisms presented in section 2.2.1. The partitioning is ~~modelled~~modeled for all stable organic compounds (i) considering

an accommodation coefficient equals to 0.7 (close to the value reported by ~~in~~ Liu et al. (2019)); (ii) by estimating the P^{sat}

with the structure/property relationship of Nannoolal et al. (2008) and (iii) by estimating the effective Henry's law constants

260   (H^{eff}) following the UNIversal Functional group Activity Coefficient (UNIFAC) (Fredenslund et al., 1975) method from their P^{sat}.

Non-ideality of condensed phases can be taken into account considering (i) short range interactions between uncharged organic molecules (computed using UNIFAC) in both organic and aqueous phases only (computed using UNIFAC) or (ii) the combination of interactions between uncharged organic molecules in both organic and aqueous phases and short,

265 medium and long-range interactions that also take into account interactions of organic molecules of SOA with inorganic ions in the aqueous phase (computed using the Aerosol Inorganic-Organic Mixtures Functional groups Activity Coefficients model, AIOMFAC (Zuend et al., 2008)). Each organic molecule is automatically associated to a list of UNIFAC functional groups. Due to the high functionalization of several compounds, an exact decomposition in UNIFAC functional groups is not always possible. In those cases, some approximations are made in order to use the decomposition of a similar molecule such

270 as relocating a functional group on a free carbon or adding a carbon to the molecule to take into account every oxygenated group.

Wall losses

A wall loss parameterization of gaseous organic compounds was implemented in SSH-aerosol for the modeling partitioning

275 study of this work. In the absence of wall loss studies in Pyrex OFR, this parameterization follows the approach developed for Teflon chamber studies (Huang et al., 2018; Krechmer et al., 2016; Zhang et al., 2015b). The parametrizationparameterization represents an irreversible first-order process whose kinetics depend on the saturation concentration of each species. Two parameters are tuned to correctly reproduce the final SOA concentration of the studied case and allows the analysis of wall loss effectses on the speciation and distribution of secondary organic compounds. The

280 parameterization details are presented in the SI.

Irreversible partitioning of methylglyoxal

A simplified parametrization of the irreversible gas-particle partitioning (due to oxidation in condensed phase) is tested only for methylglyoxal (as glyoxal was not measured in this study). This parameterization represents irreversible partitioning as

285 depending on RH. This empiric parameterization is based on effective uptake rates ($k_{eff,uptake}$) calculated with atmospheric observation values in Hu et al. (2022) for high RH cases (RH > 40%) and with experimental values in De Haan et al. (2018) for low RH cases (RH < 5%). A third-degree polynomial is fitted on experimental $k_{eff,uptake}$ to establish the RH dependency used in this study. Polynomial, experimental $k_{eff,uptake}$ and details of the parameterization are presented in the SI.

Here modeled K_p are not directly compared experimental K_p for several reasons: (i) the significant variations and

290 uncertainties in the calculation of the modeled K_p ng depending on the processes considered, especially non-ideality, (ii) the impossibility of calculating K_p for many major compounds of the modeled SOA due to their total transfer in the condensed phase and (iii) the impossibility of calculating K_p for compounds with experimental K_p but present only in the gas phase in the simulations (i.e. light compounds).

2.2.3 Simulation setup

295 To model the experimental oxidation conditions, chemical equilibria and radical concentrations, a modified version of the Regional Atmospheric Chemistry Mechanism version 2 (RACM2) (Goliff et al., 2013) is used. The modifications to RACM2 are described in detail in Lannuque et al. (2021). This new version aims at better representing the evolution of HO_X radical concentrations during the oxidation of mono-aromatic species such as toluene and xylenes. The experimental formation of NO_X and OH radical is represented by 5 reactions from the IPN photochemistry, which are added to the

300 mechanism as described in Lannuque et al. (2021). The kinetics of these reactions are based on the work of Fittschen et al. (1999) and Raff and Finlayson-Pitts (2010). The photolysis rate of IPN is calculated considering a quantum yield of 1, based on the absorption spectrum of Raff and Finlayson-Pitts (2010). The heterogeneous reaction of NO_2 on the OFR walls is also ~~modelled~~modeled to regulate the simulated NO_X concentrations (Lannuque et al., 2021). The kinetics of this reaction takes into account the gas diffusion and the uptake. It is estimated according to the method proposed in Fiorentino et al. (2021)

305 considering an uptake coefficient of 10^{-5} as recommended in Jacob (2000).

The toluene oxidation mechanisms presented in section 2.2.1 are added in SSH-aerosol to represent the formation of condensable species for SOA formation. The consumption/production of oxidants are neglected in these added mechanism as it is computed ~~controlled~~ by RACM2. All the photolysis rates (from RACM2, IPN chemistry and toluene oxidation mechanisms) are recalculated considering the irradiation spectrum of the lamps of the experiments.

310 The simulations were conducted using the SSH-aerosol box model. The temperature and RH were forced by the experimental conditions. The simulation duration time was set to 13 minutes to match the residence time in the OFR. The simulated initial toluene and pre-existing aerosol concentrations corresponded to the experimental measured values at the inlet of the OFR. Since IPN concentration was not monitored, the initial simulated IPN concentration was set to reproduce experimental toluene decay.

315 Only one size bin was considered (no size distribution), and the nucleation and coagulation processes were ignored. The phase partitioning is represented dynamically considering the transfer to non-ideal organic and aqueous phases with only ~~short range~~ interactions between uncharged organic molecules (computed with UNIFAC). As presented in section 4.2, several tests on partitioning processes were performed considering the transfer (i) to an ideal organic phase only (without interactions between compounds within the phase), (ii) to ideal organic and aqueous phases and (iii) to non-ideal organic and

320 aqueous phases with ~~short, medium and long range interactions or short range~~ interactions between uncharged organic molecules only or also with interactions of organic molecules with inorganic ions. Tests taking into account wall losses of the gaseous organic compounds and irreversible partitioning of methylglyoxal are also performed.

~~24 toluene oxidation experiments were carried out to test the impact of temperature, RH, toluene and IPN concentration as pre-existing aerosol. These differences showed little impact on the overall speciation. Therefore, as for experiments, t~~The

325 simulation results presented in this study focus on two experiments carried out at 280 and 295 K with 24% of RH, 112 ppbv of toluene and 120 ppbv of IPN (experiments n°21 and 7 respectively in Table S1). The pre-existing aerosol concentration is

9 µg m^{-3} of AS, and a small concentration of organic matter (0.01 µg/m^3) is also added to the initial concentrations to allow for the formation of organic aerosols in the model.

330 Nitro-aliphatic and peroxy acyl nitrate (PAN) compounds are not correctly quantified by the PTR-ToF-MS due to fragmentation. A correction is therefore applied to simulated aliphatic nitrates and PAN concentrations to reflect this instrumental feature. Concretely, during post-processing of model results on speciation, we consider that these simulated compounds automatically fragment and lose their -ONO$_2$ or -OONO$_2$ groups (replaced by a hydrogen atom).

3 Experimental results and discussion

3.1 Temperature dependence of SOA formation and yield

335 SOA yield from toluene was investigated for 24 experiments using different initial conditions as of temperature, toluene concentration, OH-radical concentration and ammonium sulphate seeds. Detailed information on experimental conditions and SOA derived by HR-ToF-AMS and CHARON inlet/PTR-ToF-MS can be found in Table S1 in the SI (tab. S1 in the SI). Around 30 40 to 4560% of the toluene concentration was consumed during the experiments. Figure 1 compares the calculated SOA yield as a function of the produced SOA mass with previous published works using the data from the HR-ToF-AMS. All

340 experiments were carried out under high NO$_X$ conditions. The red squares refer to experiments carried out at 295 K, the green circles at 285 K and the blue triangles at 280 K, respectively. The empty markers correspond to low initial toluene concentration experiments (below 23 ppbv) and the filled markers correspond to higher initial toluene concentration (above 100 ppbv). Both the calculated SOA yield and measured aerosol concentrations are strongly dependent on the experimental conditions and are consistent with previous studies carried out in smog chambers using higher toluene (200-1000 ppbv) and seeds concentrations

345 (Hildebrandt et al. 2009; Ng et al., 2007; Takekawa et al., 2003). For toluene concentrations between 112-162 ppbv SOA yields are located at the lower edge of the Hildebrandt et al. (2009) gray area, determined using basis-set parametrisationsparameterizations, and are closer to Ng et al. (2007) yields. One reason might be the yield correction for both organic vapours and particles wall losses performed by Hildebrandt et al. (2009) while Ng et al. (2007) applied wall losses corrections for particles only. Since the residence time into the OFR was below 15 13 minutes and seed particles (between

350 115113-1695 nm) did not show any significatesignificant depletion (below 5%). we did not correct for particle losses, while between 5 to 8 % of toluene wall losses were measured depending on the flow tube temperature.

Figure 1: SOA yield (measured by HR-ToF-AMS) vs organic aerosol formed. Red squares refer to 295 K, green circles stand for 285 K and blue triangles represent data points at 280 K. Empty markers present experiments with low toluene concentration (8 and 23 ppbv), filled markers indicate high toluene concentration experiments (above 110 ppbv). Data points from this work are compared with toluene experiments from Ng et al. (2007), Hildebrandt et al. (2009) and Takekawa et al. (2003).

For the same initial reactant concentration, the SOA yield is linearly dependent on the temperature (in the range of temperatures investigated); for toluene concentration above 110 ppbv (filled symbols) a slope of 0.4 can be traced and for toluene concentration below 23 ppbv (empty symbols) a much steeper slope of about 11 can be drawn. The temperature dependence observed in this work is consistent with previous studies (Takekawa et al., 2003) that reported twice higher toluene SOA yield for a temperature decrease from 303 to 283 K. Also, Hildebrandt et al. (2009) reported a significant increase of toluene SOA yield when the temperature decreased from 305 to 284 K (Fig.ure 1). Other experiments clearly show the influence of seeds (ammonium sulphate) concentration on SOA yield, presented in Ffig. S2. An increase in seed concentration from 5 to 10 $\mu g\ m^{-3}$ lead to increment of the SOA yield from 0.8 to almost 2.3 % at 295 K and from 4 to 10% at 280 K. These findings are in agreement with previous studies (Ng et al., 2007). The observed behaviour can be rationalized by an increased seed surface that favours condensation of toluene semi-volatile oxidation products at lower temperatures, with enhancement of aerosol concentration and SOA yield.

3.2. Experimental speciation of toluene oxidation products chemical composition

In total 97 significant signals were detected in the gas phase (from *m/z* 31 to 171), 103 signals were detected in the particle phase (from *m/z* 47 to 189) and only 65 of them were in common among the two phases. Overall chemical characteristics of toluene reaction products in the gas (PTR-ToF-MS) and particle (CHARON-/PTR-ToF-MS) phases are presented in Ffig. 2.a and 2.b respectively for an experiment at 280 K with an initial toluene concentration of 112 ppbv (experiment n°21, see

Table S1). A similar plot for the same experiment at 295 K (experiment n°7, see Table S1) is presented in figFig. S4 in the
supplementary SIsection., Tthe overall product distribution is comparable at the two temperatures. The mass fractions (in μg
m^{-3}) of the reaction products were further classified depending on their number of oxygen atoms and the molecular weight
distribution were divided in four groups: m/z 30-50, m/z 51-100, m/z 101-150, and m/z above 150. The detected gas phase
products account for 31-60% of the toluene carbon balance depending on the oxidation conditions, and considering that CO,
CO_2 and glyoxal were not measured in these experiments, as IPN degradation produces high amount of acetone that
interferes with the glyoxal signal. The SOA formed accounted for 1% and 3 % at 295K and 280K of the toluene carbon
balance, respectively. Additional information on gas and particle chemical composition for six experiments is available in
the SI (Table S9).

**Figure 2: Mass products fraction (y-axis) distribution based on the number of carbon atoms (x-axis) for an experiment with 112
ppbv toluene at 280 K. Detected ions in the (a) gas phase and (b) particle phase. Pie charts correspond to the molecular weight
contribution to the overall mass.**

The identified gas phase products shown in Figfig. 2.a are characterized by a high fraction of C7 compounds (31%) followed
by C2 (19%), C4 (16%), C1(12%), C3 (11%), C5 (6%) and C6 (2%). The product distribution in the particle phase (Figfig.
2.b) exhibits a different trend with increasing mass fraction from C1 (2%), C2 (5%), C3 (9%), C4 (12%), C5 (15%), C6

390 (21%) and finally C7 (26%). The condensed phase is generally more oxygenated., Mmore than half of the molecules contains from 3 to 5 oxygen atoms and shows higher molecular weight (pie chart in Figfig. 2.b) with respect to the gas phase products distribution.

TableTab. 1 lists the measured m/z signals, the assigned ion formula and a tentative assignment to the reaction products. The tentative chemical assignment is based on the results of a consistent number of dedicated studies (Bloss et al., 2005; Borrás

395 and Tortajada-Genaro, 2012; Forstner et al., 1997; Hamilton et al., 2005; Jang and Kamens, 2001; Kleindienst et al., 2004; Schwantes et al., 2017; White et al., 2014; Wu et al., 2014; Zaytsev et al., 2019), on the CHARON assignment procedure recommended by Gkatzelis et al. (2018a) where average saturation mass concentration $\log(C_i^*)$ are used to discriminate between parent and fragment ions (see Figfig. S3 in the SI). Furthermore, some reference compounds detected by CHARON/PTR-ToF-MSwere acquired in the laboratory and are listed in Tabletab. S2 in the SI.

400 In Tabletab. 1 the compounds are classified with respect the decreasing number of carbon atoms for two set of experiments with an initial toluene concentration of 112 ppbv at 280 K and 295 K. For each temperature three columns are presented: the first indicates the gas phase carbon balance (% of ppbC with respect to the toluene consumed), the second one presents the fraction of gas phase reaction products (% of µg m^{-3}) and the third present the fraction of the SOA products (% of µg m^{-3}). The C7 compounds account for approximately 31% of the total gas phase products. The most abundant C7 ions are

405 associated to ring retaining compounds and could be tentatively assigned to benzaldehyde (m/z 107.049), cresols and isomers (m/z 109.065, 91.057), benzoic acid and isomers (m/z 123.046) but also nitro-compounds as nitrocresol (m/z 154.051 and 136.039) and nitrotoluene (m/z 138.057). These results are in very good agreement with previous works listed above. The C7 particle phase compounds are the most abundant accounting for 25 % of the SOA mass fraction. The major identified ions contain several oxygen atoms associated to the following ion formulas $(C_7H_6O_4)H+$ at m/z 155.034, $(C_7H_8O_4)H^+$ at m/z

410 157.050, $(C_7H_6O_3)H^+$ at m/z 139.044, $(C_7H_8O_3)H^+$ at m/z 141.054, $(C_7H_6O_5)H^+$ at m/z 171.029 and $(C_7H_8O_5)H^+$ at m/z 173.044. The highest number of carbon atoms observed in the particle phase is 7. Oligomers were therefore not observed as the operating conditions used in this study (E/N = 105 Td) might induce oligomers fragmentation upon protonation.

The C6 carbon compounds account for 2% only of the gas phase products but reach 21% of organic fraction in the condensed phase. Major C6 ions are found at m/z 127.041 $(C_6H_6O_3)H^+$, m/z 143.034 $(C_6H_6O_4)H^+$ and at m/z 125.029

415 $(C_6H_4O_3)H^+$ tentatively assigned to hydroxyquinol, hydroxymethylfurfural and functionalised acids. Other less abundant C6 ions are found at m/z 111.04 $(C_6H_6O_2)H^+$, m/z 113.06 $(C_6H_8O_2)H^+$, m/z 97.064 $(C_6H_6O)H^+$ and m/z 129.057 $(C_6H_8O_3)H^+$ (Tabletab. 1). Among the C7 and C6 compounds several nitro-aromatic compounds have been identified (nitrotoluene, nitrocresol, methylnitrocatechol and nitrophenol), these nitro-aromatic compounds account for 13% and 4% of the gas and particle phase products, respectively, in agreement with previous studies (Sato et al., 2007; Tuazon et al., 1984; Zaytsev et

420 al., 2019).

The C1 to C5 compounds correspond to products formed upon cleavage of the aromatic ring. Most of the C3-C5 products are associated to non-aromatic ring retaining compounds as functionalised furans and anhydrides or ring opening products (oxocarboxylic acids, dicarbonyl or oxo-carbonyl compounds) (Hamilton et al., 2005; Jang and Kamens, 2001; Zaytsev et

al., 2019). The C5 compounds represent 7% and 15% of the gas and particle phase reaction products, respectively The most

425 important ions in the particle phase are at m/z 115.042 $(C_5H_6O_3)H^+$, at m/z 97.032 $(C_5H_4O_2)H^+$, at m/z 99.046 $(C_5H_6O_2)H^+$ and at m/z 113.025 $(C_5H_4O_3)H$. See Table~~tab.~~ 1 for tentative assignment.

Table 1: List of ion sum formulas of the major toluene degradation products monitored during the experiments. Reaction products are given as % of the total carbon of toluene consumed (carbon yield), as fraction of the gas phase products (in % of
430 **μg/m³) and as fraction of the SOA products (% of μg/m³).**

Carbon number	Measured m/z and ion sum formula	Tentative assignment	T=280 K			T= 295 K		
			Gas Phase Carbon Yield (%)	Gas Phase Products (%)	SOA Products (%)	Gas Phase Carbon Yield (%)	Gas Phase Products (%)	SOA Products (%)
7	107.049 $(C_7H_6O)H^+$	Benzaldehyde	3.98±0.41	5.65±1.50	0.23±0.08	3.69±0.11	4.46±1.07	0.14±0.02
7	109.065 $(C_7H_8O)H^+$	Cresols/ benzyl alcohol	4.21±0.45	5.55±0.96	n.d.	2.68±0.40	4.80±0.39	n.d.
7	154.051 $(C_7H_7NO_3)H^+$	**Nitrocresol**	2.45±1.07	4.94±0.90	1.00±0.18	3.47±1.14	4.07±1.20	0.66±0.28
7	141.054 $(C_7H_8O_3)H^+$	Oxo-heptedienoic acid/ epoxy-methyl-hexenedial interference with Hydroxybenzaldehyde/Benzoic acid/Methylbenzoquinone at m/z 123.046	0.08±0.03	0.15±0.06	1.56±0.95	0.10±0.03	0.15±0.06	1.54±0.65
7	123.046 $(C_7H_6O_2)H^+$ 105.038 $(C_7H_4O)H^+$	Hydroxybenzaldehyde/ Benzoic acid	1.55±0.85	3.58±0.93	1.46±0.81	2.44±0.38	4.30±1.10	0.84±0.34
7	138.062 $(C_7H_7NO_2)H^+$	**Nitrotoluene**	1.48±0.6	2.89±0.67	n.d.	2.76±0.70	4.40±0.82	n.d.
7	157.050 $(C_7H_8O_4)H^+$	Tetrahydroxybenzene/ Hydroxy-dioxo-heptenal interference at m/z 139.04	0.08±0.03	0.16±0.04	5.32±1.10	0.17±0.08	0.29±0.18	3.31±0.96
7	139.040 $(C_7H_6O_3)H^+$	Methyl cyclohexene tricarbonyls/ Hydroxy methyl benzoquinone	0.29±0.15	0.52±0.10	3.78±0.54	0.46±0.08	0.62±0.06	2.92±0.12
7	173.045 $(C_7H_8O_5)H^+$ 155.040$(C_7H_6O_2)H^+$	Hydroxy-dioxo-heptenoic acid (and isomers) interference with dihydroxy methyl benzoquinone at m/z 155.04	n.d 0.11±0.03	n.d. 0.23±0.04	3.32±0.28 5.36±0.31	n.d. 0.18±0.04	n.d. 0.30±0.04	2.28±0.98 5.70±0.91
7	170.048 $(C_7H_7NO_4)H^+$	**Methylnitrocatechol**	n.d.	n.d.	1.67±0.70	n.d.	n.d.	0.70±0.30
7	171.029 $(C_7H_6O_5)H+$	Trihydroxymethyl benzoquinone	0.02±0.01	0.04±0.02	1.57±0.60	0.06±0.02	0.11±0.04	2.43±0.95
6	127.041 $(C_6H_6O_3)H^+$ 109.033 $(C_6H_4O_2)H^+$	Hydroxyquinol/Hydroxymethylfurfural possible interference with Benzoquinone/Hydroquinone at m/z 109.033	0.08±0.04 0.20 ±0.08	0.16±0.04 0.33±0.14	6.50±0.92 0.25±0.07	0.16±0.09 0.27 ±0.09	0.26±0.13 0.38±0.11	6.23±0.55 0.33±0.10
6	143.034 $(C_6H_6O_4)H^+$ 125.029 $(C_6H_4O_3)H^+$	Dioxo-hexenoic acid/ Methyl-dioxo-pentenoic acid possible interference with Hydroxybenzoquinone	0.03±0.01 0.03±0.02	0.07±0.02 0.06±0.04	2.50±0.60 1.89±0.50	0.09±0.04 0.04±0.02	0.12±0.06 0.10±0.05	3.23±0.65 3.33±0.75
6	129.057 $(C_6H_8O_3)H^+$	Methyl-oxo-pentenoic acid /Hydroxy-oxo-hexenal	0.03±0.02	0.06±0.04	1.77±0.70	0.06±0.03	0.10±0.08	1.27±0.50
6	111.045 $(C_6H_6O_2)H^+$	Methylfurandione/Methylfuraldehyde	0.17±0.05	0.30±0.11	2.91±0.41	0.31±0.09	0.43±0.13	2.24±0.66
6	156.029$(C_6H_5NO_4)H^+$	**Nitrocatechol**	n.d.	n.d.	0.83±0.22	n.d.	n.d.	0.63±0.12
6	140.038 $(C_6H_5NO_3)H^+$	**Nitrophenol**	0.50 ±0.18	1.08±0.06	0.76 ±0.11	0.40±0.05	0.91 ±0.04	0.80 ±0.36
6	113.057$(C_6H_8O_2)H^+$	Methyl-oxo-pentenal possible interference with phenol m/z 95.04	0.05±0.02	0.08±0.05	0.78±0.21	0.14±0.05	0.31±0.04	0.35±0.16
6	95.047 $(C_6H_6O)H^+$	Phenol	0.18±0.09	0.27±0.10	0.77±0.30	0.20±0.09	0.24±0.12	0.30±0.13
5	115.042 $(C_5H_6O_3)H^+$ 97.032 $(C_5H_4O_2)H^+$	Oxo-pentenoic acid/ Methylsuccinic anhydride/ interference furaldehyde at m/z 97.032	0.14±0.05 0.16±0.06	0.28±0.10 0.29±0.12	2.88±0.40 1.75±0.30	0.37±0.20 0.55±0.32	0.64 ±0.35 0.82±0.39	3.17±0.78 1.75±0.48
5	113.025 $(C_5H_4O_3)H^+$	Methylfurandione	0.84±0.22	1.77±0.66	2.85±0.95	1.86±0.45	3.27±0.59	2.88±0.95
5	101.060 $(C_5H_8O_2)H^+$	Methyl-dihydrofuranone	0.87±0.47	1.63±0.70	n.d.	0.81±0.36	1.23±0.58	n.d.

5	149.045(C$_5$H$_8$O$_5$)H$^+$ 131.034 (C$_5$H$_6$O$_4$)H$^+$	Dihydro-oxy-pentanoic acid (DHOPA)	n.d.	n.d.	1.88±0.08	n.d.	n.d.	1.79±0.44
5	99.046 (C$_5$H$_6$O$_2$)H$^+$ 81.035 (C$_5$H$_4$O)H$^+$	Methylfuranone/Methylbutendial/ Oxo-pentenal interference methylfuran	1.18±0.21 0.14±0.05	2.16±0.22 0.21±0.12	4.11±0.28 0.34±0.09	1.87±0.66 0.19±0.05	2.79±0.95 0.24±0.08	3.20±0.74 0.12±0.04
4	99.010 (C$_4$H$_2$O$_3$)H$^+$	Maleic anhydride	4.76±1.10	11.91±0.70	0.05±0.16	6.39±0.78	11.9±1.07	0.04±0.06
4	117.021 (C$_4$H$_4$O$_4$)H$^+$	Oxo-hydroxybutanedial and isomers	0.19±0.09	0.52±0.03	2.31±0.15	0.37±0.05	0.81±0.13	2.65±0.19
4	103.042 (C$_4$H$_6$O$_3$)H$^+$	Hydroxy-oxo-butanal	0.06±0.02	0.15±0.04	2.81 ±0.65	0.12±0.06	0.23±0.10	3.17±0.44
4	85.031 (C$_4$H$_4$O$_2$)H$^+$	Butenedial	0.79±0.19	1.56±0.14	2.58±0.25	1.24±0.19	1.99±0.12	2.26±0.48
4	87.046 (C$_4$H$_6$O$_2$)H$^+$	Butanedial/crotonic acid	0.23±0.18	0.46±0.09	1.43±0.15	0.50±0.11	0.81±0.08	1.11±0.36
4	101.026 (C$_4$H$_4$O$_3$)H$^+$ 83.014 (C$_4$H$_2$O$_2$)H$^+$	Dioxobutanal	0.31±0.14	0.72±0.10	3.18±0.13	0.70±0.21	1.22±0.28	3.71±0.76
3	89.026 (C$_3$H$_4$O$_3$)H$^+$ 71.016 (C$_3$H$_2$O$_2$)H$^+$	Pyruvic acid / Hydroxy-propanedial	0.29±0.14	0.76 ±0.08	4.04±0.88	0.56±0.06	1.21±0.16	4.82±0.62
3	73.030 (C$_3$H$_4$O$_2$)H$^+$ 45.030 (C$_2$H$_4$O)H$^+$ 91.040 (C$_3$H$_6$O$_3$)H$^+$	Methylglyoxal and its hydrate	3.92±0.73	8.95±1.30	5.45±0.23	4.20±0.10	7.50±1.15	6.20±0.88
2	77.025 (C$_2$H$_4$O$_3$)H+	PAN fragment	0.42±0.11	1.48±0.44	0.19±0.08	0.55±0.18	1.59±0.32	0.21±0.07
2	61.028 (C$_2$H$_4$O$_2$)H$^+$ 43.019 (C$_2$H$_2$O)H+ 79.030 (C$_2$H$_4$O$_2$)(H$_2$O)H$^+$	Acetic acid /Hydroxyacetaldehyde and hydrate	4.73±1.4	13.31±1.26	3.96±1.03	5.50±0.73	13.23±1.69	1.56±0.39
2	45.030 (C$_2$H$_4$O)H$^+$ 63.040 (C$_2$H$_4$O)(H$_2$O)H$^+$	Potential artefact acetaldehyde and its hydrate	1.85±0.57	3.92±0.76	n.d.	2.26±0.67	3.88±0.93	n.d.
1	47.013 (CH$_2$O$_2$)H$^+$ 65.027 (CH$_2$O$_2$)(H$_2$O)H$^+$	Potential artefact formic acid and its hydrate	2.41±0.90	10.30±0.68	1.91±0.23	2.81±0.32	9.80±0.72	1.61±0.31
1	31.018(CH$_2$O)H$^+$	Potential artefact formaldehyde	0.78±0.30	2.2±0.48	n.d.	0.60±0.28	1.36±0.40	n.d.

The C4 compounds represent 16% and 12% of the gaseous and particulate phase products, respectively. A far major ion fragment is detected at *m/z* 99.010, assigned to maleic anhydride, that alone represents more than 12% of the gas phase products, in agreement to several previous studies (Hamilton et al., 2005; Jang and Kamens 2001). In the condensed phase other identified ions are: (C$_4$H$_6$O$_3$)H$^+$ at *m/z* 103.042, (C$_4$H$_4$O$_2$)H$^+$ at *m/z* 85.031, (C$_4$H$_6$O$_2$)H$^+$ at *m/z* 87.046, (C$_4$H$_4$O$_3$)H$^+$ at *m/z* 101.026 and (C$_4$H$_4$O$_4$)H$^+$ at m/z 117.021.

The C3 compounds represent approximately 11% and 9% of the gaseous and particulate phase products, respectively. Methylglyoxal and its hydrate are among the most important reaction products in both phases. Other ions at *m/z* 89.026 and 71.016 assigned to pyruvic acid (White et al. 2014) are mostly present in the particle phase. Based on previous works glyoxal molar yield under medium and high NO$_X$ conditions would vary between 8-20 % as a function of the NO$_X$ concentration (Nishino et al., 2010; Tuazon et al., 1984) but during our experiment it could not be detected due to interference with acetone produced upon photolysis of IPN.

Thermal decomposition such as the decarboxylation of organic acids does not occur at the temperatures used in this study (Piel et al., 2021). This is also confirmed by the ion distribution of formic and succinic acid in Table S2. Piel et al. (2021) found evidence for the thermal decomposition in the CHARON inlet of other compounds as hydroperoxides. But previous

works (Gkatzelis et al., 2018a; Leglise et al., 2019) show that at the conditions used in this study (E/N = 105 Td), scission of the C-C bond may occur. Therefore, a minor fraction of the low C compounds found in the particle phase could thus be measurement artifacts. ~~A series of small molecules such as acetic~~ Acetic acid/hydroxyacetaldehyde at m/z 61.028 and formic acid at 47.013 are found both in the gas and particle phase and can be both produced during toluene degradation and be surface artefacts due to heterogeneous reactions. ~~Some s~~mall aldehydes as acetaldehyde and formaldehyde ~~are found in the gas phase and~~ can also be surface artefacts, as adsorbed molecules on OFR walls can undergo chemical reaction and produce such small molecules (Doussin et al., 2023). Aliphatic nitrogen containing compounds are not easily detected due to fragmentation in the PTR-MS. Nevertheless the fragment ion at m/z 77.024 $(C_2H_3O)H^+$ previously assigned to peroxy acetyl nitrate fragment has been detected (Müller et al. 2012).

The particle phase mass loading recovered by CHARON/PTR-ToF-MS accounts for approximately 77 % of the mass measured by the HR-ToF-AMS (Fig. S5.a) when considering all the 24 experiments (Table S1). Part of this discrepancy can be explained by the loss of water occurring in the PTR-ToF-MS technique (see Table S2) but also from the different size cut-off of the two instruments inlets. This hypothesis is confirmed in Fig. S5.b, where CHARON/PTR-ToF-MS mass recovering decreases to 55% of that observed by HR-ToF-AMS when only particles below 150 nm (mobility diameter) are considered.

3.~~3~~4 Experimentally derived gas-particle phase partitioning

Figure 3 depicts the oxidation state (OSc) of the identified major ion fragments i versus the $log_{10}C_i^*$ at 295 K (magenta) and 280 K (light violet). The c~~i~~ercles are proportional to the mass associated to each ion. The error bars indicate the standard deviation of repeated experiments. The 2D-VBS (Donahue et al., 2011; Murphy et al., 2012) framework was used to implement the results, with background colours corresponding to the different volatility classes, ranging from IVOCs (light blue) to SVOCs (light green). The OSc is derived from Kroll et al. (2011) method for each individual species based on carbon, hydrogen, and oxygen number of atoms. In total 103 ions were detected in the particulate phases, among them 29 were classified as parent ions and did partition between the gas and particle phases. Table S3 (SI section) lists both $log_{10}C_i^*$ calculated at 280 and 295 K C for the identified parent ions. ~~Other~~ 20 other ions were detected in particle phase only accounting for 10-17% of the SOA mass. The remaining 62-71% of the particle mass occupied the semi-volatile organic compounds area, SVOCs, and approximately 12 to 19 % lied in the intermediate volatile organic compounds area, IVOCs. A shift of the experimental temperature from 295 to 280 K induced an important increase of the total organic aerosol mass (from 8 to 15.7 µg m^{-3}) since a higher fraction of the oxidation products was able to condense onto the particulate phase. This can be observed in Fig~~fig~~. 3 where the volatility of the individual parent ions appreciably shifts toward lower $log_{10}C_i^*$ values with $\Delta log_{10}C_i^*$ varying from 0.29 to 1.07 (Table~~tab.~~ S3).

Figure 3: The oxidation state for the detected parent ions (OSc), versus the averaged saturation concentration in terms of $\log_{10}C_i^*$. The ~~area~~ size ~~of~~ the dots denotes the mass ~~of~~ associated to each species. In light violet are represented the ions fragments identified for an experiment carried out at 280 K and in magenta those at 295 K. Errors bars correspond to ± 1σ of the experimental average. ~~Pie charts show the percent of mass measured by Charon when adding all the parent ions compared to the total organic mass evaluated by the AMS at the two experimental temperatures.~~

The saturation concentration (C_i^*) values ranged between 3 to 31000 µg m^{-3} exhibiting similar values with respect those observed for other SOA systems (Gkatzelis et al., 2018b). Previous findings suggested a volatility decrease with increasing OSc and oxygen atom number (Gkatzelis et al., 2018b; Jimenez et al., 2009; Kroll et al., 2011). In this work, however, such a trend is not observed (see also ~~Fig~~ Fig. S6 in the SI) as it was not for SOA formed from tree emissions (Gkatzelis et al., 2018b) suggesting that a higher oxidation state may not always be the key parameter for explaining volatility (Kostenidou et al., 2018). Additionally, in this study we report volatility properties for all ions detected while previous works considered only compounds with more than 5 carbon atoms.

In ~~Fig~~ Fig. 4, the volatility distribution of the toluene SOA is compared to a previous study (Hildebrandt et al., 2009). CHARON data are categorized in volatility bins in order to be comparable to the above work. Our results indicate that our products were generally in a good agreement with those extracted by Hildebrandt et al. (2009) applying the volatility basis-set parameterization for 4 products to chamber experiments at 293K and low-NO$_x$ conditions. However, our volatility distribution is shifted somehow to lower volatility products as we observed higher mass fraction of compounds with saturation concentration 100 µg m^{-3} (logC*=2) and lower contribution of species with saturation concentration 1000 µg m^{-3} (logC*=3) in comparison to Hildebrandt et al. (2009). One explanation for this behavior could be the lower initial toluene concentrations (105±49 ppb) used in this study compared to those used in Hildebrandt et al. (2009) (362 ± 176 ppb),

resulting to a higher fraction of less volatile species. The sum of the volatility bins mass fraction in ~~Fig~~Fig. 4 is less tha~~nt~~ unity since approximately 12-15% of the mass was detected ~~only~~ in the particle phase only and it has not included in these bins.

500

Figure 4: Saturation concentration (shown as volatility distribution) of the toluene SOA species. The black bars correspond to the categorization in volatility bins of this work, while the red bars correspond to the volatility distribution derived from Hildebrandt et al. (2009) applying the volatility basis-set parameterization for 4 products to chamber experiments (20°C, low-NOₓ).

4 Modeling results and discussion

505 ### 4.1 Modeling of products chemical composition

Table 2 shows a comparison between the final experimental concentrations at the outlet of the OFR and the simulated concentrations estimated with the different gas-phase chemical mechanisms for the 24% ~~of~~ RH and 112 ppbv of toluene experiments at 280 K and 295 K. In these simulations partitioning to non-ideal organic and aqueous condensed phases (with only ~~short-range~~ interactions between uncharged organic molecules estimated with UNIFAC) is considered and no wall loss

510 process is represented. Normalized root mean square error (NRMSE) for each mechanism is calculated as:

$$NRMSE = \frac{\sqrt{\frac{\sum_i^n\left\{\left(c_i^{mod}-c_i^{exp}\right)^2\right\}}{n}}}{\frac{\sum_i^n\left\{c_i^{exp}\right\}}{n}}, \tag{3}$$

where c_i^{mod} and c_i^{exp} are the mass concentrations of each simulated and experimental m/z i respectively and n the number of m/z for which the concentrations are non-zero according to both experiment and modeling. For comparison, experimental m/z are rounded to the unit. At 280 K (295 K), about 81 (88) rounded experimental m/z are measured. We observe an

515 important variation of the total mass formed (gas + particle) with the temperature during the experiments (139.9 μg m⁻³ at

280 K and 185.4 µg m^{-3} at 295 K: +32.5 %) not reproduced by the model which overestimate the mass at 280 K and underestimate it at 295 K. The mechanism modifications lead to a decrease in the simulated total mass about 3 and 11 % whatever the temperature with MG-Cr and MG-Cr-Al respectively, which is mainly due to the increasing importance of fragmentation pathways compared to functionalization ones. The modifications of chemical mechanism improve the number of represented experimental *m/z*: 31, 35 and 42 (33, 37 and 44) with MG, MG-Cr and MG-Cr-Al respectively. The better reproduction of the experimental *m/z* by the modified mechanisms results in a decrease of the NRMSE which is 2.74, 2.23 and 1.89 for MG, MG-Cr and MG-Cr-Al respectively at 280 K (2.13, 1.81 and 1.62 at 295 K). However, this NRMSE remains very high.

Table 2: Number of identified *m/z*, total mass and NRMSE for the 3 mechanisms and experiments.

	280 K (295 K)		
	number of identified exp. *m/z*	identified total mass in µg m^{-3}	NRMSE /EXP
EXP	81 (88)	139.9 (185.4)	/
MG	31 (33)	179.1 (173.7)	2.74 (2.13)
MG-Cr	35 (37)	173.7 (170.1)	2.23 (1.81)
MG-Cr-Al	42 (44)	157.2 (155.0)	1.89 (1.62)

Figure 5 shows the chemical characteristics of simulated toluene reaction products at 280 K both in the gaseous and particulate phases. Simulated glyoxal is not considered and the correction for nitro products is applied. Similarly to the experimental results (see ~~Fig~~fig. 2), the distributions of the simulated compounds in the gas phase is dominated by C7 compounds, but their mass fraction is higher (~39% for MG and MG-Cr and ~43% for MG-Cr-Al) than the measured fraction (31%). Although the three mechanisms reproduce correctly the low fraction of C6 in the gas phase, they all underestimate the C2 gas-phase fraction (~10% for MG and MG-Cr and ~13% for MG-Cr-Al). With all three mechanisms, the gas-phase fraction of C5 is the second most important (~25%), much higher than the measured value (7%). The gas-phase fraction of C1 is underestimated. Although there is little difference in the gas-phase distribution of compounds between the MG and MG-Cr mechanisms, the MG-Cr-Al mechanism introduces some differences: (i) a more important C7 gas-phase fraction (+5%), (ii) C1 are no longer negligible (~3% due to the higher formation of formaldehyde) and (iii) the gas-phase fraction of C2 is proportionally higher due to the higher formation of acetaldehyde. In terms of compound oxidation, the main difference between the experimental and simulated gas phase distribution is the formation of more oxidized C7 compounds (~40% of the gaseous C7 have 4 or 5 oxygen atoms).

540

Figure 5: Simulated mass products fraction (y-axis) distribution based on the number of carbon atoms (x-axis) for the oxidation of 112 ppbv toluene at 24% RH and 280 K with MG (a and b), MG-Cr (c and d) and MG-Cr-Al (e and f) mechanisms in the gas (a, c and e) and condensed phases (b, d and f). Pie charts correspond to the molecular weight contribution to the overall mass.

In the condensed phase, the simulated distribution of compounds by carbon number strongly differ from measured ones. First, the simulations do not reproduce the "staircase" distribution observed experimentally, regardless of the mechanism used. According to the simulations, the SOA is composed of a large majority of C7 (~64% with MG-Cr and ~73% with MG and MG-Cr-Al), followed by C5 (17 and 22%) and C4 (7 and 14%). The other compounds (C6, C3, C2 and C1) represent less than 1% of the mass of SOA formed. The simulated SOA is more oxidized than the experimentally observed SOA. It is mostly composed of molecules with 4 or more oxygen atoms (taking into account the breakup of aliphatic nitro compounds) and only a fraction of C7 has just 3 oxygens. The large fraction of C7 with 4 oxygen atoms simulated with the MG mechanism is due to the accumulation of methylnitrocatechol. The near absence of C6 in the simulated condensed phase can be explained by the low formation of these compounds in the gas phase, while the absence of short carbon chain compounds (C1 to C3) could be mainly explained by partitioning processes implemented in the model: these compounds have P^{sat} and H^{eff} too high and low respectively to condense according to Raoult's or Henry's laws as implemented in the SSH-aerosol model under the low RH conditions of simulation.

The simulated m/z distributions indicate that: (i) the MG and MG-Cr mechanisms overestimate the gaseous formation of heavy compounds and underestimate the formation of light ones (0% of the total mass with $m/z \leq 50$ against 17 % experimentally), (ii) the MG-Cr-Al mechanism improves the representation of $m/z \leq 50$ but mainly at the expense of the fraction with m/z between 50 and 100 and (iii) there is an over-representation of heavy compounds in the condensed phase ($m/z > 150$ representing between 48.9 and 71.2 % of the SOA mass against 23% experimentally) compared to the lighter ones ($m/z < 100$ representing less than 0.1 % against ~~47~~30 % experimentally).

Figure 6 represents the experimental mass spectra for the gas and condensed phases (~~Fig~~fig. 6.a) and the reconstructions of similar spectra from the simulated concentrations with the three mechanisms (~~Fig~~fig. 6.b to d) at 280 K. ~~In these figures, Gg~~lyoxal is not represented in Fig. 6. Species formed according to the MG mechanism are less numerous, and heavier than those observed in the experiment with only 3 significant peaks of species with m/z below 99 and none below 61 (~~Fig~~fig. 6.b). In contrast, there is a strong accumulation of species with m/z above 140 (up to $m/z > 250$) in both the gas and the condensed phases. A very high peak in the gas phase is observed at m/z 99. It consists of more than 50% of aliphatic nitro compounds (with one or two nitrate or PAN functions) of higher m/z from which the nitro groups have been subtracted to represent the effect of PTR-ToF-MS on these compounds. Similarly, the peak at m/z 61, normally corresponding to acetic acid, here consists almost exclusively of the 2-carbon PAN from which -OONO$_2$ has been removed. Finally, with MG, an important accumulation of methylnitrocatechol at m/z 170 (AR0128, see ~~Table~~tab. S4 in the SI) is observed in the condense phase (23 µg m^{-3}). The methylnitrocatechol strong formation originates from the MCM mechanism, and it has already been reported in other simulation studies, which estimated this species as the major contributor to the SOA of toluene (Kelly et al., 2010), in disagreement with our experimental observations.

575 The modification of the cresol chemistry in the MG-Cr mechanism corrects the overestimation of methylnitrocatechol whose formation is now competing with alternative oxidation pathways. Its concentration in the condensed phase is thus divided by about 10 (~ 2.5 µg m^{-3}). However, new compounds accumulate in the condensed phase, namely methylbenzenes with 3, 4 and 5 -OH groups on the ring, corresponding to *m/z* 141, 157 and 170 with concentrations of 6.5, 4.3 and 1.6 µg m^{-3} respectively. This version of the mechanism does not improve the representation of light compounds which remain largely

580 underestimated.

The latest modifications and the addition of a new ring-opening chemistry in the MG-Cr-Al mechanism leads to a clear improvement in the representation of light compounds with (i) enhanced formation in particular of formaldehyde (*m/z* 31) and acetaldehyde (*m/z* 45) and (ii) reduction of *m/z* 99 species. This mechanism leads to a decrease of large compounds able to partition to the condensed phase with a consequent decrease of the SOA mass formed. The modifications lead to a

585 significant improvement in the representation of the gas-phase products with the MG-Cr and then MG-Cr-Al mechanisms. Despite some important improvement, all the three mechanisms show some limitation in reproducing experimental light compounds concentrations while they tend to overestimate the formation of heavy compounds (above m/z 151) in the gas phase. Additionally for all three mechanisms we observe the absence of compounds with *m/z* < 130 in the simulated SOA while they do represent the largest fraction according to the experimental results as also other recent studies on toluene

590 derived SOA (Zaytsev et al., 2019). This discrepancy between model and experimental results can be tentatively explained by (i) the absence of some reaction products in the gas-phase oxidation mechanisms or (ii) non-accounted condensation processes of many gas phase products in the common version of the model such as irreversible gas-particle partitioning processes of α-dicarbonyl compounds and small acids (Hu et al., 2022). Even though the MG-Cr-Al mechanism leads to a better representation of light compounds in the gas phase, it does not result in a better agreement regarding the distribution

595 by carbon number in the condensed phase, suggesting that the main problem is the representation of products partitioning in the model. Several tests on the partitioning are presented in the next section in an effort to provide a better insight in the process.

Figure 6: Mass spectra of gaseous (blue) and condense (red) secondary compounds during the oxidation of 112 ppbv toluene at 280 K according to experiments (a)~~.~~, MG (b), MG-Cr (c) and MG-Cr-Al (d) mechanisms. The yellow fractions of spectra represent simulated mass after recalculation by removing functional groups with nitrogen for aliphatic compounds. Scale of the experimental SOA (a) is modified for a better readability of concentrations.

4.2 Partitioning modeling and tests on partitioning processes

To explore the partitioning of organic compounds and to try to improve the representation of the experimental observations, different tests on the partitioning processes have been carried out. In this section the formation of SOA is studied using the MG-Cr-Al chemical mechanism to represent the formation of secondary condensable species. The partitioning of these species between the gaseous and condensed phases is simulated under the same experimental conditions as presented in section 2.2.3 at 280 and 295 K by considering different physicochemical processes impacting it. The studied cases are:

- T1: partitioning to an ideal organic phase;

- T2: T1 conditions + partitioning to an ideal aqueous phase;

- T3: partitioning to non-ideal organic and aqueous phases, considering the ~~short range~~ interactions between the uncharged organic ~~compounds~~ molecules in both condensed phases (according to the UNIFAC method);

- T4: T3 conditions + consideration ~~of medium and long range~~ interactions of organic molecules with inorganic ions in the aqueous ~~one~~ phase (according to the AIOMFAC method);

- T5: T4 conditions + consideration of the loss at the walls of the OFR of gaseous organic compounds according to the parameterization presented in supplementary materials;

- T6: T5 conditions + consideration of an irreversible pathway for methylglyoxal condensation according to the parameterization presented in supplementary materials.

Figure 7 represents the temporal evolution of the concentrations of SOA formed during ~~the~~ 13 minutes of toluene oxidation ~~of toluene~~ for the six~~6~~ test cases as well as the final experimental concentration measured ~~with an~~ by the HR-ToF-AMS at 280 K. In addition, results at 295 K are presented in Fig~~fig~~. S10 in the SI and reconstructions of mass spectra at 280 K with the simulated concentrations for the test cases are presented in Fig~~fig~~. S8 and S9. ~~In the case of~~For partitioning to an ideal organic phase (T1), ~~only~~ driven by Raoult's law only and thus depending on the P^{sat} of the compounds, the SOA formation ~~of SOA~~ is very slow and ~~only~~ reaches ~3 µg m^{-3} after 13 min. This is due to the small amount of pre-existing particulate organic matter (0.01 µg m^{-3}) on~~to~~ which the compounds can condense (inorganic seeds). The addition of partitioning toward an aqueous phase, also ideal (T2), following Henry's law and thus depending on the H^{eff} of the compounds accelerates ~~the~~ SOA formation ~~of SOA~~. In this case ~~the~~ SOA mass concentration reaches ~19 µg m^{-3} after 13 min, closer to the mass concentration measured experimentally (~~16~~ 15.7 µg m^{-3}). SOA formation is here ~~facilitated~~ enhanced by the presence of inorganic ions in the pre-existing condensed phase (NH_4^+ and SO_4^{2-})~~. without however taking into account the organic/inorganic interactions within the particle~~. ~~Consideration~~ Considering~~of~~ the interactions between organic compounds within the particulate phase according to the UNIFAC method (T3) leads to an ~~important increase~~overestimation of ~~the~~ SOA formation (~30 µg m^{-3})~~. This leads to an overestimation of the SOA concentration~~ by a factor of 2 compared to the

experiment~~sal value~~al value. ~~Consideration~~ Considering~~of~~ the ~~medium and long-range~~ interactions of organic ~~compounds~~ molecules with ~~inorganic~~ ions in aqueous phase (according to AIOMFAC) ~~in addition to~~and the ~~short range~~ interactions between uncharged organic molecules in the both particulate phases (T4) lead to the formation of SOA mass concentration (~21 µg m^{-3}) closer to the experimental value. ~~(~21 µg m^{-3}). In our experiment, the~~The interactions ~~of the~~between organic compounds ~~with each other~~ in the condensed phase tend to shift the equilibria towards the particulate phase (reflecting an affinity of the compounds with each other)~~. However~~, while the interactions ~~of the~~between organic ~~compounds and~~with the inorganics compounds result in the opposite effect. Even though these two processes ~~types of interactions~~ compensate each other, there is still a relatively high error (+31%) between the simulated and the experimental total SOA mass concentration ~~of SOA~~.

Even though T2 and T4 final SOA concentrations are close, ~~The~~the modeled mass spectra show significant differences ~~that the SOA~~ in composition ~~differs significantly~~ (see ~~Fig~~fig. S8) ~~even if the SOA mass concentrations simulated during the partitioning test towards two ideal condensed phases and the one considering all the interactions with AIOMFAC are close (with a difference of ~2 µg m^{-3}). Indeed, the consideration of~~ The interactions between organic ~~compounds~~ molecules favors the condensation of many compounds (*m/z* = 149, 155, 157, 170, 175, or 191 for example) and particularly the lighter ones~~compounds~~ (*m/z* = 131, 132, 135). This also ~~has the effect of reducing~~reduces the accumulation of the *m/z* 141 compounds ~~with an *m/z* = 141~~. ~~The consideration of t~~The interactions between organic ~~compounds~~ and inorganic ~~ions~~ compounds in the aqueous phase modifies the SOA speciation ~~of SOA~~ by limiting the partitioning of several ~~of them~~chemical species (*m/z* = 141, 157, 170, 175 and 191 in particular) and favoring the uptake~~that~~ of others (*m/z* = 173, 186 or 202). The result is a condensed phase composed of a greater variety of compounds~~, each with lower mass concentration and together~~ covering a wider range of *m/z*~~.~~ values.

Figure 7: Temporal evolution of the SOA concentrations during toluene oxidation under experimental conditions (see sect. 2.2.3) simulated with MG-Cr-Al mechanism at 280 K considering mass transfer through an ideal organic phase (T1, black line), ideal

organic and aqueous phases (T2, blue line), organic and aqueous phases with ~~long-range~~ interactions **between organic molecules (T3, green line)**, organic and aqueous phases with ~~long- and short-range~~ interactions **between organic molecules and inorganic ions (T4, purple line)**, organic and aqueous phases with **interactions between organic molecules and inorganic ions** ~~long- and short-range interactions~~ and wall losses (T5, dark red line) and organic and aqueous phases with **interactions between organic molecules and inorganic ions** ~~long- and short-range interactions~~, wall losses and irreversible pathway for methylglyoxal condensation (T6, orange line). The red point represent**s** the experimental SOA concentration measured by AMS.

The T5 test involves adding a **wall loss** parameterization ~~of wall losses on the OFR walls of~~**for** gaseous organic compounds as described in Section 2.2.2. These P^{sat}/C^*-dependent wall losses logically lead to a better reproduction of the SOA concentration (~15.7 µg m^{-3}) as the parameters ~~of the wall loss parameterization~~ have been optimized for. However, it is interesting to analyze the effect of the wall-~~loss~~**losses** parameterization on the mass ~~spectrum~~**spectra** of the secondary compounds (see ~~Fig~~**fig**. S8). **For the gas phase, we observe a slight** ~~In the gaseous compound spectrum, the parametrization slightly~~ decreases **in** the concentrations of some heavy compounds (**as** m/z = 184, 175, 170, 157 for example) **and also of some lighter ones.** ~~It also leads to a decrease of the concentrations of~~ (m/z = 61 and 99**, due to the loss** ~~by the reduction of the concentrations~~ of ~~the~~ heav**ier** compounds **before their** fragment**ation**~~ing~~ **in the PTR-ToF-MS,**~~during the measurement~~ (**indicated** in yellow in ~~Fig~~**fig**. S8). Regarding the particulate phase, the parameterization ~~leads to the reduction~~**reduces** ~~of~~ the concentrations of all the **simulated** m/z ~~simulated~~**proportionally to their mass** ~~in a homogeneous way~~ **meaning that all the condensed compounds have enough low volatility to undergo partial wall losses.** ~~It~~**Finally, the parameterization** results in a better representation of the condensed fraction without significantly affecting the representation of the gas phase.

T1 to T5 simulations at 295 K show the same behavior for the SOA mass evolution depending on the considered processes (see ~~Fig~~**fig**. S10). Even if ~~the~~ wall-~~loss~~**losses** parameterization was optimized on the 280 K case, ~~the~~ T5 test ~~also~~ well reproduces the experimental SOA mass at 295 K (with 8.7 µg m^{-3} simulated versus 8.2 µg m^{-3} measured by the **HR-Tof-**AMS, see ~~Fig~~**fig**. S10).

Regardless of the considered partitioning processes, the model fails to represent the experimentally observed partitioning of light compounds. In T6 test, an irreversible gas-particle partitioning parameterization ~~of~~ **for** methylglyoxal based on atmospheric observations by Hu et al. (2022) and chamber experiments by De Haan et al. (2018) is implemented to the SSH-aerosol model in an attempt to reproduce the experimentally observed partitioning of this compound (see Section 2.2.2). The mass spectrum of the simulation at 280 K considering all the processes tested in this section and adding ~~the~~ **this** new parameterization is presented in ~~Fig~~**fig**. S9 in the SI. The addition of the irreversible partitioning at 280 K leads to the condensation of about 0.49 µg m^{-3} of the simulated methylglyoxal, which is of the same order of magnitude as the experimental value (~0.56 µg m^{-3}) despite an underestimation of the gaseous methylglyoxal mass concentration (~7.5 µg m^{-3} simulated versus ~10.4 µg m^{-3} experimentally observed). This increase in the condensed mass concentration of methylglyoxal logically affects the simulated mass concentration of SOA (~16.2 µg m^{-3}). At 295 K, the irreversible partitioning leads to the condensation of about 0.47 µg m^{-3} of the simulated methylglyoxal higher than the measured value (~0.30 µg m^{-3}). Experimental and simulated values are still in the same order of magnitude ~~but the~~**with a** higher error at 295 K (+56% vs. -12.5% at 280 K)**.** ~~T~~**and t**he low variation of the condensed methylglyoxal with the temperature variation show

the limits of the simplified parameterization only based on methylglyoxal concentration and RH (here fixed at 24 % for both temperatures).

The objective of the modeling ~~part of this study~~exercise was to reproduce the experimentally observed SOA masses for the right reasons supported by ~~and thus start from the~~ molecular information~~level~~. However, by making the chemistry representation more complex, it ~~becomes~~ became necessary to increase the complexity of ~~make~~ the partitioning processes ~~more complex~~ as well. ~~The successive consideration of each of the different physicochemical processes that can impact the partitioning between the gaseous and condensed phases greatly influence the concentrations of SOA formed.~~ In ~~our case~~this study, neglecting~~, without considering~~ the aqueous partitioning, leads to ~~the formation of~~ SOA underestimation ~~is underestimated~~ because of the quasi absence of a pre-existing organic phase, and because compounds are too volatile to condense on an organic phase. ~~The consideration of interactions between~~Considering organic compound interactions~~s~~ in the particulate phase leads to a shift of equilibria towards the particulate phase and thus favors the condensation of molecules. In ~~our case study,~~the simulation at 280 K~~,~~ this increases the ~~estimated mass of~~ SOA mass formed by ~50% (+11 µg m^{-3}) compared to the ideal case. Contrariwise ~~the consideration of~~ the interactions between inorganic ions and organic compounds in the aqueous phase ~~seems here to~~ limit the condensation of gaseous organic species ~~(there is a high concentration of ions due to the seeds) and~~ therefore reduc~~ing~~es the estimated SOA mass concentration by ~33% (-9 µg m^{-3}) compared to the case where only organic interactions are considered. All these tests highlight the large uncertainties in SOA formation related to the representation of phase-transfer processes independently of the gaseous oxidation mechanism. Whether or not the different processes are taken into account has a considerable effect on the simulated SOA mass. ~~It~~This work therefore raises questions about the significance of the results and the representativeness of (i) simplified models that do not include them, (ii) models that include only a part of them with the risk of introducing biases in the results, or (iii) more complex models that include as many processes as possible, increasing the potential sources of error and the resources needed to resolve them. This study underlines the need to develop semi-explicit mechanisms, such as those presented by Wang et al. (2022), preserving~~that keep~~ the SOA properties in terms of solubility and interactions with organics/inorganics.

5 Summary and perspectives

This work focuses on the experimental and modelling study of toluene-SOA formation upon OH radical reaction. The calculated SOA yield and measured aerosol concentrations was strongly dependent on the experimental conditions (temperature, seed concentration~~, OH~~ and toluene initial concentrations~~, NO$_x$ levels~~) and agreed with previous works. The CHARON-inlet coupled to a PTR-ToF-MS successfully quantified approximately ~~70~~77 % of the total organic mass measured from an aerosol mass spectrometer (HR-ToF-AMS). Despite possible fragmentation of the measured compounds, the major products both in the gas and particulate phases were confirmed through intercomparison with the literature. The partitioning properties of the identified reaction products were determined. Approximately 80-85 % of the organic aerosol fraction detected by CHARON showed volatility distributions, expressed as saturation mass concentration, logCi*, ranging

from 0.65 to 5.30, another 10-17% was detected in the condensed phase only. Temperature variation, from 295 to 280 K, induced an appreciable decrease of the compound's volatility with a $\Delta log_{10}C_i^*$ varying from 0.28 to 1.07. Parent ions were mapped onto the 2D-VBS framework, and results did not exhibit a clear correlation with increasing oxidation state or oxygen atom number.

To reproduce the observed SOA mass loading and composition, a new semi-detailed chemical mechanism for the gaseous oxidation of toluene has been developed to reproduce the experimentally observed speciation of secondary compounds in the gas phase and SOA. It is based on an explicit reference mechanism using MCM for the aromatic chemistry and GECKO-A for the aliphatic chemistry. This reference has been simplified and modified on the basis of the experimental data and previous works on cresol chemistry, furan formation and aromatic ring opening chemistry, formation of HOM and SAR of GECKO-A to estimate missing kinetic data. All these modifications improved the representativeness of the chemical mechanism with +35% of major secondary compounds identified across all phases (number of species) and an error on the total secondary organic mass reduced by ~55%. At the molecular scale, this translates into a better representation of the formation of light compounds (i.e. $m/z < 100$) and lower concentration of larger compounds (i.e. $m/z \geq 100$). However, the mechanism still tends to underestimate the formation of light compounds and overestimate that of heavier ones compared to experimental observations.

The modeled reaction products are more oxidized and less fragmented than the experimentally observed ones, especially in the condensed phase. In the gas phase, the model favors the formation of C7 and C5 at the expense of the shorter carbon chains. The level of oxidation of the reaction products is generally similar to the observations except for the more oxidized C7 compounds. The underestimation of the fragmentation pathways compared to the functionalization ones and the risk of products fragmentation during the experimental measurement, may lead to some discrepancy between simulated and observed concentrations in both phases. The larger errors in the condensed phase than in the gas phase highlight the remaining uncertainty in the partitioning processes and their modeling. Tests on partitioning reveal that taking into account some processes leads to large variation of the simulated SOA mass concentration resulting in discrepancies with respect to the experimental values from +88% to -81%. The addition of an aqueous phase with few organic seeds favored the formation of SOA. Taking into account the interactions of the organic compounds among themselves shifted the equilibrium towards the condensed phase (error raised to +88%) while the interaction between inorganic ions and organic compounds in aqueous phase had the opposite effect (error reduced to +31%). The introduction of wall losses parameterization also reduced the discrepancy. When including all these processes, the model reproduces much better the experimental SOA mass concentration formed and its temperature dependence, despite relevant discrepancies in the chemical speciation. The model, in its current state, does not reproduce the partitioning of light compounds, but a test of a simplified parameterization for methylglyoxal irreversible partitioning led to an improvement of the representation of this light compound in SOA, opening thus the way to further research and developments.

Data availability. SSH-aerosol model is open-source (GNU GPL-3 licence). The last version of SSH-aerosol is available at https://github.com/sshaerosol/ssh-aerosol (last access: June 08 2023).

Competing interests. The authors declare that they have no conflict of interest.

760

Author Contribution. .VL, BD, AW and KS designed the research. PI, BTR, AMV, MM performed the experiments and contributed to the acquisition and analysis of the data. VL, KS and FC developed the software. VL and RV contributed to photolysis and mechanistic data for the model. VL, KS, BD, EK and PI analyzed and interpreted the data. VL and BD drafted the article. VL, BD, KS, EK, MM and AW revised the article. KS, BD and VL were responsible for funding
765   acquisition.

Acknowledgments. The France-Austria Hubert Curien Partnership 2016 with the Amadeus' Program. The program provided financial support for mobility of PhD students between Univ. Innsbruck (Austria) and IRCELYON (France)

770   **Financial support.** This work was funded by the POLEMICS project of the Agence Nationale de la Recherche (ANR) program (grant ANR-18-CE22-0011), DIM QI^2 (Air Quality Research Network on air quality in the Ile-de-France region) and the MAESTRO-EU6 project (ADEME CORTEA n. 1866C0001). This work also benefited from the IPSL-CGS EUR and was partially supported by a government grant under the Programme d'Investissements d'avenir, reference ANR-11-IDEX-0004-17-EURE-0006, managed by the Agence Nationale de la Recherche.

775   **References**

Atkinson, R., Aschmann, S. M., Arey, J., and Carter, W. P. L.: Formation of ring-retaining products from the OH radical-initiated reactions of benzene and toluene, Int. J. Chem. Kinet., 21, 801–827, https://doi.org/10.1002/KIN.550210907, 1989.

Aumont, B., Szopa, S., and Madronich, S.: Modelling the evolution of organic carbon during its gas-phase tropospheric
780   oxidation: development of an explicit model based on a self generating approach, Atmos. Chem. Phys., 5, 2497–2517, https://doi.org/10.5194/acp-5-2497-2005, 2005.

Aumont, B., Valorso, R., Mouchel-Vallon, C., Camredon, M., Lee-Taylor, J., and Madronich, S.: Modeling SOA formation from the oxidation of intermediate volatility n-alkanes, Atmos. Chem. Phys., 12, 7577–7589, https://doi.org/10.5194/acp-12-7577-2012, 2012.

785   Baltaretu, C. O., Lichtman, E. I., Hadler, A. B., and Elrod, M. J.: Primary atmospheric oxidation mechanism for toluene, J. Phys. Chem. A, 113, 221–230, https://doi.org/10.1021/jp806841t, 2009.

Bloss, C., Wagner, V., Jenkin, M. E., Volkamer, R., Bloss, W. J., Lee, J. D., Heard, D. E., Wirtz, K., Martin-Reviejo, M., Rea, G., Wenger, J. C., and Pilling, M. J.: Development of a detailed chemical mechanism (MCMv3.1) for the atmospheric oxidation of aromatic hydrocarbons, Atmos. Chem. Phys., 5, 641–664, https://doi.org/10.5194/acp-5-641-
790   2005, 2005.

Bohn, B.: Formation of peroxy radicals from OH-toluene adducts and O2, J. Phys. Chem. A, 105, 6092–6101, https://doi.org/10.1021/jp0033972, 2001.

Borrás, E. and Tortajada-Genaro, L. A.: Determination of oxygenated compounds in secondary organic aerosol from isoprene and toluene smog chamber experiments, Int. J. Environ. Anal. Chem., 92, 110–124, https://doi.org/10.1080/03067319.2011.572164, 2012.

Boucher, O., Randall, D., Artaxo, P., Bretherton, C., Feingold, G., Forster, P., Kerminen, V.-M., Kondo, Y., Liao, H., Lohmann, U., Rasch, P., Satheesh, S. K., Sherwood, S., Stevens, B., and Zhang, X. Y.: Clouds and Aerosols, in: Climate Change 2013 - The Physical Science Basis. Contribution of Working Group I to the Fifth Assessment Report of the Intergovernmental Panel on Climate Change, edited by: Stocker, T. F., Qin, D., Plattner, G.-K., Tignor, M., Allen, S. K., Boschung, J., Nauels, A., Xia, Y., Bex, V., and Midgley, P. M., Cambridge University Press, Cambridge, United Kingdom and New York, NY, USA, 571–658, https://doi.org/10.1017/CBO9781107415324.016, 2013.

Calvert, J. G., Atkinson, R., Becker, K. H., Kamens, R. M., Seinfeld, J. H., Wallington, T. J., and Yarwood, G.: The mechanisms of atmospheric oxidation of aromatic hydrocarbons, Oxford University Press, Oxford, UK, 2002.

Canagaratna, M. R., Jimenez, J. L., Kroll, J. H., Chen, Q., Kessler, S. H., Massoli, P., Hildebrandt Ruiz, L., Fortner, E., Williams, L. R., Wilson, K. R., Surratt, J. D., Donahue, N. M., Jayne, J. T., and Worsnop, D. R.: Elemental ratio measurements of organic compounds using aerosol mass spectrometry: Characterization, improved calibration, and implications, Atmos. Chem. Phys., 15, 253–272, https://doi.org/10.5194/acp-15-253-2015, 2015.

Couvidat, F. and Sartelet, K.: The Secondary Organic Aerosol Processor (SOAP v1.0) model: a unified model with different ranges of complexity based on the molecular surrogate approach, Geosci. Model Dev., 8, 1111–1138, https://doi.org/10.5194/gmd-8-1111-2015, 2015.

Couvidat, F., Debry, É., Sartelet, K., and Seigneur, C.: A hydrophilic/hydrophobic organic (H2O) aerosol model: Development, evaluation and sensitivity analysis, J. Geophys. Res., 117, D10304, https://doi.org/10.1029/2011JD017214, 2012.

DeCarlo, P. F., Kimmel, J. R., Trimborn, A., Northway, M. J., Jayne, J. T., Aiken, A. C., Gonin, M., Fuhrer, K., Horvath, T., Docherty, K. S., Worsnop, D. R., and Jimenez, J. L.: Field-deployable, high-resolution, time-of-flight aerosol mass spectrometer, Anal. Chem., 78, 8281–8289, https://doi.org/10.1021/ac061249n, 2006.

Donahue, N. M., Epstein, S. a., Pandis, S. N., and Robinson, a. L.: A two-dimensional volatility basis set: 1. organic-aerosol mixing thermodynamics, Atmos. Chem. Phys., 11, 3303–3318, https://doi.org/10.5194/acp-11-3303-2011, 2011.

Doussin, J.-F., Fuchs, H., Kiendler-Scharr, A., Seakins, P., and Wenger, J. (Eds.): A Practical Guide to Atmospheric Simulation Chambers, Springer International Publishing, Cham, https://doi.org/10.1007/978-3-031-22277-1, 2023.

Drewnick, F., Hings, S. S., DeCarlo, P., Jayne, J. T., Gonin, M., Fuhrer, K., Weimer, S., Jimenez, J. L., Demerjian, K. L., Borrmann, S., and Worsnop, D. R.: A new time-of-flight aerosol mass spectrometer (TOF-AMS) - Instrument description and first field deployment, Aerosol Sci. Technol., 39, 637–658, https://doi.org/10.1080/02786820500182040, 2005.

Drewnick, F., Hings, S. S., Alfarra, M. R., Prevot, A. S. H., and Borrmann, S.: Atmospheric Measurement Techniques Aerosol quantification with the Aerodyne Aerosol Mass Spectrometer: detection limits and ionizer background effects, Atmos. Meas. Tech, 2, 33–46, 2009.

Ehn, M., Thornton, J. A., Kleist, E., Sipila, M., Junninen, H., Pullinen, I., Springer, M., Rubach, F., Tillmann, R., Lee, B., Lopez-Hilfiker, F., Andres, S., Acir, I. H., Rissanen, M., Jokinen, T., Schobesberger, S., Kangasluoma, J., Kontkanen, J., Nieminen, T., Kurten, T., Nielsen, L. B., Jorgensen, S., Kjaergaard, H. G., Canagaratna, M., Dal Maso, M., Berndt, T., Petaja, T., Wahner, A., Kerminen, V. M., Kulmala, M., Worsnop, D. R., Wildt, J., and Mentel, T. F.: A large source of low-volatility secondary organic aerosol, Nature, 506, 476–479, https://doi.org/10.1038/Nature13032, 2014.

Eichler, P., Müller, M., D'Anna, B., and Wisthaler, A.: A novel inlet system for online chemical analysis of semi-volatile submicron particulate matter, Atmos. Meas. Tech., 8, 1353–1360, https://doi.org/10.5194/AMT-8-1353-2015, 2015.

835 Fiorentino, E. A., Wortham, H., and Sartelet, K.: Combining homogeneous and heterogeneous chemistry to model inorganic compound concentrations in indoor environments: The H2I model (v1.0), Geosci. Model Dev., 14, 2747–2780, https://doi.org/10.5194/GMD-14-2747-2021, 2021.

Fittschen, C., Frenzel, A., Imrik, K., and Devolder, P.: Rate constants for the reactions of C2H5O, i-C3H7O, and n-C3H7O with NO and O2 as a function of temperature, Int. J. Chem. Kinet., 31, 860–866, https://doi.org/10.1002/(SICI)1097-840 4601(1999)31:12<860::AID-KIN4>3.0.CO;2-E, 1999.

Forstner, H. J. L., Flagan, R. C., and Seinfeld, J. H.: Secondary organic aerosol from the photooxidation of aromatic hydrocarbons: Molecular composition, Environ. Sci. Technol., 31, 1345–1358, https://doi.org/10.1021/es9605376, 1997.

Fredenslund, A., Jones, R. L., and Prausnitz, J. M.: Group-contribution estimation of activity coefficients in nonideal liquid 845 mixtures, AIChE J., 21, 1086–1099, https://doi.org/10.1002/aic.690210607, 1975.

Gelencsér, A., May, B., Simpson, D., Sánchez-Ochoa, A., Kasper-Giebl, A., Puxbaum, H., Caseiro, A., Pio, C., and Legrand, M.: Source apportionment of PM2.5 organic aerosol over Europe: Primary/secondary, natural/anthropogenic, and fossil/biogenic origin, J. Geophys. Res., 112, D23S04, https://doi.org/10.1029/2006JD008094, 2007.

Gkatzelis, G. I., Tillmann, R., Hohaus, T., Müller, M., Eichler, P., Xu, K.-M., Schlag, P., Schmitt, S. H., Wegener, R., 850 Kaminski, M., Holzinger, R., Wisthaler, A., and Kiendler-Scharr, A.: Comparison of three aerosol chemical characterization techniques utilizing PTR-ToF-MS: a study on freshly formed and aged biogenic SOA, Atmos. Meas. Tech, 11, 1481–1500, https://doi.org/10.5194/amt-11-1481-2018, 2018a.

Gkatzelis, G. I., Hohaus, T., Tillmann, R., Gensch, I., Müller, M., Eichler, P., Xu, K.-M., Schlag, P., Schmitt, S. H., Yu, Z., Wegener, R., Kaminski, M., Holzinger, R., Wisthaler, A., and Kiendler-Scharr, A.: Gas-to-particle partitioning of 855 major biogenic oxidation products: a study on freshly formed and aged biogenic SOA, Atmos. Chem. Phys, 18, 12969–12989, https://doi.org/10.5194/acp-18-12969-2018, 2018b.

Goliff, W. S., Stockwell, W. R., and Lawson, C. V.: The regional atmospheric chemistry mechanism, version 2, Atmos. Environ., 68, 174–185, https://doi.org/10.1016/j.atmosenv.2012.11.038, 2013.

Graus, M., Müller, M., and Hansel, A.: High Resolution PTR-TOF: Quantification and Formula Confirmation of VOC in 860 Real Time, J Am Soc Mass Spectrom, 21, 1037–1044, https://doi.org/10.1016/j.jasms.2010.02.006, 2010.

De Haan, D. O., Jimenez, N. G., de Loera, A., Cazaunau, M., Gratien, A., Pangui, E., and Doussin, J.-F.: Methylglyoxal Uptake Coefficients on Aqueous Aerosol Surfaces, J. Phys. Chem. A, 122, 4854–4860, https://doi.org/10.1021/acs.jpca.8b00533, 2018.

Hamilton, J. F., Webb, P. J., Lewis, A. C., and Reviejo, M. M.: Quantifying small molecules in secondary organic aerosol 865 formed during the photo-oxidation of toluene with hydroxyl radicals, Atmos. Environ., 39, 7263–7275, https://doi.org/10.1016/J.ATMOSENV.2005.09.006, 2005.

Han, S., Bian, H., Zhang, Y., Wu, J., Wang, Y., Tie, X., Li, Y., Li, X., and Yao, Q.: Effect of Aerosols on Visibility and Radiation in Spring 2009 in Tianjin, China, Aerosol Air Qual. Res., 12, 211–217, https://doi.org/10.4209/aaqr.2011.05.0073, 2012.

870 Hildebrandt, L., Donahue, N. M., and Pandis, S. N.: High formation of secondary organic aerosol from the photo-oxidation of toluene, Atmos. Chem. Phys., 9, 2973–2986, https://doi.org/10.5194/acp-9-2973-2009, 2009.

Hu, D., Bian, Q., Li, T. W. Y., Lau, A. K. H., and Yu, J. Z.: Contributions of isoprene, monoterpenes, β-caryophyllene, and toluene to secondary organic aerosols in Hong Kong during the summer of 2006, J. Geophys. Res. Atmos., 113, 22206,

https://doi.org/10.1029/2008JD010437, 2008.

875   Hu, J., Chen, Z., Qin, X., and Dong, P.: Reversible and irreversible gas-particle partitioning of dicarbonyl compounds observed in the real atmosphere, Atmos. Chem. Phys, 22, 6971–6987, https://doi.org/10.5194/acp-22-6971-2022, 2022.

Huang, Y., Zhao, R., Charan, S. M., Kenseth, C. M., Zhang, X., and Seinfeld, J. H.: Unified Theory of Vapor-Wall Mass Transport in Teflon-Walled Environmental Chambers, Environ. Sci. Technol., 52, 2134–2142, 880   https://doi.org/10.1021/acs.est.7b05575, 2018.

Jacob, D.: Heterogeneous chemistry and tropospheric ozone, Atmos. Environ., 34, 2131–2159, https://doi.org/10.1016/S1352-2310(99)00462-8, 2000.

Jang, M. and Kamens, R. M.: Characterization of secondary aerosol from the photooxidation of toluene in the presence of NOx and 1-propene, Environ. Sci. Technol., 35, 3626–3639, https://doi.org/10.1021/es010676+, 2001.

885   Jenkin, M. E., Saunders, S. M., Wagner, V., and Pilling, M. J.: Protocol for the development of the Master Chemical Mechanism, MCM v3 (Part B): tropospheric degradation of aromatic volatile organic compounds, Atmos. Chem. Phys., 3, 181–193, https://doi.org/10.5194/acp-3-181-2003, 2003.

Jenkin, M. E., Valorso, R., Aumont, B., Rickard, A. R., and Wallington, T. J.: Estimation of rate coefficients and branching ratios for gas-phase reactions of OH with aliphatic organic compounds for use in automated mechanism construction, 890   Atmos. Chem. Phys., 18, 9297–9328, https://doi.org/10.5194/acp-18-9297-2018, 2018.

Jenkin, M. E., Valorso, R., Aumont, B., and Rickard, A. R.: Estimation of rate coefficients and branching ratios for reactions of organic peroxy radicals for use in automated mechanism construction, Atmos. Chem. Phys., 19, 7691–7717, https://doi.org/10.5194/acp-19-7691-2019, 2019.

Jimenez, J. L., Canagaratna, M. R., Donahue, N. M., Prevot, A. S. H., Zhang, Q., Kroll, J. H., DeCarlo, P. F., Allan, J. D., 895   Coe, H., Ng, N. L., Aiken, A. C., Docherty, K. S., Ulbrich, I. M., Grieshop, A. P., Robinson, A. L., Duplissy, J., Smith, J. D., Wilson, K. R., Lanz, V. A., Hueglin, C., Sun, Y. L., Tian, J., Laaksonen, A., Raatikainen, T., Rautiainen, J., Vaattovaara, P., Ehn, M., Kulmala, M., Tomlinson, J. M., Collins, D. R., Cubison, M. J., Dunlea, E. J., Huffman, J. A., Onasch, T. B., Alfarra, M. R., Williams, P. I., Bower, K., Kondo, Y., Schneider, J., Drewnick, F., Borrmann, S., Weimer, S., Demerjian, K., Salcedo, D., Cottrell, L., Griffin, R., Takami, A., Miyoshi, T., Hatakeyama, S., Shimono, 900   A., Sun, J. Y., Zhang, Y. M., Dzepina, K., Kimmel, J. R., Sueper, D., Jayne, J. T., Herndon, S. C., Trimborn, A. M., Williams, L. R., Wood, E. C., Middlebrook, A. M., Kolb, C. E., Baltensperger, U., and Worsnop, D. R.: Evolution of organic aerosols in the atmosphere., Science (80-.)., 326, 1525–9, https://doi.org/10.1126/science.1180353, 2009.

Johnson, J. R.: Organic Synthesis (Vol. XIX, p. 64), Wiley (Ed.), New York, 1939.

Jordan, A., Haidacher, S., Hanel, G., Hartungen, E., Märk, L., Seehauser, H., Schottkowsky, R., Sulzer, P., and Märk, T. D.: 905   A high resolution and high sensitivity proton-transfer-reaction time-of-flight mass spectrometer (PTR-TOF-MS), Int. J. Mass Spectrom., 286, 122–128, https://doi.org/10.1016/J.IJMS.2009.07.005, 2009.

Kamens, R. M., Zhang, H., Chen, E. H., Zhou, Y., Parikh, H. M., Wilson, R. L., Galloway, K. E., and Rosen, E. P.: Secondary organic aerosol formation from toluene in an atmospheric hydrocarbon mixture: Water and particle seed effects, Atmos. Environ., 45, 2324–2334, https://doi.org/10.1016/j.atmosenv.2010.11.007, 2011.

910   Kelly, J. L., Michelangeli, D. V., Makar, P. A., Hastie, D. R., Mozurkewich, M., and Auld, J.: Aerosol speciation and mass prediction from toluene oxidation under high NOx conditions, Atmos. Environ., 44, 361–369, https://doi.org/10.1016/J.ATMOSENV.2009.10.035, 2010.

Kim, Y., Couvidat, F., Sartelet, K., and Seigneur, C.: Comparison of Different Gas-Phase Mechanisms and Aerosol Modules for Simulating Particulate Matter Formation, J. Air Waste Manage. Assoc., 61, 1218–1226,

915 https://doi.org/10.1080/10473289.2011.603999, 2011.

Kleindienst, T. E., Conver, T. S., McIver, C. D., and Edney, E. O.: Determination of secondary organic aerosol products from the photooxidation of toluene and their implications in ambient PM2.5, J. Atmos. Chem., 47, 79–100, https://doi.org/10.1023/B:JOCH.0000012305.94498.28, 2004.

Klotz, B., Sørensen, S., Barnes, I., Becker, K. H., Etzkorn, T., Volkamer, R., Platt, U., Wirtz, K., and Martin-Reviejo, M.:
920 Atmospheric oxidation of toluene in a large-volume outdoor photoreactor: In situ determination of ring-retaining product yields, J. Phys. Chem. A, 102, 10289–10299, https://doi.org/10.1021/jp982719n, 1998.

Kostenidou, E., Karnezi, E., Hite, J., Bougiatioti, A., Cerully, K., Xu, L., Ng, N., Nenes, A., and Pandis, S.: Organic aerosol in the summertime southeastern United States: Components and their link to volatility distribution, oxidation state and hygroscopicity, Atmos. Chem. Phys., 18, 5799–5819, https://doi.org/10.5194/ACP-18-5799-2018, 2018.

925 Krechmer, J. E., Pagonis, D., Ziemann, P. J., and Jimenez, J. L.: Quantification of Gas-Wall Partitioning in Teflon Environmental Chambers Using Rapid Bursts of Low-Volatility Oxidized Species Generated in Situ, Environ. Sci. Technol., 50, 5757–5765, https://doi.org/10.1021/acs.est.6b00606, 2016.

Kroll, J. H., Donahue, N. M., Jimenez, J. L., Kessler, S. H., Canagaratna, M. R., Wilson, K. R., Altieri, K. E., Mazzoleni, L. R., Wozniak, A. S., Bluhm, H., Mysak, E. R., Smith, J. D., Kolb, C. E., and Worsnop, D. R.: Carbon oxidation state as
930 a metric for describing the chemistry of atmospheric organic aerosol., Nat. Chem., 3, 133–139, https://doi.org/10.1038/nchem.948, 2011.

La, Y. S., Camredon, M., Ziemann, P. J., Valorso, R., Matsunaga, A., Lannuque, V., Lee-Taylor, J., Hodzic, A., Madronich, S., and Aumont, B.: Impact of chamber wall loss of gaseous organic compounds on secondary organic aerosol formation: Explicit modeling of SOA formation from alkane and alkene oxidation, Atmos. Chem. Phys., 16, 1417–
935 1431, https://doi.org/10.5194/acp-16-1417-2016, 2016.

Lannuque, V., Camredon, M., Couvidat, F., Hodzic, A., Valorso, R., Madronich, S., Bessagnet, B., and Aumont, B.: Exploration of the influence of environmental conditions on secondary organic aerosol formation and organic species properties using explicit simulations: development of the VBS-GECKO parameterization, Atmos. Chem. Phys., 18, 13411–13428, https://doi.org/10.5194/acp-18-13411-2018, 2018.

940 Lannuque, V., D'Anna, B., Couvidat, F., Valorso, R., and Sartelet, K.: Improvement in modeling of oh and ho2 radical concentrations during toluene and xylene oxidation with racm2 using mcm/gecko-a, Atmosphere (Basel)., 12, 732, https://doi.org/10.3390/atmos12060732, 2021.

Lee, S. C., Chiu, M. Y., Ho, K. F., Zou, S. C., and Wang, X.: Volatile organic compounds (VOCs) in urban atmosphere of Hong Kong, Chemosphere, 48, 375–382, https://doi.org/10.1016/S0045-6535(02)00040-1, 2002.

945 Leglise, J., Müller, M., Piel, F., Otto, T., and Wisthaler, A.: Bulk Organic Aerosol Analysis by Proton-Transfer-Reaction Mass Spectrometry: An Improved Methodology for the Determination of Total Organic Mass, O:C and H:C Elemental Ratios, and the Average Molecular Formula, Anal. Chem., 91, 12619–12624, https://doi.org/10.1021/acs.analchem.9b02949, 2019.

Li, Y., Zhao, J., Wang, Y., Seinfeld, J. H., and Zhang, R.: Multigeneration Production of Secondary Organic Aerosol from
950 Toluene Photooxidation, Environ. Sci. Technol., 55, 8592–8603, https://doi.org/10.1021/acs.est.1c02026, 2021a.

Li, Y., Ji, Y., Zhao, J., Wang, Y., Shi, Q., Peng, J., Wang, Y., Wang, C., Zhang, F., Wang, Y., Seinfeld, J. H., and Zhang, R.: Unexpected Oligomerization of Small α-Dicarbonyls for Secondary Organic Aerosol and Brown Carbon Formation, Environ. Sci. Technol., 55, 4430–4439, https://doi.org/10.1021/acs.est.0c08066, 2021b.

Lim, C. C., Hayes, R. B., Ahn, J., Shao, Y., Silverman, D. T., Jones, R. R., Garcia, C., and Thurston, G. D.: Association
955 between long-term exposure to ambient air pollution and diabetes mortality in the US, Environ. Res., 165, 330–336,

https://doi.org/10.1016/J.ENVRES.2018.04.011, 2018.

Lim, S. S., Vos, T., Flaxman, A. D., Danaei, G., Shibuya, K., Adair-Rohani, H., AlMazroa, M. A., Amann, M., Anderson, H. R., Andrews, K. G., Aryee, M., Atkinson, C., Bacchus, L. J., Bahalim, A. N., Balakrishnan, K., Balmes, J., Barker-Collo, S., Baxter, A., Bell, M. L., Blore, J. D., Blyth, F., Bonner, C., Borges, G., Bourne, R., Boussinesq, M., Brauer, M., Brooks, P., Bruce, N. G., Brunekreef, B., Bryan-Hancock, C., Bucello, C., Buchbinder, R., Bull, F., Burnett, R. T., Byers, T. E., Calabria, B., Carapetis, J., Carnahan, E., Chafe, Z., Charlson, F., Chen, H., Chen, J. S., Cheng, A. T.-A., Child, J. C., Cohen, A., Colson, K. E., Cowie, B. C., Darby, S., Darling, S., Davis, A., Degenhardt, L., Dentener, F., Des Jarlais, D. C., Devries, K., Dherani, M., Ding, E. L., Dorsey, E. R., Driscoll, T., Edmond, K., Ali, S. E., Engell, R. E., Erwin, P. J., Fahimi, S., Falder, G., Farzadfar, F., Ferrari, A., Finucane, M. M., Flaxman, S., Fowkes, F. G. R., Freedman, G., Freeman, M. K., Gakidou, E., Ghosh, S., Giovannucci, E., Gmel, G., Graham, K., Grainger, R., Grant, B., Gunnell, D., Gutierrez, H. R., Hall, W., Hoek, H. W., Hogan, A., Hosgood, H. D., Hoy, D., Hu, H., Hubbell, B. J., Hutchings, S. J., Ibeanusi, S. E., Jacklyn, G. L., Jasrasaria, R., Jonas, J. B., Kan, H., Kanis, J. A., Kassebaum, N., Kawakami, N., Khang, Y.-H., Khatibzadeh, S., Khoo, J.-P., et al.: A comparative risk assessment of burden of disease and injury attributable to 67 risk factors and risk factor clusters in 21 regions, 1990–2010: a systematic analysis for the Global Burden of Disease Study 2010, Lancet, 380, 2224–2260, https://doi.org/10.1016/S0140-6736(12)61766-8, 2012.

Liu, X., Day, D. A., Krechmer, J. E., Brown, W., Peng, Z., Ziemann, P. J., and Jimenez, J. L.: Direct measurements of semi-volatile organic compound dynamics show near-unity mass accommodation coefficients for diverse aerosols, Commun. Chem. 2019 21, 2, 1–9, https://doi.org/10.1038/s42004-019-0200-x, 2019.

Malley, C. S., Kuylenstierna, J. C. I., Vallack, H. W., Henze, D. K., Blencowe, H., and Ashmore, M. R.: Preterm birth associated with maternal fine particulate matter exposure: A global, regional and national assessment, Environ. Int., 101, 173–182, https://doi.org/10.1016/j.envint.2017.01.023, 2017.

Mao, J., Ren, X., Brune, W. H., Olson, J. R., Crawford, J. H., Fried, A., Huey, L. G., Cohen, R. C., Heikes, B., Singh, H. B., Blake, D. R., Sachse, G. W., Diskin, G. S., Hall, S. R., and Shetter, R. E.: Airborne measurement of OH reactivity during INTEX-B, Atmos. Chem. Phys., 9, 163–173, https://doi.org/10.5194/acp-9-163-2009, 2009.

Marrero-Ortiz, W., Hu, M., Du, Z., Ji, Y., Wang, Y., Guo, S., Lin, Y., Gomez-Hermandez, M., Peng, J., Li, Y., Secrest, J., Zamora, M. L., Wang, Y., An, T., and Zhang, R.: Formation and Optical Properties of Brown Carbon from Small α-Dicarbonyls and Amines, Environ. Sci. Technol., 53, 117–126, https://doi.org/10.1021/acs.est.8b03995, 2019.

Molteni, U., Bianchi, F., Klein, F., El Haddad, I., Frege, C., Rossi, M. J., Dommen, J., and Baltensperger, U.: Formation of highly oxygenated organic molecules from aromatic compounds, Atmos. Chem. Phys., 18, 1909–1921, https://doi.org/10.5194/acp-18-1909-2018, 2018.

Müller, M., Graus, M., Wisthaler, A., Hansel, A., Metzger, A., Dommen, J., and Baltensperger, U.: Analysis of high mass resolution PTR-TOF mass spectra from 1,3,5-trimethylbenzene (TMB) environmental chamber experiments, Atmos. Chem. Phys., 12, 829–843, https://doi.org/10.5194/acp-12-829-2012, 2012.

Müller, M., Mikoviny, T., Jud, W., D'Anna, B., and Wisthaler, A.: A new software tool for the analysis of high resolution PTR-TOF mass spectra, Chemom. Intell. Lab. Syst., 127, 158–165, https://doi.org/10.1016/J.CHEMOLAB.2013.06.011, 2013.

Müller, M., Eichler, P., D'Anna, B., Tan, W., and Wisthaler, A.: Direct Sampling and Analysis of Atmospheric Particulate Organic Matter by Proton-Transfer-Reaction Mass Spectrometry, Anal. Chem., 89, 10889–10897, https://doi.org/10.1021/acs.analchem.7b02582, 2017.

Murphy, B. N., Donahue, N. M., Fountoukis, C., Dall'osto, M., O'dowd, C., Kiendler-Scharr, A., and Pandis, S. N.: Atmospheric Chemistry and Physics Functionalization and fragmentation during ambient organic aerosol aging: application of the 2-D volatility basis set to field studies, Atmos. Chem. Phys, 12, 10797–10816,

https://doi.org/10.5194/acp-12-10797-2012, 2012.

1000   Nannoolal, Y., Rarey, J., and Ramjugernath, D.: Estimation of pure component properties: Part 3. Estimation of the vapor pressure of non-electrolyte organic compounds via group contributions and group interactions, Fluid Phase Equilib., 269, 117–133, https://doi.org/10.1016/j.fluid.2008.04.020, 2008.

Ng, N. L., Chhabra, P. S., Chan, a. W. H., Surratt, J. D., Kroll, J. H., Kwan, a. J., McCabe, D. C., Wennberg, P. O., Sorooshian, A., Murphy, S. M., Dalleska, N. F., Flagan, R. C., and Seinfeld, J. H.: Effect of NOx level on secondary
1005   organic aerosol (SOA) formation from the photooxidation of terpenes, Atmos. Chem. Phys., 7, 5159–5174, https://doi.org/10.5194/acpd-7-10131-2007, 2007.

Nishino, N., Arey, J., and Atkinson, R.: Formation yields of glyoxal and methylglyoxal from the gas-phase OH radical-initiated reactions of toluene, xylenes, and trimethylbenzenes as a function of NO2 concentration, J. Phys. Chem. A, 114, 10140–10147, https://doi.org/10.1021/jp105112h, 2010.

1010   Piel, F., Müller, M., Winkler, K., Skytte Af Sätra, J., and Wisthaler, A.: Introducing the extended volatility range proton-transfer-reaction mass spectrometer (EVR PTR-MS), Atmos. Meas. Tech, 14, 1355–1363, https://doi.org/10.5194/amt-14-1355-2021, 2021.

Platz, J., Nielsen, O. J., Wallington, T. J., Ball, J. C., Hurley, M. D., Straccia, A. M., Schneider, W. F., and Sehested, J.: Atmospheric Chemistry of the Phenoxy Radical, C6H5O(•): UV Spectrum and Kinetics of Its Reaction with NO, NO2
1015   , and O2, J. Phys. Chem. A, 102, 7964–7974, https://doi.org/10.1021/jp982221l, 1998.

Raff, J. D. and Finlayson-Pitts, B. J.: Hydroxyl Radical Quantum Yields from Isopropyl Nitrite Photolysis in Air, Environ. Sci. Technol., 44, 8150–8155, https://doi.org/10.1021/es102218d, 2010.

Sartelet, K., Couvidat, F., Wang, Z., Flageul, C., and Kim, Y.: SSH-Aerosol v1.1: A Modular Box Model to Simulate the Evolution of Primary and Secondary Aerosols, Atmosphere (Basel)., 11, 525, https://doi.org/10.3390/atmos11050525,
1020   2020.

Sato, K., Hatakeyama, S., and Imamura, T.: Secondary Organic Aerosol Formation during the Photooxidation of Toluene: NO x Dependence of Chemical Composition, J. Phys. Chem. A, 111, 9796–9808, https://doi.org/10.1021/jp071419f, 2007.

Schwantes, R. H., Schilling, K. A., Mcvay, R. C., Lignell, H., Coggon, M. M., Zhang, X., Wennberg, P. O., and Seinfeld, J.
1025   H.: Formation of highly oxygenated low-volatility products from cresol oxidation, Atmos. Chem. Phys, 17, 3453–3474, https://doi.org/10.5194/acp-17-3453-2017, 2017.

Seigneur, C.: Air Pollution, Cambridge University Press, https://doi.org/10.1017/9781108674614, 2019.

Singh, H. B., Salas, L., Viezee, W., Sitton, B., and Ferek, R.: Measurement of volatile organic chemicals at selected sites in California, Atmos. Environ. Part A, Gen. Top., 26, 2929–2946, https://doi.org/10.1016/0960-1686(92)90285-S, 1992.

1030   Skorokhod, A. I., Berezina, E. V., Moiseenko, K. B., Elansky, N. F., and Belikov, I. B.: Benzene and toluene in the surface air of northern Eurasia from TROICA-12 campaign along the Trans-Siberian Railway, Atmos. Chem. Phys., 17, 5501–5514, https://doi.org/10.5194/ACP-17-5501-2017, 2017.

Suh, I., Zhang, D., Zhang, R., Molina, L. T., and Molina, M. J.: Theoretical study of OH addition reaction to toluene, Chem. Phys. Lett., 364, 454–462, https://doi.org/10.1016/S0009-2614(02)01364-7, 2002.

1035   Takekawa, H., Minoura, H., and Yamazaki, S.: Temperature dependence of secondary organic aerosol formation by photo-oxidation of hydrocarbons, Atmos. Environ., 37, 3413–3424, https://doi.org/10.1016/S1352-2310(03)00359-5, 2003.

Tao, Z. and Li, Z.: A kinetics study on reactions of C6H5O with C6H5O and O3 at 298 k, Int. J. Chem. Kinet., 31, 65–72, https://doi.org/10.1002/(SICI)1097-4601(1999)31:1<65::AID-KIN8>3.0.CO;2-J, 1999.

Tuazon, E. C., Atkinson, R., Leod, H. Mac, Biermann, H. W., Winer, A. M., Carter, W. P. L., and Pitts, J. N.: Yields of Glyoxal and Methylglyoxal from the NOx-Air Photooxidations of Toluene and m- and p-Xylene, Environ. Sci. Technol., 18, 981–984, https://doi.org/10.1021/es00130a017, 1984.

US Environmental Protection Agency: Health Effects Note-book for Hazardous Air Pollutants, https://www.epa.gov/sites/default/files/2016-09/documents/toluene.pdf, (last access: 13 March 2023), 2012.

Valorso, R., Aumont, B., Camredon, M., Raventos-Duran, T., Mouchel-Vallon, C., Ng, N. L., Seinfeld, J. H., Lee-Taylor, J., and Madronich, S.: Explicit modelling of SOA formation from α-pinene photooxidation: Sensitivity to vapour pressure estimation, Atmos. Chem. Phys., 11, 6895–6910, https://doi.org/10.5194/acp-11-6895-2011, 2011.

Vereecken, L. and Peeters, J.: Decomposition of substituted alkoxy radicals—part I: a generalized structure–activity relationship for reaction barrier heights, Phys. Chem. Chem. Phys., 11, 9062, https://doi.org/10.1039/b909712k, 2009.

Wagner, V., Jenkin, M. E., Saunders, S. M., Stanton, J., Wirtz, K., and Pilling, M. J.: Modelling of the photooxidation of toluene: Conceptual ideas for validating detailed mechanisms, Atmos. Chem. Phys., 3, 89–106, https://doi.org/10.5194/acp-3-89-2003, 2003.

Wang, M., Chen, D., Xiao, M., Ye, Q., Stolzenburg, D., Hofbauer, V., Ye, P., Vogel, A. L., Mauldin, R. L., Amorim, A., Baccarini, A., Baumgartner, B., Brilke, S., Dada, L., Dias, A., Duplissy, J., Finkenzeller, H., Garmash, O., He, X.-C., Hoyle, C. R., Kim, C., Kvashnin, A., Lehtipalo, K., Fischer, L., Molteni, U., Petäjä, T., Pospisilova, V., Quéléver, L. L. J., Rissanen, M., Simon, M., Tauber, C., Tomé, A., Wagner, A. C., Weitz, L., Volkamer, R., Winkler, P. M., Kirkby, J., Worsnop, D. R., Kulmala, M., Baltensperger, U., Dommen, J., El-Haddad, I., and Donahue, N. M.: Photo-oxidation of Aromatic Hydrocarbons Produces Low-Volatility Organic Compounds, Environ. Sci. Technol., 54, 7911–7921, https://doi.org/10.1021/acs.est.0c02100, 2020.

Wang, S., Wu, R., Berndt, T., Ehn, M., and Wang, L.: Formation of Highly Oxidized Radicals and Multifunctional Products from the Atmospheric Oxidation of Alkylbenzenes, Environ. Sci. Technol., 51, 8442–8449, https://doi.org/10.1021/acs.est.7b02374, 2017.

Wang, Z., Couvidat, F., and Sartelet, K.: GENerator of reduced Organic Aerosol mechanism (GENOA v1.0): an automatic generation tool of semi-explicit mechanisms, Geosci. Model Dev, 15, 8957–8982, https://doi.org/10.5194/gmd-15-8957-2022, 2022.

White, S. J., Jamie, I. M., and Angove, D. E.: Chemical characterisation of semi-volatile and aerosol compounds from the photooxidation of toluene and NOx, Atmos. Environ., 83, 237–244, https://doi.org/10.1016/J.ATMOSENV.2013.11.023, 2014.

Wu, R., Pan, S., Li, Y., and Wang, L.: Atmospheric Oxidation Mechanism of Toluene, J. Phys. Chem. A, 118, 4533–4547, https://doi.org/10.1021/JP500077F, 2014.

Xu, J., Griffin, R. J., Liu, Y., Nakao, S., and Cocker, D. R.: Simulated impact of NOx on SOA formation from oxidation of toluene and m-xylene, Atmos. Environ., 101, 217–225, https://doi.org/10.1016/J.ATMOSENV.2014.11.008, 2015.

Yamasaki, H., Kuwata, K., and Miyamoto, H.: Effects of ambient temperature on aspects of airborne polycyclic aromatic hydrocarbons, Environ. Sci. Technol., 16, 189–194, https://doi.org/10.1021/es00098a003, 1982.

Yan, Y., Cabrera-Perez, D., Lin, J., Pozzer, A., Hu, L., Millet, D. B., Porter, W. C., and Lelieveld, J.: Global tropospheric effects of aromatic chemistry with the SAPRC-11 mechanism implemented in GEOS-Chem version 9-02, Geosci. Model Dev., 12, 111–130, https://doi.org/10.5194/GMD-12-111-2019, 2019.

Zaytsev, A., Koss, A. R., Breitenlechner, M., Krechmer, J. E., Nihill, K. J., Lim, C. Y., Rowe, J. C., Cox, J. L., Moss, J., Roscioli, J. R., Canagaratna, M. R., Worsnop, D. R., Kroll, J. H., Keutsch, F. N., and Paulson, J. A.: Mechanistic study of the formation of ring-retaining and ring-opening products from the oxidation of aromatic compounds under urban

1080   atmospheric conditions, Atmos. Chem. Phys, 19, 15117–15129, https://doi.org/10.5194/acp-19-15117-2019, 2019.

Zhang, R., Wang, G., Guo, S., Zamora, M. L., Ying, Q., Lin, Y., Wang, W., Hu, M., and Wang, Y.: Formation of Urban Fine Particulate Matter, Chem. Rev., 115, 3803–3855, https://doi.org/10.1021/acs.chemrev.5b00067, 2015a.

Zhang, X., Schwantes, R. H., McVay, R. C., Lignell, H., Coggon, M. M., Flagan, R. C., and Seinfeld, J. H.: Vapor wall deposition in Teflon chambers, Atmos. Chem. Phys., 15, 4197–4214, https://doi.org/10.5194/ACP-15-4197-2015, 1085   2015b.

Zhu, S., Sartelet, K. N., and Seigneur, C.: A size-composition resolved aerosol model for simulating the dynamics of externally mixed particles: SCRAM (v 1.0), Geosci. Model Dev., 8, 1595–1612, https://doi.org/10.5194/GMD-8-1595-2015, 2015.

Zuend, A., Marcolli, C., Luo, B. P., and Peter, T.: A thermodynamic model of mixed organic-inorganic aerosols to predict 1090   activity coefficients, Atmos. Chem. Phys., 8, 4559–4593, https://doi.org/10.5194/acp-8-4559-2008, 2008.