

A cloud-by-cloud approach for studying aerosol-cloud interaction in satellite observations

Fani Alexandri¹, Felix Müller¹, Goutam Choudhury², Peggy Achtert^{1,3}, Torsten Seelig¹, and Matthias Tesche¹

¹Leipzig Institute for Meteorology, Leipzig University, Stephanstraße 3, 04103 Leipzig, Germany

²now at Department of Geography and the Environment, Bar-Ilan University, Tel Aviv, Israel

³Meteorological Observatory Hohenpeißenberg, German Weather Service, Hohenpeißenberg, Germany

Correspondence: Matthias Tesche (matthias.tesche@uni-leipzig.de)

Abstract. The effective radiative forcing (ERF) due to aerosol-cloud interactions (ACI) and rapid adjustments (ERFaci) still causes the largest uncertainty in the assessment of climate change. It is understood only with medium confidence and studied primarily for warm clouds. Here, we present a novel cloud-by-cloud (C×C) approach for studying ACI in satellite observations that combines the concentration of cloud condensation nuclei (n_{CCN}) and ice nucleating particles (n_{INP}) from polar-orbiting
5 lidar measurements with the development of the properties of individual clouds from tracking them in geostationary observations. We present a step-by-step description for obtaining matched aerosol-cloud cases. The application to satellite observations over Central Europe and Northern Africa during 2014 together with rigorous quality assurance leads to 399 liquid-only clouds and 95 ice-containing clouds that can be matched to surrounding n_{CCN} and n_{INP} , respectively, at cloud level. We use this initial data set for assessing the impact of changes in cloud-relevant aerosol concentrations on the cloud droplet number concentration
10 (N_d) and effective radius (r_{eff}) of liquid clouds and the phase of clouds in the regime of heterogeneous ice formation. We find a $\Delta \ln N_d / \Delta \ln n_{CCN}$ of 0.13 to 0.30 which is at the lower end of commonly inferred values of 0.3 to 0.8. The $\Delta \ln r_{eff} / \Delta \ln n_{CCN}$ between -0.09 and -0.21 suggests that r_{eff} decreases by -0.81 to -3.78 nm per increase in n_{CCN} of 1 cm^{-3} . We also find a tendency towards more cloud ice and more fully glaciated clouds with increasing n_{INP} that cannot be explained by the increasingly lower cloud-top temperature of super-cooled liquid, mixed-phase, and fully glaciated clouds alone. Applied to a larger amount
15 of observations, the C×C approach has the potential to enable the systematic investigation of warm and cold clouds. This marks a step change in the quantification of ERFaci from space.

1 Introduction

The optical and microphysical properties of clouds depend on the presence of atmospheric aerosol particles. Aerosols facilitate the formation of cloud droplets by acting as cloud condensation nuclei (CCN, Quinn et al. 2008). They also affect supercooled
20 liquid and ice-containing clouds by acting as ice nucleating particles (INP, Kanji et al. 2017). Changes in the amount of aerosols that can act as CCN and INP through natural and anthropogenic emissions therefore influence the properties and the life cycle of clouds through aerosol-cloud interactions (ACI) and the accompanying rapid adjustments. The resulting effective radiative

forcing (ERF, Boucher et al. 2013) due to ACI (ERFaci) of $-1.0 \pm 0.7 \text{ W m}^{-2}$ is still assessed with only medium confidence and marks the largest uncertainty in our understanding of man-made changes to the Earth's energy budget (Forster et al., 2021).

25 ACI can be distinguished for warm (liquid-water) and cold (mixed-phase and ice) clouds. The ERFaci in warm clouds is defined as the disturbance in short- and long-wave radiation due to a change in cloud droplet number concentration (N_d) triggered by a change in aerosol concentration (Bellouin et al., 2020; Quaas et al., 2020). ERFaci consists of (i) the instantaneous radiative forcing (IRFaci) related to brightening of clouds in polluted environment (cloud albedo or Twomey effect, Twomey 1974) and (ii) the rapid adjustments of cloud fraction f , liquid water path L , and cloud top temperature T_{top} (Albrecht, 1989; 30 Ackerman et al., 2004) in prompt reaction to the perturbation of the Twomey effect. The challenge lies in quantifying (i) the sign of the combined adjustments (Mülmenstädt and Feingold, 2018; Gryspeerdt et al., 2019) and (ii) the anthropogenic contribution to the disturbance in aerosol concentration.

So far, the Twomey effect has been studied most extensively. Other proposed ACI mechanisms suggest that smaller droplets in non-precipitating clouds can be transported to larger heights where they release latent heat for a stronger development of 35 convective clouds (cloud invigoration effect, Rosenfeld et al. 2008) or delay cloud glaciation (thermodynamic effect, Lohmann and Feichter 2005). At the same time, increased amounts of aerosols that can act as INP might lead to an earlier onset of cloud glaciation which increases the precipitation efficiency of the clouds (glaciation effect, Lohmann 2002). Depending on the type of aerosols and clouds, their interaction might either de- or increase the susceptibility for clouds to form rain (Rosenfeld et al., 2008). While observational evidence of the invigoration effect is still ambiguous (Fan et al., 2018; Douglas and L'Ecuyer, 40 2021; Igel and van den Heever, 2021; Romps et al., 2023), effects of aerosols on cloud glaciation have barely been studied on a global scale due to a lack of both suitable INP proxies (Villanueva et al., 2020) and reliable long-term observations of ice-containing clouds (Villanueva et al., 2021).

It is not only because of the conflictive impact of different adjustments that observation-based ACI studies are notoriously complicated. They require (i) separating between meteorological and aerosol effects on the observed clouds and (ii) establishing 45 causality of the identified processes (Koren et al., 2010). Different ACI mechanisms rarely occur in their pure form but rather act within a buffered system (Stevens and Feingold, 2009) which means that overlapping feedbacks might compensate or strengthen the overall effect. In addition, ACI effects are regime dependent (Stevens and Feingold, 2009), implying the need for a separated investigation of different cloud types and regimes.

There is a wealth of studies regarding the impact and relevance of different aerosol effects on clouds based on spaceborne 50 observations (Bellouin et al., 2020) with known challenges and clear visions for ways forward (Quaas et al., 2020; Rosenfeld et al., 2023). Spaceborne remote sensing is the only observational technique for gaining a global picture of ERFaci and provides the best available benchmark for evaluating the performance of global climate models (Quaas et al., 2009). The instruments in the polar-orbiting A-Train constellation of satellites form the work horses for most ACI studies (Rosenfeld et al., 2014, 2023; Bellouin et al., 2020; Quaas et al., 2020). These instruments provide observations of column-integrated parameters like aerosol 55 optical thickness (AOT), aerosol index (AI), cloud optical thickness (COT), cloud droplet number concentration N_d , cloud droplet effective radius r_{eff} , L , as well as insights into the vertical distribution of aerosol and cloud layers.

Spaceborne ERFaci studies employ sophisticated data processing to extract aerosol effects on clouds from noisy data and to establish causality of the identified processes (Quaas et al., 2020). In most cases, they investigate statistical relationships between cloud properties (i.e. albedo, COT, N_d , r_{eff} , and L) and aerosol parameters (AOT or AI) to resolve the underlying mechanisms (Rosenfeld et al., 2014, 2023) – carefully accounting for effects of meteorological parameters (e.g., Koren et al. 2010; Yuan et al. 2011; Chen et al. 2014; McCoy et al. 2017).

We are far from reaching consensus in ERFaci even for warm clouds (Bellouin et al., 2020). As a result of the imperfect data from satellite observations (Quaas et al., 2020; Jia et al., 2021, 2022), there are major challenges that hamper progress in the satellite-based quantification of ERFaci.

First, there is a lack of properly quantifying those aerosols that interact with liquid clouds. Most studies of the Twomey effect rely on AOT or AI from passive remote sensing. However, these column-integrated parameters are unlikely to provide the CCN information needed for studying ACI (Shinozuka et al., 2015; Stier, 2016). Hence, height-resolved information on CCN concentrations is needed for further progress in understanding the effect of aerosols on warm clouds (Quaas et al., 2020). Such methodologies have been developed based on ground-based (Mamouri and Ansmann, 2016) and spaceborne lidar measurements (Choudhury and Tesche, 2022a, b, 2023; Choudhury et al., 2022).

Second, ERFaci assessments generally exclude the effect of aerosols on cold clouds (Bellouin et al., 2020) due to a lack of reliable proxies for INP concentrations (Murray et al., 2021). However, a clear dependence of the fraction of glaciated clouds on the concentration of aerosols known to be efficient INP, such as mineral dust, is found from both ground-based (Kanitz et al., 2011) and spaceborne remote-sensing observations (Villanueva et al., 2020, 2021). This calls for a systematic investigation of clouds in different regimes by using realistic metrics for the acting aerosols, i.e. INP concentrations instead of proxies. Such information can also be provided by lidar measurements (Mamouri and Ansmann, 2016; Marinou et al., 2019; Choudhury et al., 2022).

Third, observations of polar-orbiting instruments only provide snapshots and are incapable of resolving the temporal development of a cloud that is affected by a perturbation of the aerosol field. As a consequence, satellite-based studies of the cloud-lifetime effect resort to the concept of precipitation susceptibility (L'Ecuyer et al., 2009) rather than the actual age of the cloud at the time of observation. The recent introduction of Lagrangian studies in which backward trajectories are used to account for the origin of observed cloud fields further highlights the need to consider temporal development for quantifying aerosol-cloud interactions (Christensen et al., 2020; Goren et al., 2019; Gryspeerdt et al., 2021, 2022). The tracking of clouds in geostationary satellite observations (Seelig et al., 2021, 2023) marks a way forward in more realistically considering cloud development and lifetime in ACI studies.

The combination of polar-orbiting and geostationary observations resolves processes impossible to deduce solely from snapshots. It has been shown that aerosols from ship tracks and continental outflow cause polluted marine stratocumulus to form longer-lasting closed cells (Goren and Rosenfeld, 2012, 2015) and that the history of both the observed clouds and the air masses they are embedded in is vital for untangling ACI effects (Christensen et al., 2020). Observations with the Spinning Enhanced Visible and InfraRed Imager (SEVIRI, Derrien and Gléau 2005) on Europe's geostationary Meteosat Second Generation (MSG) satellite have been employed to identify phase transitions in individually tracked convective clouds

(Coopman et al., 2019) and to identify at which T_{top} glaciation is initiated (Coopman et al., 2020). Nevertheless, the potential of the time-resolved cloud observations with geostationary sensors has not yet been exploited sufficiently for studying ERFaci.

In general, three approaches are used for studying ACI from space. In the first one, spatially aggregated information on aerosols and clouds – often for specific regions or cloud regimes – is correlated to identify relationships between the selected parameters (e.g., Quaas et al. 2004; Yuan et al. 2008; Costantino and Bréon 2010; Chen et al. 2014; Gryspeerdt et al. 2017) which are likely intrinsically biased (Jia et al., 2021; Goren et al., 2023; Gryspeerdt et al., 2023). The second one makes use of specific aerosol sources such as ships, industrial centres, or volcanoes during natural experiments (Christensen et al., 2022) but faces the challenge of how to expand the findings to the global scale. The third is focused on resolving hemispheric differences under the premise that anthropogenic effects will only occur in the northern hemisphere (McCoy et al., 2020). Here, we are proposing a fourth approach – referred to as cloud-by-cloud (C×C) approach – in which data of (i) individually tracked clouds from geostationary satellite observations are matched with (ii) height-resolved and aerosol-type specific information on the concentration of CCN and INP around those clouds from polar-orbiting satellite observations (and (iii) fields from meteorological and aerosol reanalysis) to form a bottom-up data set of warm and cold clouds that can be stratified according to different aerosol and cloud properties or meteorological parameters to investigate the Twomey effect, rapid adjustments, and aerosol effects on ice-containing clouds.

This paper starts with a description of the used data and methodologies as well as the general concept of employing the combination of geostationary and polar-orbiting satellite observations for ACI studies in Section 2. First results that demonstrate the new approach are presented in Section 3. The work finishes with a summary and an outlook in Section 4.

110 2 Data and methodology

ACI studies based on spaceborne observations conventionally aggregate temporally averaged (at least daily values) aerosol and cloud parameters (often from different sensors) within a coarse grid box (generally $1^\circ \times 1^\circ$) with meteorological parameters from reanalysis fields (Quaas et al., 2004, 2009; Koren et al., 2010; Rosenfeld et al., 2014, 2023; Bellouin et al., 2020) and investigate the change in cloud properties (N_d , L , f) with increasing aerosol concentration for situations with constrained meteorological conditions (Gryspeerdt et al., 2016, 2017, 2019, 2021). In contrast, our C×C approach matches individual clouds (from geostationary observations) with their surrounding aerosol fields (from polar-orbiting observations) to form a bottom-up data set that allows for stratifying the data according to the parameters of interest for subsequent ACI studies.

Figure 1 gives an overview of the steps of our approach, provides essential references, and links towards to corresponding sections in the paper.

120 2.1 Cloud-tracking in geostationary satellite observations

The cloud-tracking toolbox of Seelig et al. (2021, 2023) is used to track individual clouds in time-resolved observations with geostationary sensors. The algorithm identifies objects in two consecutive time steps and uses Particle Image Velocimetry (Adrian and Westerweel, 2010) to create a velocity field between them in multiple overlapping windows of different sizes.

This process determines the displacement that best matches objects in a pair of consecutive binary 2d images by means of cross-correlation. Matches between the objects from one time step to the next are created by considering the distance of the centroids of the identified objects as well as their overlapping area. The best match within set thresholds is kept if the difference in area does not exceed a factor of four. This areal threshold ensures realistic growth (decay) rates for non-merging (non-splitting) clouds and is based on our observations of small clouds – particularly the growth of one-pixel and two-pixel clouds. In case of a splitting event (one object is matched to multiple objects), one match is chosen arbitrarily. In case of a merging event (multiple objects are matched to one object), the best match is kept. In case of a tie, again one is chosen arbitrarily. This process is repeated for all consecutive time steps to form a trajectory of a tracked object.

The method has so far been applied to the binary cloud mask inferred from observations of MSG-SEVIRI (Seelig et al., 2021) and the Advanced Baseline Imager (ABI, Schmit et al. 2017) aboard NASA’s Geostationary Operational Environmental Satellites – R Series (GOES-R-ABI) (Seelig et al., 2023). Cloud physical properties (CPP) can be derived from those observations only during daytime, as visible reflectances are needed for the retrieval. The CPP generally include T_{top} , cloud top height (h_{top}), cloud top pressure (p_{top}), COT, r_{eff} , and L . N_d is derived using COT and r_{eff} (Grosvenor et al., 2018; Quaas et al., 2020). This work uses CPP derived from MSG-SEVIRI observations and provided in the CLAAS-2 (Benas et al., 2017) data set with a temporal resolution of 15 minutes. These CPP are matched to the trajectories of tracked clouds to obtain mean and median values per time step as well as for the lifetime of individual clouds.

For a first application of the $C \times C$ approach, we want to focus on low-level liquid clouds and mid-level mixed-phase clouds as observed by MSG-SEVIRI over Europe, the Mediterranean, and Northern Africa. As outlined in Seelig et al. (2021, 2023), the data set of all tracked clouds is filtered to obtain sub-samples that correspond to the targeted cloud types. First, a cloud has to show a cloud top height that relates to the targeted cloud type. Second, a cloud has to form and dissolve in clear air to assure that well-defined development can be observed. Finally, a cloud has to occur entirely during daytime so that CPP data are available throughout its lifetime.

2.2 Cloud-relevant aerosol concentrations from spaceborne lidar observations

Ground-based lidar measurements provide great potential for inferring height-resolved CCN and INP concentrations (Mamouri and Ansmann, 2016; Marinou et al., 2019). However, adaptation of the ground-based approach to spaceborne lidar observations is not straightforward as the required extinction-to-number-concentration conversion factors show strong regional variation (Ansmann et al., 2019). The Optical Modelling of CALIPSO Microphysics (OMCAM, Choudhury and Tesche 2022a) algorithm provides an alternative approach for inferring CCN concentrations from spaceborne Cloud-Aerosol Lidar and Infrared Pathfinder Satellite Observations (CALIPSO, Winker et al. 2009) lidar observations that is consistent within the wider CALIPSO retrieval. Figure 2 presents a flow chart of the OMCAM algorithm. In short, quality-assured CALIPSO level 2 aerosol profiles are used to obtain aerosol-type specific extinction coefficients (upper panel in Figure 2) that constrain light-scattering calculations (Gasteiger and Wiegner, 2018) based on the normalized size distribution and complex refractive indices (middle panel in Figure 2) for different aerosol types in the CALIPSO aerosol model (Omar et al., 2009). The scaled size distribution relating to the modelled extinction coefficient that best reproduced the measurement is then integrated from a lower

size limit at which the different aerosol types are likely to be relevant for cloud properties to obtain the number concentration of reservoir particles ([lower panels in Figure 2](#)). The latter are then used as input to commonly used parametrizations (DeMott et al., 2010, 2015; Steinke et al., 2015; Ullrich et al., 2017) to infer CCN and INP number concentrations n_{CCN} and n_{INP} , respectively. For more details on the OMCAM retrieval and its uncertainties, readers are referred to Choudhury and Tesche (2022a).

Thorough validation of OMCAM-derived n_{CCN} generally finds values that are within a factor of 1.5 to 2.0 of independent airborne and ground-based in-situ observations (Aravindhavel et al., 2023; Choudhury et al., 2022; Choudhury and Tesche, 2022b), which is far less than their natural variability. OMCAM-derived data have been used to compile a global height-resolved n_{CCN} climatology from 15 years of CALIPSO observations (Choudhury and Tesche, 2023) that can be used complementary to model-derived n_{CCN} (Block et al., 2023) as a benchmark for cloud-resolved climate modelling.

For this work, OMCAM was expanded ~~to give analogous to Mamouri and Ansmann (2016) and Marinou et al. (2019) to estimate the concentration of INP reservoir particles and to subsequently use them in which are subsequently used as input to~~ INP parametrizations to obtain n_{INP} ~~analogous to Mamouri and Ansmann (2016) and Marinou et al. (2019) (see (lower right panel in Figure 2). This capability allows for extending the scope of the C×C approach towards studying aerosol effects on ice-containing clouds.~~ In contrast to n_{CCN} , independent in-situ measurements of n_{INP} are sparse. This is why the validation of OMCAM-derived values is still a matter of ongoing research. Nevertheless, initial findings [based on comparison to airborne in-situ measurements](#) indicate that CALIPSO-derived n_{INP} have a quality comparable to those inferred from ground-based lidar measurements (Marinou et al., 2019; Choudhury et al., 2022).

2.3 Matching cloud trajectories with aerosol observations

The intercept points between individual cloud trajectories and the CALIPSO ground track are obtained with the TrackMatcher tool (Bräuer and Tesche 2022, <https://github.com/LIM-AeroCloud/TrackMatcher.jl.git>). The purpose of TrackMatcher is the identification of intercept points between two lines on a latitude-longitude grid and the collocation of the respective data fields along those tracks. [In the context of the C×C approach, this enables to match cloud properties along a cloud trajectory from geostationary satellite observations \(Section 2.1\) to the surrounding cloud-relevant aerosol concentrations from polar-orbiting lidar observations \(Section 2.2\).](#) The algorithm allows for finding intersections in any pair of tracks that provide information on time (t), latitude (φ), longitude (λ), and height (h). The main steps of the algorithm are to (i) load track data related to two platforms, (ii) interpolate the individual tracks using a piecewise cubic Hermite interpolating polynomial, (iii) find intersections by minimising the norm between the different track point coordinate pairs, and (iv) extracting auxiliary information at or around the intercept point as set by the operator. [For applying the C×C approach, the auxiliary formation extracted from the CALIPSO level 2 aerosol profile product consists of height profiles of the OMCAM input parameters, i.e., backscatter and extinction coefficients, particle linear depolarization ratio, vertical feature mask, and cloud-aerosol-discrimination \(CAD\) score.](#) In addition, the accepted time difference between the two tracks can be chosen to best suit the application. In this study, we didn't limit the time difference for finding matches between a cloud track and the CALIPSO satellite but most cases fell

within a range between 0 and ± 90 minutes. [This time difference is well below the time scale for which major changes in an aerosol field could be expected \(Anderson et al., 2003; Kovacs, 2006\).](#)

195 An example for matching a cloud trajectory with a CALIPSO measurement is presented in Figure 3. CALIPSO level 2 data are available in 5-km intervals along the ground track while the example trajectory consists of four time steps. When a match is made, CALIPSO profiles are filtered for quality-assured data at the height levels of the paired cloud [following the criteria summarized in Table 1 of Tackett et al. \(2018\)](#). Aerosol data might be absent or dismissed in case of low aerosol load (low signal-to-noise ratio), retrievals with low confidence score, or cloud presence. In Figure 3, the cloud changes from purely liquid (time steps 1 and 2), over mixed-phase (time step 3), to purely ice (time step 4). Aerosol information is available in the vicinity of the matching point and can be used to infer mean CCN or INP concentrations surrounding the tracked cloud.
200 Further details on this procedure are provided below.

2.4 Quality-assured development of matched clouds

Our cloud tracking (Section 2.1) is generally performed on a binary cloud mask in which pixels are differentiated as either cloud or cloud-free. In passive observations, cloudy pixels are not unambiguously referring to a specific cloud type (Rossow and Schiffer, 1999). Instead, the column information observed at the top of the atmosphere might actually be the product of
205 contributions of very different clouds, such as low-level water clouds and high-level ice clouds. While these contributions will not be discernible in a cloud mask, they will propagate into the inferred cloud physical properties. Clouds that are found to intercept a CALIPSO overpass (Section 2.3) therefore have to undergo quality assurance before they can be considered for further analysis.

This quality-screening is performed in two steps. Clouds are initially sorted according to their phase and subsequently
210 investigated for realistic development of their physical properties. The *phase categorization* sorts clouds as:

1. **liquid-water** if (i) the phase of all pixels is liquid or (ii) the median cloud top temperature is warmer than -5°C
2. **mixed-phase** if there are both liquid and ice pixels in the temperature range from -5°C to -38°C
3. **ice (heterogeneously frozen)** if there are only ice pixels in the temperature range from -5°C to -38°C
4. **ice (homogeneously frozen)** if the median cloud top temperature of all pixels is lower than -38°C

215 The objective of our $C \times C$ approach is to investigate liquid-water clouds for their response to changes in CCN concentrations and mixed-phase and heterogeneously frozen ice clouds for their response to changes on INP concentrations. To obtain meaningful results, however, we need to exclude those clouds that appear to evolve non-physically, i.e. that show a large variation in their properties from time step to time step or throughout their lifetime. We have therefore identified four objective criteria for assessing *realistic cloud development* based on cloud-top temperature, area, and phase. A cloud is flagged, if it shows

- 220
1. **unrealistic development of T_{top} from start to end**: the norm of the difference between median T_{top} at cloud beginning and end exceeds 30 K

2. **unrealistic development of T_{top} between time steps:** the norm of the change in median T_{top} from time step to time step exceeds 15 K
- 225 3. **unrealistic spread of T_{top} within individual time steps:** the spread in T_{top} (maximum T_{top} - minimum T_{top} per time step) exceeds 35 K for more than 50% of all time steps
4. **unrealistic development of cloud size:** the change in cloud size from time step to time step for clouds that consist of more than four pixels exceeds 100%, i.e. cloud size should neither double nor half

These criteria apply to the entire trajectory. A cloud is kept for by-eye inspection if one of criteria 1 to 4 is met. It is dismissed (considered as unrealistic), if ~~more than one of the criteria is~~ multiple criteria are met. The latter also applies if criterion 2 or 230 4 are met multiple times. While this rigorous screening of tracked clouds implies a high level of data reduction, it ensures that only cases in which the observations show a cloud that develops in a physically meaningful way along its trajectory, i.e., that are not affected by any of the limitations of passive remote sensing, will be considered in the subsequent investigation of aerosol-cloud interactions. In other words, we can only obtain robust findings from the bottom-up data base if the highest level of scrutiny is applied in the identification trustworthy aerosol-cloud cases.

235 Figure 4 presents the development of two tracked clouds to illustrate the quality-assurance methodology. The example cloud on 14 August 2014 shows a development that we consider as realistic. The cloud was tracked from its formation at 1315 UTC until it dissolved at 1645 UTC. Median, minimum, and maximum T_{top} all vary within a reasonable range throughout all 15-min time steps. The cloud is partly or fully glaciated at temperatures where this is not unlikely. The change in cloud size is indicative of plausible growth and decay rather than merging and splitting. Overall, this case represents a heterogeneously frozen ice cloud 240 that can be used in studies of the effect of surrounding INP concentrations on cloud properties and development. In contrast, the example cloud on 24 March 2014 raises some of the flags listed above. Over the length of its existence from 0845 UTC to 1130 UTC, median T_{top} shows multiple time-step-by-time-step changes of more than 15 K (criterion 3). This indicates the coinciding presence of low and high clouds within the cloud area or even on pixel basis and would already lead us to dismiss that cloud as unrealistic. The spread in T_{top} per time step exceeds 35 K for 10 out of 12 time steps (criterion 4) provides another 245 indicator that clouds at different height levels are contributing to the column signal detected in the passive observation. Finally, the areal growth from time step 2 to time step 3 exceeds a doubling (criterion 2) and the norm of the difference in T_{top} at the first and last time steps is very close to 30 K (criterion 1).

The consideration for realistic cloud development puts another constraint on the selection of cases that can actually be used in the formation of our bottom-up data base. Overall, the initial matching of trajectories to CALIPSO overpasses, followed 250 by the demand for valid aerosol observations at cloud level, and the subsequent requirement for realistic cloud development reduce the data base from an order of a million tracked clouds to an order of a few hundred cases for consideration in our $C \times C$ approach. We have opted for the exceptionally high level of scrutiny despite the resulting poor data yield to assure that findings that are later inferred from the bottom-up data base are physically meaningful. In future, the length of the available time series of around 15 years, the possibility to extend the CCN and INP retrievals to newer spaceborne lidar missions, the option for

255 expanding the study area, and application to further geostationary sensors provide ample opportunity for extending the number of cases without compromising their quality.

2.5 Study region

For testing the new C×C approach, we have selected a region that covers Europe and northern Africa. Figure 5 shows that our study region extends from the Atlantic coast to eastern Ukraine and from southern Sweden to the southern tip of Tunisia and 260 the Sinai peninsula. All four cloud categories listed in Section 2.4 are found in the study region. In addition, the region covers the pathways of mineral dust transport to Europe. This is of particular interest to our work as mineral dust particles are very efficient INP and most likely to cause detectable changes in cloud phase.

2.6 Deriving matched aerosol and cloud parameters

The data obtained from matching the information related to tracked cloud properties and cloud-relevant aerosol properties 265 are presented based on the case study of 18 March 2014 shown in Figure 6. A liquid-water cloud could be tracked for four time steps between 1100 and 1145 UTC. Its first time step shows a median T_{top} of about 14 °C which corresponds to a h_{top} of about 500 m. The median r_{eff} for this initial time step is 12.5 μm . Over the next three time steps, T_{top} decreases to 2 °C as h_{top} increases to 2.2 km. At the same time, r_{eff} decreases slightly to 12 μm . Throughout its lifetime, the cloud consisted of 18 pixels of which none revealed the presence of ice. The CALIPSO overpass matched with this trajectory occurred at 1137 UTC 270 between the third and fourth time step of cloud lifetime. Around the overpass, CALIOP measurements reveal the presence of aerosols and clouds with upper-level clouds attenuating the lidar signal before it can reach the surface (Figure 6b). The OMCAM retrieval gives an estimated n_{CCN} of around 2000 cm^{-3} between the surface and 2.5 km height – well within the height range of the observed cloud.

Pixel-wise cloud properties are matched to the aerosol field within an along-track distance of 13 5-km CALIPSO intervals 275 and 5 60-m height bins around the pixel's h_{top} . Valid data in CCN concentration within such a box is averaged to obtain a median n_{CCN} that can be related to the cloud properties. In the example in Figure 6, 14 cloud pixels show values of h_{top} that allow for assigning a median n_{CCN} to their cloud properties while 4 pixels revealed values of h_{top} that fell within a height range for which no CCN information could be retrieved. Consequently, the case of 18 March 2014 contributes 14 pairs of matched aerosol-cloud information to the statistical analysis presented below.

280 To summarize, the C×C approach allows for decomposing clouds at three stages:

1. the **pixel stage** considers individual cloud pixels and the 13-profiles-by-5-height-bins CALIPSO aerosol around the pixel's h_{top} . This is referred to as pixel-wise information in this paper.
2. the **time-step stage** considers cloud and aerosol mean and median values for individual time steps of a considered cloud. This information is not used in this paper.
- 285 3. the **trajectory stage** considers cloud and aerosol mean and median values for the entirety of a cloud trajectory, i.e., all time steps. This is referred to as whole-trajectory information in this paper.

3 Results

3.1 General overview

For a first application of the C×C approach, we want to focus on (i) liquid clouds which have been extensively studied with other methods and (ii) ice-containing clouds for which our new approach will enable assessing the impact of INP concentrations on cloud-phase and development. The tracking of clouds in CLAAS-2 data (Section 2.1) within the region of interest (Figure 5) for 2014 gives a total of 8,924,639 trajectories of clouds with well-defined start and end, i.e. forming and dissolving in clear air. The matching procedure outlined in Sections 2.3 implies rigorous screening of that data set to trajectories that coincide with a CALIPSO observation during both day and night. This constraint reduces the amount of data to 4393 tracked and matched clouds that could potentially be used for further investigation. Out of those, 964 daytime trajectories of liquid clouds are found to be vertically co-located with CCN layers (Section 2.2). Further quality-assurance regarding realistic cloud development (Section 2.4) finally gives 399 trajectories for further analysis. In the case of ice-containing clouds, 844 daytime trajectories could be matched to vertically co-located INP layers of which 95 clouds remained after quality assurance (Section 2.4). Following the phase categorisation in Section 2.4, the ice-containing clouds can be further separated into 42 clouds that are homogeneously frozen, 8 clouds that are heterogeneously frozen, and 45 mixed-phase clouds. The data set of liquid clouds also contains 37 trajectories of supercooled clouds for which neither the median T_{top} per time step exceeds 0°C nor cloud ice is detected. These supercooled liquid clouds provide a reference in studying the impact of n_{INP} on the ice-containing clouds.

Figure 5 gives an overview of the cloud trajectories that could be matched to aerosol information from CALIPSO measurements over Europe and north Africa for the year 2014. We will start with a description of the matched data sets before presenting first results of applying the C×C approach for studying liquid-water and ice-containing clouds.

3.2 The matched aerosol-cloud data sets

The data set of matched cases for the year 2014 within the study region in Figure 5 consists of 399 trajectories of liquid clouds and 95 trajectories of ice-containing clouds. Both cloud types are rather small and short-lived. They span lifetimes from 3 to 47 (3 to 20 steps for ice-containing clouds) time steps of 15 min with a median of 4 time steps. The histogram of trajectory length in Figure 7 shows that the majority of clouds exists for less than 2 h. The size of the liquid clouds per time step ranges from 1 to 341 pixels with a median of 5 pixels (not shown). Clouds consisting of 10 pixels or less make up 70% of the data set. The ice-containing clouds considered here are smaller than the liquid clouds with sizes ranging from 1 to 53 pixels, a median of 4 pixels, and 90% of clouds consisting of 15 pixels or less (not shown).

Figure 8 gives an overview of the distribution of h_{top} and T_{top} of the liquid and ice-containing clouds that could be matched with information of the surrounding aerosol field. Most of liquid clouds persist below 1.0 km. The median h_{top} is 0.6 km while the occurrence of few pixels with large h_{top} increases the mean to 0.9 ± 1.1 km. The majority of cloud pixels (95%) show positive values of T_{top} with a mean of $21.0 \pm 12.4^{\circ}\text{C}$ and a median of 20.9°C . These comparably high temperatures are related to the fact that a large number of tracked clouds is located over northern Africa (see Figure 5). Cloud pixels with negative

320 T_{top} in the liquid data set refer to super-cooled clouds which can be used as reference in the investigation of the effect of
 n_{INP} on ice-containing clouds. When data are aggregated to represent the median values of entire trajectories, h_{top} slightly
increases to 1.3 ± 1.5 km with a median of 0.8 km while T_{top} decreases correspondingly to 17.4 ± 15.0 °C with a median of
16.9 °C. The overview of the ice-containing clouds in Figure 8b shows that those clouds generally occur at larger heights and
lower temperature than the liquid clouds. One group of ice-containing clouds occurs at $T_{\text{top}} < -38$ °C and $h_{\text{top}} > 8$ km – in line
325 with the regime of homogeneous freezing. The other group with $T_{\text{top}} > -38$ °C covers the regime of heterogeneous freezing,
i.e., INP are needed to form cloud ice (Kanji et al., 2017), and represents the temperature range at which supercooled, mixed-
phase, and ice clouds can be observed. ~~Those clouds~~ We expect that the latter clouds would be most susceptible to changes
in aerosol concentrations. They make up 2673 pixels (53 clouds) with h_{top} ranging from 0.4 to 9.7 km (0.8 to 9.2 km) and
a median of 5.8 km (5.7 km). When considering all ice-containing clouds, the pixel-wise (whole-trajectory) mean values are
330 $h_{\text{top}} = 6.8 \pm 2.4$ km (7.5 ± 2.5 km) and $T_{\text{top}} = -23.6 \pm 18.5$ °C (-30.0 ± 18.8 °C) with median value of 6.6 km (7.2 km) and
 -17.2 °C (-25.2 °C).

The pixel-wise and whole-trajectory histograms of COT and r_{eff} for both liquid and ice-containing clouds are presented in
Figure 9. Because retrievals of cloud microphysical properties require data at visible wavelengths, this information is available
only during daytime. Hence, and as a result of measurement restrictions such as weak signal-to-noise ratio, not all tracked
335 pixels provide meaningful data. The majority of liquid clouds is optically thin with a median of 0.92 and 0.74 and means of
 2.38 ± 5.23 and 2.47 ± 3.83 for the pixel- and trajectory-based analysis, respectively. About 75% of all cases are below the mean
value. For ice-containing clouds, these values increase to pixel- and trajectory based medians of 4.88 and 1.85, respectively,
and means of 8.26 ± 10.77 and 3.94 ± 4.86 . An even larger difference is revealed in the size of the cloud particles. For liquid
clouds, the median r_{eff} is 7.8 μm for both the pixel- and trajectory-based analysis with means of 10.1 ± 5.0 μm and 9.8 ± 4.0 μm ,
340 respectively. Only 15% of cases show median values larger than 12 μm which indicates the likely presence of precipitation
(Rosenfeld et al., 2012). The presence of ice in clouds increases the inferred values of r_{eff} to pixel- and trajectory-based means
of 20.9 ± 7.5 μm and 22.0 ± 5.7 μm and medians of 23.2 μm and 24.4 μm , respectively.

The histogram of n_{CCN} for the 399 matched liquid clouds in Figure 10 shows that the C×C approach is capable of covering
a wide range of CCN conditions. While values range from 17 to 25721 cm^{-3} with a median of 872 cm^{-3} , the majority of
345 cases (about 90%) are in a realistic range below 3000 cm^{-3} . In the analysis of our data set, we will use n_{CCN} to discriminate
between clean and polluted conditions. This is done in two steps. First, the upper and lower 5% of cases are dismissed from
the data set as they are likely to represent unrealistic values that result from propagating unreliable measurements through the
analysis chain. For the present data set, this means that $n_{\text{CCN}} < 154$ cm^{-3} and $n_{\text{CCN}} > 4409$ cm^{-3} and the related cloud data are
omitted from further analysis. While the exclusion of unrealistic values of n_{CCN} doesn't affect the data set presented here, it will
350 become more crucial as the volume of the bottom-up data set increases. Second, the remaining 90% of cases are split into three
ranges that represent clean (lower quantile), moderate (middle quantile), and polluted conditions (upper quantile). The resulting
ranges contain about 4800 matched data points each and are 154 $\text{cm}^{-3} \leq n_{\text{CCN}} < 610$ cm^{-3} , 610 $\text{cm}^{-3} \leq n_{\text{CCN}} < 1210$ cm^{-3} ,
and 1210 $\text{cm}^{-3} \leq n_{\text{CCN}} < 4409$ cm^{-3} .

Figure 11 presents the histogram of n_{INP} related to the 95 ice-containing clouds. The majority of clouds (81%) occurs in aerosol fields that relate to values of n_{INP} between 10^{-3} and 10L^{-1} which are realistically found at atmospheric conditions (Kanji et al., 2017). About 3% of inferred values fall outside the presented range of seven orders of magnitude (2% lower, 1% higher). These values are likely the result of unreliable CALIPSO retrievals or originate from extrapolating the applied INP parametrizations to temperatures at which they are no longer applicable (Marinou et al., 2019). As in the case of n_{CCN} , unrealistic n_{INP} are excluded by dismissing the lowest and highest 5% of values and related cloud data from further data analysis. As mentioned earlier, the detailed evaluation of the number concentration of reservoir particles and n_{INP} with independent in-situ measurements analogous to Aravindhavel et al. (2023), Choudhury et al. (2022), and Choudhury and Tesche (2022b) is ongoing and will be the focus of a future publication.

3.3 CCN effects on liquid-water clouds

Now that we have obtained a data set of matched cloud and aerosol observations, we can start to investigate cloud properties for different ranges of n_{CCN} . Figure 12 shows that the mean n_{CCN} in the three quantiles mentioned before are $403 \pm 110\text{ cm}^{-3}$, $875 \pm 189\text{ cm}^{-3}$, and $2123 \pm 733\text{ cm}^{-3}$. If the values of r_{eff} that have been matched to the aerosol observation are grouped according to those three n_{CCN} ranges, we can see a clear decrease in r_{eff} and an increase in N_{d} from clean to polluted aerosol conditions that is in line with the Twomey effect. While $r_{\text{eff}} = 11.78 \pm 6.6\ \mu\text{m}$ (median of $9.0\ \mu\text{m}$) and $N_{\text{d}} = 68 \pm 166\text{ cm}^{-3}$ (median of 42 cm^{-3}) for the lower third of n_{CCN} observations, values decrease to $9.99 \pm 4.72\ \mu\text{m}$ (median of $8.0\ \mu\text{m}$) and $75 \pm 100\text{ cm}^{-3}$ (median of 53 cm^{-3}) for the middle third, and even further to $9.34 \pm 3.86\ \mu\text{m}$ (median of $7.8\ \mu\text{m}$) and $95 \pm 199\text{ cm}^{-3}$ (median of 60 cm^{-3}) for the upper third (see Figure 12).

This allows for a first quantification of the change in r_{eff} and N_{d} related to a change in n_{CCN} rather than aerosol proxies such as AOT or AI generally used in ACI studies based on satellite data (Bellouin et al., 2020; Quaas et al., 2020). An overview of the inferred sensitivities of r_{eff} and N_{d} to changes in n_{CCN} is provided in Table 1. We find a $\Delta r_{\text{eff}}/\Delta n_{\text{CCN}}$ in the range from -0.81 to -3.78 nm cm^{-3} depending on the considered quantiles and the use of median or mean values of the distributions in Figure 12. In the same way, N_{d} is found to increase between 1.17 and 2.30 per increase of 100 cm^{-3} in n_{CCN} . The larger sensitivities found when derived over just the lower two quantiles (columns 4 and 6 in Table 1) corroborate that r_{eff} and N_{d} are most susceptible to changes in CCN concentration for low baseline values and that the effect becomes saturated with further increasing n_{CCN} (Gryspeerd et al., 2023).

For better comparison to studies based on passive CCN proxies, Table 1 also provides sensitivities for logarithmic changes. The analysis of the C×C data set gives values of $\Delta \ln r_{\text{eff}}/\Delta \ln n_{\text{CCN}}$ between -0.09 and -0.21 while $\Delta \ln N_{\text{d}}/\Delta \ln n_{\text{CCN}}$ is found to vary in the range from 0.13 to 0.30. The latter values are at the lower end of earlier findings of 0.3 to 0.8 based on column CCN proxies (Bellouin et al., 2020). ~~However, they are the first ones to use actual~~ There are likely two factors at play. First, our study is the first one to derive sensitivities based on inferred CCN concentrations at cloud level and ~~the~~. On the one hand, this ensures that we only consider cases in which the observed aerosols can actually interact with the observed clouds. On the other hand, cloud-layer n_{CCN} is likely to give a weaker aerosol signal than a column proxy, potentially reducing the deduced sensitivity. Second, the isolated clouds considered in the current data set might not be as

sensitive to changes in aerosol concentration as, e.g., widespread stratocumulus clouds (Bellouin et al., 2020; Gryspeerd et al., 2017; Goren et al., 2019) [or their lifetime might be too short for revealing the full impact of the aerosol perturbation](#) (Glassmeier et al., 2021; Gryspeerd et al., 2021). Future research based on a larger C×C data set will reveal if the lower sensitivity can be corroborated and if the regional variation of sensitivity of cloud parameters to changes in n_{CCN} can also be resolved with our new approach.

Applying the same analysis to COT (mean/median of around 2/1), cloud lifetime (mean/median of 8/5 time steps), and cloud top height (mean/median of 800 m/600 m) does not reveal any change of those parameters with changing aerosol concentration (not shown). For L , we find a decrease of the mean from $25 \pm 47 \text{ g m}^{-2}$ for clean conditions to $16 \pm 37 \text{ g m}^{-2}$ for polluted conditions. However, median values show comparable values around 5 g m^{-2} for all three intervals of aerosol concentration in line with optically thin clouds. While these findings are not in line with the assumption that increased n_{CCN} increases cloud lifetime, albedo (COT), h_{top} , and L , we consider the results as still preliminary. The C×C approach will need to be applied to a longer time series and over a larger region to extend the data set for ACI studies from which more robust conclusions regarding the adjustments can be drawn. This will be the focus of follow-up work.

The use of CALIPSO observations furthermore allows for allocating n_{CCN} to a specific aerosol type. In the data set presented here, mineral dust and polluted continental make up the most of the CCN population. Therefore, an aerosol-type specific investigation of the connection between n_{CCN} and r_{eff} will also be left for follow-up studies with a larger C×C data set.

3.4 INP effects on ice-containing clouds

The capability of the C×C data set to provide information on n_{INP} and the development of the phase of a tracked cloud (Section 2.4) opens new avenues for studying the effect of aerosols also on ice-containing clouds. However, the related constraints for quality-assured cloud development and the lower abundance of successful INP retrievals from CALIPSO observations lead to a data set that is much smaller than the one for studying effects of changes in n_{CCN} on the properties of warm liquid-water clouds. Keeping this in mind, the current C×C data set for one year of data can only provide an outlook of its potential for spaceborne ACI studies.

The impact of n_{INP} on different cloud types in the regime of heterogeneous ice nucleation is illustrated in Figure 13. We consider all clouds in Figure 8 for which the whole-trajectory T_{top} as well as T_{top} per time step never exceeded 0°C and for which all pixels are classified as liquid as super-cooled. These conditions are fulfilled by 42 clouds. Mixed-phase clouds have to show a combination of pixels that are classified as liquid and ice (see Figure 3 for an example). This is the case for 45 clouds. Heterogeneously frozen clouds feature only pixels that are classified as ice and have to show values of T_{top} larger than -38°C , which is the case for 8 clouds. Super-cooled clouds show a mean (median) T_{top} of $-11.7 \pm 15.7^\circ\text{C}$ (-6.2°C). Mixed-phase clouds are colder with T_{top} of $-14.0 \pm 7.5^\circ\text{C}$ (-11.2°C) while heterogeneously frozen clouds show the lowest T_{top} of $-17.1 \pm 3.7^\circ\text{C}$ (-16.9°C). These clouds occur in an aerosol environment with n_{INP} of $0.04 \pm 0.11 \text{ L}^{-1}$ (median of 0.02 L^{-1}), $0.23 \pm 0.31 \text{ L}^{-1}$ (0.05 L^{-1}), and $2.64 \pm 1.79 \text{ L}^{-1}$ (2.92 L^{-1}), respectively.

The parametrizations used to infer n_{INP} from the CALIPSO observations are strongly dependent on temperature. For mineral dust, they generally show an increase in n_{INP} by about 1 order of magnitude per 5°C decrease (Marinou et al., 2019). The

INP data set presented here consists primarily of CALIPSO observations in which the detected aerosols are classified as mineral dust. Hence, we would expect a similar relation between the inferred T_{top} and n_{INP} of different cloud types if there was no change in the amount of reservoir particles that could become INP-active, i.e., if there was no increase in aerosol concentration. Instead, we find that mean n_{INP} changes by about 1 order of magnitude already for a 3°C decrease in mean T_{top} . This indicates that the increase in n_{INP} observed in the presence of mixed-phase clouds compared to super-cooled clouds and of heterogeneously frozen clouds compared to mixed-phase clouds is not purely related to the decreasing T_{top} of the different cloud types but also to an increase in the concentration of aerosols that can act as INP. In return, we can reason that the increased aerosol concentration facilitates earlier cloud glaciation as clouds surrounded by the largest abundance of INP are fully glaciated while those with medium and low n_{INP} are of mixed-phase and liquid phase, respectively. This is in agreement with studies in which dust concentrations from aerosol reanalysis fields is used as a proxy for the presence of INP (Seifert et al., 2010; Villanueva et al., 2020). Those studies address the issue by resolving the occurrence of ice-containing clouds within different ranges of T_{top} for different ranges of background aerosol concentrations while our approach directly relates n_{INP} at cloud level to the occurrence of ice in the matched clouds. However, resolving a consistent picture through an entirely different data analysis concept increases our overall confidence in applying the C×C to both liquid-water and ice-containing clouds.

As in the case of liquid clouds, a larger data set is needed to obtain more robust constraints on the effect of aerosol concentrations on the properties of ice-containing clouds. This would facilitate, e.g., to assess if variation in n_{INP} can also be found for super-cooled, mixed-phase, and heterogeneously frozen clouds with comparable T_{top} , which would be a more direct indication of the effect of aerosol concentration on cloud phase.

440 4 Summary and outlook

We present a detailed description of a new approach for spaceborne ACI studies in which cloud development from geostationary satellite observations is matched with height-resolved CCN and INP concentrations from polar-orbiting satellite observations on a cloud-by-cloud (C×C) basis. The novel C×C approach has been applied to observations of MSG-SEVIRI and the CALIPSO lidar over Europe and Northern Africa for the year 2014. Apart from the spatio-temporal matching of the observations, the analysis chain includes further screening to assure that the resulting data set contains only (i) realistically developing clouds during daytime for which macro- and microphysical properties can be inferred throughout their lifetime and (ii) scenarios in which cloud-relevant aerosols actually occur within the height range of the matched cloud.

Tracking objects in the CLAAS-2 cloud mask gives about 9 million clouds with well-defined start and end, i.e. forming and dissolving in clear air, over the considered region throughout one year. Further data processing steps outlined in this paper reduce this number to 399 liquid clouds and 95 ice-containing clouds that can be matched to surrounding concentrations of CCN and INP, respectively, at cloud level. Based on this initial data set, we demonstrate the potential of the C×C approach for spaceborne ACI studies on two examples: the sensitivity of N_{d} and r_{eff} to changes in n_{CCN} and the relation of the occurrence of ice-containing clouds to changes in n_{INP} .

For liquid clouds, we find a $\Delta \ln N_d / \Delta \ln n_{CCN}$ of 0.13 to 0.30 which is at the lower end of commonly inferred values of 0.3 to 0.8 (Bellouin et al., 2020). This is likely the combined result of applying n_{CCN} at cloud level rather than column aerosol proxies and the fact that the considered isolated clouds are less susceptible to aerosol perturbations than cloud decks with larger cloud fraction. The inferred $\Delta \ln r_{eff} / \Delta \ln n_{CCN}$ between -0.09 and -0.21 means that r_{eff} decreases by -0.81 to -3.78 nm per increase in n_{CCN} of 1 cm^{-3} . While further work is needed to corroborate the robustness of these findings, they would imply a weaker cooling related to aerosol-cloud interactions than currently accounted for in studies of anthropogenic climate change.

460

For ice-containing clouds, we find a tendency towards more cloud ice and more fully glaciated clouds with increasing n_{INP} that cannot be explained by the increasingly lower T_{top} of super-cooled liquid, mixed-phase, and fully glaciated clouds alone. This finding is in agreement with earlier studies in which n_{INP} is approximated by the concentration of mineral dust from aerosol transport modelling and reanalysis (Seifert et al., 2010; Villanueva et al., 2020).

465 The purpose of this publication is to present the novel C×C approach as well as its first preliminary results for low-level liquid and mixed-phase clouds from application to one year of data over a comparably small section of the full Earth disk covered by MSG-SEVIRI. A more comprehensive application of the C×C approach requires a significant increase in the volume of data that is available for detailed analysis including further stratification according to meteorological parameters to better confine cloud-controlling factors. In future work, the strong limitation in data yield imposed by the matching and 470 quality-assurance constraints will be addressed by:

1. **Extending the considered time period** to exploit the full length of the time series of coinciding MSG and CALIPSO satellite observations from 2006 to 2023. Given a comparable success rate as for 2014, this would provide a 17-fold increase of the volume of the matched aerosol-cloud data set for the region considered so far.
2. **Shifting or widening the study region** within MSG-SEVIRI's field of view. This allows for covering different cloud regimes, assessing the impact of different dominating aerosol types, and evaluating results with independent data from regional field experiments with the overall driver of increase the robustness of our findings.
3. **Adapting the cloud screening method** to consider a larger set of cloud types such as cirrus and deep convection. These cloud types have rarely been considered in spaceborne studies and the C×C approach might provide a step forward in that respect, particularly regarding aerosol effects on cloud glaciation.
- 480 4. **Expanding the application to other geostationary sensors** that cover further regions of the globe. This includes coverage of the Americas with GOES-R-ABI and of East Asia by the Advanced Himawari Imager (AHI, Bessho et al. 2016) aboard JAXA's Himawari-8 – implicitly supporting items 1 and 2 above. Both sensors also feature an improved spatial and temporal resolution compared to MSG-SEVIRI.
- 485 5. **Adapting the retrieval of cloud-relevant aerosol properties** to spaceborne lidar missions beyond CALIPSO, such as the Atmospheric Lidar on the Earth Cloud, Aerosol and Radiation Explorer (EarthCARE, Wehr et al. 2023) which is

set for launch in 2024, to extend the time range that can be considered for ACI studies with the C×C approach [and to provide continuity of data in times of decreasing aerosol concentrations \(Quaas et al., 2022\)](#).

490 6. **Refining and further developing the methods** for assessing different ACI mechanisms from the inferred data set of matched aerosol-cloud cases. The added time dimension related to resolving cloud development calls for dedicated and creative analysis approaches that best exploit the novel information.

For now, auxiliary information on meteorological parameters such as temperature, humidity, and pressure is taken from the CALIPSO Aerosol Profile product, as it is also needed for deriving CCN and INP concentrations. Future developments of our methodology will include a more comprehensive consideration of meteorological information – specifically of confounding factors such as relative humidity, lower tropospheric stability, and vertical velocity – from meteorological reanalysis data.

495 Finally, continuity to the MSG-SEVIRI-CALIPSO data matching as well as advanced data products from next-generation sensors will soon be available in the form of combining geostationary observations with the Flexible Combined Imager (FCI) on Meteosat Third Generation (MTG-I1, Holmlund et al. 2021) which was launched in 2022 with the polar-orbiting lidar observations provided by EarthCARE which is currently on schedule for launch in May 2024.

500 *Code availability.* The TrackMatcher code (Bräuer and Tesche, 2022) is available at <https://github.com/LIM-AeroCloud/TrackMatcher.jl> (last access: 23 November 2023).

Data availability. CALIPSO level 2 aerosol profiles can be accessed at https://doi.org/10.5067/CALIOP/CALIPSO/LID_L2_05KMAPRO-STANDARD- (last access: 23 November 2023). CLAAS-2 data are available at https://doi.org/10.5676/EUM_SAF_CM/CLAAS/V002 (last access: 23 November 2023). The global gridded CCN data set (Choudhury and Tesche, 2023) is available at <https://doi.pangaea.de/10.1594/PANGAEA.956215> (last access: 23 November 2023).

505 *Author contributions.* MT and PA conceived the presented approach. FA and MT developed the matching methodology. FA and GC developed the INP and CCN retrievals. FM and TS developed the cloud-tracking methodology. All authors contributed to the revision of the methodology, the discussion of the findings, and participated in writing the original manuscript.

Competing interests. The authors declare no competing interests.

510 *Acknowledgements.* This research has been supported by the Franco-German Fellowship Program on Climate, Energy, and Earth System Research (Make Our Planet Great Again-German Research Initiative (MOPGA-GRI), grant number 57429422) of the German Academic Exchange Service (DAAD), funded by the German Ministry of Education and Research. This research has also been supported by the Federal State of Saxony and the European Social Fund (ESF) in the framework of the program “Projects in the fields of higher education and research” (grant no. 100649813).

References

- 515 Ackerman, A., Kirkpatrick, M., Stevens, D., and Toon, O.: The impact of humidity above stratiform clouds on indirect aerosol climate forcing, *Nature*, 432, 1014-1017, <https://doi.org/10.1038/nature03174>, 2004.
- Adrian, R. J. and Westerweel, J.: Particle image velocimetry, Cambridge University Press, ISBN: 9780521440080, 586 pages, 2010.
- Albrecht, B.: Aerosols, cloud microphysics, and fractional cloudiness, *Science*, 245, 1227-1230, <https://doi.org/10.1126/science.245.4923.1227>, 1989.
- 520 [Anderson, T. L., Charlson, R. J., Winker, D. M., Ogren, J. A., and Holmén, K.: Mesoscale Variations of Tropospheric Aerosols, *J. Atmos. Sci.*, 60, 119-136, \[https://doi.org/10.1175/1520-0469\\(2003\\)060<0119:MVOTA>2.0.CO;2\]\(https://doi.org/10.1175/1520-0469\(2003\)060<0119:MVOTA>2.0.CO;2\), 2003.](https://doi.org/10.1175/1520-0469(2003)060<0119:MVOTA>2.0.CO;2)
- Ansmann, A., Mamouri, R.-E., Hofer, J., Baars, H., Althausen, D., and Abdullaev, S. F.: Dust mass, cloud condensation nuclei, and ice-nucleating particle profiling with polarization lidar: updated POLIPHON conversion factors from global AERONET analysis, *Atmos. Meas. Tech.*, 12, 4849-4865, <https://doi.org/10.5194/amt-12-4849-2019>, 2019.
- 525 Aravindhavel, A., Choudhury, G., Prabhakaran, T., Murugavel, P., and Tesche, M.: Retrieval and validation of cloud condensation nuclei from satellite and airborne measurements over the Indian Monsoon region, *Atmos. Res.*, 290, 106802, <https://doi.org/10.1016/j.atmosres.2023.106802>, 2023.
- Bellouin, N., Quaas, J., Gryspeerdt, E., Kinne, S., Stier, P., Watson-Parris, D., Boucher, O., Carslaw, K., Christensen, M., Daniau, A.-L., Dufresne, J.-L., Feingold, G., Fiedler, S., Forster, P., Gettelman, A., Haywood, J. M., Malavelle, F., Lohmann, U., Mauritsen, T.,
- 530 McCoy, D., Myhre, G., Mülmenstädt, J., Neubauer, D., Possner, A., Rugenstein, M., Sato, Y., Schulz, M., Schwartz, S. E., Sourdeval, O., Storelvmo, T., Toll, V., Winker, D., and Stevens, B.: Bounding global aerosol radiative forcing of climate change, *Rev. Geophys.*, 58, e2019RG000660, <https://doi.org/10.1029/2019RG000660>, 2020.
- Benas, N., Finkensieper, S., Stengel, M., Van Zadelhoff, G. J., Hanschmann, T., Hollmann, R., and Meirink, J. F.: The MSG-SEVIRI-based cloud property data record CLAAS-2, *Earth System Science Data*, 9, 415-434, <https://doi.org/10.5194/essd-9-415-2017>, 2017.
- 535 Bessho, K., Date, K., Hayashi, M., Ikeda, A., Imai, T., Inoue, H., Kumagai, Y., Miyakawa, T., Murata, H., Ohno, T., Okuyama, A., Oyama, R., Sasaki, Y., Shimazu, Y., Shimoji, K., and Sumida, Y.: An introduction to Himawari-8/9—Japan's new-generation geostationary meteorological satellites, *J. Meteor. Soc. Japan*, 94, 151-183, <https://doi.org/10.2151/jmsj.2016-009>, 2016.
- Block, K., Haghghatnasab, M., Partridge, D. G., Stier, P., and Quaas, J.: Cloud condensation nuclei concentrations derived from the CAMS reanalysis, *Earth Syst. Sci. Data Discuss.* [preprint], <https://doi.org/10.5194/essd-2023-172>, in review, 2023.
- 540 Boucher, O., Randall, D., Artaxo, P., Bretherton, C., Feingold, G., Forster, P., Kerminen, V.-M., Kondo, Y., Liao, H., Lohmann, U., Rasch, P., Satheesh, S., Sherwood, S., Stevens, B., and Zhang, X.: Clouds and Aerosols, in: *Climate Change 2013: The Physical Science Basis. Contribution of Working Group I to the Fifth Assessment Report of the Intergovernmental Panel on Climate Change*, edited by: Stocker, T., Qin, D., Plattner, G.-K., Tignor, M., Allen, S., Boschung, J., Nauels, A., Xia, Y., Bex, V., and Midgley, P., chap. 7, Cambridge University Press, Cambridge, United Kingdom and New York, NY, USA, 571-658, <https://doi.org/10.1017/CBO9781107415324.016>, 2013.
- 545 Bräuer, P. and Tesche, M.: TrackMatcher – A tool for finding intercepts in tracks of geographical positions, *Geosci. Model Dev.*, <https://doi.org/10.5194/gmd-2021-395>, 2022.
- Chen, Y.-C., Christensen, M., Stephens, G., and Seinfeld, J. H.: Satellite-based estimate of global aerosol-cloud radiative forcing by marine warm clouds, *Nature Geosci.*, 7, 643-646, <https://doi.org/10.1038/ngeo2214>, 2014.
- Choudhury, G. and Tesche, M.: Estimating cloud condensation nuclei concentrations from CALIPSO lidar measurements, *Atmos. Meas. Tech.*, 15, 639-654, <https://doi.org/10.5194/amt-15-639-2022>, 2022a.
- 550

- Choudhury, G., Ansmann, A., and Tesche, M.: Evaluation of aerosol number concentrations from CALIPSO with ATom airborne in situ measurements, *Atmos. Chem. Phys.*, 22, 7143–7161, <https://doi.org/10.5194/acp-22-7143-2022>, 2022b.
- Choudhury, G. and Tesche, M.: Assessment of CALIOP-Derived CCN Concentrations by In Situ Surface Measurements, *Remote Sens.*, 14, 3342, <https://doi.org/10.3390/rs14143342>, 2022.
- 555 Choudhury, G. and Tesche, M.: A first global height-resolved cloud condensation nuclei data set derived from spaceborne lidar measurements, *Earth Syst. Sci. Data*, 15, 3747–3760, <https://doi.org/10.5194/essd-15-3747-2023>, 2023.
- Christensen, M. W., Jones, W. K., and Stier, P.: Aerosols Enhance Cloud Lifetime and Brightness along the Stratus-to-Cumulus Transition, *P. Natl. Acad. Sci. USA*, 117, 17591-17598, <https://doi.org/10.1073/pnas.1921231117>, 2020.
- Christensen, M. W., Gettelman, A., Cermak, J., Dagan, G., Diamond, M., Douglas, A., Feingold, G., Glassmeier, F., Goren, T., Grosvenor,
560 D. P., Grypsperdt, E., Kahn, R., Li, Z., Ma, P.-L., Malavelle, F., McCoy, I. L., McCoy, D. T., McFarquhar, G., Mülmenstädt, J., Pal, S.,
Possner, A., Povey, A., Quaas, J., Rosenfeld, D., Schmidt, A., Schrödner, R., Sorooshian, A., Stier, P., Toll, V., Watson-Parris, D., Wood,
R., Yang, M., and Yuan, T.: Opportunistic experiments to constrain aerosol effective radiative forcing, *Atmos. Chem. Phys.*, 22, 641-674,
<https://doi.org/10.5194/acp-22-641-2022>, 2022.
- Coopman, Q., Hoose, C., and Stengel, M.: Detection of mixed-phase convective clouds by a binary phase information from the passive
565 geostationary instrument SEVIRI, *J. Geophys. Res.-Atmos.*, 124(9), 5045-5057, <https://doi.org/10.1029/2018jd029772>, 2019.
- Coopman, Q., Hoose, C., and Stengel, M.: Analysis of the thermodynamic phase transition of tracked convective clouds based on geostationary satellite observations, *J. Geophys. Res.-Atmos.*, 125(11), <https://doi.org/10.1029/2019JD032146>, 2020.
- Costantino, L. and Bréon, F.-M.: Analysis of aerosol-cloud interaction from multi-sensor satellite observations, *Geophys. Res. Lett.*, 37, L11801, <https://doi.org/10.1029/2009GL041828>, 2010.
- 570 DeMott, P. J., Prenni, A. J., Liu, X., Kreidenweis, S. M., Petters, M. D., Twohy, C. H., Richardson, M. S., Eidhammer, T., and Rogers,
D. C.: Predicting global atmospheric ice nuclei distributions and their impacts on climate, *P. Natl. Acad. Sci. USA*, 107, 11217-11222,
<https://doi.org/10.1073/pnas.0910818107>, 2010.
- DeMott, P. J., Prenni, A. J., McMeeking, G. R., Sullivan, R. C., Petters, M. D., Tobo, Y., Niemand, M., Möhler, O., Snider, J. R., Wang, Z.,
and Kreidenweis, S. M.: Integrating laboratory and field data to quantify the immersion freezing ice nucleation activity of mineral dust
575 particles, *Atmos. Chem. Phys.*, 15, 393-409, <https://doi.org/10.5194/acp-15-393-2015>, 2015.
- Derrien, M. and Le Gléau, H.: MSG/SEVIRI cloud mask and type from SAFNWC, *Intern. J. Rem. Sens.*, 26, 4707-4732,
<https://doi.org/10.1080/01431160500166128>.
- Douglas, A. and L'Ecuyer, T.: Global evidence of aerosol-induced invigoration in marine cumulus clouds, *Atmos. Chem. Phys.*, 21, 15103-
15114, <https://doi.org/10.5194/acp-21-15103-2021>, 2021.
- 580 Fan, J., Rosenfeld, D., Zhang, Y., Giangrande, S. E., Li, Z., Machado, L. A. T., Martin, S. T., Yang, Y., Wang, J., Artaxo, P., Bar-
bosa, H. M. J., Braga, R. C., Comstock, J. M., Feng, Z., Gao, W., Gomes, H. B., Mei, F., Pöhlker, C., Pöhlker, M. L., Pöschl, U.,
and de Souza, R. A. F.: Substantial convection and precipitation enhancements by ultrafine aerosol particles, *Science*, 359, 411-418,
<https://doi.org/10.1126/science.aan8461>, 2018.
- Forster, P., Storelvmo, T., Armour, K., Collins, W., Dufresne, J. L., Frame, D., Lunt, D. J., Mauritsen, T., Palmer, M. D., Watanabe, M., Wild,
585 M., and Zhang, H.: The Earth's energy budget, climate feedbacks, and climate sensitivity, in: *Climate Change 2021: The Physical Science
Basis, Contribution of Working Group I to the Sixth Assessment Report of the Intergovernmental Panel on Climate Change*, edited by:
Masson-Delmotte, V., Zhai, P., Pirant, A., Connors, S. L., Pean, C., Berger, S., Caud, C., Chen, Y., Goldfarb, L., Gomis, M. I., Huang,

- M., Leitzell, K., Lonnoy, E., Matthews, L. B. R., Maycock, T. K., Waterfield, T., Yelekci, O., Yu, R., and Zhou, B., Cambridge University Press, 923-1054, <https://www.ipcc.ch/report/ar6/wg1/> (last access: xx xxxx 2023), 2021.
- 590 Gasteiger, J. and Wiegner, M.: MOPSMAP v1.0: a versatile tool for the modeling of aerosol optical properties, *Geosci. Model Dev.*, 11, 2739-2762, <https://doi.org/10.5194/gmd-11-2739-2018>, 2018.
- [Glassmeier, F., Hoffmann, F., Johnson, J. S., Yamaguchi, T., Carslaw, K. S., and Feingold, G.: Aerosol-cloud-climate cooling overestimated by ship-track data, *Science*, 371, 485-489, <https://doi.org/10.1126/science.abd3980>, 2021.](https://doi.org/10.1126/science.abd3980)
- Goren, T. and Rosenfeld, D.: Satellite Observations of Ship Emission Induced Transitions from Broken to Closed Cell Marine Stratocumulus over Large Areas, *J. Geophys. Res.-Atmos.*, 117, D17206, <https://doi.org/10.1029/2012jd017981>, 2012.
- 595 Goren, T. and Rosenfeld, D.: Extensive Closed Cell Marine Stratocumulus Downwind of Europe – A Large Aerosol Cloud Mediated Radiative Effect or Forcing?, *J. Geophys. Res.-Atmos.*, 120, 6098-6116, <https://doi.org/10.1002/2015JD023176>, 2015.
- Goren, T., Kazil, J., Hoffmann, F., Yamaguchi, T., and Feingold, G.: Anthropogenic air pollution delays marine stratocumulus break-up to open-cells, *Geophys. Res. Lett.*, 46, 14135-14144, <https://doi.org/10.1029/2019GL085412>, 2019.
- 600 Goren, T., Sourdeval, O., Kretzschmar, J., and Quaas, J.: Spatial aggregation of satellite observations leads to an overestimation of the radiative forcing due to aerosol-cloud interactions, *Geophys. Res. Lett.*, 50, e2023GL105282, <https://doi.org/10.1029/2023GL105282>, 2023.
- Grosvenor, D. P., Sourdeval, O., Zuidema, P., Ackerman, A., Alexandrov, M. D., Bennartz, R., Boers, R., Cairns, B., Chiu, J. C., Christensen, M., Deneke, H., Diamond, M., Feingold, G., Fridlind, A., Hünerbein, A., Knist, C., Kollias, P., Marshak, A., McCoy, D., Merk, D., Painemal, D., Rausch, J., Rosenfeld, D., Russchenberg, H., Seifert, P., Sinclair, K., Stier, P., van Diedenhoven, B., Wendisch, M., Werner, F., Wood, R., Zhang, Z., and Quaas, J.: Remote Sensing of Droplet Number Concentration in Warm Clouds: A Review of the Current State of Knowledge and Perspectives, *Rev. Geophys.*, 56, 409-453, <https://doi.org/10.1029/2017RG000593>, 2018.
- 605 Gryspeerdt, E., Quaas, J., and Bellouin, N.: Constraining the aerosol influence on cloud fraction, *J. Geophys. Res.-Atmos.*, 121, 3566-3583, <https://doi.org/10.1002/2015JD023744>, 2016.
- Gryspeerdt, E., Quaas, J., Ferrachat, S., Gettelman, A., Ghan, S., Lohmann, U., Morrison, H., Neubauer, D., Partridge, D. G., Stier, P., Takemura, T., Wang, H., Wang, M., and Zhang, K.: Constraining the instantaneous aerosol influence on cloud albedo, *P. Nat. Acad. Sci. USA*, 114, 4899-4904, <https://doi.org/10.1073/pnas.1617765114>, 2017.
- 610 Gryspeerdt, E., Goren, T., Sourdeval, O., Quaas, J., Mülmenstädt, J., Dipu, S., Unglaub, C., Gettelman, A., and Christensen, M.: Constraining the aerosol influence on cloud liquid water path, *Atmos. Chem. Phys.*, 19, 5331-5347, <https://doi.org/10.5194/acp-19-5331-2019>, 2019.
- Gryspeerdt, E., Goren, T., and Smith, T. W. P.: Observing the timescales of aerosol–cloud interactions in snapshot satellite images, *Atmos. Chem. Phys.*, 21, 6093-6109, <https://doi.org/10.5194/acp-21-6093-2021>, 2021.
- 615 Gryspeerdt, E., Glassmeier, F., Feingold, G., Hoffmann, F., and Murray-Watson, R. J.: Observing short-timescale cloud development to constrain aerosol–cloud interactions, *Atmos. Chem. Phys.*, 22, 11727-11738, <https://doi.org/10.5194/acp-22-11727-2022>, 2022.
- Gryspeerdt, E., Povey, A. C., Grainger, R. G., Hasekamp, O., Hsu, N. C., Mulcahy, J. P., Sayer, A. M., and Sorooshian, A.: Uncertainty in aerosol-cloud radiative forcing is driven by clean conditions, *Atmos. Chem. Phys.*, 23, 4115-4122, <https://doi.org/10.5194/acp-23-4115-2023>, 2023.
- 620 Holmlund, K., Grandell, J., Schmetz, J., Stuhlmann, R., Bojkov, B., Munro, R., Lekouara, M., Coppens, D., Viticchie, B., August, T., Theodore, B., Watts, P., Dobber, M., Fowler, G., Bojinski, S., Schmid, A., Salonen, K., Tjemkes, S., Aminou, D., and Blythe, P.: Meteosat Third Generation (MTG): Continuation and Innovation of Observations from Geostationary Orbit, *Bull. Amer. Meteor. Soc.*, 102, E990-E1015, <https://doi.org/10.1175/BAMS-D-19-0304.1>, 2021.

- 625 Igel, A. L., and van den Heever, S. C.: Invigoration or enervation of convective clouds by aerosols? *Geophys. Res. Lett.*, 48, e2021GL093804, <https://doi.org/10.1029/2021GL093804>, 2021.
- Jia, H., Ma, X., Yu, F., and Quaas, J.: Significant underestimation of radiative forcing by aerosol–cloud interactions derived from satellite-based methods, *Nat. Commun.*, 12, 3649, <https://doi.org/10.1038/s41467-021-23888-1>, 2021.
- Jia, H., Quaas, J., Gryspeerd, E., Böhm, C., and Sourdeval, O.: Addressing the difficulties in quantifying droplet number response to aerosol
630 from satellite observations, *Atmos. Chem. Phys.*, 22, 7353-7372, <https://doi.org/10.5194/acp-22-7353-2022>, 2022.
- Kanitz, T., Seifert, P., Ansmann, A., Engelmann, R., Althausen, D., Casiccia, C., and Rohwer, E. G.: Contrasting the impact of aerosols at northern and southern midlatitudes on heterogeneous ice formation, *Geophys. Res. Lett.*, 38, L17802, <https://doi.org/10.1029/2011GL048532>, 2011.
- Kanji, Z. A., Ladino, L. A., Wex, H., Boose, Y., Burkert-Kohn, M., Cziczo, D. J., and Krämer, M.: Overview of Ice Nucleating Particles, *Meteorological Monographs*, 58, 1.1-1.33, <https://doi.org/10.1175/AMSMONOGRAPHS-D-16-0006.1>, 2017.
- 635 Koren, I., Feingold, G., and Remer, L. A.: The invigoration of deep convective clouds over the Atlantic: aerosol effect, meteorology or retrieval artifact?, *Atmos. Chem. Phys.*, 10, 8855-8872, <https://doi.org/10.5194/acp-10-8855-2010>, 2010.
- [Kovacs, T.: Comparing MODIS and AERONET aerosol optical depth at varying separation distances to assess ground-based validation strategies for spaceborne lidar, *J. Geophys. Res.*, 111, D24203, https://doi.org/10.1029/2006JD007349, 2006.](https://doi.org/10.1029/2006JD007349)
- 640 L'Ecuyer, T. S., Berg, W., Haynes, J., Lebsack, M., and Takemura, T.: Global observations of aerosol impacts on precipitation occurrence in warm maritime clouds, *J. Geophys. Res.*, 114, D09211, <https://doi.org/10.1029/2008JD011273>, 2009.
- Lohmann, U.: A glaciation indirect aerosol effect caused by soot aerosols, *Geophys. Res. Lett.*, 29, <https://doi.org/10.1029/2001GL014357>, 2002.
- Lohmann, U. and Feichter, J.: Global indirect aerosol effects: a review, *Atmos. Chem. Phys.*, 5, 715-737, <https://doi.org/10.5194/acp-5-715-2005>, 2005.
- 645 Mamouri, R.-E. and Ansmann, A.: Potential of polarization lidar to provide profiles of CCN- and INP-relevant aerosol parameters, *Atmos. Chem. Phys.*, 16, 5905-5931, <https://doi.org/10.5194/acp-16-5905-2016>, 2016.
- Marinou, E., Tesche, M., Nenes, A., Ansmann, A., Schrod, J., Mamali, D., Tsekeri, A., Pikridas, M., Baars, H., Engelmann, R., Voudouri, K.-A., Solomos, S., Sciare, J., Groß, S., Ewald, F., and Amiridis, V.: Retrieval of ice-nucleating particle concentrations from lidar observations and comparison with UAV in situ measurements, *Atmos. Chem. Phys.*, 19, 11315-11342, <https://doi.org/10.5194/acp-19-11315-2019>, 2019.
- 650 McCoy, D. T., Bender, F. A.-M., Mohrmann, J. K. C., Hartmann, D. L., Wood, R., and Grosvenor, D. P.: The global aerosol-cloud first indirect effect estimated using MODIS, MERRA, and AeroCom, *J. Geophys. Res. Atmos.*, 122, 1779-1796, <https://doi.org/10.1002/2016JD026141>, 2017.
- 655 McCoy, I. L., McCoy, D. T., Wood, R., and Gordon, H.: The hemispheric contrast in cloud microphysical properties constrains aerosol forcing, *P. Nat. Acad. Sci. USA*, 117, 18998-19006, <https://doi.org/10.1073/pnas.1922502117>, 2020.
- Mülmenstädt, J. and Feingold, G.: The radiative forcing of aerosol-cloud interactions in liquid clouds: Wrestling and embracing uncertainty, *Curr. Clim. Change Rep.*, 4, 23-40, <https://doi.org/10.1007/s40641-018-0089-y>, 2018.
- Murray, B. J., Carslaw, K. S., and Field, P. R.: Opinion: Cloud-phase climate feedback and the importance of ice-nucleating particles, *Atmos. Chem. Phys.*, 21, 665-679, <https://doi.org/10.5194/acp-21-665-2021>, 2021.
- 660

- Niemand, M., Möhler, O., Vogel, B., Vogel, H., Hoose, C., Connolly, P., Klein, H., Bingemer, H., DeMott, P., Skrotzki, J., and Leisner, T.: Parameterization of immersion freezing on mineral dust particles: an application in a regional scale model, *J. Atmos. Sci.*, 69, 3077-3092, <https://doi.org/10.1175/JAS-D-11-0249.1>, 2012.
- Omar, A., Winker, D., Kittaka, C., Vaughan, M., Liu, Z., Hu, Y., Trepte, C., Rogers, R., Ferrare, R., Kuehn, R., and Hostetler, C.: The CALIPSO Automated Aerosol Classification and Lidar Ratio Selection Algorithm, *J. Atmos. Ocean. Techn.*, 26, 1994-2014, <https://doi.org/10.1175/2009JTECHA1231.1>, 2009.
- Quaas, J., Boucher, O., and Bréon, F.-M.: Aerosol indirect effects in POLDER satellite data and the Laboratoire de Météorologie Dynamique-Zoom (LMDZ) general circulation model, *J. Geophys. Res.*, 109, D08205, <https://doi.org/10.1029/2003JD004317>, 2004.
- Quaas, J., Ming, Y., Menon, S., Takemura, T., Wang, M., Penner, J. E., Gettelman, A., Lohmann, U., Bellouin, N., Boucher, O., Sayer, A. M., Thomas, G. E., McComiskey, A., Feingold, G., Hoose, C., Kristjánsson, J. E., Liu, X., Balkanski, Y., Donner, L. J., Ginoux, P. A., Stier, P., Grandey, B., Feichter, J., Sednev, I., Bauer, S. E., Koch, D., Grainger, R. G., Kirkevåg, A., Iversen, T., Seland, Ø., Easter, R., Ghan, S. J., Rasch, P. J., Morrison, H., Lamarque, J.-F., Iacono, M. J., Kinne, S., and Schulz, M.: Aerosol indirect effects – general circulation model intercomparison and evaluation with satellite data, *Atmos. Chem. Phys.*, 9, 8697-8717, <https://doi.org/10.5194/acp-9-8697-2009>, 2009.
- Quaas, J., Arola, A., Cairns, B., Christensen, M., Deneke, H., Ekman, A. M. L., Feingold, G., Fridlind, A., Gryspeerdt, E., Hasekamp, O., Li, Z., Lipponen, A., Ma, P.-L., Mülmenstädt, J., Nenes, A., Penner, J. E., Rosenfeld, D., Schrödner, R., Sinclair, K., Sourdeval, O., Stier, P., Tesche, M., van Dierenhoven, B., and Wendisch, M.: Constraining the Twomey effect from satellite observations: issues and perspectives, *Atmos. Chem. Phys.*, 20, 15079-15099, <https://doi.org/10.5194/acp-20-15079-2020>, 2020.
- [Quaas, J., Jia, H., Smith, C., Albright, A. L., Aas, W., Bellouin, N., Boucher, O., Doutriaux-Boucher, M., Forster, P. M., Grosvenor, D., Jenkins, S., Klimont, Z., Loeb, N. G., Ma, X., Naik, V., Paulot, F., Stier, P., Wild, M., Myhre, G., and Schulz, M.: Robust evidence for reversal of the trend in aerosol effective climate forcing, *Atmos. Chem. Phys.*, 22, 12221-12239, <https://doi.org/10.5194/acp-22-12221-2022>, 2022.](https://doi.org/10.5194/acp-22-12221-2022)
- Quinn, P. K., Bates, T. S., Coffman, D. J., and Covert, D. S.: Influence of particle size and chemistry on the cloud nucleating properties of aerosols, *Atmos. Chem. Phys.*, 8, 1029-1042, <https://doi.org/10.5194/acp-8-1029-2008>, 2008.
- Romps, D. M., Latimer, K., Zhu, Q., Jurkat-Witschas, T., Mahnke, C., Prabhakaran, T., Weigel, R., and Wendisch, M.: Air pollution unable to intensify storms via warm-phase invigoration, *Geophys. Res. Lett.*, 50, e2022GL100409, <https://doi.org/10.1029/2022GL100409>, 2023.
- Rosenfeld, D., Lohmann, U., Raga, G. B., O'Dowd, C. D., Kulmala, M., Fuzzi, S., Reissell, A., and Andreae, M. O.: Flood or Drought: How Do Aerosols Affect Precipitation?, *Science*, 321, 1309-1313, <https://doi.org/10.1126/science.1160606>, 2008.
- Rosenfeld, D., Wang, H., and Rasch, P. J.: The roles of cloud drop effective radius and LWP in determining rain properties in marine stratocumulus, *Geophys. Res. Lett.*, 39, L13801, <https://doi.org/10.1029/2012GL052028>, 2012.
- Rosenfeld, D., Andreae, M. O., Asmi, A., Chin, M., de Leeuw, G., Donovan, D. P., Kahn, R., Kinne, S., Kivekäs, N., Kulmala, M., Lau, W., Schmidt, K. S., Suni, T., Wagner, T., Wild, M., Quaas, J.: Global observations of aerosol-cloud-precipitation-climate interactions, *Rev. Geophys.*, 52, 750-808, <https://doi.org/10.1002/2013RG000441>, 2014.
- Rosenfeld, D., Kokhanovsky, A., Goren, T., Gryspeerdt, E., Hasekamp, O., Jia, H., Lopatin, A., Pan, Z., and Sourdeval, O.: Frontiers in satellite-based estimates of cloud-mediated aerosol forcing, *Rev. Geophys.*, 61, e2022RG000799, <https://doi.org/10.1029/2022RG000799>, 2023.
- Rossow, W. B. and Schiffer, R. A.: Advances in understanding clouds from ISCCP, *Bull. Am. Meteorol. Soc.*, 80, 2261-2288, [https://doi.org/10.1175/1520-0477\(1999\)080<2261:AIUCFI>2.0.CO;2](https://doi.org/10.1175/1520-0477(1999)080<2261:AIUCFI>2.0.CO;2), 1999.

- Schmit, T. J., Griffith, P., Gunshor, M. M., Daniels, J. M., Goodman, S. J., and Lehair, W. J.: A Closer Look at the ABI on the GOES-R Series, *Bull. Amer. Meteor. Soc.*, 98, 681-698, <https://doi.org/10.1175/BAMS-D-15-00230.1>, 2017.
- 700 Seelig, T., Deneke, H., Quaas, J., and Tesche, M.: Life cycle of shallow marine cumulus clouds from geostationary satellite observations, *J. Geophys. Res.-Atmos.*, 126, e2021JD035577, <https://doi.org/10.1029/2021JD035577>, 2021.
- Seelig, T., Müller, F., and Tesche, M.: Do optically denser trade-wind cumuli live longer?, *Geophys. Res. Lett.*, 50, e2023GL103339, <https://doi.org/10.1029/2023GL103339>, 2023.
- Seifert, P., Ansmann, A., Mattis, I., Wandinger, U., Tesche, M., Engelmann, R., Müller, D., Pérez, C., and Hausteiner, K.: Saharan dust and heterogeneous ice formation: Eleven years of cloud observations at a central European EARLINET site, *J. Geophys. Res.*, 115, D20201, <https://doi.org/10.1029/2009JD013222>, 2010.
- 705 Shinozuka, Y., Clarke, A. D., Nenes, A., Jefferson, A., Wood, R., McNaughton, C. S., Ström, J., Tunved, P., Redemann, J., Thornhill, K. L., Moore, R. H., Latham, T. L., Lin, J. J., and Yoon, Y. J.: The relationship between cloud condensation nuclei (CCN) concentration and light extinction of dried particles: indications of underlying aerosol processes and implications for satellite-based CCN estimates, *Atmos. Chem. Phys.*, 15, 7585-7604, <https://doi.org/10.5194/acp-15-7585-2015>, 2015.
- 710 Steinke, I., Hoose, C., Möhler, O., Connolly, P., and Leisner, T.: A new temperature- and humidity-dependent surface site density approach for deposition ice nucleation, *Atmos. Chem. Phys.*, 15, 3703–3717, <https://doi.org/10.5194/acp-15-3703-2015>, 2015.
- Stevens, B. and Feingold, G.: Untangling aerosol effects on clouds and precipitation in a buffered system, *Nature*, 461, 607-613, <https://doi.org/10.1038/nature08281>, 2009.
- 715 Stier, P.: Limitations of passive remote sensing to constrain global cloud condensation nuclei, *Atmos. Chem. Phys.*, 16, 6595-6607, <https://doi.org/10.5194/acp-16-6595-2016>, 2016.
- [Tackett, J. L., Winker, D. M., Getzewich, B. J., Vaughan, M. A., Young, S. A., and Kar, J.: CALIPSO lidar level 3 aerosol profile product: version 3 algorithm design, *Atmos. Meas. Tech.*, 11, 4129–4152, <https://doi.org/10.5194/amt-11-4129-2018>, 2018.](https://doi.org/10.5194/amt-11-4129-2018)
- Twomey, S.: Pollution and the planetary albedo, *Atmos. Environ.*, 8, 1251-1256, [https://doi.org/10.1016/0004-6981\(74\)90004-3](https://doi.org/10.1016/0004-6981(74)90004-3), 1974.
- 720 Ullrich, R., Hoose, C., Möhler, O., Niemand, M., Wagner, R., Höhler, K., Hiranuma, H., Saathoff, H., and Leisner, T.: A new ice nucleation active site parameterization for desert dust and soot, *J. Atmos. Sci.*, 74, 699-717, <https://doi.org/10.1175/JAS-D-16-0074.1>, 2017.
- Villanueva, D., Heinold, B., Seifert, P., Deneke, H., Radenz, M., and Tegen, I.: The day-to-day co-variability between mineral dust and cloud glaciation: a proxy for heterogeneous freezing, *Atmos. Chem. Phys.*, 20, 2177-2199, <https://doi.org/10.5194/acp-20-2177-2020>, 2020.
- Villanueva, D., Senf, F., and Tegen, I.: Hemispheric and seasonal contrast in cloud thermodynamic phase from A-Train spaceborne instruments, *J. Geophys. Res.-Atmos.*, 126, e2020JD034322, <https://doi.org/10.1029/2020JD034322>, 2021.
- 725 Wehr, T., Kubota, T., Tzeremes, G., Wallace, K., Nakatsuka, H., Ohno, Y., Koopman, R., Rusli, S., Kikuchi, M., Eisinger, M., Tanaka, T., Taga, M., Deghaye, P., Tomita, E., and Bernaerts, D.: The EarthCARE mission – science and system overview, *Atmos. Meas. Tech.*, 16, 3581-3608, <https://doi.org/10.5194/amt-16-3581-2023>, 2023.
- Winker, D. M., Vaughan, M. A., Omar, A., Hu, Y., Powell, K. A., Liu, Z., Hunt, W. H., and Young, S. A.: Overview of the CALIPSO Mission and CALIOP Data Processing Algorithms, *J. Atmos. and Ocean. Techn.*, 26, 2310-2323, <https://doi.org/10.1175/2009JTECHA1281.1>, 2009.
- 730 Yuan, T., Li, Z., Zhang, R., and Fan, J.: Increase of cloud droplet size with aerosol optical depth: An observation and modeling study, *J. Geophys. Res.*, 113, D04201, <https://doi.org/10.1029/2007JD008632>, 2008.
- Yuan, T., Remer, L. A., and Yu, H.: Microphysical, macrophysical and radiative signatures of volcanic aerosols in trade wind cumulus observed by the A-Train, *Atmos. Chem. Phys.*, 11, 7119-7132, <https://doi.org/10.5194/acp-11-7119-2011>, 2011.
- 735




Figure 1. Flow chart of the different steps in the data analysis (solid boxes) with references to the corresponding literature and sections in this paper and the inferred data products (dashed boxes).

Table 1. Sensitivity of r_{eff} and N_d to changes in n_{CCN} . Values refer to the full range of n_{CCN} represented by the three quantiles in Figure 12 (all) and the change from clean to moderately polluted conditions (lower two) and are based on median and mean values, respectively. The unit for $\Delta r_{\text{eff}}/\Delta n_{\text{CCN}}$ is nm/cm^{-3} while all other parameters have no units. However, $\Delta N_d/\Delta n_{\text{CCN}}$ is multiplied by 100, i.e., refers to a Δn_{CCN} of 100 cm^{-3} .

	based on medians		based on means	
	all	lower two	all	lower two
$\Delta r_{\text{eff}}/\Delta n_{\text{CCN}}$	-0.81	-1.94	-1.42	-3.78
$\Delta \ln r_{\text{eff}}/\Delta \ln n_{\text{CCN}}$	-0.09	-0.14	-0.14	-0.21
$\Delta N_d/\Delta n_{\text{CCN}}$	1.17	2.30	1.51	1.48
$\Delta \ln N_d/\Delta \ln n_{\text{CCN}}$	0.23	0.30	0.19	0.13




Figure 2. Flowchart of the OMCAM retrieval for inferring n_{CCN} and n_{INP} from spaceborne CALIPSO lidar observations. Input from CALIPSO measurements and the CALIPSO aerosol model is marked by blue boxes. The grey area covers the hygroscopicity correction and particle number size distribution (PNSD) scaling with the help of MOPSMAP. White boxes mark intermediate products. The final n_{CCN} and n_{INP} for different aerosol types are given in the red boxes. RH and RI relate to relative humidity and refractive index, respectively. Figure revised from (Choudhury and Tesche, 2022a).




Figure 3. Example for matching a SEVIRI cloud trajectory from 1215 to 1300 on 20 March 2014 (grey line connecting the centroids of each time step) with the 5-km averaged footprints along the CALIPSO ground track for an overpass at 1215 on 20 March 2014. Filled CALIPSO footprints mark profiles with valid aerosol data while empty circles refer to profiles without aerosol information. The yellow star marks the intercept point. Light red and blue areas refer to SEVIRI pixels for which cloud water is identified as liquid and ice, respectively.




Figure 4. Realistic (a) and unrealistic (b) development of T_{top} , cloud area, and cloud phase found on 14 August 2014 and 24 March 2014, respectively. T_{top} per time step refers to the median over all cloud pixels (black dot) while the range marks the temperatures of the warmest (lower whisker) and coldest (upper whisker) pixel, respectively. Numbers at the bottom refer to the size of the cloud in pixels (black) and the number of pixels identified as ice (blue). The start and end times (in UTC) of the trajectories and the time of the CALIPSO observation (grey triangle) are given at the top of the plot.




Figure 5. Overview of the study region with trajectories of liquid-only (red, $N = 399$) and ice-containing (blue, $N = 95$) clouds that could be matched to surrounding n_{CCN} and n_{INP} , respectively.




Figure 6. Example of (a) the development of T_{top} (black), h_{top} (red), and r_{eff} (blue) for a liquid-only cloud observed by MSG-SEVIRI between 1100 and 1145 UTC on 18 March 2014 and the surrounding aerosol field from CALIOP observations in terms of (b) the feature type and (c) n_{CCN} for an overpass at 1137 UTC. The grey triangles mark the intercept between the cloud trajectory and the CALIPSO ground track. The example boxes in (c) illustrate the along-track distance and height range centred around the location and h_{top} (crosses) of individual pixels in (a) used for matching aerosol and cloud data. Successful matches, i.e. valid CCN data is available within a set distance to a pixel of a tracked cloud, are given in black while matches without valid CCN data are marked grey. White in (b) marks regions where the lidar signal has already been fully attenuated from clouds above. Note that not all detected aerosol features (orange in b) provide CCN information as the result of applying quality flags in the CCN retrieval (see Figure 2).




Figure 7. Frequency of occurrence of trajectories of different length in 15-min time steps for trajectories of 399 tracked liquid-only (red) and 95 ice-containing clouds (blue) that could be matched to CALIPSO overpasses with valid aerosol data.




Figure 8. Frequency of occurrence of h_{top} (black) and T_{top} (red) of liquid (a) and ice-containing clouds (b) that could be matched to CALIPSO overpasses with valid aerosol data. Open bars refer to pixel-wise information (35799 for liquid-only, 4016 for ice-containing) and solid bars mark whole-trajectory medians (399 for liquid-only, 95 for ice-containing). Note that data relating to the left and right scales, respectively, are independent of each other.




Figure 9. Frequency of occurrence of COT (black) and r_{eff} (red) for (a) liquid-only and (b) ice-containing clouds that could be matched to CALIPSO overpasses with valid aerosol data. Note that the number of pixels with valid cloud information is reduced compared to Figure 8. Open bars refer to pixel-wise information (24089 out of 35799 available pixels for liquid-only clouds and 3769 out of 4016 available pixels for ice-containing clouds) and solid bars mark whole-trajectory medians (399 for liquid-only, 95 for ice-containing). Numbers at the top of the plots refer to the pixel-wise/whole-trajectory values related to the intervals for which the frequency of occurrence exceeds the scale.




Figure 10. Frequency of occurrence of median n_{CCN} for 399 CALIPSO overpasses that could be matched to tracked liquid-only clouds.




Figure 11. Frequency of occurrence of median n_{INP} for 95 CALIPSO overpasses that could be matched to tracked ice-containing clouds.




Figure 12. Boxplots of n_{CCN} (black), r_{eff} (blue), and N_d (red) for 16230 matches of cloud pixels and aerosol information sorted into three quantiles. See text for details.




Figure 13. Boxplots of cloud-top T_{top} (black) and n_{INP} (blue) for super-cooled liquid clouds (27 cases), mixed-phase clouds (45 cases), and heterogeneously frozen ice clouds (8 cases) as determined with the C×C approach. See text for details.