

# High-resolution numerical modelling of seasonal volume, freshwater, and heat transport along the Indian coast

Kunal Madkaiker<sup>1</sup>, Ambarukhana D. Rao<sup>1</sup>, Sudheer Joseph<sup>2</sup>

<sup>1</sup>Indian Institute of Technology Delhi, New Delhi, India

5 <sup>2</sup>Indian National Centre for Ocean Information Services (INCOIS), Ministry of Earth Sciences, Hyderabad, India

Correspondence to: Kunal Madkaiker ( [Kunal.Ajit.Madkaiker@cas.iitd.ac.in](mailto:Kunal.Ajit.Madkaiker@cas.iitd.ac.in) )

**Abstract.** Seasonal reversal of winds and equatorial remote forcing influences the circulation of the Arabian Sea (AS) and Bay of Bengal (BoB) basins in the North Indian Ocean. In this study, we numerically modelled the physical characteristics of AS and BoB, using the MITgcm model at a high spatial resolution of 1/20° forced with climatological initial and boundary conditions. The simulated temperature, salinity, and flow fields were validated with satellite and in situ datasets. We then studied the exchange of coastal waters by evaluating transports computed from the model simulations. The alongshore volume transport on the eastern coast is stronger with high seasonal variability due to the poleward-flowing western boundary current and equatorward-flowing East Indian Coastal Current. West coast transport is influenced by large intraseasonal oscillations.

15 The alongshore freshwater transport an order less than the alongshore volume transport. Out of the net volume transport, freshwater accounts for a maximum of 6.03 % during the southwest monsoon season followed by 4.85 % in the post-monsoon season. We observe an inverse relationship between alongshore freshwater and volume transport on the western coast and a direct relationship on the eastern coast. The contribution of eddy-induced heat and freshwater transport was also examined. The relation between net heat transport and net heat flux illustrates the role of coastal currents and equatorial forcing in  
20 dissipating heat within the coastal waters. We observed that meridional heat transport over AS is stronger than BoB. Both basins act as a heat source during the summer monsoon and heat sink during the winter. This high-resolution model set-up simulates all the important physical climatological patterns leading to better understanding of the state of the north Indian ocean.

## 25 1 Introduction

The Indian coastline is surrounded by the north Indian Ocean (NIO) with the Arabian Sea (AS) on the west of the mainland and the Bay of Bengal (BoB) to the east. The current pattern in the NIO is dictated by the reversal of winds and equatorial remote forcing ([Rao et al., 2010](#); [Schott and McCreary, 2001](#); [Shankar et al., 2002](#)). This helps in the exchange of freshwater and thermal ventilation of AS and BoB waters. These waters are unique as both the basins are landlocked from three sides and have proximity to the coasts. Also, the thermohaline properties are different in these basins. AS is a highly saline basin due to excessive evaporation over precipitation and the advent of high-saline waters from the Persian Gulf and Red Sea ([Bower and Furey, 2012](#); [Zhang et al., 2020](#)). BoB is comparatively fresher due to the impact of precipitation and river runoff ([Amol et al.,](#)

**Deleted:** is two orders

**Deleted:** . Seasonal variations between the cross-shore volume transport and its alongshore component also present such a contradiction along the western coast while displaying in-phase behaviour on the eastern coast

**Deleted:** also

**Deleted:** making it a useful tool in various physical as well as biogeochemical studies in this region

**Deleted:** (Schott and McCreary, 2001; Shankar et al., 2002; Rao et al., 2010)...

**Deleted:** (Bower and Furey, 2012; Zhang et al., 2020)

45 [2020; Behara and Vinayachandran, 2016; Jana et al., 2015, 2018; Srivastava et al., 2022](#)), Modelling studies in these basins help to understand the impact of these unique characteristics over various physical and biogeochemical aspects.

**Deleted:** (Behara and Vinayachandran, 2016; Amol et al., 2020; Jana et al., 2015, 2018; Srivastava et al., 2022)

Two important coastal current systems [flows](#) in these basins. In the AS, the West Indian Coastal Current (WICC) is an eastern boundary current along the west coast with an equatorward (poleward) flow during the summer (winter) season ([Shankar et al., 2002; Shetye et al., 1991a; Shetye and Gouveia, 1998](#)). The course of this current also varies interannually. It is strongly seasonal around its central path (Mumbai, ~20°N) coast as compared to the southern (Kollam, ~9°N) coast ([Chaudhuri et al., 2020](#)). It becomes wider (narrower) along the southwest (northwest) coast of India ([Shetye et al., 1991a](#)). The flow of WICC is governed by winds as well as remote forcing ([Shankar et al., 2002; Shankar and Shetye, 1997; Shetye et al., 2008](#)). In the BoB, a poleward flowing Western Boundary Current (WBC) flows during the pre-summer monsoon season and an equatorward flowing East Indian Coastal Current (EICC) flows during the winter season ([Shetye et al., 1996](#)). The WBC is formed due to the wind-stress curl ([Gangopadhyay et al., 2013](#)), whereas the EICC is generated as a combined effect of density-driven flow and a coastally trapped Kelvin wave ([Rao et al., 2010](#)). These current systems are integral components governing the transport of volume and freshwater alongshore within the basins. [Additionally](#), two monsoon currents namely the southwest monsoon current and the northeast monsoon current are responsible for the transport of water between the AS and BoB. The southwest monsoon current associated with summer monsoon winds, advects saltier water from southeastern AS into southwestern BoB ([Murty et al., 1992; Vinayachandran et al., 1999](#)). The northeast monsoon current flows as a combined effect of the coastally trapped Kelvin wave and the westward propagated Rossby wave originated in the eastern equatorial IO ([Schott et al., 1994; Shankar et al., 2002](#)). It transports freshwater from southwestern BoB into southeastern AS. Various studies have attempted to understand the freshwater exchanges in the NIO based on satellite-derived observations ([Akhil et al., 2020; Mahadevan et al., 2016; Papa et al., 2012](#)), surface drifters ([Hormann et al., 2019](#)), and Argo floats ([Lin et al., 2019; Parampil et al., 2010](#)). Using numerical modelling we can additionally account for the subsurface ocean state, to understand the transports at deeper depths. This remains a limitation in surface observational studies.

**Deleted:** are flowing

**Deleted:** (Shetye et al., 1991a; Shetye and Gouveia, 1998; Shankar et al., 2002)...

**Deleted:** (Chaudhuri et al., 2020)

**Deleted:** (Shetye et al., 1991a)

**Deleted:** (Shankar and Shetye, 1997; Shankar et al., 2002; Shetye et al., 2008)

**Deleted:** (Shetye et al., 1996)

**Deleted:** (Gangopadhyay et al., 2013)

**Deleted:** (Rao et al., 2010)

**Deleted:** T

**Deleted:** (Murty et al., 1992; Vinayachandran et al., 1999).

**Deleted:** Schott et al., 1994; Shankar et al., 2002)

**Formatted:** Font colour: Black, English (US)

**Deleted:** (Akhil et al., 2020; Papa et al., 2012; Mahadevan et al., 2016)...

**Deleted:** Hormann et al., 2019)

**Deleted:** (Parampil et al., 2010; Lin et al., 2019)

**Deleted:** (Marshall et al., 1997)

The MITgcm (Massachusetts Institute of Technology general circulation model) ([Marshall et al., 1997](#)), is a numerical model which finds widespread utility in studying diverse ocean-related applications globally ([Forget et al., 2015; Gopalakrishnan et al., 2020; Mazloff et al., 2010; Menemenlis et al., 2005; Srivastava et al., 2016; Stammer et al., 2003](#)). This model includes several built-in packages, facilitating the ability to simulate various biogeochemical processes, thereby advancing our understanding of complex oceanic interplays. The broad goal of this study was to understand the exchanges of heat and freshwater by quantifying transports along the coastal pathways of AS and BoB using a robust MITgcm model setup. [Additionally](#), we have also investigated the eddy-induced heat and freshwater transports in BoB, as eddies play an important role in understanding the water budgets ([Ding et al., 2021](#)). For this, we configured the MITgcm model over AS and BoB (Fig. 1) using climatological initial and boundary forcing data. We initialized the model simulations with precise data from *in situ* and the latest satellite observations to minimize the margin of error. Then, we selected appropriate physical parametrization

**Deleted:** (Menemenlis et al., 2005; Forget et al., 2015; Stammer et al., 2003; Mazloff et al., 2010; Gopalakrishnan et al., 2020; Srivastava et al., 2016)

**Deleted:** Notably, its significance is underscored by the inclusion of various packages, augmenting its physical model to extend to various biogeochemical processes, thereby advancing our understanding of complex oceanic interplays

**Deleted:** set up the MITgcm model over our domain and estimate surface and subsurface volume, freshwater and heat transports in the basin...

**Formatted:** Font colour: Black, English (US)

schemes and determined the optimal values for horizontal, and vertical viscosity and diffusivity. We also rigorously validated the simulated physical parameters with satellite and gridded Argo observations. This setup was then used to simulate the coastal circulation and the resulting volume, freshwater and heat transports along the Indian as well as eastern Sri Lanka coastline (Fig. 1) and to understand how it gets modulated by winds, remote forcing, and flow fields. Estimating transports using *in situ* observations in the NIO is challenging due to their sparse coverage in time and space. Satellite derived surface currents too are limited due to their coarser resolution and inability to capture subsurface data. Thus, employing our validated MITgcm setup for transport computations emerges as a favourable alternative. To ensure the meaningfulness of our simulations in areas where observations are lacking, we conducted a model-to-model comparison of transports using an another assimilated model data. Our study is vital in taking forward our understanding from existing studies such as Sen et al. (2022), which provides an averaged picture of the volume transports along the WICC and EICC. We also analysed the alongshore flow in our analysis which is a main component of the coastal currents and their exchanges (Amol et al., 2014). Furthermore, we investigated the AS and BoB meridional heat transport to analyse the heat distribution which helps to understand how heat gets distributed in the NIO during different seasons.





Figure 1. Study area depicting the bathymetry of the MITgcm model domain in colour scale. The dashed black line represents the 1000m bathymetry contour. Red symbols represent the discharge points of major river systems in India. the dashed blue box represents the region considered for eddy-induced transports. All transects are 3° in length (solid black lines).

Deleted: the INC-HYC setup

Deleted: Sen et al. (2022)

Deleted: (Amol et al., 2014)



Deleted:

Deleted: (

Deleted: )

Deleted: Purple symbols represent the slope ADCP locations, along which the transects have been considered

135 The resolution of the modelling experiments plays an important role in the accurate forecasting and simulation of mesoscale and sub-mesoscale processes over regional domains (Benshila et al., 2014). We selected a horizontal resolution of  $1/20^\circ$  (~5 km) which allows the simulations to be eddy-resolving. Such a fine resolution is important when considering basins which are close to coasts. This setup can also be used with appropriate forcings to forecast the physical state of the ocean in this region. We describe the models used for this study, their configuration, the different datasets, and methods used in section 2. In section 3, we present the MITgcm model validation. In section 4 we report our major findings of various transport analyses and discuss our major findings in section 5. Summary is presented in Section 6.

Deleted: (Benshila et al., 2014)

Deleted: This study is further aimed to help researchers assess its implications on nutrients/sediment transport, biological productivity, and the fishery sector

Deleted: discuss

Deleted: and discussion

Deleted: Conclusions

Deleted: are

Deleted: 4.

## 2 Materials and Methods

### 2.1 Model

#### 145 2.1.1 MITgcm description and configuration

The MITgcm (Marshall et al., 1997) is configured for a regional domain ( $62^\circ\text{E} - 92^\circ\text{E}$ ,  $4^\circ\text{N} - 26^\circ\text{N}$ ) which includes the AS and the BoB. This model solves Navier-Stokes equations by using Boussinesq approximation. Here we have chosen the hydrostatic approximation. The finite volume approach is used over a staggered Arakawa-C grid. The third-order direct space-time advection scheme is used for temperature and salinity. This setup has a uniform high spatial resolution of  $1/20^\circ$  (~5 km), with 49 vertical levels in a z-coordinate system. Such a fine resolution allows the simulations to be eddy-resolving. The vertical resolution is 5m from the surface to 250 m depth, and gradually decreases at a deeper depth. The maximum depth of the setup is 4500m. Bathymetry is obtained from the General Bathymetric Chart of the Oceans (GEBCO) (Weatherall et al., 2020), having a high spatial resolution of 15-arc-sec. We use K-profile parameterization (KPP) (Large et al., 1994) as the vertical mixing parameterization scheme and MDJWF equation of state (McDougall et al., 2003). There are three lateral open boundaries along the western, eastern, and southern edges of the model domain. No-slip and free-slip boundary conditions are applied at the bottom and lateral boundaries, respectively for velocities. An implicit free surface and a non-rigid lid condition are implemented for the surface pressure. The model is integrated over an optimized timestep of 120 seconds and is designed using climatological forcing data. Initial temperature and salinity are prescribed from the World Ocean Atlas 2018 (WOA18) climatology (Locarnini et al., 2018; Zweng et al., 2019). To reduce the spin-up time and computational expenditure, the model is initialized with a warm start. For this, climatological zonal and meridional currents are prescribed from the Simple Ocean Data Assimilation (SODA) 3.12.2 dataset (Carton et al., 2018). Lateral boundary conditions, that is, temperature, salinity, and currents are also prescribed from SODA 3.12.2 on a pentad climatological time scale. The model is forced with daily climatology of 2m air temperature, 2m specific humidity, 10m zonal and meridional wind, net shortwave, and longwave radiation as the atmospheric forcing, from the fifth-generation reanalysis (ERA5) (Hersbach et al., 2020). Precipitation is obtained from Global Precipitation Measurement level 3 (GPM) (Huffman et al., 2015). Along with this, climatological river discharge from Dai and Trenberth (2002) is fed to the model using a point-source method, to incorporate the effect of river runoff at the locations marked red in Fig. 1. The model uses bulk formulae to calculate net heat and freshwater flux using the

Deleted: (Marshall et al., 1997)

Deleted: (hereafter model)

Deleted: e

Deleted: The model

Deleted: model

Deleted: (Weatherall et al., 2020)

Deleted: (Large et al., 1994)

Deleted: (McDougall et al., 2003)

Deleted: (Locarnini et al., 2018; Zweng et al., 2019)

Deleted: (Carton et al., 2018)

Deleted: (Hersbach et al., 2020)

Deleted: (Huffman et al., 2015)

Deleted: Dai and Trenberth (2002)

190 above parameters. The model is relaxed at the surface with monthly climatology of Multi-scale Ultra-high Resolution v4.1 Sea  
Surface Temperature (MUR SST) (Chin et al., 2017) and Soil Moisture Active Passive Sea Surface Salinity (SMAP SSS)  
(Tang et al., 2017) satellite data, prescribed every 10th day. The data links of all datasets are provided in the code and data  
availability section.

Deleted: (Chin et al., 2017)

Deleted: (Tang et al., 2017)

### 195 2.1.2 HYCOM model description

We used the assimilated Hybrid Coordinate Ocean Model (HYCOM) (Bleck, 2002) data for performing a model-to-model  
comparison with the MITgcm simulations. The model is simulated at the Indian National Centre for Ocean Information  
Services (INCOIS; hereafter referred to as INC-HYC) and is an eddy-resolving model with a high spatial resolution of 1/16°  
(~ 6.25 km) over the IO (20°E–120°E, 43.5°S–30°N). It is one-way nested within a global HYCOM setup of 1/4° (~ 25 km)  
200 spatial resolution. The model equations are solved on the Arakawa-C grid using the finite volume method. The second-order  
entropy conserving scheme is used to compute momentum advection (Bleck and Boudra, 1986; Bleck and Smith, 1990).  
Continuity equations and physical tracers such as temperature, and salinity are computed using a second-order flux-corrected  
transport scheme (Iskandarani et al., 2005; Zalesak, 1979). The model has 29 vertical hybrid layers. This setup incorporates  
the Central Statistical Interpolation (T-SIS) data assimilation scheme, based on multivariate linear statistical estimation. A  
205 combination of GEBCO and Earth TOPOgraphy One Arc-Minute Global Relief Model (ETOPO-1) is used as the model  
bathymetry. The atmospheric forcings, that is, 2m air temperature, 2m vapour mixture, surface downward and upward long  
and shortwave radiation, precipitation, and 10 m zonal and meridional wind are obtained from NOAA Global Forecasting  
System (GFS). Wind stress is computed according to Kara et al. (2005), whereas bulk formulae used to calculate surface fluxes  
are referred from Kara et al. (2000). KPP (Large et al., 1994) is chosen as the vertical mixing scheme. Monthly climatological  
210 river discharge is used from the Naval Research Lab (NRL). The model is simulated for a five-year hindcast period (2012-  
2016) and the state variables are written on daily intervals. We have computed daily climatology from this data. The technical  
report (<https://incois.gov.in/documents/TechnicalReports/ESSO-INCOIS-CSG-TR-01-2018.pdf>) can be referred to for more  
details and exhaustive validation. The HYCOM simulated data is reliable and performs reasonably well when compared with  
other data assimilated products such as NRL-HYCOM and INCOIS- Global Ocean Data Assimilation System (GODAS).

Deleted: (Bleck, 2002)

Deleted: (Bleck and Boudra, 1986; Bleck and Smith, 1990)

Deleted: (Zalesak, 1979; Iskandarani et al., 2005)

Deleted: Kara et al. (2005)

Deleted: Kara et al. (2000)

Deleted: (Large et al., 1994)

Deleted: GODAS

### 215 2.2 Data

To validate the seasonal model SST and SSS, we used the Group for High-Resolution Sea Surface Temperature (GHRSSST)  
(Donlon et al., 2012) and Soil Moisture and Ocean Salinity (SMOS) SSS v8.0 level 3 (Boutin et al., 2023) datasets respectively.  
The GHRSSST level 4 data by NASA's JPL, is produced using the optimal interpolation method at 0.054° spatial resolution.  
220 The latest version of SMOS uses an improved de-biasing technique and is available at 0.259° x 0.196° spatial resolution. Apart  
from these satellite datasets, we have also validated the model temperature and salinity with the gridded Coriolis Ocean Dataset  
for Reanalysis (CORA v5.2) (Szekely et al., 2019) and RAMA buoy (McPhaden et al., 2009) (refer supplementary text S3 and  
S4). CORA v5.2 data has been produced using multiple *in situ* sampling techniques such as Argo floats, drifters, gliders,

Deleted: (Donlon et al., 2012)

Deleted: (Boutin et al., 2023)

Deleted: (Szekely et al., 2019)

Deleted: (McPhaden et al., 2009)

Deleted: 1

Deleted: 2

moorings, etc. It has a spatial resolution of 0.5°, with data available from the surface to 2000 m depth. GlobCurrent zonal and meridional surface currents (Rio et al., 2014) were used to validate model computed surface currents. This observational data, derived from satellite mean dynamic topography, is available at the surface as well as 15m, as a sum of geostrophic and Ekman currents. This data has a spatial resolution of 0.25°. We computed monthly climatology for all these datasets and compared them with seasonal patterns of simulations.

**Deleted:** (Rio et al., 2014)

### 245 2.3 Methods

We initialized the model with the December monthly climatology of ocean temperature and salinity from WOA18, and zonal and meridional currents from SODA 3.12.2. Boundary conditions were forced from SODA 3.12.2 for the climatological year, on a pentad time scale. For appropriate selection of boundary conditions, we conducted a few sensitivity experiments using different reanalysis products (SODA 3.12.2, ECCOv4, and INCOIS-GODAS) and observed that SODA 3.12.2 was able to represent the ocean temperature, salinity, and circulation better in the domain, than others. Similarly, ERA5 wind data was compared with wind from RAMA buoy at various locations over AS and BoB and it was observed that ERA5 shows a strong correlation, lower RMSE and low standard deviation with RAMA. Hence, we selected this dataset for the surface forcings. All forcing datasets were regridded to the model domain resolution. The model was spun up for 5 years. Based on the temporal evolution of kinetic energy, we found that it achieves a steady state after 5 years. The 6<sup>th</sup> year model output was considered for our analysis. Model outputs were written on a pentad scale. To compute the transports, the transects were drawn by the following method. We drew a tangent vector at the curvature of each coastal point. Then, the normal vector of length 3 degree each was drawn beginning from the coast. Further, to calculate the alongshore and cross-shore current component, the angle of rotation was considered from the normal vector to the truth north, in anticlockwise direction. The alongshore and cross-shore current components can be denoted as:

**Deleted:** To compute the transports for the western coast of India, we computed the

**Deleted:** current

**Deleted:** following Shah et al. (2015)

**Deleted:** -  $\sin(\theta)$

**Formatted:** Portuguese

**Formatted:** Portuguese

**Formatted:** Portuguese

**Formatted:** Portuguese

**Formatted:** Portuguese

**Deleted:** (between true north and coast, anticlockwise (+ve) direction)...

**Deleted:** The angle of rotation for the western and eastern coasts was obtained from Amol et al. (2014) and Mukherjee et al. (2014) respectively. Similarly, on the eastern coast:  
 $a_{comp} = (v \cos(\theta) + u \sin(\theta))$  → → → → → (3)  
 $c_{comp} = (u \cos(\theta) - v \sin(\theta))$  → → → → → (4)  
 The angle of rotation is clockwise (-ve) direction.

**Deleted:** Stammer et al. (2003)

**Formatted:** Superscript

**Deleted:** :

**Deleted:** x

**Deleted:** 5

**Deleted:** x

**Deleted:** 6

**Deleted:** Stammer et al. (2003) and

**Deleted:** Rainville et al. (2022)

**Deleted:** x

**Deleted:** 7

$$260 \quad a_{comp} = (u \sin(\theta) - v \cos(\theta)) \quad (1)$$

$$c_{comp} = -(u \cos(\theta) + v \sin(\theta)) \quad (2)$$

where u and v are the zonal and meridional current components and  $\theta$  is the angle of rotation, in radians. Here,  $a_{comp}$  and  $c_{comp}$  are the alongshore and cross-shore current components respectively. The alongshore volume transport (AVT) and cross-shore volume transport (CVT) are computed in  $Sv$  ( $1 Sv = 1 \times 10^6 m^3/s$ ) following Stammer et al. (2003). The transports are computed by integrating in depth and along the length of the normal vector.

$$265 \quad AVT = \iint a_{comp} dz d\mathbf{n}_v \quad (3)$$

$$CVT = \iint c_{comp} dz d\mathbf{n}_v \quad (4)$$

Alongshore freshwater transport (AFT, in  $Sv$ ) is computed referring to Rainville et al. (2022):

$$270 \quad AFT = \iint a_{comp} \frac{(S_{ref} - S)}{S_{ref}} dz d\mathbf{n}_v \quad (5)$$

295 where S is the ocean salinity (psu) and  $S_{ref}$  is the reference mean salinity of 34.67 psu of the study area. It should be noted here that the freshwater fraction is always negative when  $S_{ref} < S$  as in the AS, irrespective of the orientation of the alongshore component. Thus, the sign convention of AFT in AS will always be inverse of the volume transport. However, in the BoB, the freshwater fraction will be mostly positive ( $S_{ref} > S$ ). This makes the direction of AFT to be dependent only on the alongshore flow.

300 Alongshore heat transport (AHT) is computed in PW (1 PW =  $1 \times 10^{15}$  W) referring to Stammer et al. (2003) and Chirokova and Webster (2006):

$$AHT = \rho C_p \iint u \text{comp} T \, dz \, dx \quad (6)$$

where T is ocean temperature ( $^{\circ}\text{C}$ ),  $\rho$  is seawater density ( $\text{kg}/\text{m}^3$ ) and  $C_p$  is the specific heat capacity of seawater ( $3898 \text{ J}/\text{kg}^{\circ}\text{C}$ ).

305 Components of eddy heat transport (EHT) are computed as:

$$ZEHT = \rho C_p \iint u \, T \, dz \, dx \quad (7)$$

$$MEHT = \rho C_p \iint v \, T \, dz \, dy \quad (8)$$

Where, ZEHT is the zonal and MEHT is the meridional EHT. Similarly, the components of eddy freshwater transport (EFT) are computed as:

$$310 \quad ZEFT = \iint u \frac{(S_{ref} - S)}{S_{ref}} \, dz \, dx \quad (9)$$

$$MEFT = \iint v \frac{(S_{ref} - S)}{S_{ref}} \, dz \, dy \quad (10)$$

The net volume transport (NVT), net freshwater transport (NFT), net eddy heat transport (NEHT), net eddy freshwater transport (NEFT) and net heat transport (NHT) were obtained by summing their respective zonal and meridional components (Arora, 2021). The zonal and meridional components were computed at each grid point integrated over the upper 100 m.

### 3. Model validation

Deleted: 83

Deleted: Stammer et al. (2003)

Deleted: Chirokova and Webster (2006)

Deleted: x

Deleted: 8

Formatted: English (US)

Deleted: volume

Deleted: V

Deleted: ,

Deleted: ), and net heat transport (NHT)


Deleted: (Arora, 2021)

Deleted: following Stammer et al. (2003). To understand the seasonal transport variability, NVT and NFT were computed

Deleted: Based on the transport estimates, we quantified how much freshwater gets advected by WBC and EICC along the eastern coast of India. The freshwater contribution was computed as a percentage of the NVT. The transports computed from the MITgem model are compared with the same from INC-HYC.

Deleted: 3. Results and Discussion


Deleted: 3.1.



340 **Figure 2. Seasonal climatology of SST (in °C) from (a-d) MITgcm, and its bias with (e-h) GHRSSST and (i-l) Argo. R values represent Pearson's correlation coefficients.**

Model validation is a crucial step which ensures that the model accurately represents the complexities of oceanic dynamics. For validation, we compared the model SST (Fig. 2), SSS (Fig. 3) and surface currents (Fig. 4) with observations and computed biases.

345 **There are four seasons which are distinguished as pre-summer monsoon (MAM), summer monsoon (JJAS), post-summer monsoon (ON) and winter (DJF). The characteristics of SST distribution across AS and BoB are included in supplementary information (Text S1).** The model setup simulates these seasonal SST patterns and compares well with both GHRSSST and gridded Argo with an acceptable bias range. The model has a warmer bias in northeastern AS during JJAS when compared with GHRSSST (Fig. 2f) owing to an increase in net heat flux. In ON, model SST is warmer along the western coast of India, compared to the observations (Fig. 2g-k). Overall, we note that the model has a slightly warmer bias over parts of northern AS and along the western coast where the shelf is wide with shallower water depth in the coastal regions. The heat gets trapped into the upper few meters, thereby increasing the surface net heat flux. We evaluated the model SST with observations statistically using a robust parameter, Pearson's correlation coefficient. We observe that simulated SST shows a strong positive correlation up to 0.98 with GHRSSST and gridded Argo SST throughout the climatological year.



**Deleted:**

**Deleted:** model

**Deleted:** (e-h) GHRSSST and (i-l) gridded Argo SST ...nd its bias of model ...ith (cm...hp ... [1]

**Deleted:** q...lt ... [2]

**Deleted:** 1

**Deleted:** As seen from both the observation datasets (Fig. 2e-l), we note some climatological characteristics in the SST distribution across these two basins. ...here are four seasons have been ... [3]

**Deleted:** In MAM, NIO is the warmest and we observe BoB to be warmer than AS. This is a cumulative effect of heat being stored in the upper few meters of the ocean due to strong stratification and increased surface net heat flux. The WBC advects warmer waters from the southwest up into the northwestern BoB. During JJAS, the temperature difference between the South Asian landmass and ocean causes the Intertropical Convergence Zone to shift northward ... [4]

**Formatted:** Font: Not Bold, Font colour: Auto







Figure 3. Seasonal climatology of SSS (in psu) from (a-d) MITgcm, and its bias with (e-h) SMOS and (i-l) Argo. R values represent Pearson's correlation coefficients.

SSS is another important parameter governing the transports. The characteristics of SSS distribution across AS and BoB are included in supplementary information (Text S2). The model captures the SSS spatial variations and seasonality well and conforms with the observed SSS. The salinity difference between AS and BoB is substantial in all seasons, which is also simulated well by the model. In DJF, model SSS is saltier in the eastern BoB, as compared to observations (Fig. 3h-l). This bias can be attributed to the slight overestimation in the eastern boundary forcing data which influences the simulated SSS of this region. Statistically, the model SSS shows a high spatial Pearson's correlation with both SMOS and gridded Argo SSS in all seasons. We have also statistically validated the simulated subsurface temperature and salinity with RAMA buoys and gridded Argo data to a depth of 500m and 100m respectively at various locations. This validation is included in the supplementary information (Text S3 and S4).



Deleted:

Deleted: model


Deleted: (e-h) SMOS and (i-l) gridded Argo SSS ...and its bias of model ...ith (em...p...) SMOS and (q) ... [5]

Deleted: t

Deleted: Similar to SST, climatological SSS has certain characteristic features in NIO. During MAM season, the poleward WBC brings saltier water from the southwestern up into the head BoB region. As the JJAS season commences, the Indian peninsula receives huge amounts of freshwater as a cumulative effect of precipitation as well as the melting of snow in the Himalayan regions. This increases the riverine discharge into the head BoB making it less saline. The equatorward flow of freshwater is limited up to 18°N ... [6]

Formatted: Font: Not Bold, Font colour: Auto

Deleted: p... t...). This bias can be attributed to the slight overestimation in the eastern boundary forcing data which influences the simulated SSS of this region. Statistically, the model SSS shows a high spatial Pearson's correlation with both SMOS and gridded Argo SSS in all seasons. We have also statistically validated the simulated subsurface temperature and salinity with RAMA buoys and gridded Argo data to a depth of 500m and 100m respectively at various locations ... [7]



535

Figure 4. Seasonal climatology of surface currents overlaid with vectors (in m/s) from (a-d) MITgcm, its bias with (e-h) GlobCurrent and (i-l) INCOIS-HYCOM. R values represent Pearson's correlation coefficients.

We validated the model currents with GlobCurrent observations and compared them with INC-HYC simulated currents, averaged over the upper 15 meters. The model-simulated currents show consistent agreement with both the GlobCurrent and the INC-HYC. The model also captures the transition in coastal currents like WBC and EICC well. During JJAS, equatorward flowing WICC brings waters from AS near the southern Sri Lankan coast, where the Sri Lankan Dome presides. During the same period, EICC forms over the northern BoB, which the model simulates well. By ON, the EICC dominates the eastern coast of India and brings relatively fresher water into the southeastern AS, causing temperature inversions and barrier layer formation along this region (Mathew et al., 2018). During DJF, the model simulates the anticyclonic circulation of Laccadive High (LH) in the same region. In the AS, the WICC reverses its direction and flows poleward. We computed the bias of the current magnitude of our MITgcm model with GlobCurrent and INC-HYC. The bias is well within limits and model surface currents spatially correlate well with both datasets (Fig. 4e-l).


540

545

#### 4 Results

##### 4.1 Alongshore Volume Transport (AVT) and Alongshore Freshwater Transport (AFT)

550



Deleted:

Deleted: model

Deleted: (e-h) GlobCurrent and (i-l) gridded INCOIS-HYCOM and ...ias ...of model ...ith (m...p) ... [8]

Deleted: q...t ... [9]

Deleted: observations


Deleted: model... The model also captures the transition in coastal currents like WBC and EICC well. One interesting thing to note is the eastward diversion of WBC along 18°N (Gangopadhyay et al., 2013), which is seen in GlobCurrent (Fig. 4e). However, in t... [10]


Deleted: following the other datasets

Deleted: (Mathew et al., 2018)

Deleted: m...-t ... [11]

Deleted: To validate the model subsurface currents, we computed the alongshore currents at various locations and compared them with GlobCurrent over the upper 15 meters (Fig. 5). The stick plots of surface alongshore current at given locations (Figure 5 a-j), r... [12]





680 **Figure 5. AVT (in Sv) of the MITgcm model (solid lines) and INC-HYC (dashed lines). R represents the Pearson's correlation coefficient between the MITgcm model and INC-HYC.**

685 To analyse the volume transports, we selected nine transects and computed the AVT. The three-degree width of the transects was selected to incorporate the coastal currents, which typically flow conforming to the 1000 m isobath (Amol et al., 2014; Mukherjee et al., 2014; Shetye et al., 1991a) (refer Fig. 1). We considered three transects each along the eastern (Gopalpur, Kakinada and Cuddalore) and western (Okha, Mumbai and Goa) coasts. Two transects are located along the southern coast of India (Kollam and Kanyakumari) and one transect is located along the eastern coast of Sri Lanka. The AVTs were plotted as a function over time to observe their seasonal and intraseasonal variability. Positive values indicate poleward transport, whereas negative values indicate equatorward transport. Black lines indicate the transport integrated over upper 200 m depth ( $M_{0-200}$  and  $H_{0-200}$ ) and red colour ( $M_{200-1200}$  and  $H_{200-1200}$ ) indicate the transport integrated from 200 m to 1200 m depth, to understand the seasonal variability over the surface and subsurface ocean.

690 Along the eastern coast, the seasonal cycle dominates the transport of EICC (Mukherjee et al., 2014; Mukhopadhyay et al., 2020). A poleward transport during MAM owing to the WBC and an equatorward flow during ON season is observed due to the EICC. However, we observe intraseasonal variability at Cuddalore. The flow of the transport reduces from north to south. It is interesting to note that the AVT is highest at Gopalpur and lowest at Mumbai, both being at almost the same latitude. In the west coast locations along the WICC, we observe weaker seasonal variations. We observe a dip at all the three locations i.e. Okha, Mumbai and Goa during summer monsoon, which is attributed to the equatorward flowing WICC. In the southern part, the AVT at Kollam uniformly deviates around its mean signal throughout the year, which has also been noted by the

current pattern in Chaudhuri et al. (2020). The transport at Kanyakumari is dominated by the eastward flowing southwest monsoon current during the summer monsoon and the westward flowing northeast monsoon current during the winter. The strong poleward flow during JJAS season indicates the transport of waters from AS into the southwestern BoB. Cuddalore, Kollam, Kanyakumari and eastern coast of Sri Lanka are closer to the equatorial Indian ocean, thus experience stronger impact of remote forcing compared to other locations in the northern AS and BoB. The subsurface AVT over the western coast is of the same magnitude as compared to surface. However, they are stronger along the eastern coast.

We also compared the MITgcm model simulated transport values with the ones from INC-HYC and computed correlation coefficients (Fig. 5). Statistically, we observe a strong positive correlation between the transport from both models, the only exception being Cuddalore and Kanyakumari. The surface and subsurface transports over Gopalpur and Kakinada have opposite flows during MAM seasons, indicating a strong countercurrent seen in both MITgcm model as well as INC-HYC. The strongest subsurface AVT is observed at Cuddalore and eastern coast of Sri Lanka. Our estimates are also consistent with the findings from Shetye et al. (1991b, 1996). The heat component of transport i.e., AHT has also been computed to provide a complete picture. The seasonality of computed AHT is similar to that of AVT (refer to supplementary information, Fig. S3).




Figure 6. AFT (in Sv) of the MITgcm model (solid lines) and INC-HYC (dashed lines). R represents the Pearson's correlation coefficient between the MITgcm model and INC-HYC.

Along the Indian coasts, the analysis of freshwater transports is crucial. This importance arises from the significant contributions of precipitation and discharge of glacial meltwater, both of which are integral components of coastal dynamics.

For this, we computed AFT by taking the double integral of freshwater fraction and alongshore velocity component in length and depth at the same locations as the AVT (Fig. 6). We computed the AFT in Sverdrup (volume) instead of kg/s (mass) to maintain uniformity. We observe some interesting patterns in the AFT variability. First, the direction of seasonal variations of AVT and AFT contradict each other on the western coast. However, they are similar on the eastern coast. This can be attributed to the role of salinity in both basins. Second, we note that the magnitude of AFT is an order lower than that of AVT. During February-April, the WBC transports freshwater poleward along the eastern coast. As the salinity in BoB is always lesser than the reference ( $S_{ref}$ ) and the alongshore current component is positive, the directions of AVT and AFT are the same as each other in this period. As the summer monsoon arrives, we see a reversal in flow of freshwater driven by EICC due to a negative alongshore current component. This equatorward flow is prominent during October-November at Gopalpur and Kakinada. The AFT at Cuddalore flows equatorward by December-January. The contradictory behaviour of subsurface AFT can be observed at Gopalpur due to the countercurrent. On the western coast, we observe a positive AFT at Okha, Mumbai and Goa during the summer monsoon. This can be attributed to the high precipitation along these regions in addition to the river runoff which is discharged into the coastal AS (Behara et al., 2019). Also at Kanyakumari, we observe two peaks, one during JJAS season and other during December. The first peak is attributed due to the high precipitation, whereas the second peak is due to freshwater flow from BoB to AS. The surface AFT estimates from MITgcm model conforms well at all locations except Kanyakumari with the AFT computed from the INC-HYC (Fig. 6), as seen by the positive correlation.

#### 4.2 Spatial variability of Net Volume Transport (NVT) and Net Freshwater Transport (NFT)




Figure 7. Seasonal spatial variability of NVT and NFT of MITgcm model. Positive values (red) indicate northward / eastward flow whereas negative values (blue) indicate southward/westward flow.

Formatted: Centred

740 To understand the seasonal spatial transport over the domain, we computed NVT and NFT at each grid point integrated over the upper 100 m (Fig. 7). When analysing transports at transects along the coasts, the alongshore and components become pertinent. However, for a grid-wise computation in the domain, the net component involving the zonal and meridional information is a more robust and meaningful metric. As observed in previous sections, the transport along coastal BoB is stronger as compared to AS. In MAM, the MITgcm model simulates a strong poleward NVT due to WBC extending from 10°N-20°N. Simultaneously, a weaker westward flow (2.5 Sv to 5 Sv) streams along the southern coast of Sri Lanka. During JJAS, a pair of cyclonic eddies situated over the northwestern BoB is observed. During this period, we also observed the Sri Lankan Dome along the eastern coast of Sri Lanka. It forms during early June and strengthens into a cyclonic circulation (Cullen and Shroyer, 2019). The NVT in this region exceeds 10 Sv during JJAS and weakens by ON as it moves northward. In ON, the EICC in BoB has a discontinuous flow (Durand et al., 2009) and shifts equatorward along the southwest BoB. By DJF, it is observed that the equatorward flow of EICC gets further carried westward by the northeast monsoon current into southeastern AS but remains confined between 4°N-6°N. This is simulated well by both models and is also reported by (Zhang and Du, 2012).

We quantified the NFT as a percentage of NVT over different seasons to understand how much freshwater gets advected by WBC and EICC along the eastern coast of India. During MAM, the NFT of WBC is 2.10 % of the NVT from the MITgcm model. Low saline water of 0.1-0.3 Sv is advected poleward in this period. In the JJAS season, the equatorward EICC transports around 0.2-0.4 Sv of freshwater. It is bounded between the head and northwestern BoB and transports most freshwater (6.03 %). Also, the major Indian rivers have the largest riverine discharge during this season (Dai and Trenberth, 2002). By ON, the equatorward NFT along the eastern coast of India reaches southwest BoB and transport exceeds 0.4 Sv at few locations. By this period, the NFT reduces to 4.86 % of the NVT, as the freshwater mixes with the saltwater. By DJF, the freshwater is further transported westward into southeastern AS. The flow seems to be strongest along the southeastern coast of India and the southern coast of Sri Lanka (> 0.3 Sv). As the water propagates from BoB into southeastern AS, its freshness decreases slowly due to continuous mixing with saltier waters and the NFT further reduces to 2.83 % of the NVT. Our results along the coast of Sri Lanka agree with (Rainville et al., 2022).

### 765 **4.3 Contribution of heat and freshwater transport due to eddies**

#### **4.3.1 Eddy heat transport along the eastern coast of India**


Formatted: Font colour: Black, English (US)

Formatted: Font colour: Black, English (US)

Formatted: Font colour: Black, English (US)

Formatted: Font colour: Black, English (US)

Formatted: Font colour: Black, English (US)



**Figure 8:** (a-c) Sea level anomaly overlaid with current vectors depicting the cyclonic and anticyclonic eddies simulated along the eastern coast of India. Vertical profile of ocean temperature, vertical velocity and MLD for Box 1 (d,e) and Box 2 (g,h) and their computed zonal, meridional and net eddy heat transports (f and i).

In addition to the alongshore volume and freshwater transports, our eddy-resolving MITgcm setup allows us to look into the heat and freshwater transport by eddies. Bay of Bengal experiences significant mesoscale and submesoscale eddies (Chen et al., 2012; Cheng et al., 2018). For our analysis, we selected the northwestern BoB region to study the transport by the mesoscale activities, as shown in Fig. 8. (Kurien et al., 2010) reported that the generation of these eddies is driven by baroclinic instability due to the poleward flowing WBC. Two eddy regions were identified where the eddies exist from April to July and they extend up to 100m depth in the vertical, which can be seen from the current vectors (Fig. 8, a-c). Box 1 identifies an anticyclonic eddy (ACE) followed by a cyclonic eddy (CE). Box 2 identifies a CE which is strongest in May and starts weakening in July. In Box 1, the ACE begins to dissipate by May and the CE strengthens. This can be seen by the slight shoaling of MLD and the shift in vertical velocity from downward (negative) to upward (positive), due to divergence at the eddy centre (Fig. 8, e). The

Formatted: Font colour: Black, English (US)


Formatted: Font colour: Black, English (US)

Formatted: Not Highlight

780 eddy-induced transports have been computed over the upper 100m. The ZEHT shows a consistent eastward transport between  
 0.22-0.11 GW from April to July. The MEHT transitions from being northward  $\sim 0.07$  GW by April-May to southward by  
 785 June-July, reaching a maximum  $-0.06$  GW during June. The NEHT propagates in the eastern-northeastern direction  
 transporting  $0.28-0.06$  GW during the period.

In Box 2, we observe strong upward vertical velocity during May-June. The MLD shoals from 30m to 20m within  
 785 June (Figure 8, h). The ZEHT transports a maximum of  $\sim 0.52$  GW in April and weakens to around  $0.06$  GW by July. Similarly,  
 the MEHT has a southward transport of  $-0.18$  GW in April which transitions into weak northward transport of  $0.06$  GW by  
 July. Overall, the NEHT shows that the eddy propagates in the east-west direction transporting about  $0.36-0.06$  GW during  
 the period.

790 **4.3.2 Eddy freshwater transport along the eastern coast of India**



**Figure 9: (a) SSS overlaid with current vectors depicting the cyclonic eddy simulated along the eastern coast of India. Vertical profile of ocean salinity, vertical velocity and MLD for Box 1 (b, c) and their computed zonal, meridional, and net eddy freshwater transports (d).**




795 The EICC in BoB has been described as a discontinuous flow (Durand et al., 2009) due to possible eddy activity as a means of baroclinic/barotropic instabilities. We identified a CE transporting fresher water along the eastern coast with intensity peaking by the month of October. The eddy extends up to 100m depth. The upwelling at the centre of the CE is evident due to the shoaling of the MLD (Fig. 9b). The eddy-induced ZFEFT transports westward, intensifying around 0.08 Sv by the end of November whereas, the MEFT has a peak southward transport of 0.15 Sv by the end of October. The order of the computed MEFT matches with that of (Lin et al., 2019). Overall, the NEFT shows that the eddy propagates in the southwestern direction transporting upto 0.16 Sv freshwater during October-November.

Formatted: Font colour: Black, English (US)

800

Formatted: Font colour: Black, English (US)

#### 4.4 Net Heat Transport (NHT) and Net Heat Flux



805 **Figure 10. MITgcm model computed (a) seasonal NHT (GW, 1GW=  $1 \times 10^9$  W) integrated over the upper 100m. For the upper panel, (a) colour red indicates northward/eastward flow whereas blue indicates southward/westward flow. (b) seasonal surface net heat flux ( $W/m^2$ ). For the lower panel, (b) colour red represents heat gain and blue represents heat loss.**


810 Studying the NHT in addition to volume transport provides a more comprehensive view, as heat transport is an important link influencing the dynamics of water movement. We aimed to understand the thermal component of the transports and its spatio-temporal variability in the NIO. In MAM, the WBC carries the warmer water along a strong poleward transport. With the onset of June, the NHT is prominently high along the Sri Lankan Dome. This cyclonic eddy is strengthened by JJAS, and the warm water is transported northwards by ON. This is clear in the NHT signature of JJAS and ON. In the winter season, the heat transport is relatively low because of several factors.

815 The characteristics of net heat flux are considerably different from that of the NHT. The heat flux is primarily governed by atmospheric forcings and vertical mixing. During MAM, there is an increase in net shortwave radiation and the winds are weak

which stalls the vertical mixing. This causes shoaling of the mixed layer depth, increases stratification and traps heat in the upper surface layers in almost the entire domain. In JJAS, we observe the cooling of surface waters due to rain-bearing clouds, which block incoming shortwave radiation (Das et al., 2016). This further prevents evaporation leading to a net heat gain in JJAS. At the same time, the waters along the eastern coast of India in BoB gain heat owing to stratification. By ON, net shortwave radiation decreases, and the wind direction reverses. The northeasterly cold dry winds cool the surface waters of northern AS and BoB, which triggers convective mixing. We observe similar cooling near the southern tip of the mainland owing to latent heat release due to strong winds (Luis and Kawamura, 2000). The southeastern AS region has high heat flux throughout the ON, DJF and MAM seasons.

#### 4.5 Evaluation of meridional heat transport

To understand the meridional heat distribution and ventilation in the NIO basin by currents, we computed the MHT in AS and BoB basins for the MITgcm model. We zonally integrated MHT at each latitude, over the upper 100m. The MHT is plotted as a function over time (Fig. 11).



**Figure 11. Meridional heat transport (MHT, in PW) computed over the upper 100m using the MITgcm model for AS and BoB. Red colour indicates northward transport and blue colour indicates southward transport.**

The MHT pattern of AS is considerably different from that of BoB. The AS MHT has a prominent seasonal signature with a southward transport exceeding 1.25 PW during the JJAS and a northward transport ( $> 1$  PW) during the DJF (Fig. 11 a). In other words, the heat flows out from the AS into the equatorial Indian Ocean during the summer monsoon and the heat flows into AS in the winter (Garternicht and Schott, 1997). The latitudinal band between  $6^{\circ}\text{N}$ - $12^{\circ}\text{N}$  sees the strongest positive and negative signals of MHT. The reversal in the direction of MHT occurs during the MAM and ON seasons. The BoB MHT is observed to be weaker than AS (Fig. 11 b). Overall, the MHT does not exceed  $\pm 0.75$  PW in the BoB basin. We observe a weak southward MHT ( $\sim 0.25$  PW) during the JJAS and a weak northward MHT ( $\sim 0.5$  PW) during the DJF and MAM seasons. The values agree with Shi et al., (2002). Along  $6^{\circ}\text{N}$  latitude,  $\sim 0.5$  PW of southward MHT exists between February and April. The lower latitudinal band between  $4^{\circ}\text{N}$ - $6^{\circ}\text{N}$  shows a comparatively stronger intra-seasonal modulation of MHT. We find small bursts of northward MHT between November-January and April-May, and southward MHT during JJAS. This is influenced by the transport from equatorial IO.

## 5 Discussion


This study indicates that the transports in the eastern and western coasts of India are different from each other wherein the transport along the eastern coast is largely seasonal whereas on the western coast, it is modulated mostly by intraseasonal oscillations. This is majorly because the transport in the eastern coast is governed by EICC which is more seasonal and at the western coast, more intraseasonal WICC dominates. The modelled AVT estimates are consistent with earlier findings in both the coasts as well as along Sri Lanka coast (Anutaliya et al., 2017; Chaudhuri et al., 2020). In case of AFT, we observed evidence of countercurrents due to which the directions of surface and subsurface transports counter each other. Higher river runoff during the monsoon season governs the peak in the AFT at both the coasts, whereas at Kanyakumari we observed high transport in December due to freshwater flow from the BoB to AS. Along the eastern coast of Sri Lanka the freshwater transport peaks during November, a month prior to that of Kanyakumari. This analysis shows interesting contrasts in the AVT on the eastern and western coast. In the western coasts, seasonal variations of AFT and AVT oppose each other due to salinity dynamics. In contrast, the eastern coast shows similar seasonal trends in AVT and AFT, reflecting the influence of freshwater inputs from precipitation and river discharge

The model setup also simulates climatological eddies and the Sri Lankan Dome. The climatological eddies along the eastern coasts are active during June-July, but by August-September, they get disrupted due to an equatorward transport initiated by the EICC. The seasonal spatial NFT pattern is similar to that of spatial NVT. However, its value is an order less than NVT. Important seasonal dynamics that we understand from our analysis is that, during the pre-monsoon period, the poleward transport by the WBC is relatively low. However, in the monsoon season, the EICC significantly enhances equatorward freshwater transport due to high riverine discharge. As the season progresses into ON, the freshwater transport decreases as it mixes with saltwater. By winter, the transport continues westward into the Arabian Sea, with the intensity of flow decreasing as it further mixes with saltier waters.

Eddies are generated in the northwestern BoB due to baroclinic instability driven by the poleward flowing WBC. The identified eddy regions in this study exhibit distinct seasonal patterns, with the presence of anticyclonic and cyclonic eddies impacting the vertical structure and transport dynamics. One of the interesting findings was that the eddies with persistent cyclonic circulation influences the MLD and vertical velocity patterns significantly more than the eddies where transition from anticyclonic to cyclonic circulation takes place. In August-November, however, the eddies formed in the BoB transport freshwater zonally and meridionally with its intensity peaking by the end of September. These mesoscale eddies play an important role in the transporting the freshwater accumulated in the head of the BoB region along the coast. The westward and southward transports of freshwater by the eddies show the interaction between mesoscale eddies and coastal currents. The consistency of the transports computed match with previous studies and further validate the model simulations.

The NHT analysis shows the significant role of heat transport in influencing water movement dynamics in the northern Indian Ocean (NIO). In the pre-monsoon season, the WBC's poleward transport of warmer water establishes a strong thermal gradient. The winter season shows a decline in heat transport due to seasonal atmospheric conditions, which highlights the influence of

### Deleted: 3.2 Alongshore Volume transport (AVT) and Cross-shore Volume transport (CVT)



**Deleted:** Figure 6. AVT (in Sv) of the model (solid lines: M200 / M1200) and INC-HYC (dashed lines: H200 / H1200). R represents the Pearson's correlation coefficient between the model and INC-HYC. Articles in black colour indicate transport integrated over 200 m depth and red colour indicates transport integrated over 1200 m depth.

To analyse the volume transports, we selected nine transects and computed the AVT and CVT. The three-degree width of the transects was selected to incorporate the WICC and EICC, which typically flow conforming to the 1000 m isobath (Shetye et al., 1991a; Amol et al., 2014; Mukherjee et al., 2014) (refer Fig. 1). We considered three transects each along the eastern (Gopalpur, Kakinada and Cuddalore) and western (Okha, Mumbai and Goa) coasts. Two transects are located along the southern coast of India (Kollam and Kanyakumari) and one transect is located along the eastern coast of Sri Lanka. The AVT were plotted as a function over time to observe their seasonal and intraseasonal variability. Positive values indicate poleward transport, whereas negative values indicate equatorward transport. For the Kanyakumari and Sri Lanka transects, positive values indicate eastward (northward) flow, while negative values indicate westward (southward) flow. We assume the AVT to be purely meridional flow at the eastern coast of Sri Lanka. Black lines represent the transport computed over the upper 200m (M200 or H200) to understand the seasonal variability over the upper ocean, whereas red lines represent transport over the upper 1200m (M1200 or H1200) (C... [14])

**Formatted:** Font: Bold

**Formatted:** Font colour: Black, English (US)

950 cooler, drier winds and reduced solar radiation. Net heat flux patterns are primarily driven by atmospheric conditions and vertical mixing processes. In MAM, the increased shortwave radiation and weak winds result in stratification and heat entrapment in the upper ocean layers. In JJAS, monsoon clouds reduce incoming radiation thereby cooling the surface waters. Besides this, large evaporation results in the release of latent heat which increases cooling majorly in the open waters (Das et al., 2016). The western AS is saturated due to an increase in the specific humidity of air (Pinker et al., 2020). Post monsoon, the reduction in net heat flux is attributed to heat loss in the form of latent heat which further intensifies by DJF in these parts of the basin (Kumar and Prasad, 1999). The southeastern AS maintains high heat flux due to the export of freshwater from southwestern BoB and a downwelling Rossby wave which creates a thick barrier layer and prohibits vertical mixing, thus capping heat in the upper layers (Mathew et al., 2018).

955 The MHT in the AS shows a clear seasonal reversal, driven by the reversal of winds along with meridional Ekman transports, and vertical thermal wind shear (Lee and Marotzke, 1998; Schott and McCreary, 2001; Wacongne and Pacanowski, 1996). This seasonal pattern is influenced by the annual bi-mode westward propagating Rossby wave, particularly in the latitudinal band between 6°N-12°N (Brandt et al., 2002). The reversal in MHT direction during the MAM and ON seasons aligns with known wind and circulation changes. The weakening of the summer monsoon impacts Ekman transport, leading to weaker southward MHT and further warming of the AS (Pratik et al., 2019; Swapna et al., 2017). In contrast, the BoB exhibits weaker MHT due to higher stratification and weaker winds, which result in slower circulation and poor vertical mixing (Mahadevan, 2016; Mallick et al., 2020; Sheno, 2002). Overall, we understand that NIO becomes a heat source (sink) during the summer (winter) season. The heat stored in the upper waters gets flushed out due to an overall southward transport during March-September whereas, water from the equatorial Indian Ocean is brought in by the northward transport during November-February.

Formatted: Font colour: Black, English (US)

Formatted: Font colour: Black, English (US)

Formatted: Font colour: Black, English (US)

Deleted: 4 Summary

Formatted: Font colour: Black, English (US)

Formatted: Font colour: Black, English (US)

Formatted: Font colour: Black, English (US)

Formatted: Font colour: Black, English (US)

Formatted: Font colour: Black, English (US)

## 970 **6 Summary**

Formatted: Font: Bold

Our high-resolution MITgcm model setup, as demonstrated in this study, provides a comprehensive understanding of volume, freshwater and heat transport dynamics in the North Indian Ocean. The eddy-resolving capability and finer bathymetry in high-resolution modelling improve the overall estimates of exchange along and in the coastal waters. Major patterns observed are that the Alongshore Volume Transport (AVT) is stronger on the eastern coast and is highly seasonal, as compared to the western coast, where it is influenced by large intraseasonal oscillations. Seasonal variations between AVT and Alongshore Freshwater Transport (AFT) along the western coast show a contradiction, while on the eastern coast, they display in-phase behaviour. This depends majorly on the intricate coastal dynamics influenced by salinity variations in AS and BoB. The eddy-resolving setup allowed us to identify eddies and their interaction with coastal currents. These eddies help in exchanging heat and freshwater along the coastal waters. The relation between NHT and net heat flux illustrates the role of coastal currents and equatorial forcing in dissipating heat within the coastal waters. Another important finding is that the Meridional Heat Transport (MHT) is stronger in the AS compared to the BoB. The MHT plays a crucial role in flushing heat out during summer monsoon seasons while bringing equatorial waters in during the winter season. The model setup successfully simulates these vital

climatological patterns, emphasizing the significance of high-resolution modelling in understanding the complex ocean dynamics of this region.

#### Code and data availability

GEBCO bathymetry data has been downloaded from [https://www.gebco.net/data\\_and\\_products/gridded\\_bathymetry\\_data/](https://www.gebco.net/data_and_products/gridded_bathymetry_data/). WOA18 ocean temperature and salinity are obtained from <https://www.ncei.noaa.gov/access/world-ocean-atlas-2018/>. SODA 3.12.2 data can be accessed from [https://www2.atmos.umd.edu/%7Eocean/index\\_files/soda3.12.2\\_mn\\_download\\_b.htm](https://www2.atmos.umd.edu/%7Eocean/index_files/soda3.12.2_mn_download_b.htm). The ERA5 data on a single level is obtained at <https://cds.climate.copernicus.eu/cdsapp#!/dataset/reanalysis-era5-single-levels?tab=form>. ERA5 specific humidity has been obtained from <https://cds.climate.copernicus.eu/cdsapp#!/dataset/reanalysis-era5-pressure-levels?tab=form>. GPM precipitation data can be downloaded from [http://apdrc.soest.hawaii.edu/datadoc/gpm\\_imerg\\_mon.php](http://apdrc.soest.hawaii.edu/datadoc/gpm_imerg_mon.php). MUR SST is downloaded from <https://podaac.jpl.nasa.gov/dataset/MUR-JPL-L4-GLOB-v4.1>. SMAP SSS is downloaded from [https://podaac.jpl.nasa.gov/dataset/SMAP\\_JPL\\_L3\\_SSS\\_CAP\\_MONTHLY\\_V5](https://podaac.jpl.nasa.gov/dataset/SMAP_JPL_L3_SSS_CAP_MONTHLY_V5). GHRSSST can be downloaded from <https://podaac.jpl.nasa.gov/dataset/OSTIA-UKMO-L4-GLOB-v2.0>. SMOS SSS is downloaded from <https://www.seanoe.org/data/00417/52804/>. CORA data is downloaded from <https://www.seanoe.org/data/00351/46219/>. GlobCurrent currents data is available at [https://data.marine.copernicus.eu/product/MULTIOBS\\_GLO\\_PHY\\_REP\\_015\\_004/services](https://data.marine.copernicus.eu/product/MULTIOBS_GLO_PHY_REP_015_004/services). MATLAB and Pyferret software were used for analysis and data visualization. The HYCOM model-simulated data used in this manuscript can be made available at <https://incois.gov.in/portal/datainfo/drform.jsp>.

#### Author Contributions

Conceptualization, K.M. and A.D.R.; methodology, K.M. and A.D.R.; software, K.M.; validation, K.M.; formal analysis, K.M.; investigation, K.M. and S.J.; resources, A.D.R.; data curation, S.J.; writing—original draft preparation, K.M.; writing—review and editing, K.M., A.D.R. and S.J.; visualization, K.M.; supervision, A.D.R. All authors have read and agreed to the published version of the manuscript.

#### Competing interests

The authors declare that they have no conflict of interest.

#### Acknowledgements

The first author acknowledges IIT Delhi for PhD fellowship support.

#### Funding support

This research received no external funding.

**Deleted:** In summary, our high-resolution climatological model setup, as demonstrated in this study, provides a robust foundation for advancing our understanding of volume, freshwater and heat transport dynamics in the North Indian Ocean. The eddy-resolving capability and finer bathymetry in high-resolution modelling improve the overall estimates of exchange along and in the coastal waters. The model accurately captures significant patterns. Major patterns observed are that the Alongshore Volume Transport (AVT) is stronger on the eastern coast and is highly seasonal, as compared to the western coast, where it is influenced by large intraseasonal oscillations. We observe an inverse relationship between AVT and Cross-shore Volume Transport (CVT) on the western coast and a direct relationship on the eastern coast. Seasonal variations between AVT and Alongshore Freshwater Transport along the western coast also present such a contradiction, while on the eastern coast, they display in-phase behaviour. This depends majorly on the intricate coastal dynamics influenced by salinity variations in AS and BoB. Spatially, our analysis indicates a similar seasonal pattern between Net Freshwater Transport and Net Volume Transport, with the freshwater transport values notably lower than the total transport. Out of the NVT, freshwater accounts for the maximum during the JJAS season (6.03 %) primarily confined to the head BoB and northeastern coast of India. This is followed by the ON season (4.85 %) when it flows along the entire eastern coast. The relation between NHT and net heat flux illustrates the role of coastal currents and equatorial forcing in dissipating heat within the coastal waters. Another important finding is that the Meridional Heat Transport (MHT) is stronger in the AS compared to the BoB. The MHT plays a crucial role in flushing heat out during summer monsoon seasons while bringing equatorial waters in during the winter season.

**Deleted:**

**Deleted:** The model setup successfully simulates these vital climatological patterns, emphasizing the significance of high-resolution modelling in understanding the complex ocean dynamics in this region. This work serves as a comprehensive study of model setup intricacies, providing valuable insights into freshwater and heat distribution patterns both at the surface and in the depths of the basin. The established high-resolution physical model, coupled with biogeochemical modules, can be used as a promising tool for further investigations into the biological processes and the transport of nutrients and carbon along the Indian coastal seas. Ultimately, this work contributes significantly to our understanding of oceanic dynamics, paving the way for more nuanced research into the productivity and ecological aspects of this region.

C

## References

- 065 [Akhil, V. P., Vialard, J., Lengaigne, M., Keerthi, M. G., Boutin, J., Vergely, J. L., and Papa, F.: Bay of Bengal Sea surface salinity variability using a decade of improved SMOS re-processing, \*Remote Sens Environ.\* 248, <https://doi.org/10.1016/j.rse.2020.111964>, 2020.](#)
- [Amol, P., Shankar, D., Fernando, V., Mukherjee, A., Aparna, S. G., Fernandes, R., Michael, G. S., Khalap, S. T., Satelkar, N. P., Agarvadekar, Y., Gaonkar, M. G., Tari, A. P., Kankonkar, A., and Vernekar, S. P.: Observed intraseasonal and seasonal variability of the West India Coastal Current on the continental slope, \*Journal of Earth System Science.\* 123, <https://doi.org/10.1007/s12040-014-0449-5>, 2014.](#)
- 070 [Amol, P., Vinayachandran, P. N., Shankar, D., Thushara, V., Vijith, V., Chatterjee, A., and Kankonkar, A.: Effect of freshwater advection and winds on the vertical structure of chlorophyll in the northern Bay of Bengal, \*Deep Sea Res 2 Top Stud Oceanogr.\* 179, <https://doi.org/10.1016/j.dsr2.2019.07.010>, 2020.](#)
- 075 [Anutaliya, A., Send, U., McClean, J. L., Sprintall, J., Rainville, L., Lee, C. M., Jinadasa, S. U. P., Wallcraft, A. J., and Metzger, E. J.: An undercurrent off the east coast of Sri Lanka, \*Ocean Science.\* 13, <https://doi.org/10.5194/os-13-1035-2017>, 2017.](#)
- [Arora, A.: On the role of the Arabian Sea thermal variability in governing rainfall variability over the Western Ghats, \*Journal of Earth System Science.\* 130, <https://doi.org/10.1007/s12040-021-01615-0>, 2021.](#)
- [Behara, A. and Vinayachandran, P. N.: An OGCM study of the impact of rain and river water forcing on the Bay of Bengal, \*J Geophys Res Oceans.\* 121, <https://doi.org/10.1002/2015JC011325>, 2016.](#)
- 080 [Behara, A., Vinayachandran, P. N., and Shankar, D.: Influence of Rainfall Over Eastern Arabian Sea on Its Salinity, \*J Geophys Res Oceans.\* 124, <https://doi.org/10.1029/2019JC014999>, 2019.](#)
- [Benshila, R., Durand, F., Masson, S., Bourdallé-Badie, R., de Boyer Montégut, C., Papa, F., and Madec, G.: The upper Bay of Bengal salinity structure in a high-resolution model, \*Ocean Model \(Oxf\).\* 74, <https://doi.org/10.1016/j.ocemod.2013.12.001>,](#)
- 085 [2014.](#)
- [Bleck, R.: An oceanic general circulation model framed in hybrid isopycnic-Cartesian coordinates, \*Ocean Model \(Oxf\).\* 4, 55–88, \[https://doi.org/10.1016/S1463-5003\\(01\\)00012-9\]\(https://doi.org/10.1016/S1463-5003\(01\)00012-9\), 2002.](#)
- [Bleck, R. and Boudra, D.: Wind-driven spin-up in eddy-resolving ocean models formulated in isopycnic and isobaric coordinates, \*J Geophys Res.\* 91, 7611, <https://doi.org/10.1029/JC091iC06p07611>, 1986.](#)
- 090 [Bleck, R. and Smith, L. T.: A wind-driven isopycnic coordinate model of the north and equatorial Atlantic Ocean: 1. Model development and supporting experiments, \*J Geophys Res.\* 95, 3273, <https://doi.org/10.1029/JC095iC03p03273>, 1990.](#)
- [Boutin Jacqueline, Vergely Jean-Luc, Khvorostyanov Dmitry, and Supply Alexandre: SMOS SSS L3 maps generated by CATDS CEC LOCEAN. debias V8.0. SEANOE., <https://doi.org/https://doi.org/10.17882/52804>, 2023.](#)
- 095 [Bower, A. S. and Furey, H. H.: Mesoscale eddies in the Gulf of Aden and their impact on the spreading of Red Sea Outflow Water, \*Prog Oceanogr.\* 96, <https://doi.org/10.1016/j.pcean.2011.09.003>, 2012.](#)

- Brandt, P., Stramma, L., Schott, F., Fischer, J., Dengler, M., and Quadfasel, D.: Annual Rossby waves in the Arabian Sea from TOPEX/POSEIDON altimeter and in situ data, *Deep Sea Res 2 Top Stud Oceanogr*, 49, [https://doi.org/10.1016/S0967-0645\(01\)00166-7](https://doi.org/10.1016/S0967-0645(01)00166-7), 2002.
- 100 Carton, J. A., Chepurin, G. A., and Chen, L.: SODA3: A New Ocean Climate Reanalysis, *J Clim*, 31, 6967–6983, <https://doi.org/10.1175/JCLI-D-18-0149.1>, 2018.
- Chaudhuri, A., Shankar, D., Aparna, S. G., Amol, P., Fernando, V., Kankonkar, A., Michael, G. S., Satelkar, N. P., Khalap, S. T., Tari, A. P., Gaonkar, M. G., Ghatkar, S., and Khedekar, R. R.: Observed variability of the West India Coastal Current on the continental slope from 2009–2018, *Journal of Earth System Science*, 129, <https://doi.org/10.1007/s12040-019-1322-3>, 2020.
- 105 Chen, G., Wang, D., and Hou, Y.: The features and interannual variability mechanism of mesoscale eddies in the Bay of Bengal, *Cont Shelf Res*, 47, 178–185, <https://doi.org/10.1016/j.csr.2012.07.011>, 2012.
- Cheng, X., McCreary, J. P., Qiu, B., Qi, Y., Du, Y., and Chen, X.: Dynamics of Eddy Generation in the Central Bay of Bengal, *J Geophys Res Oceans*, 123, <https://doi.org/10.1029/2018JC014100>, 2018.
- 110 Chin, T. M., Vazquez-Cuervo, J., and Armstrong, E. M.: A multi-scale high-resolution analysis of global sea surface temperature, *Remote Sens Environ*, 200, <https://doi.org/10.1016/j.rse.2017.07.029>, 2017.
- Chirokova, G. and Webster, P. J.: Interannual variability of Indian Ocean heat transport, *J Clim*, 19, <https://doi.org/10.1175/JCLI3676.1>, 2006.
- Cullen, K. E. and Shroyer, E. L.: Seasonality and interannual variability of the Sri Lanka dome, *Deep Sea Res 2 Top Stud Oceanogr*, 168, <https://doi.org/10.1016/j.dsr2.2019.104642>, 2019.
- 115 Dai, A. and Trenberth, K. E.: Estimates of freshwater discharge from continents: Latitudinal and seasonal variations, *J Hydrometeorol*, 3, [https://doi.org/10.1175/1525-7541\(2002\)003<0660:EOFDfC>2.0.CO;2](https://doi.org/10.1175/1525-7541(2002)003<0660:EOFDfC>2.0.CO;2), 2002.
- Das, U., Vinayachandran, P. N., and Behara, A.: Formation of the southern Bay of Bengal cold pool, *Clim Dyn*, 47, <https://doi.org/10.1007/s00382-015-2947-9>, 2016.
- 120 Ding, R., Xuan, J., Zhang, T., Zhou, L., Zhou, F., Meng, Q., and Kang, I. S.: Eddy-induced heat transport in the South China sea, *J Phys Oceanogr*, 51, <https://doi.org/10.1175/JPO-D-20-0206.1>, 2021.
- Donlon, C. J., Martin, M., Stark, J., Roberts-Jones, J., Fiedler, E., and Wimmer, W.: The Operational Sea Surface Temperature and Sea Ice Analysis (OSTIA) system, *Remote Sens Environ*, 116, <https://doi.org/10.1016/j.rse.2010.10.017>, 2012.
- Durand, F., Shankar, D., Birol, F., and Shenoi, S. S. C.: Spatiotemporal structure of the East India Coastal Current from satellite altimetry, *J Geophys Res Oceans*, 114, <https://doi.org/10.1029/2008JC004807>, 2009.
- 125 Forget, G., Campin, J. M., Heimbach, P., Hill, C. N., Ponte, R. M., and Wunsch, C.: ECCO version 4: An integrated framework for non-linear inverse modeling and global ocean state estimation, *Geosci Model Dev*, 8, <https://doi.org/10.5194/gmd-8-3071-2015>, 2015.
- Gadgil, S.: The Indian Monsoon and Its Variability, *Annu Rev Earth Planet Sci*, 31, 429–467, <https://doi.org/10.1146/annurev.earth.31.100901.141251>, 2003.
- 130

- Gangopadhyay, A., Bharat Raj, G. N., Chaudhuri, A. H., Babu, M. T., and Sengupta, D.: On the nature of meandering of the springtime western boundary current in the Bay of Bengal, *Geophys Res Lett*, 40, <https://doi.org/10.1002/grl.50412>, 2013.
- Gartemicht, U. and Schott, F.: Heat fluxes of the Indian Ocean from a global eddy-resolving model, *J Geophys Res Oceans*, 102, <https://doi.org/10.1029/97JC01585>, 1997.
- 135 Gopalakrishnan, G., Subramanian, A. C., Miller, A. J., Seo, H., and Sengupta, D.: Estimation and prediction of the upper ocean circulation in the Bay of Bengal, *Deep Sea Research Part II: Topical Studies in Oceanography*, 172, 104721, <https://doi.org/10.1016/j.dsr2.2019.104721>, 2020.
- Hersbach, H., Bell, B., Berrisford, P., Hirahara, S., Horányi, A., Muñoz-Sabater, J., Nicolas, J., Peubey, C., Radu, R., Schepers, D., Simmons, A., Soci, C., Abdalla, S., Abellan, X., Balsamo, G., Bechtold, P., Biavati, G., Bidlot, J., Bonavita, M., Chiara, G., Dahlgren, P., Dee, D., Diamantakis, M., Dragani, R., Flemming, J., Forbes, R., Fuentes, M., Geer, A., Haimberger, L., Healy, S., Hogan, R. J., Hólm, E., Janisková, M., Keeley, S., Laloyaux, P., Lopez, P., Lupu, C., Radnoti, G., Rosnay, P., Rozum, I., Vamborg, F., Villaume, S., and Thépaut, J.: The ERA5 global reanalysis, *Quarterly Journal of the Royal Meteorological Society*, 146, 1999–2049, <https://doi.org/10.1002/qj.3803>, 2020.
- 140 Hormann, V., Centurioni, L. R., and Gordon, A. L.: Freshwater export pathways from the Bay of Bengal, *Deep Sea Res 2 Top Stud Oceanogr*, 168, <https://doi.org/10.1016/j.dsr2.2019.104645>, 2019.
- Huffman, G. J., Bolvin, D. T., Braithwaite, D., Hsu, K., Joyce, R., Kidd, C., Nelkin, E. J., and Xie, P.: NASA Global Precipitation Measurement (GPM) Integrated Multi-satellitE Retrievals for GPM (IMERG), Algorithm Theoretical Basis Document (ATBD) Version 4.5, 2015.
- 145 Iskandarani, M., Levin, J. C., Choi, B.-J., and Haidvogel, D. B.: Comparison of advection schemes for high-order h–p finite element and finite volume methods, *Ocean Model (Oxf)*, 10, 233–252, <https://doi.org/10.1016/j.ocemod.2004.09.005>, 2005.
- 150 Jana, S., Gangopadhyay, A., and Chakraborty, A.: Impact of seasonal river input on the Bay of Bengal simulation, *Cont Shelf Res*, 104, 45–62, <https://doi.org/10.1016/j.csr.2015.05.001>, 2015.
- Jana, S., Gangopadhyay, A., Lermusiaux, P. F. J., Chakraborty, A., Sil, S., and Haley, P. J.: Sensitivity of the Bay of Bengal upper ocean to different winds and river input conditions, *Journal of Marine Systems*, 187, 206–222, <https://doi.org/10.1016/j.jmarsys.2018.08.001>, 2018.
- 155 Kara, A. B., Rochford, P. A., and Hurlburt, H. E.: An optimal definition for ocean mixed layer depth, *J Geophys Res Oceans*, 105, 16803–16821, <https://doi.org/10.1029/2000JC900072>, 2000.
- Kara, A. B., Hurlburt, H. E., and Wallcraft, A. J.: Stability-Dependent Exchange Coefficients for Air–Sea Fluxes\*, *J Atmos Ocean Technol*, 22, 1080–1094, <https://doi.org/10.1175/JTECH1747.1>, 2005.
- 160 Kumar, S. P. and Prasad, T. G.: Winter cooling in the northern Arabian Sea, *Curr Sci*, 71, 834–841, 1996.
- Kumar, S. P. and Prasad, T. G.: Formation and spreading of Arabian Sea high-salinity water mass, *J Geophys Res Oceans*, 104, <https://doi.org/10.1029/1998jc900022>, 1999.
- Kurien, P., Ikeda, M., and Valsala, V. K.: Mesoscale variability along the east coast of India in spring as revealed from satellite data and OGCM simulations, *J Oceanogr*, 66, <https://doi.org/10.1007/s10872-010-0024-x>, 2010.



- 165 [Kushwaha, V. K., Kumar, S. P., Feba, F., and Ashok, K.: Findlater jet induced summer monsoon memory in the Arabian Sea, \*Sci Rep\*, 12, <https://doi.org/10.1038/s41598-022-17025-1>, 2022.](#)  
[Large, W. G., McWilliams, J. C., and Doney, S. C.: Oceanic vertical mixing: A review and a model with a nonlocal boundary layer parameterization, \*Reviews of Geophysics\*, 32, 363, <https://doi.org/10.1029/94RG01872>, 1994.](#)  
[Lee, T. and Marotzke, J.: Seasonal cycles of meridional overturning and heat transport of the Indian Ocean, \*J Phys Oceanogr\*, 28, \[https://doi.org/10.1175/1520-0485\\(1998\\)028<0923:SCOMOA>2.0.CO;2\]\(https://doi.org/10.1175/1520-0485\(1998\)028<0923:SCOMOA>2.0.CO;2\), 1998.](#)
- 170 [Lin, X., Qiu, Y., and Sun, D.: Thermohaline structures and heat/freshwater transports of mesoscale eddies in the Bay of Bengal observed by Argo and satellite data, \*Remote Sens \(Basel\)\*, 11, <https://doi.org/10.3390/rs11242989>, 2019.](#)  
[Locarnini, R. A., Mishonov, A. V., Baranova, O. K., Boyer, T. P., Zweng, M. M., Garcia, H. E., Reagan, J. R., Seidov, D., Weathers, K. W., Paver, C. R., and Smolyar, I. V.: \*World Ocean Atlas 2018, Volume 1: Temperature\*, NOAA Atlas NESDIS 81, 1, 2018.](#)
- 175 [Luis, A. J. and Kawamura, H.: Wintertime wind forcing and sea surface cooling near the South India tip observed using NSCAT and AVHRR, \*Remote Sens Environ\*, 73, \[https://doi.org/10.1016/S0034-4257\\(00\\)00081-X\]\(https://doi.org/10.1016/S0034-4257\(00\)00081-X\), 2000.](#)  
[Mahadevan, A.: The Impact of Submesoscale Physics on Primary Productivity of Plankton, \*Ann Rev Mar Sci\*, 8, <https://doi.org/10.1146/annurev-marine-010814-015912>, 2016.](#)
- 180 [Mahadevan, A., Paluszkiwicz, T., Ravichandran, M., Sengupta, D., and Tandon, A.: Introduction to the Special Issue on the Bay of Bengal: From Monsoons to Mixing, \*Oceanography\*, 29, <https://doi.org/10.5670/oceanog.2016.34>, 2016.](#)  
[Mallick, S. K., Agarwal, N., Sharma, R., Prasad, K. V. S. R., and Ramakrishna, S. S. V. S.: Thermodynamic Response of a High-Resolution Tropical Indian Ocean Model to TOGA COARE Bulk Air–Sea Flux Parameterization: Case Study for the Bay of Bengal \(BoB\), \*Pure Appl Geophys\*, 177, 4025–4044, <https://doi.org/10.1007/s00024-020-02448-6>, 2020.](#)
- 185 [Marshall, J., Adcroft, A., Hill, C., Perelman, L., and Heisey, C.: A finite-volume, incompressible Navier Stokes model for studies of the ocean on parallel computers, \*J Geophys Res Oceans\*, 102, 5753–5766, <https://doi.org/10.1029/96JC02775>, 1997.](#)  
[Mathew, S., Natesan, U., Latha, G., and Venkatesan, R.: Dynamics behind warming of the southeastern Arabian Sea and its interruption based on in situ measurements, \*Ocean Dyn\*, 68, <https://doi.org/10.1007/s10236-018-1130-3>, 2018.](#)  
[Mazloff, M. R., Heimbach, P., and Wunsch, C.: An eddy-permitting Southern Ocean state estimate, \*J Phys Oceanogr\*, 40, <https://doi.org/10.1175/2009JPO4236.1>, 2010.](#)
- 190 [McDougall, T. J., Jackett, D. R., Wright, D. G., and Feistel, R.: Accurate and computationally efficient algorithms for potential temperature and density of seawater, \*J Atmos Ocean Technol\*, 20, \[https://doi.org/10.1175/1520-0426\\(2003\\)20<730:AACEAF>2.0.CO;2\]\(https://doi.org/10.1175/1520-0426\(2003\)20<730:AACEAF>2.0.CO;2\), 2003.](#)  
[McPhaden, M. J., Meyers, G., Ando, K., Masumoto, Y., Murty, V. S. N., Ravichandran, M., Syamsudin, F., Vialard, J., Yu, L., and Yu, W.: RAMA: The research moored array for African-Asian-Australian monsoon analysis and prediction, \*Bull Am Meteorol Soc\*, 90, <https://doi.org/10.1175/2008BAMS2608.1>, 2009.](#)
- 195 [Menemenlis, D., Fukumori, I., and Lee, T.: Using Green's Functions to Calibrate an Ocean General Circulation Model, \*Mon Weather Rev\*, 133, 1224–1240, <https://doi.org/10.1175/MWR2912.1>, 2005.](#)

- 200 [Mukherjee, A., Shankar, D., Fernando, V., Amol, P., Aparna, S. G., Fernandes, R., Michael, G. S., Khalap, S. T., Satelkar, N. P., Agarvadekar, Y., Gaonkar, M. G., Tari, A. P., Kankonkar, A., and Vernekar, S.: Observed seasonal and intraseasonal variability of the east india coastal current on the continental slope, \*Journal of Earth System Science\*, 123, <https://doi.org/10.1007/s12040-014-0471-7>, 2014.](#)
- 205 [Mukhopadhyay, S., Shankar, D., Aparna, S. G., Mukherjee, A., Fernando, V., Kankonkar, A., Khalap, S., Satelkar, N. P., Gaonkar, M. G., Tari, A. P., Khedekar, R. R., and Ghatkar, S.: Observed variability of the East India Coastal Current on the continental slope during 2009–2018, \*Journal of Earth System Science\*, 129, <https://doi.org/10.1007/s12040-020-1346-8>, 2020.](#)
- [Murty, V. S. N., Sarma, Y. V. B., Rao, D. P., and Murty, C. S.: Water characteristics, mixing and circulation in the Bay of Bengal during southwest monsoon, \*J Mar Res\*, 50, <https://doi.org/10.1357/002224092784797700>, 1992.](#)
- 210 [Papa, F., Bala, S. K., Pandey, R. K., Durand, F., Gopalakrishna, V. V., Rahman, A., and Rossow, W. B.: Ganga-Brahmaputra river discharge from Jason-2 radar altimetry: An update to the long-term satellite-derived estimates of continental freshwater forcing flux into the Bay of Bengal, \*J Geophys Res Oceans\*, 117, <https://doi.org/10.1029/2012JC008158>, 2012.](#)
- [Parampil, S. R., Gera, A., Ravichandran, M., and Sengupta, D.: Intraseasonal response of mixed layer temperature and salinity in the Bay of Bengal to heat and freshwater flux, \*J Geophys Res Oceans\*, 115, <https://doi.org/10.1029/2009JC005790>, 2010.](#)
- [Pinker, R. T., Bentamy, A., Grodsky, S. A., and Chen, W.: Annual and seasonal variability of net heat flux in the Northern Indian Ocean, \*Int J Remote Sens\*, 41, <https://doi.org/10.1080/01431161.2020.1746858>, 2020.](#)
- 215 [Pratik, K., Parekh, A., Karmakar, A., Chowdary, J. S., and Gnanaseelan, C.: Recent changes in the summer monsoon circulation and their impact on dynamics and thermodynamics of the Arabian Sea, \*Theor Appl Climatol\*, 136, <https://doi.org/10.1007/s00704-018-2493-6>, 2019.](#)
- [Rainville, L., Lee, C. M., Arulananthan, K., Jinadasa, S. U. P., Fernando, H. J. S., Priyadarshani, W. N. C., and Wijesekera, H.: Water Mass Exchanges between the Bay of Bengal and Arabian Sea from Multiyear Sampling with Autonomous Gliders, \*J Phys Oceanogr\*, 52, <https://doi.org/10.1175/JPO-D-21-0279.1>, 2022.](#)
- 220 [Rao, R. R., Girish Kumar, M. S., Ravichandran, M., Rao, A. R., Gopalakrishna, V. V., and Thadathil, P.: Interannual variability of Kelvin wave propagation in the wave guides of the equatorial Indian Ocean, the coastal Bay of Bengal and the southeastern Arabian Sea during 1993–2006, \*Deep Sea Research Part I: Oceanographic Research Papers\*, 57, 1–13, <https://doi.org/10.1016/j.dsr.2009.10.008>, 2010.](#)
- 225 [Rio, M. H., Mulet, S., and Picot, N.: Beyond GOCE for the ocean circulation estimate: Synergetic use of altimetry, gravimetry, and in situ data provides new insight into geostrophic and Ekman currents, \*Geophys Res Lett\*, 41, <https://doi.org/10.1002/2014GL061773>, 2014.](#)
- [Schott, F., Reppin, J., Fischer, J., and Quadfasel, D.: Currents and transports of the Monsoon Current south of Sri Lanka, \*J Geophys Res\*, 99, <https://doi.org/10.1029/94jc02216>, 1994.](#)
- 230 [Schott, F. A. and McCreary, J. P.: The monsoon circulation of the Indian Ocean, \[https://doi.org/10.1016/S0079-6611\\(01\\)00083-0\]\(https://doi.org/10.1016/S0079-6611\(01\)00083-0\), 2001.](#)

- Sen, R., Pandey, S., Dandapat, S., Francis, P. A., and Chakraborty, A.: A numerical study on seasonal transport variability of the North Indian Ocean boundary currents using Regional Ocean Modeling System (ROMS), *Journal of Operational Oceanography*, 15, 32–51, <https://doi.org/10.1080/1755876X.2020.1846266>, 2022.
- 235 Shah, P., Sajeev, R., and Gopika, N.: Study of upwelling along the west coast of India-A climatological approach, *J Coast Res*, 31, <https://doi.org/10.2112/JCOASTRES-D-13-00094.1>, 2015.
- Shankar, D. and Shetye, S. R.: On the dynamics of the Lakshadweep high and low in the southeastern Arabian Sea, *J Geophys Res Oceans*, 102, <https://doi.org/10.1029/97JC00465>, 1997.
- Shankar, D., Vinayachandran, P. N., and Unnikrishnan, A. S.: The monsoon currents in the north Indian Ocean, [https://doi.org/10.1016/S0079-6611\(02\)00024-1](https://doi.org/10.1016/S0079-6611(02)00024-1), 2002.
- 240 Shenoi, S. S. C.: Differences in heat budgets of the near-surface Arabian Sea and Bay of Bengal: Implications for the summer monsoon, *J Geophys Res*, 107, <https://doi.org/10.1029/2000jc000679>, 2002.
- Shetye, S. R. and Gouveia, A. D.: Coastal circulation in the North Indian Ocean: Coastal segment (14, SW), in: *The Sea: Ideas and Observations in the Study of the Seas*, vol. 11, John Wiley and Sons, New York, USA, 1998.
- 245 Shetye, S. R., Gouveia, A. D., Shenoi, S. S. C., Michael, G. S., Sundar, D., Almeida, A. M., and Santanam, K.: The coastal current off western India during the northeast monsoon, *Deep Sea Research Part A, Oceanographic Research Papers*, 38, [https://doi.org/10.1016/0198-0149\(91\)90087-V](https://doi.org/10.1016/0198-0149(91)90087-V), 1991a.
- Shetye, S. R., Shenoi, S. S. C., Gouveia, A. D., Michael, G. S., Sundar, D., and Nampoothiri, G.: Wind-driven coastal upwelling along the western boundary of the Bay of Bengal during the southwest monsoon, *Cont Shelf Res*, 11, [https://doi.org/10.1016/0278-4343\(91\)90042-5](https://doi.org/10.1016/0278-4343(91)90042-5), 1991b.
- 250 Shetye, S. R., Gouveia, A. D., Shankar, D., Shenoi, S. S. C., Vinayachandran, P. N., Sundar, D., Michael, G. S., and Nampoothiri, G.: Hydrography and circulation in the western Bay of Bengal during the northeast monsoon, *J Geophys Res Oceans*, 101, <https://doi.org/10.1029/95JC03307>, 1996.
- Shetye, S. R., Suresh, I., Shankar, D., Sundar, D., Jayakumar, S., Mehra, P., Prabhudesai, R. G., and Pednekar, P. S.: 255 Observational evidence for remote forcing of the West India Coastal Current, *J Geophys Res Oceans*, 113, <https://doi.org/10.1029/2008JC004874>, 2008.
- Shi, W., Morrison, J. M., and Bryden, H. L.: Water, heat and freshwater flux out of the northern Indian Ocean in September-October 1995, *Deep Sea Res 2 Top Stud Oceanogr*, 49, [https://doi.org/10.1016/S0967-0645\(01\)00154-0](https://doi.org/10.1016/S0967-0645(01)00154-0), 2002.
- 260 Srivastava, A., Dwivedi, S., and Mishra, A. K.: Intercomparison of High-Resolution Bay of Bengal Circulation Models Forced with Different Winds, *Marine Geodesy*, 39, <https://doi.org/10.1080/01490419.2016.1173606>, 2016.
- Srivastava, A., Rao, S. A., and Ghosh, S.: Impact of Riverine Fresh Water on Indian Summer Monsoon: Coupling a Runoff Routing Model to a Global Seasonal Forecast Model, *Frontiers in Climate*, 4, <https://doi.org/10.3389/fclim.2022.902586>, 2022.
- Stammer, D., Wunsch, C., Giering, R., Eckert, C., Heimbach, P., Marotzke, J., Adcroft, A., Hill, C. N., and Marshall, J.: Volume, heat, and freshwater transports of the global ocean circulation 1993-2000, estimated from a general circulation model

265 [constrained by World Ocean Circulation Experiment \(WOCE\) data, \*J Geophys Res Oceans\*, 108, <https://doi.org/10.1029/2001jc001115>, 2003.](#)

[Swapna, P., Jyoti, J., Krishnan, R., Sandeep, N., and Griffies, S. M.: Multidecadal Weakening of Indian Summer Monsoon Circulation Induces an Increasing Northern Indian Ocean Sea Level, \*Geophys Res Lett\*, 44, <https://doi.org/10.1002/2017GL074706>, 2017.](#)

270 [Szekely, T., Gourrion, J., Pouliquen, S., and Reverdin, G.: The CORA 5.2 dataset for global in situ temperature and salinity measurements: Data description and validation, \*Ocean Science\*, 15, <https://doi.org/10.5194/os-15-1601-2019>, 2019.](#)

[Tang, W., Fore, A., Yueh, S., Lee, T., Hayashi, A., Sanchez-Franks, A., Martinez, J., King, B., and Baranowski, D.: Validating SMAP SSS with in situ measurements, \*Remote Sens Environ\*, 200, <https://doi.org/10.1016/j.rse.2017.08.021>, 2017.](#)

[Vinayachandran, P. N., Masumoto, Y., Mikawa, T., and Yamagata, T.: Intrusion of the southwest monsoon current into the Bay of Bengal, \*J Geophys Res Oceans\*, 104, <https://doi.org/10.1029/1999jc900035>, 1999.](#)

275 [Vinayachandran, P. N., Shankar, D., Vernekar, S., Sandeep, K. K., Amol, P., Neema, C. P., and Chatterjee, A.: A summer monsoon pump to keep the Bay of Bengal salty, \*Geophys Res Lett\*, 40, 1777–1782, <https://doi.org/10.1002/grl.50274>, 2013.](#)

[Vinayachandran, P. N., Das, U., Shankar, D., Jahfer, S., Behara, A., Nair, T. M. B., and Bhat, G. S.: Maintenance of the southern Bay of Bengal cold pool, \*Deep Sea Res 2 Top Stud Oceanogr\*, 179, <https://doi.org/10.1016/j.dsr2.2019.07.012>, 2020.](#)

280 [Wacongne, S. and Pacanowski, R.: Seasonal heat transport in a primitive equations model of the tropical Indian ocean, \*J Phys Oceanogr\*, 26, \[https://doi.org/10.1175/1520-0485\\(1996\\)026<2666:SHTIAP>2.0.CO;2\]\(https://doi.org/10.1175/1520-0485\(1996\)026<2666:SHTIAP>2.0.CO;2\), 1996.](#)

[Weatherall, P., Tozer, B., Arndt, J. E., Bazhenova, E., Bringsenspar, C., Castro, C., Dorschel, B., Ferrini, V., Hehemann, L., and Jakobsson, M.: The gebco 2020 grid—A continuous terrain model of the global oceans and land, \*British Oceanographic Data Centre, National Oceanography Centre, NERC, UK\*. DOI: <http://dx.doi.org/10.5285/a29c5465-b138-234d-e053-6c86abc040b9>, 2020.](#)

285 [Zalesak, S. T.: Fully multidimensional flux-corrected transport algorithms for fluids, \*J Comput Phys\*, 31, 335–362, \[https://doi.org/10.1016/0021-9991\\(79\\)90051-2\]\(https://doi.org/10.1016/0021-9991\(79\)90051-2\), 1979.](#)

[Zhang, Y. and Du, Y.: Seasonal variability of salinity budget and water exchange in the northern Indian Ocean from HYCOM assimilation, \*Chinese Journal of Oceanology and Limnology\*, 30, <https://doi.org/10.1007/s00343-012-1284-7>, 2012.](#)

290 [Zhang, Y., Du, Y., Jayarathna, W. N. D. S., Qiwei, S., Zhang, Y., Fengchao, Y., and Feng, M.: A prolonged high-salinity event in the northern Arabian sea during 2014–17, \*J Phys Oceanogr\*, 50, <https://doi.org/10.1175/JPO-D-19-0220.1>, 2020.](#)

[Zweng, M. M., Reagan, J. R., Seidov, D., Boyer, T. P., Antonov, J. I., Locarnini, R. A., Garcia, H. E., Mishonov, A. V., Baranova, O. K., Weathers, K. W., Paver, C. R., and Smolyar, I. V.: World Ocean Atlas 2018 Volume 2: Salinity, NOAA Atlas NESDIS, 82, 2019.](#)

**Deleted:** [Amol, P., Shankar, D., Fernando, V., Mukherjee, A., Aparna, S. G., Fernandes, R., Michael, G. S., Khalap, S. T., Satelkar, N. P., Agarvadekar, Y., Gaonkar, M. G., Tari, A. P., Kankonkar, A., and Vernekar, S. P.: Observed intraseasonal and seasonal variability of the West India Coastal Current on the continental slope, \*Journal of Earth System Science\*, 123, <https://doi.org/10.1007/s12040-014-0449-5>, 2014.](#)

[Amol, P., Vinayachandran, P. N., Shankar, D., Thushara, V., Vijith, V., Chatterjee, A., and Kankonkar, A.: Effect of freshwater advection and winds on the vertical structure of chlorophyll in the northern Bay of Bengal, \*Deep Sea Res 2 Top Stud Oceanogr\*, 179, <https://doi.org/10.1016/j.dsr2.2019.07.010>, 2020.](#)

[Anutaliya, A., Send, U., McClean, J. L., Sprintall, J., Rainville, L., Lee, C. M., Jinadasa, S. U. P., Wallcraft, A. J., and Metzger, E. J.: An undercurrent off the east coast of Sri Lanka, \*Ocean Science\*, 13, <https://doi.org/10.5194/os-13-1035-2017>, 2017.](#)

[Arora, A.: On the role of the Arabian Sea thermal variability in governing rainfall variability over the Western Ghats, \*Journal of Earth System Science\*, 130, <https://doi.org/10.1007/s12040-021-01615-0>, 2021.](#)

[Behara, A. and Vinayachandran, P. N.: An OGCM study of the impact of rain and river water forcing on the Bay of Bengal, \*J Geophys Res Oceans\*, 121, <https://doi.org/10.1002/2015JC011325>, 2016.](#)

[Behara, A., Vinayachandran, P. N., and Shankar, D.: Influence of Rainfall Over Eastern Arabian Sea on Its Salinity, \*J Geophys Res Oceans\*, 124, <https://doi.org/10.1029/2019JC014999>, 2019.](#)

[Benshila, R., Durand, F., Masson, S., Bourdallé-Badie, R., de Boyer Montégut, C., Papa, F., and Madec, G.: The upper Bay of Bengal salinity structure in a high-resolution model, \*Ocean Model \(OxJ\)\*, 74, <https://doi.org/10.1016/j.ocemod.2013.12.001>, 2014.](#)

[Bleck, R.: An oceanic general circulation model framed in hybrid isopycnic-Cartesian coordinates, \*Ocean Model \(OxJ\)\*, 4, 55–88, \[https://doi.org/10.1016/S1463-5003\\(01\\)00012-9\]\(https://doi.org/10.1016/S1463-5003\(01\)00012-9\), 2002.](#)

[Bleck, R. and Boudra, D.: Wind-driven spin-up in eddy-resolving ocean models formulated in isopycnic and isobaric coordinates, \*J Geophys Res\*, 91, 7611, <https://doi.org/10.1029/JC091iC06p07611>, 1986.](#)

[Bleck, R. and Smith, L. T.: A wind-driven isopycnic coordinate model of the north and equatorial Atlantic Ocean: I. Model development and supporting experiments, \*J Geophys Res\*, 95, 3273, <https://doi.org/10.1029/JC095iC03p03273>, 1990.](#)

[Boutin Jacqueline, Vergely Jean-Luc, Khvorostyanov Dmitry, and Supply Alexandre: SMOS SSS L3 maps generated by CATDS CEC LOCEAN, debias V8.0. SEANOE, <https://doi.org/https://doi.org/10.17882/52804>, 2023.](#)

[Bower, A. S. and Furey, H. H.: Mesoscale eddies in the Gulf of Aden and their impact on the spreading of Red Sea Outflow Water, \*Prog Oceanogr\*, 96, <https://doi.org/10.1016/j.pocean.2011.09.003>, 2012.](#)

[Brandt, P., Stramma, L., Schott, F., Fischer, J., Dengler, M., and Quadfasel, D.: Annual Rossby waves in the Arabian Sea from TOPEX/POSEIDON altimeter and in situ data, \*Deep Sea Res 2 Top Stud Oceanogr\*, 49, \[https://doi.org/10.1016/S0967-0645\\(01\\)00166-7\]\(https://doi.org/10.1016/S0967-0645\(01\)00166-7\), 2002.](#)

[Carton, J. A., Chepurin, G. A., and Chen, L.: SODA3: A New Ocean Climate Reanalysis, \*J Clim\*, 31, 6967–6983, <https://doi.org/10.1175/JCLI-D-18-0149.1>, 2018.](#)

[Chaudhuri, A., Shankar, D., Aparna, S. G., Amol, P., Fernando, V., Kankonkar, A., Michael, G. S., Satelkar, N. P., Khalap, S. T., Tari, A. P., Gaonkar, M. G., Ghatkar, S., and Khedekar, R. R.: Observed variability of the West India Coastal Current on the continental slope from 2009–2018, \*Journal of Earth System Science\*, 129, <https://doi.org/10.1007/s12040-019-1322-3>, 2020.](#)

**Page 8: [1] Deleted      Kunal Ajit Madkaiker      20/05/2024 03:27:00**

**Page 8: [1] Deleted      Kunal Ajit Madkaiker      20/05/2024 03:27:00**

**Page 8: [1] Deleted      Kunal Ajit Madkaiker      20/05/2024 03:27:00**

**Page 8: [1] Deleted      Kunal Ajit Madkaiker      20/05/2024 03:27:00**

**Page 8: [2] Deleted      Kunal Ajit Madkaiker      20/05/2024 03:27:00**

**Page 8: [2] Deleted      Kunal Ajit Madkaiker      20/05/2024 03:27:00**

**Page 8: [3] Deleted      Kunal Ajit Madkaiker      20/05/2024 06:42:00**

**Page 8: [3] Deleted      Kunal Ajit Madkaiker      20/05/2024 06:42:00**

**Page 8: [4] Deleted      Kunal Ajit Madkaiker      17/06/2024 12:55:00**

**Page 8: [4] Deleted      Kunal Ajit Madkaiker      17/06/2024 12:55:00**

**Page 8: [4] Deleted      Kunal Ajit Madkaiker      17/06/2024 12:55:00**

**Page 8: [4] Deleted      Kunal Ajit Madkaiker      17/06/2024 12:55:00**

**Page 8: [4] Deleted      Kunal Ajit Madkaiker      17/06/2024 12:55:00**

**Page 8: [4] Deleted      Kunal Ajit Madkaiker      17/06/2024 12:55:00**

**Page 9: [5] Deleted      Kunal Ajit Madkaiker      20/05/2024 03:45:00**

**Page 9: [5] Deleted      Kunal Ajit Madkaiker      20/05/2024 03:45:00**

**Page 9: [5] Deleted      Kunal Ajit Madkaiker      20/05/2024 03:45:00**

**Page 9: [5] Deleted      Kunal Ajit Madkaiker      20/05/2024 03:45:00**

**Page 9: [5] Deleted      Kunal Ajit Madkaiker      20/05/2024 03:45:00**

**Page 9: [7] Deleted      Kunal Ajit Madkaiker      20/05/2024 06:55:00**



**Page 9: [7] Deleted      Kunal Ajit Madkaiker      20/05/2024 06:55:00**



**Page 9: [7] Deleted      Kunal Ajit Madkaiker      20/05/2024 06:55:00**



**Page 9: [7] Deleted      Kunal Ajit Madkaiker      20/05/2024 06:55:00**



**Page 10: [8] Deleted      Kunal Ajit Madkaiker      20/05/2024 03:49:00**



**Page 10: [8] Deleted      Kunal Ajit Madkaiker      20/05/2024 03:49:00**



**Page 10: [8] Deleted      Kunal Ajit Madkaiker      20/05/2024 03:49:00**



**Page 10: [8] Deleted      Kunal Ajit Madkaiker      20/05/2024 03:49:00**



**Page 10: [8] Deleted      Kunal Ajit Madkaiker      20/05/2024 03:49:00**



**Page 10: [9] Deleted      Kunal Ajit Madkaiker      20/05/2024 03:51:00**



**Page 10: [9] Deleted      Kunal Ajit Madkaiker      20/05/2024 03:51:00**



**Page 10: [10] Deleted      Kunal Ajit Madkaiker      20/05/2024 06:58:00**



**Page 10: [10] Deleted      Kunal Ajit Madkaiker      20/05/2024 06:58:00**



**Page 10: [11] Deleted      Kunal Ajit Madkaiker      20/05/2024 07:03:00**



**Page 10: [11] Deleted      Kunal Ajit Madkaiker      20/05/2024 07:03:00**



**Page 10: [12] Deleted      Kunal Ajit Madkaiker      20/05/2024 07:04:00**

