

**Broken Terrains v. 1.0: A supervised detection of fault-related lineaments on triangulated models of subsurface interfaces with preferred orientation-geological terrains**

Michał P. Michalak<sup>1</sup>, Christian Gerhards<sup>2</sup>, Peter Menzel<sup>2</sup>



<sup>1</sup>Faculty of Geology, Geophysics and Environmental Protection, AGH University of Science and Technology, Mickiewicza 30, 30-059 Cracow, Poland, ORCID: <https://orcid.org/0000-0002-1376-235X>

<sup>2</sup>Institute of Geophysics and Geoinformatics, TU Bergakademie Freiberg, Gustav-Zeuner-Straße 12, 09599 Freiberg, Germany

*Correspondence to:* Michał P. Michalak ([michalm@agh.edu.pl](mailto:michalm@agh.edu.pl))

**Abstract.**

The study presents a novel approach for fault detection on geological terrains using supervised learning algorithm and careful input variables (features) selection. Synthetic faulted terrains are generated using Delaunay triangulation via the Computational Geometry Algorithms Library (CGAL) allowing for adjustments of parameters. We introduce 24 variablefeatures, including local geometric features and neighbourhood analysis, for classification. Support Vector Machine (SVM) is employed as the classification algorithm, achieving high precision and recall rates for fault-related observations. Application to real borehole data demonstrates the effectiveness of the method in detecting fault orientations, the challenges remain with respect to distinguishing faults with opposite dip directions. The study highlights the need to address 3D fault zone complexities and their identification. Despite limitations, the proposed supervised approach offers significant advancement over clustering-based methods, showing promise in detecting faults of various orientations. Future research directions include exploring more complex geological scenarios and refining fault detection methodologies.




~~This study presents a novel method for fault detection on geological terrains. Using synthetic geometric features of synthetic triangulated models of geological terrains with preferred orientation, we applied machine learning to detect faults, classify terrain shape and nearby features.~~ Testing on real borehole data validated its effectiveness across various fault orientations. The supervised approach represents a significant improvement over older methods that relied on simpler clustering techniques which were capable of identifying less orientations of faults.

## 1 Introduction

Geological engineers and structural geologists aim to identify lineaments or faults on geological terrains. However, current methods are typically tailored for seismic data rather than terrains (An et al., 2021; Kaur et al., 2023). Additionally, supervised methods for fault detection can encounter challenges related to subjectivity, ambiguity, or time-consuming processes such as manual labeling of training data (Mattéo et al., 2021; Vega-Ramirez et al., 2021).

In this study, we focus on detecting faults on triangulated models of subsurface geological interfaces with preferred orientation (Fig. 1). The interfaces can be thought of as boundaries between conformal (sub-parallel) geological units often investigated in geological modelling (de la Varga et al., 2018). Data used in our study come from an irregular network of boreholes that document the transition between geological units. Consequently, the fault-related deviations from the preferred orientation are investigated using a supervised framework. In this approach, faces of the triangulation are observations described by features such as their orientation and geometric relationships with neighbours.



**Figure 1.** The supervised fault detection method developed in this study is designed for terrains with preferred orientation. An example of such a terrain can be a portion of the boundary between folded strata. The model with two folded surface and one erosive surface presented in this figure was generated using GemPy and GemGis software (Jüstel et al., 2022, 2023; de la Varga et al., 2018).

Sformatowano: Razem z następnym

— sformatowano: Czcionka: Nie Pogrubienie

Sformatowano: Legenda;CaptionNGU


— sformatowano: Czcionka: Nie Pogrubienie


Sformatowano: Normalny, Interlinia: pojedyncze

Our goal is to expedite the process of generating ground truth data for faulted triangulated terrains using the Computational Geometry Algorithms Library (CGAL.org, 2023). We will employ supervised machine learning algorithms for binary classification to predict possible lineament fault presence within faulted terrains (Fig. 42). Our hypothesis posits that while traditional geometric attributes such as normal or dip vectors can still be useful for classification, integrating variablefeatures reflecting angular relationships between triangles and their neighbours is crucial for accurate classification, especially for fault detection on homoclines. We assert that analyzing distances for neighbours (Fig. 23) is advantageous due to its insensitivity to terrain rotation, unlike traditional geometric attributes such as dip direction (Hu et al., 2021) or the orientation of normal vectors (Michalak et al., 2022). As such, neighbourhood analysis can be linked, e.g., to curvature in seismic data (de Oliveira Neto et al., 2023) in terms of its insensitivity to terrain rotation.


The main challenges relate to the effectiveness of machine learning algorithms, variablefeatures selection, and the applicability of the method to diverse geological structures, potentially impacting classification accuracy and generalizability. To mitigate these challenges, we will conduct optimization of the algorithm's performance and variablefeatures selection (see [MethodologyMethods](#)). Validation across various geological terrains will ensure the method's robustness and applicability for

65 fault detection on homoclines (Fig. 4). This structured approach aims to enhance classification accuracy and the method's utility in practical geological applications. The overall workflow of the study is presented in Fig. 35.






**Figure 21.** A triangulated model of a faulted geological terrain: (Aa) we can see an inclined terrain and triangles that intersect a fault line. (Bb) A set of terrains with different parameters (dip angle and dip direction) can be used as training data in the classification task. In this panel, we showed only three terrains, but in practice an arbitrary number of terrains can be generated.



**Figure 23.** Because the fault introduced changes in the angular relationships between the orientation of fault-related triangles (t) and their neighbours (n1, n2, n3), the analysis of these relationships is essential for a successful classification. For example, we can measure the angular distance between normal vectors for three pairs corresponding to a specific triangle and its neighbours. The resulting value of angular distance can serve as a **variablefeature** in the classification task.

— sformatowano: Czcionka: Pogrubienie



85 **Figure 3** Workflow applied in this study. We create many random faulted geological terrains controlled by random parameters. Then, for each triangle, we sort the distances between neighbours to reduce randomness. In the next step, we test machine learning algorithms for synthetic data. At the end of the procedure, we evaluate the proposed approach for real data to test generalizability.



## 2 State-of-the-art Background

### 2.1 Related methodological developments

In geological mapping, machine-learning methods have been applied in the supervised lithology classification (Cracknell and Reading, 2014; Kuhn et al., 2018; Xiong and Zuo, 2021; Wang et al., 2020). In geological engineering, unsupervised methods were used to delineate subsets of observations representing discontinuities (Hammah and Curran, 1999; Zhan et al., 2017). In subsurface geological modelling, neural networks were used to delineate paleovalleys using topographic data as input data (Jiang et al., 2021) and convolutional neural network were used to create geological models with structural features controlled by a set of random parameters (Bi et al., 2022). As a specific unsupervised learning method, clustering algorithms find application in triangulated geological terrains (Michalak et al., 2022). These methods For example, the k-means algorithm generates partitions comprising geometrically similar observations based on cosine similarity (Choi et al., 2014). However, they place the burden on the user to determine whether a specific observation represents a fault. This can pose challenges, as some anomalous orientations may be associated with other structures or measurement errors. Moreover, applying unsupervised learning to 3D orientations reveals sensitivity to the choice of vectorial representation (Michalak et al., 2022), resulting in varying clustering results for dip and normal vectors. From a geological viewpoint, a serious limitation of unsupervised learning is that the orientations of the identified lineaments depend on the partition resulting from the clustering. For example, previous results suggest that for uniformly oriented sub-horizontal terrains (homoclines) the clustering algorithms may find it difficult to distinguish between observations related to the regional trend and observations related to faults striking perpendicular to the regional trend (Fig. 4b4b, 4e4c) (Michalak et al., 2022). In the problem of fault or lineament detection, the majority of available supervised methods are primarily tailored for seismic data (An et al., 2021; Kaur et al., 2023). For topographic data, supervised methods were utilized for fault-scarp prediction (Vega-Ramirez et al., 2021) using Fisher Linear Discriminant Analysis. However, this analysis relied on high-resolution bathymetric data based on a small training dataset (163 samples). Another example involves the use of topographic attributes such as DEM, slope, aspect, faults and environmental variablefeatures such as vegetation and climate for monitoring of ground deformation (Hu et al., 2021).

### 2.2 Geological Setting

#### 2.2.1 Regional and geometric background

As a relevant case study, we selected Kraków-Silesian Homocline (KSH) – a geological unit considered to be a slope of the Szczecin-Łódź-Miechów Synclinorium. The formation of KSH is mainly attributed to the inversion of the Permian-Mesozoic Polish Basin (Dadlez et al., 1995; Słonka and Krzywiec, 2019). From a geometric perspective, KSH dips at low angles to NE (Matyszkiewicz et al., 2015; Marynowski et al., 2007; Michalak et al., 2019; Znosko, 1960). It is generally assumed that the faults form a unimodal set of sub-parallel faults trending NE-SW (Fig. 44a) (Hermański, 1993; Bardziński et al., 1985).

However, later [clustering](#) experiments [with two or three clusters](#) (Michalak et al., 2022) added knowledge about geometric anomalies also aligned with the N-S direction (Fig. [44b](#), [4c](#)).

### [2.2.2 Discussion of previous results](#)

125 Little is known about faults trending perpendicular to the preferred dip direction. While the results (Fig. [4b4b](#), [4e4c](#)) suggest that they may not exist, we note that this negative effect can be due to limitations of unsupervised learning methods: the spatial distribution of labels depends on the partition induced by clustering algorithms. This dependence may result in visual disintegration of rare structures represented by observations being in different clusters. For example, the boundary between blue and purple labels may be related to faults dipping to SW (Fig. [44](#)). Likewise, it is unlikely that all observations dipping  
130 to NE are genetically related to the homocline; instead, observations dipping to NE but having dip angle greater than that of the homocline, may be related to faults dipping to NE.



140 panels (b) and (c) are borehole data used in this study, as well. The figure is a modified figure from using unsupervised classification to the dataset used of triangulated models of borehole data used in this study (Michalak et al., 2022).

3 Methods

In this section, we explain the workflow starting from generating synthetic data, through training the model on synthetic data to the final evaluation on real data. The stages are summarised in Fig. 5.

145 3.1 Generating terrains

In our study, the synthetic training data consists of many one thousand triangulated terrains using the Delaunay triangulation (De Berg et al., 2008). A user has the flexibility to adjust parameters of the resulting data set in the following fields: the number of files to generate, the lower and upper bound of terrain sizes, the left and right range of the dip direction, the lower and upper bound of the dip angle, the lower and upper bound of the number of points in the triangulation, the lower and upper bound of the surface noise, the lower and upper bound of the fault throw. The user-defined parameters and their admissible ranges are specified in Table 1. However, if a constant value of a parameter should be investigated, it is possible to set the same value for the lower and upper bound. In the next step, tools from the C++ random number library generate random numbers from the uniform distribution using the bounds entered by a user. The information about parameters are-is saved to a text file to allow further inspection.

155 The faulted triangulated terrains are created in the following sequence which is also summarized in Fig. 56 (numbers 1-6 below correspond to letters e-f in Fig. 6).

1. First, a container with 2D points is generated within a square of a given size.
2. Then, a new container of 3D points is created with the Z coordinate corresponding to the random value of dip and dip direction (ranges specified by a user). In the next step, a
- 160 3. Noise is introduced to the surface defined as a random fraction (ranges specified by a user) of the elevation difference within the terrain. Then,
4. a fault is introduced with the throw defined as a random fraction (ranges specified by a user) of the maximum elevation difference within the generated terrains. The orientation of the fault is determined by two points randomly selected from the boundary of the square.
- 165 5. Next, the Triangulation of the terrain is performed and the attributes including relationships with neighbours are calculated. Finally, we note that the
6. Classification task involves labeling each observation based on whether it is a fault-related observation (label=1) or not (label=-1). Therefore, we use the intersection predicate (CGAL.org, 2023) to test whether a specific triangle intersect the line representing a fault.

— sformatowano: Czcionka: Nie Pogrubienie


— sformatowano: Czcionka: Nie Pogrubienie

— sformatowano: Czcionka: Nie Pogrubienie

170       Following this approach, we are capable of generating great amount of synthetic and labeled ground truth data. [Parameters](#)  
used in this study are given in the Table 2.

To ensure that the training is performed on good quality data, we removed triangles with high degree (0.90 and greater) of  
collinearity defined as a ratio between the longest triangle's edge and the sum of remaining lengths (Michalak, 2018). This  
coefficient lies in the interval [0.5, 1] with lower and higher values pointing to equilateral and collinear configurations,  
175       respectively (Michalak et al., 2021; Michalak, 2018).

Sformatowano: Wcięcie: Z lewej: 0 cm



**Figure 35.** Workflow applied in this study. We create ~~many~~ **one thousand** random faulted geological terrains controlled by random parameters. Then, for each triangle, we sort the distances between neighbours to reduce randomness (see section 3.2 for a more detailed explanation). In the next step, we test ~~the~~ machine learning algorithms for synthetic data. At the end of the procedure, we evaluate the proposed approach for real data to test generalizability.

Sformatowano: Wcięcie: Z lewej: 0,63 cm

**Table 1.** Input parameters. The parameters given in the table are specified by the user by providing ranges. To generate a single model, a number from the uniform distribution is drawn using the provided ranges. Please note that dip angle and dip direction are not used directly in the later stages as features for classification but first are converted into normal and dip vectors.

<u>Name of the parameter</u>	<u>Range of possible values</u>	<u>Name of the variable in the code</u>
<u>Number of files</u>	<u>&gt;=1</u>	<u>number_of_files</u>
<u>Terrain sizes</u>	<u>&gt;=0</u>	<u>left_terrain_size, right_terrain_size</u>
<u>Dip angle</u>	<u>0-90</u>	<u>min_terrain_dip, max_terrain_dip</u>
<u>Dip direction</u>	<u>0-360</u>	<u>left_range_azimuth,</u> <u>right_range_azimuth</u>
<u>Number of points in the triangulation</u>	<u>&gt;=3</u>	<u>left_number_triangulation,</u> <u>right_number_triangulation</u>
<u>Noise of the surface</u>	<u>0.00-1.00</u>	<u>left_surface_noise,</u> <u>right_surface_noise</u>
<u>Fault throw</u>	<u>0.00-1.00</u>	<u>left_fault_throw,</u> <u>right_fault_throw</u>

**Table 2.** Values or ranges for parameters used in this study.

<u>Name of the paramter</u>	<u>Value</u>
<u>Number of files</u>	<u>1000</u>
<u>Terrain sizes</u>	<u>1</u>
<u>Dip angle</u>	<u>0.5-2.0</u>
<u>Dip direction</u>	<u>20-70</u>
<u>Number of points in the triangulation</u>	<u>100</u>
<u>Noise of the surface</u>	<u>0.02-0.04</u>
<u>Fault throw</u>	<u>-0.05-0.25</u>

— sformatowano: Czcionka: Pogrubienie

— sformatowano: Czcionka: Pogrubienie


— sformatowano: Czcionka: Pogrubienie

Tabela sformatowana

— sformatowano: Czcionka: Pogrubienie

— sformatowano: Czcionka: Pogrubienie

Tabela sformatowana



**Figure 56.** Depiction of sequence of processes applied to generate training data: (a) creating points in 2D space. (b) assigning elevation to the data depending on the randomly generated dip angle and dip direction, (c) adding noise to the data, (d) introducing faults and resulting elevation changes, (e) applying triangulation to the data, (f) labelling the data according to the intersection test with the fault line.



### 3.2 Selecting meaningful and consistent ~~variablefeatures~~

There can be numerous geometric ~~variablefeatures~~ used for the purpose of classification such as dip angle or dip direction (Hu et al., 2021; Wang et al., 2021). However, including dip direction for classification as a value within the [0, 360] range may not always be successful. This is because northern directions indicate great numerical difference (e.g. 358-2=356) but very small geometric difference (4 degrees). Sometimes the limitations of using dip direction are acknowledged and the ~~variablefeature~~ is removed from the analysis (Yang et al., 2023). Therefore, in this study we didn't use dip direction as a feature for classification.

In this study, to predict the correct label (label=1 for fault-related observations and label=-1 for non-fault-related observations), we used 24 ~~variablefeatures~~. The set consists of six local geometric ~~variablefeatures~~ and eighteen ~~variablefeatures~~ corresponding to the neighbourhood analysis. The first group consists of coordinates of normal and dip vectors. The second group includes ~~variable features~~ corresponding to the neighbourhood component of the analysis. The ~~variablefeatures~~ are as follows: angular distance, Euclidean distance and cosine distance applied to both normal and dip vector representations. The formulas for angular, Euclidean and cosine distances are given in the below equations, respectively:

$$d_a(x, x') = \arccos\left(\frac{|x \cdot x'|}{||x|| \cdot ||x'||}\right) \quad (\text{Eq. 1})$$

where " $\cdot$ " is the dot product, and  $||x||$  is the length of the vector  $x$ . In our case, the vectors have unit length. The use of absolute value in the numerator reflects the use of acute angles between vectors.

$$d_e(x, x') = ||x - x'|| \quad (\text{Eq. 2})$$

$$d_c(x, x') = 1 - x \cdot x' \quad (\text{Eq. 3})$$

However, in relation to the proposed neighbourhood analysis, an obstacle arises in processing this data due to the lack of a clear distinction between first, second, and third neighbouring triangles (Fig. 23, middle part of Fig. 35). This lack of order introduces randomness or arbitrariness into the analysis and compromises the consistency of data processing, which is crucial for the accuracy and reliability of the results.

To address this, we sort the distances to neighbouring triangles in decreasing order. Sorting these values eliminates randomness from the analysis and ensures consistency in data processing, thereby enhancing the correctness and credibility of the results. Subsequently, several classification algorithms available in the scikit-learn library (Pedregosa et al., 2011) can be tested in terms of precision and recall. However, in this study we work with a single algorithm to keep focus on the new classification method. We selected the Support Vector Machine which is considered a suitable tool for binary classification problems in high-dimensional spaces (Bishop, 2006) and which performed well in terms of precision and recall in our preliminary research.

### 3.3 Visualization

In our study, we visualize the classification results for real data using spatial clustering (Fisher, 1993; Fisher et al., 1985). The labels of triangles are recorded initially as integers corresponding to fault-related triangles (label=1) or triangles belonging to the homocline (label=-1). Then, the integers are converted to colors and presented on a map.

### 3.4 Support Vector Machine

For the purpose of binary classification, we used the support vector machine algorithm, a two class classifier (Bishop, 2006; Vapnik, 2000), available in the scikit-learn library (Pedregosa et al., 2011). The support vector machine algorithm can be considered an optimization algorithm because the decision is based on a hyperplane with the maximum margin. The margin is defined to be the minimal distance between a point in the training set and the hyperplane. The motivation behind the concept of margin is that if a margin is large, then it will be capable of separating the training set even after small perturbation of the instances (Shalev-Shwartz and Ben-David, 2013). Formally, the optimization objective looks as follows (Bishop, 2006):

$$\arg \max_{w,b} \left\{ \min_n \left[ t_n \left( \frac{w^T f(x_n) + b}{\|w\|} \right) \right] \right\}, \quad (\text{Eq. 4})$$

where  $t_n \in \{-1, 1\}$  are target values,  $f(x)$  denotes a fixed feature-space transformation. This transformation is expected to facilitate separation of instances which were not linearly separable in the original space. Common choices of transformations (kernel functions) include: linear, polynomial and radial basis functions. Next,  $w$  is the vector of weights which determines the orientation of the decision surface, and  $b$  is the bias parameter (not to be confused with bias in the statistical sense). The

expression  $\left( \frac{w^T f(x_n) + b}{\|w\|} \right)$  denotes the perpendicular distance of a point  $x_n$  to the decision surface  $y(x) = w^T f(x) + b = 0$ .

This decision surface separates points with different labels:  $-1$  and  $1$ . The multiplication  $t_n y(x_n)$  visible in the optimization task filters solutions for which all data points are correctly classified, i.e.  $t_n y(x_n) > 0$ . We note that in some formulations of the optimization problem, the vector of weights has unit length (Shalev-Shwartz and Ben-David, 2013). Because all  $N$  points lie beyond the margin area, they are at some distance from the hyperplane corresponding to the size of the margin. While the distances of  $N$  points relative to the decision boundary can be different, they are all greater than a fixed number corresponding to the size of the margin which can be expressed by a set of  $N$  inequalities. Therefore, the optimization objective (Eq. 4) together with the set of  $N$  inequalities form a constrained optimization problem which can be solved by using the Lagrange multipliers (Bishop, 2006 - Appendix E).

In the presence of outliers, a soft margin classifier can be applied which allows some samples to be classified incorrectly (Shalev-Shwartz and Ben-David, 2013). For the radial basis function kernel,  $C$  and  $\gamma$  parameters are considered. The parameter  $C$ , common to all SVM kernels, is a penalty parameter: a low  $C$  tends to make the decision surface simple (thus, avoiding overfitting but possibly affecting the correct classification of the training data), while setting a high  $C$  will result in

255 classifying training examples more correctly (possibly leading to poorer generalizability). Gamma defines the radius of the  
similarity of a single training sample. The lower gamma is, the greater the similarity radius of a sample (Pedregosa et al.,  
2011).

We use the following metrics as evaluation metrics:

$$260 \text{ precision} = \frac{\text{true positive}}{\text{true positive} + \text{false positive}} \text{ and } \text{recall} = \frac{\text{true positive}}{\text{true positive} + \text{false negatives}}.$$

The definition implies that precision is maximized if there are no false positives and the recall is maximized when there are no  
false negatives. Based on these definitions the harmonic mean of both can be defined as follows

$$F_1 = 2 * \frac{1}{\frac{1}{\text{precision}} + \frac{1}{\text{recall}}} = 2 * \frac{\text{precision} * \text{recall}}{\text{precision} + \text{recall}}.$$

### 3.34 Visualization Spatial clustering

265 In our study, we visualize the classification results for real data using the concept of spatial clustering (Fisher, 1993; Fisher et  
al., 1985). The definition of spatial clustering is studying first the directional information of the data without taking into account  
spatial information. This study aims to group geometrically similar observations and at the end the resulting clusters of  
directions are put back into their spatial context (Fisher, 1993) Indeed, in our case the Support Vector Machine algorithm  
270 performs the classification ignoring spatial information. It uses only geometric information such as the orientation of a triangle  
and the relationships between a triangle and its neighbours. The labels of clusters grouping similar triangles are recorded  
initially as integers corresponding to fault-related triangles (label=1) or triangles belonging to the homocline (label=-1). Then,  
the integers are converted to colors and presented on a map receiving again spatial information. As Fisher notes (Fisher, 1993),  
the spatial clustering is somewhat paradoxical: “to perform the desired directional-spatial clustering, it may be necessary to  
decouple the directional from the spatial information initially”.

275

## 4 Results

### 4.1 Synthetic data

In our study, we used 1000 triangulated terrains with 100 points in every terrain (see also Table 2). This configuration resulted  
in the initial number of 185980 triangles. We removed collinear configurations (collinearity>0.90) and triangles which did not  
280 have three finite neighbours. As a result, 145297 triangles remained. And only a small fraction of triangles are fault-related  
triangles (12411 vs 132886). Therefore, to reduce class-imbalance, we randomly select 12411 observations from the class with  
non-fault observations. Taking all considerations into account, we have 24822 samples with -12411 observations for each class  
(-1 and 1). Then, the set was divided into training (18616) and test (6206) set.

285

For arbitrarily selected hyperparameters ( $C=0.05$ ,  $\gamma=0.042$ ), with radial basis function as kernel function) in the scikit-learn framework we achieved the following confusion matrix for the test data (Table 3):

290

**Table 3.** Confusion matrix for the classification task before hyperparameter tuning. The sum of the entries is equal to the number of samples in the test data.

2993 (true negatives)	243 (false positives)
123 (false negatives)	2847 (true positives)

295

The values of precision and recall for the fault-related observations to be 0.92 and 0.9596, respectively (Table 4). These results relate to the test data which were not seen by the algorithm during training. However, the arbitrarily selected hyperparameters are not guaranteed to give the best performance of the algorithm. To further increase the values of the classification metrics, we tested many combinations of the hyperparameters as a part of the grid search optimization (Pedregosa et al., 2011). The optimal combination of hyperparameters turned out to be as follows:  $C=100$ ,  $\gamma=0.01$  with radial basis function as the kernel function. The classification results change slightly after the grid optimization stage (Tables 25 and 6). We note that after every execution of the code the values of the hyperparameters can change due to random steps of the procedure.

300

**Table 1-4.** Results for the classification of test data (unseen terrains) for arbitrarily selected hyperparameters (before hyperparameter tuning)

Class	Precision	Recall	F1-score
Non-fault	0.9596	0.92	0.94
Fault	0.92	0.9596	0.9394

305

**Table 5.** Confusion matrix for the classification task after hyperparameter tuning. The sum of the entries is equal to the number of samples in the test data.

2982 (true negatives)	163 (false positives)
134 (false negatives)	2927 (true positives)

— sformatowano: Czcionka: Pogrubienie

— sformatowano: Czcionka: Nie Pogrubienie

310 **Table: 2-6.** Results for the classification of test data (unseen terrains) after fine-tuning of the hyperparameters during grid search optimization

Class	Precision	Recall	F1-score
Non-fault	0.96	0. <u>9395</u>	0.95
Fault	0. <u>9395</u>	0.96	0. <u>9495</u>

— **sformatowano:** Czcionka: Nie Pogrubienie


315 **4.2 Real data**


To investigate generalizability of the method for real data, we used borehole data (Michalak, 2024a) corresponding to a horizon separating Middle-Jurassic rock units: [Aalenian-Early Bajocian](#) Kościeliska sandstones from [Late Bajocian-Late Bathonian](#) ore-bearing clay deposits (Matyja and Wierzbowski, 2000; Kopik, 1998) [\(see also the section 2.2 Geological setting\)](#).

The results of supervised classification using SVM are similar to those obtained using unsupervised (Michalak et al., 2022) classification (compare Figs [4-4](#) and [67](#)) in that the majority of faults has the SW-NE, SSW-NNE or S-N orientation. However, there are significant differences which relate to visibility of new potential faults trending perpendicular to the preferred dip direction. For example, Fig. [6b-7a](#) in the central part (near coordinates 921500, 251000) shows two potential faults trending NW-SE at the termination of S-N and SSW-NNE trending [potential](#) faults. Another difference is that the unsupervised classification presented the major fault in the NW part of the study area as possibly composed of smaller faults with opposite dip direction (Fig. [4e4c](#), near coordinates 922000, 248500). In contrast, the binary classification cannot distinguish between faults with opposite dip directions. Therefore, the zone of fault-related labels near the discussed fault zone appears relatively wide.

320

325





**Figure 6-7.** Classification results for the Kraków-Silesian Homocline: (a) the optimal combination of the hyperparameters as **confirmed** **suggested** by the grid search optimization ( $C=100$ ,  $\gamma=0.01$ , with radial basis function as the kernel function) (b) a custom combination of the hyperparameters ( $C=1$ , with linear kernel) (c) a custom combination of the hyperparameters ( $C=10$ , with linear kernel) (d) a custom combination of the hyperparameters ( $C=10$ ,  $\gamma=0.01$  with radial basis function as the kernel function). **On the panel (a), we marked lineaments known from the unsupervised learning revealed in previous studies (Michalak et al., 2022). The new lineaments revealed in this study using the supervised classification and the area where both groups intersect are marked as well.**

## 5 Discussion

### 5.1 Advantages of using faces of triangulation

— sformatowano: Czcionka: Pogrubienie



In our study, we used local geometric attributes of triangles and neighbourhood analysis to predict faults on triangulated models of subsurface geological terrains with preferred orientation. In subsurface geological modelling, the neighbourhood analysis was already applied for individual boreholes of triangulated surfaces to analyze connectivity of strata (Guo et al., 2024). From a viewpoint of graph theory, in our case the neighbourhood analysis is performed on finite faces of the triangulation rather than on its finite vertices (boreholes). Because, for every triangulation, with  $k$  being the number of points on the edge of the convex hull, the relationship between vertices ( $n$ ) and triangles ( $m$ ) is  $m = 2n - 2 - k$  (De Berg et al., 2008), our approach will usually (except very small data sets) result in a greater number of observations compared to a potential approach of considering boreholes as observations. Moreover, our approach ensures that every observation has three finite neighbours which testifies that observations are comparable. When neighbours of points are considered, this is not the case because the degree of a vertex usually is not a constant number.

5.2 Comparison with unsupervised approaches

The improvement of the supervised approach over the unsupervised method is that the clustering results depend on the partition generated by clustering algorithms. Therefore, the unsupervised version offers to examine spatial distribution of clusters. But it doesn't offer the examination of spatial distribution of structures related to different clusters. Moreover, the empirical results showed that clustering algorithms often struggle to separate regional trend from faults striking perpendicular to the regional trend on homoclines (Fig. 4b, 4c). Compared to the unsupervised method (Fig. 4c, the NW part of the study area), the main drawback of the supervised approach is that the algorithm cannot distinguish between different dip directions of a fault. Therefore, a zone of fault-related labels may consist of many sub-parallel sequences of labels corresponding to more than one sub-parallel faults possibly with opposite dip direction (Fig. 7, the NW part of the study area).

5.3 Complexities of real data

The borehole data set documenting the interface between Kościeliska sandstones and ore-bearing clays has been traditionally used for inferring tectonics (Znosko, 1960). However, it should be admitted that there is a hiatus covering the earliest Late Bajocian confirmed by the lack of Stenoceras subfurcatum Ammonite Zone (Garbowska, 1978). It is unclear whether some of the identified lineaments (Figure. 7) can be attributed to erosion. For example, some researchers point out that erosion was present took place during the earliest Late Bajocian (Dayczak-Calikowska and Moryc, 1988). However, some underground observations did not confirm deviations from the general parallelism between older Kościeliska sandstones and younger ore-bearing clays. Moreover, the orientation of the interface separating Kościeliska sandstones from ore-bearing clays was assumed to be uniformly inclined to North East in hydrogeological models during exploitation (Hermański, 1971).

5.4 Modelling assumptions

— sformatowano: Czcionka: Pogrubienie

— sformatowano: Czcionka: Pogrubienie

— sformatowano: Czcionka: Pogrubienie

The main assumption for generating the terrain data (Sect. 3.1) is that a fault is always represented by a plane. In our case, we assume that any terrain point lies either on one or on the other side of the fault and it is not possible that any terrain point is located on the fault. When these terrain points are triangulated, each fault-related triangle connects points from both sides of the fault. Every fault-related triangle has at least one neighbour that is not associated with the fault. The fault is represented by a stripe of the fault-related triangles (see triangles with green markers in Fig. 78A, (will be merged with Figure 9 into one Figure 8 with panels a and b)).






Figure 7: Example for a terrain generated as explained in Sect 3.1 with the fault being represented by a plane.

This main assumption is a simplification. In reality, a fault structure is never a purely planar object. It is mostly a 3D structure that has an extension perpendicular to the fault line direction (Childs et al., 2009). Therefore, it is possible that at least some terrain points may be located inside the fault zone. When triangulating these points, there is the possibility to create fault-related triangles all of whose neighbours are fault-related triangles as well. (see Fig. 88B, triangles with red markers).





**Figure 8.8:** (a) Example for a terrain generated as explained in the section 3.1 with the fault being represented by a plane. (b) Example for a terrain generated as explained in the section 3.1 with extended fault zone. Triangles with green markers show at least one non fault-related triangle as a neighbour. Triangles with red markers have only fault-related triangles as neighbours. Grey planes represent the border of the extended fault zone.

— sformatowano: Czcionka: Nie Pogrubienie

These “internal fault-related” triangles show a combination of ~~patterns features~~ that was never trained. Triangles that ~~exhibit show-patterns features~~ that were actually trained are still present (see Fig. 88B, triangles with green markers) but are only located at the borders of the fault zone (grey rectangles in Fig. 88B). This leads to the assumption that the presented classification system may classify the extended fault zone not by one sequence of color-coded labels but by two quasi-parallel sequences of this type. Whether the “internal fault-related triangles” can be successfully classified is not clear. In terms of local geometric ~~variablefeatures~~ specific to a single triangle such as coordinates of normal vectors, the “internal fault-related” triangles are more similar to the classical fault-related triangles. In contrast, the neighbourhood analysis alone would likely classify these triangles as non fault-related triangles (triangles with black marker in Figs. 7-8A and 88B).

The influence of 3D fault zones for the classification result needs to be further studied. Nevertheless, in the context of this study the data points are assumed to be sparsely scattered. If the fault shows an extension significantly lower than the mean data point spacing, the simplified assumption of purely planar faults is valid. The problem of identifying internal fault triangles could possibly be ameliorated by including not only the direct neighbours of a triangle in the training procedure but also triangles that are 2<sup>nd</sup>-, 3<sup>rd</sup>-degree neighbours or even higher degrees. Using this approach, it is more likely that the extended neighbourhood of an “internal fault-related” triangle also contains non-fault related triangles. However, the concept of the suggested approach would stay the same. For illustrational purposes we, therefore, stick to the simplest setup.

## 6 Conclusions

~~In this study, we developed a supervised fault detection method for triangulated models of geological terrains with preferred orientation. The novelty lies in generating large amount of synthetic terrains using the CGAL library and their triangulated models using Delaunay triangulation. The orientation of individual triangles combined with geometric relationships with neighbours are used as features for classification.~~ The proposed supervised method has the potential to identify fault-related lineaments of any orientation ~~which can be considered improvement over unsupervised classification approaches. This is a significant improvement over the clustering-based method whose results depend on the partition generated by clustering algorithms. The latter often struggle to separate regional trend from faults striking perpendicular to the regional trend on homoclines. Compared to the unsupervised method (Fig. 4c, the NW part of the study area), the main drawback of the supervised approach is that the algorithm cannot distinguish between different dip directions of a fault. Therefore, a zone of fault-related labels may consist of many sub-parallel sequences of labels corresponding to more than one sub-parallel faults possibly with opposite dip direction (Fig. 6, the NW part of the study area).~~ The main challenge of the workflow is to eliminate arbitrariness in ~~variablefeatures~~ selection in relation to neighbourhood analysis. Sorting distances among neighbours eliminates arbitrariness from the analysis but it is also the most computationally intensive part of the workflow. ~~We believe that the classification approach can be used by geologists interested in geological complexity of subsurface environments with limited availability of data.~~ Further studies can focus on considering more complex geological scenarios including the influence of 3D fault zones and physics-based models (compare with Conclusions in Reichstein et al., 2019).

**Code availability**

**Name of code:** BrokenTerrains. **License:** GNU General Public License v3.0. **Developer:** Michał Michalak. **Contact address:** AGH University of Krakow, Poland. E-mail: [michalm@agh.edu.pl](mailto:michalm@agh.edu.pl). **Year first available:** 2024. **Hardware required:** The computer code was run on a laptop with Intel(R) Core™ i7-7500U CPU 2.70 GHz, 16 GB RAM. **Software required:** CGAL library (v. 4.8), Microsoft Visual Studio 2022. **Program language:** C++, Python. **Program size:** 738 KB. **How to access the source code:** (Michalak, 2024b) <https://doi.org/10.5281/zenodo.12375568> Setup guide: <https://github.com/michalmichalak997/BrokenTerrains/blob/main/README.md>

**Data availability**

Datasets for this research (input and processed data) are available in these intext data citation references (Michalak, 2024a)

**Author contribution**

MM devised the project, wrote the computer code and the manuscript, performed the computations and discussed the results. CG participated in the study conceptualization (sorting distances with neighbours), PM discussed the results [\(Modelling assumptions\)](#).

**Competing interests**

The authors declare that they have no conflict of interest.

**Acknowledgements**

~~The study was supported by the AGH University of Science and Technology, grant number 16.16.140.315.~~ [Research project supported by program „Excellence initiative – research university” for the AGH University. AI tools \(ChatGPT\) were used for improving computer code files and the English language. I thank Tomasz Zajac from Bluemetrica for initial discussions about formulation of the supervised fault-detection problem.](#)

**References**

An, Y., Guo, J., Ye, Q., Childs, C., Walsh, J., and Dong, R.: Deep convolutional neural network for automatic fault recognition from 3D seismic datasets, Comput. Geosci., 153, 104776, <https://doi.org/10.1016/j.cageo.2021.104776>, 2021.

Bardziński, W., Lewandowski, J., Więckowski, R., and T, Z.: Szczegółowa Mapa Geologiczna Polski 1: 50 000, ark. Częstochowa (845), 1985.

- De Berg, M., Cheong, O., Van Kreveld, M., and Overmars, M.: Computational Geometry: Algorithms and Applications, 3rd Ed., Springer, 364 pp., <https://doi.org/10.2307/3620533>, 2008.
- 455 Bi, Z., Wu, X., Li, Z., Chang, D., and Yong, X.: DeepISMNet: Three-dimensional implicit structural modeling with convolutional neural network, *Geosci. Model Dev.*, 15, 6841–6861, <https://doi.org/10.5194/gmd-15-6841-2022>, 2022.
- Bishop, C. M.: Pattern Recognition and Machine Learning (Information Science and Statistics), Springer-Verlag, Berlin, Heidelberg, 2006.
- CGAL.org: CGAL, Computational Geometry Algorithms Library, <https://www.cgal.org>, 2023.
- 460 Childs, C., Manzocchi, T., Walsh, J. J., Bonson, C. G., Nicol, A., and Schöpfer, M. P. J.: A geometric model of fault zone and fault rock thickness variations, *J. Struct. Geol.*, 31, 117–127, <https://doi.org/10.1016/j.jsg.2008.08.009>, 2009.
- Choi, J., Cho, H., Kwac, J., and Davis, L. S.: Toward sparse coding on cosine distance, in: 2014 22nd International Conference on Pattern Recognition, <https://doi.org/10.1109/ICPR.2014.757>, 2014.
- Cracknell, M. J. and Reading, A. M.: Geological mapping using remote sensing data: A comparison of five machine learning algorithms, their response to variations in the spatial distribution of training data and the use of explicit spatial information, *Comput. Geosci.*, 63, 22–33, <https://doi.org/10.1016/j.cageo.2013.10.008>, 2014.
- 465 Dadlez, R., Narkiewicz, M., Stephenson, R. A., Visser, M. T. M., and van Wees, J. D.: Tectonic evolution of the Mid-Polish Trough: modelling implications and significance for central European geology, *Tectonophysics*, 252, 179–195, [https://doi.org/10.1016/0040-1951\(95\)00104-2](https://doi.org/10.1016/0040-1951(95)00104-2), 1995.
- 470 Dayczak-Calikowska, K. and Moryc, W.: Rozwój basenu sedymencyjnego i paleotektonika jury środkowej na obszarze Polski, *Geol. Q.*, 32, 117–136, 1988.
- Fisher, N. I.: Statistical analysis of circular data, Cambridge University Press, 277 pp., <https://doi.org/10.1017/cbo9780511564345>, 1993.
- Fisher, N. I., Huntington, J. F., Jacket, D. R., Willcox, M. E., and Creasey, J. W.: Spatial analysis of two-dimensional orientation data., *J. Int. Assoc. Math. Geol.*, 17, 177–194, <https://doi.org/https://doi.org/10.1007/BF01033153>, 1985.
- 475 Garbowska, J.: Interrelation between microfauna and nature of dogger deposits of the Czeszochowa Jura (Poland), *Acta Palaeontol. Pol.*, 23, 1978.
- Guo, J., Xu, X., Wang, L., Wang, X., Wu, L., Jessell, M., Ogarko, V., Liu, Z., and Zheng, Y.: GeoPDNN 1.0: a semi-supervised deep learning neural network using pseudo-labels for three-dimensional shallow strata modelling and uncertainty analysis in urban areas from borehole data, *Geosci. Model Dev.*, 17, 957–973, <https://doi.org/10.5194/gmd-17-957-2024>, 2024.
- 480 Hammah, R. E. and Curran, J. H.: On distance measures for the fuzzy K-means algorithm for joint data, *Rock Mech. Rock Eng.*, 32, 1–27, <https://doi.org/10.1007/s006030050041>, 1999.
- Hermański, S.: Wpływ prac odwadniających kopalnictwa rud żelaza na kształtowanie warunków hydrogeologicznych w rejonie częstochowsko-kłobuckim., *Rudy Żelaza*, 9–10, 13–16, 1971.
- 485 Hermański, S.: Mapa stropu i miąższości warstw kościeliskich. Rejon Żarki-Wieluń. Skala 1:100000, 1993.
- Hu, X., Bürgmann, R., Xu, X., Fielding, E., and Liu, Z.: Machine-Learning Characterization of Tectonic, Hydrological and

Anthropogenic Sources of Active Ground Deformation in California, *J. Geophys. Res. Solid Earth*, 126, <https://doi.org/10.1029/2021JB022373>, 2021.

Jiang, Z., Mallants, D., Gao, L., Munday, T., Mariethoz, G., and Peeters, L.: Sub3DNet1.0: A deep-learning model for regional-scale 3D subsurface structure mapping, *Geosci. Model Dev.*, 14, 3421–3435, <https://doi.org/10.5194/gmd-14-3421-2021>, 2021.

Jüstel, A., Correia, A. E., Pischke, M., de la Varga, M., and Wellmann, F.: GemGIS - Spatial Data Processing for Geomodeling, *J. Open Source Softw.*, 7, 3709, <https://doi.org/10.21105/joss.03709>, 2022.

Jüstel, A., de la Varga, M., Chudalla, N., Wagner, J. D., Back, S., and Wellmann, F.: From Maps to Models - Tutorials for structural geological modeling using GemPy and GemGIS, *J. Open Source Educ.*, 6, 185, <https://doi.org/10.21105/jose.00185>, 2023.

Kaur, H., Zhang, Q., Witte, P., Liang, L., Wu, L., and Fomel, S.: Deep-learning-based 3D fault detection for carbon capture and storage, *Geophysics*, 88, IM101–IM112, <https://doi.org/10.1190/geo2022-0755.1>, 2023.

Kopik, J.: Lower and Middle Jurassic of the north-eastern margin of the Upper Silesian Coal Basin (in Polish with English summary), *Biul. Państwowego Inst. Geol.*, 378, 67–129, 1998.

Kuhn, S., Cracknell, M. J., and Reading, A. M.: Lithologic mapping using Random Forests applied to geophysical and remote-sensing data: A demonstration study from the Eastern Goldfields of Australia, *Geophysics*, 83, B183–B193, <https://doi.org/10.1190/geo2017-0590.1>, 2018.

de la Varga, M., Schaaf, A., and Wellmann, F.: GemPy 1.0: open-source stochastic geological modeling and inversion, *Geosci. Model Dev. Discuss.*, 12, 1–32, <https://doi.org/10.5194/gmd-2018-61>, 2018.

Marynowski, L., Zatoń, M., Simoneit, B., and Otto, A.: Compositions, sources and depositional environments of organic matter from the Middle Jurassic clays of Poland, *Appl. Geochemistry*, 22, 2456–2485, <https://doi.org/10.1016/j.apgeochem.2007.06.015>, 2007.

Mattéo, L., Manighetti, I., Tarabalka, Y., Gaucel, J. M., van den Ende, M., Mercier, A., Tasar, O., Girard, N., Leclerc, F., Giampetro, T., Dominguez, S., and Malavieille, J.: Automatic Fault Mapping in Remote Optical Images and Topographic Data With Deep Learning, *J. Geophys. Res. Solid Earth*, 126, <https://doi.org/10.1029/2020JB021269>, 2021.

Matyja, B. A. and Wierzbowski, A.: Ammonites and stratigraphy of the uppermost Bajocian and Lower Bathonian between Częstochowa and Wieluń Central Poland, *Acta Geol. Pol.*, 50, 191–209, 2000.

Matyszkiewicz, J., Kochman, A., Rzepa, G., Gołębiowska, B., Krajewski, M., Gaidzik, K., and Zaba, J.: Epigenetic silicification of the Upper Oxfordian limestones in the Sokole Hills (Kraków-Częstochowa Upland): Relationship to facies development and tectonics, *Acta Geol. Pol.*, 65, 181–203, <https://doi.org/10.1515/agp-2015-0007>, 2015.

Michalak, M.: Numerical limitations of the attainment of the orientation of geological planes, *Open Geosci.*, 10, <https://doi.org/10.1515/geo-2018-0031>, 2018.

Michalak, M.: Broken Terrains v. 1.0: A supervised detection of fault-related lineaments on geological terrains - Input and processed data, <https://doi.org/10.5281/zenodo.12209024>, 2024a.



- Michalak, M., Teper, L., Wellmann, F., Żaba, J., Gaidzik, K., Kostur, M., Maystrenko, Y. P., and Leonowicz, P.: Clustering has a meaning: optimization of angular similarity to detect 3D geometric anomalies in geological terrains, *Solid Earth*, 13, 1697–1720, <https://doi.org/10.5194/se-13-1697-2022>, 2022.
- Michalak, M. P.: michalmichalak997/BrokenTerrains: v. 1.0 - Initial release, <https://doi.org/10.5281/zenodo.12375568>, 2024b.
- 525 Michalak, M. P., Bardziński, W., Teper, L., and Małolepszy, Z.: Using Delaunay triangulation and cluster analysis to determine the orientation of a sub-horizontal and noise including contact in Kraków-Silesian Homocline, Poland, *Comput. Geosci.*, 133, 104322, <https://doi.org/10.1016/j.cageo.2019.104322>, 2019.
- Michalak, M. P., Kuzak, R., Gładki, P., Kulawik, A., and Ge, Y.: Constraining uncertainty of fault orientation using a combinatorial algorithm, *Comput. Geosci.*, 154, 104777, <https://doi.org/10.1016/j.cageo.2021.104777>, 2021.
- 530 de Oliveira Neto, E. R., Fatah, T. Y. A., Dias, R. M., Freire, A. F. M., and Lupinacci, W. M.: Curvature analysis and its correlation with faults and fractures in presalt carbonates, Santos Basin, Brazil, *Mar. Pet. Geol.*, 158, 106572, <https://doi.org/10.1016/j.marpetgeo.2023.106572>, 2023.
- Pedregosa, F., Varoquaux, G., Gramfort, A., Vincent, M., Thirion, B., Grisel, O., Blondel, M., Prettenhofer, P., Weiss, R., Dubourg, V., Vanderplas, J., Passos, A., Cournapeau, D., Brucher, M., Perrot, M., and Duchesnay, É.: Scikit-learn: Machine
- 535 Learning in Python, *J. Mach. Learn. Res.*, 12, 2825–2830, 2011.
- Reichstein, M., Camps-Valls, G., Stevens, B., Jung, M., Denzler, J., Carvalhais, N., and Prabhat, F.: Deep learning and process understanding for data-driven Earth system science, *Nature*, 566, 195–204, <https://doi.org/10.1038/s41586-019-0912-1>, 2019.
- Shalev-Shwartz, S. and Ben-David, S.: Understanding machine learning: From theory to algorithms, Cambridge university press, 397 pp., <https://doi.org/10.1017/CBO9781107298019>, 2013.
- 540 Słonka, L. and Krzywiec, P.: Upper Jurassic carbonate buildups in the Miechów Trough, Southern Poland – insights from seismic data interpretation, *Solid Earth Discuss.*, 11, 1097–1119, <https://doi.org/10.5194/se-2019-178>, 2019.
- Vapnik, V. N.: The nature of statistical learning theory. Statistics for Engineering and Information Science, Springer-Verlag, New York, 2000.
- Vega-Ramirez, L. A., Spelz, R. M., Negrete-Aranda, R., Neumann, F., Caress, D. W., Clague, D. A., Paduan, J. B., Contreras, J., and Peña-Dominguez, J. G.: A new method for fault-scarp detection using linear discriminant analysis in high-resolution
- 545 bathymetry data from the alarcón rise and pescadero basin, *Tectonics*, 40, e2021TC006925, <https://doi.org/10.1029/2021TC006925>, 2021.
- Wang, H., Zhang, L., Yin, K., Luo, H., and Li, J.: Landslide identification using machine learning, *Geosci. Front.*, 12, 351–364, <https://doi.org/10.1016/j.gsf.2020.02.012>, 2021.
- 550 Wang, Y., Ksienzyk, A. K., Liu, M., and Brönnner, M.: Multi-geophysical data integration using cluster analysis: Assisting geological mapping in Trøndelag, Mid-Norway, *Geophys. J. Int.*, 225, 1142–1157, <https://doi.org/10.1093/gji/ggaa571>, 2020.
- Xiong, Y. and Zuo, R.: A positive and unlabeled learning algorithm for mineral prospectivity mapping, *Comput. Geosci.*, 147, 104667, <https://doi.org/10.1016/j.cageo.2020.104667>, 2021.
- Yang, J., Xu, J., Lv, Y., Zhou, C., Zhu, Y., and Cheng, W.: Deep learning-based automated terrain classification using high-

555 resolution DEM data, *Int. J. Appl. Earth Obs. Geoinf.*, 118, 103249, <https://doi.org/10.1016/j.jag.2023.103249>, 2023.

Zhan, J., Xu, P., Chen, J., Wang, Q., Zhang, W., and Han, X.: Comprehensive characterization and clustering of orientation data: A case study from the Songta dam site, China, *Eng. Geol.*, 225, 3–18, <https://doi.org/10.1016/j.enggeo.2017.01.010>, 2017.

Znosko, J.: Tektonika obszaru częstochowskiego, *Przegląd Geol.*, 8, 418–424, 1960.