

Spatializing Net Ecosystem Exchange in the Brazilian Amazon biome using the JULES model and vegetation properties

Amauri C. Prudente Junior¹, Luiz A.T. Machado^{1,5}, Felipe S. Silva¹, Tercio Ambrizzi², Paulo Artaxo¹,
5 Santiago Botia³, Luan P. Cordeiro¹, Cleo Q. Dias Junior⁴, Edmilson Freitas², Demerval S. Moreira⁶,
Christopher Pöhlker⁵, Ivan M. C. Toro¹, Xiyan Xu⁷, and Luciana V. Rizzo¹

¹ Physics Institute, University of São Paulo, São Paulo, Brazil

² Institute of Astronomy, Geophysics and Atmosphere Science, University of São Paulo, São Paulo, Brazil

10 ³ Max Planck Institute for Biogeochemistry, Jena, Germany

⁴ Federal Institute of Education, Science, and Technology of Pará, Belém, Brazil

⁵ Max Planck Institute for Chemistry, Mainz, Germany

⁶ Department of Physics and Meteorology, State University of São Paulo, Bauru, Brazil

⁷ Chinese Academy of Sciences, Beijing, China

15 *Corresponding to:* Amauri Cassio Prudente Junior (email: amauri.cassio@usp.br)

Abstract. The large extension and diversity of the Brazilian Amazon biome hampers the assessment of regional-scale carbon budget based solely on local observations. Considering the shortage of observations, this study aims to examine the carbon fluxes throughout the Brazilian Amazon biome using ^athe process-based model (JULES, Joint UK land environment simulator).
20 A sensitivity analysis detected five critical model parameters for the Amazon tropical broadleaf evergreen forest, optimized using carbon flux and meteorological data from four forest sites. The simulations with new parametrization were compared ^{with}to JULES default parameter values and with simulations of the Vegetation Photosynthesis and Respiration Model (VPRM). Net ecosystem exchange (NEE) and gross primary production (GPP) estimates were improved at all sites, reaching a Root Mean Squared Error (RMSE) about 30% lower in comparison to the default version. The optimized parameter values varied among
25 the four sites, indicating that a single parameterization for the whole Amazonia may not be adequate. JULES model parameters were ^{estimated}extrapolated for the Brazilian Amazonia, based on canopy height and leaf area index gridded data. Applying JULES with ^{spatially}spatial dependent parameterization for the year of 2021 resulted in a carbon sink of -1.34 Pg C year⁻¹. Regional differences were observed in the carbon fluxes, with a carbon source of 0.75 Kg C m⁻² year⁻¹ in the southwest and north, likely explained by increased ecosystem respiration in older and taller forests.

30

1. Introduction

The Amazon forest is one of the largest carbon reservoirs in the world, **being relevant** to the global environment, biodiversity, and climate regulation (Brienen et al., 2015). Amazon forests are responsible for 16% of the gross primary production in terrestrial ecosystems, storing approximately 90 Pg C in above- and below-ground vegetation biomass (Saatchi et al., 2011; Malhi et al., 2021). The region's critical role in the global carbon budget is at risk, as ~~the~~ carbon dynamics are being significantly impacted by climate change, including rising air temperatures and increased hydric stress (Liu et al., 2017; Gatti et al., 2021). These effects can lead to a decrease in the leaf area index (LAI) and an increase in plant respiration (Meir et al., 2008) and hence influence the sign of the net carbon exchange, shifting areas from ~~sink~~^{a sink} to a source of carbon.

Accurate estimates of carbon fluxes are crucial for understanding how the Amazon will evolve under the impacts of climate change. The diverse vegetation of the Amazon biome and the strategies used to estimate carbon fluxes across different sites are essential for identifying the region's different behaviors (Restrepo-Coupe et al., 2013). The traditional method of carbon flux measurement is ~~the~~ Eddy Covariance (Baldochi, 2003), which quantifies the Net Ecosystem Exchange (NEE), by measuring the turbulent CO₂ exchange and correcting for canopy storage. NEE represents the difference between the gross primary production (GPP) of the vegetation and emissions from the ecosystem respiration (Reco) (Hayek et al., 2018). However, eddy covariance measurements are insufficient to represent the vast diversity of ecosystems and vegetation in the Brazilian Amazon biome (Aguirre-Gutierrez et al., 2025). This limitation arises due to logistical challenges, the substantial investment required for installation and equipment, and the need for highly skilled labor to ensure proper maintenance (Andreae et al., 2015). Considering the limitation of expanding flux towers throughout the Amazon biome, process-based and data-driven models have been applied in different studies to estimate NEE in different parts of Amazon, such as the Vegetation Photosynthesis and Respiration Model (VPRM) (Botia et al., 2022 and 2024), FluxCom (Nelson et al., 2024; Chen et al., 2024) and the Organizing Carbon and Hydrology in Dynamic Ecosystems (ORCHIDEE) (Verbeeck et al., 2011).

One of the comprehensive land surface models used to simulate the biophysical process is the Joint UK Land Environment Simulator (JULES; Best et al., 2011). JULES is a community land surface model used both as a standalone system and as the land surface component of the Met Office Unified Model. **It is considered the state-of-the-art for large-scale simulations (Moreira et al., 2013).** quite an old ref to make this claim! JULES has a tiled model of sub-grid heterogeneity **being** able to reproduce energy, water, carbon, and momentum fluxes (Best et al., 2011, Clark et al., 2011). **The model includes different configurations of plant functional types (PFT): five PFTs (HadGEM3, Clark et al., 2012), nine PFTs (Harper et al 2016), or 13 PFTs (UKESM1, Harper et al., 2018) and four non-vegetation types.** Still potentially unclear—in theory the model could be run with any number of PFTs, and 5, 9, or 13 are common choices Currently, JULES is used to simulate carbon fluxes in different biomes types, as applied for agriculture (Osborne et al., 2015; Williams et al., 2017) and in tropical forests (Moreira et al., 2013; Restrepo-Coupe et al., 2017; Caen et al., 2022).

Although JULES has been widely used in various studies to estimate carbon fluxes in tropical regions, a lack of specific parameterizations remains a challenge to simulate plant-soil-atmosphere interactions. Harper et al. (2016) introduced a PFT specific to tropical forests, but this parameterization has not been thoroughly tested or validated across different regions of the Amazon. Additionally, the most sensitive parameters in this region have not been deeply evaluated. In general, studies

to estimate NEE using process-based models have not accounted for the large differences of vegetation characteristics across this territory (Ometto et al., 2023). Based on these aspects, this study aims to characterize the seasonal and spatial variability of carbon fluxes between the biosphere and atmosphere in the Brazilian Amazon biome. Here, we present an improvement of the JULES parameterization specifically for the Brazilian Amazon, performing a sensitivity analysis of the model parameters using ~~as reference to~~ Eddy-covariance towers in different regions of the Brazilian Amazon biome. Model parameters were spatialized using two ancillary datasets— canopy height and LAI—to ^{assess?} ~~access~~ regional differences in NEE in the Brazilian Amazon biome. ^{^ as references}

2. Material and Methods

The current study combined observational datasets and modeling. Section 2.1 describes the study area and the tower flux sites in the Brazilian Amazon Basin. Section 2.2 ^{describes} ~~describe~~ the main features of the JULES model. Section 2.3 describes the meteorological and edaphological datasets used as input for the JULES run and eddy-covariance dataset used to validate the model optimization. Section 2.4 describes the gridded data used for simulations in the Brazilian Amazon biome. Section 2.5 describes the JULES model procedures adopted in this study as sensitivity ^{analyses} ~~analysis~~ and calibration procedures and the description of the remote sensing data and the regression method used to extrapolate the JULES model parameters across the Amazon Basin. Section 2.6 describes the VPRM model that was used to ^{please specify—at the tower sites or across the whole Amazon basin?} ~~compare~~ with JULES model. ^{^ the}

2.1. Study area


The study area corresponds to the Brazilian Amazon biome, covering 4,212,472 km². We compiled data from five eddy covariance towers to represent carbon ^{fluxes} ~~flux~~ and evaluate JULES simulations (Figure 1). From east to west and north to south, these sites are: The Amazon Tall Tower Observatory (ATTO), the Tapajos National Forest (K67, K83), the Reserva Jarú (RJA) and the Reserva Cuieiras near Manaus (K34). The equatorial forest was represented by 4 towers (ATTO, K34, K67, K83) and RJA represented the southern Amazonia (Restrepo-Coupe et al., 2021). The K34 tower is located 60 km north of the city of Manaus (Araujo et al., 2002; Restrepo-Coupe et al., 2013) (Table 1). The Santarem moist tropical forest (sites K67 and K83) is located at the confluence of the Amazon and Tapajós rivers, in the northeast Brazilian Amazon. The ATTO tower is the most recent tower built in the Amazon region, based 150 km northeast of the city of Manaus (Andreae et al., 2015). In the southern Amazon region, the RJA tower is located in a forest reserve in the state of Rondônia, characterized **as a tropical** ^{do you mean seasonally dry, or are some areas wet and others dry?} ~~wet and dry forest~~ (Peel et al., 2007). Some of these flux towers are still operational, while others have been discontinued. As such, observations from each tower are available for different periods ranging from 2001 to 2021, sometimes with intermittent measurements. For the current study, data from different years were used in the JULES model calibration (see Table 1), with ^{one} ~~a~~ complete year being selected that had the most reliable set of observations in terms of both data coverage and quality assurance. Using a single year of data for each site provided similar conditions for model parameter optimisation at the different ^{^ for each site}

100 sites. To minimise the influence of atypical conditions reflected in the variability of carbon fluxes, years with extreme dryness or wetness were avoided during the model optimisation process. The towers K34, K67, RJA and ATTO were used in model calibration. ^{Why was this tower chosen for validation?} The tower K83 was used as an independent tower to validate the models for the spatialization developed in this study. ^{Repetitive with previous sentence} Tower K83 was left out, for means of validation

105 All the eddy covariance flux towers are located in upland (*terra firme*) forest sites, with canopy heights in the range 27-36 m and LAI in the range 3.26-5.46 m² m⁻² (Table 1), respectively comprising 61% and 85% of the distribution of values in the study area (Figure 1). The five flux towers considered in this study represent upland forests in regions with subtle differences in the climate regime and in the level of stress associated with deforestation and climate change pressures. While the K34 and ATTO towers are located in pristine forest reserves in the Western Amazonia, the RJA tower sits in a forest reserve surrounded by agricultural areas in Southwestern Amazonia. The K67 and K83 towers sit in a forest reserve near the deforestation frontier in the Eastern Amazonia. ^{I think it would be more appropriate to say something like "includes multiple kinds of upland forest communities"} Therefore, this set of flux towers represents the diversity of upland forests, which extend through more than 80% of the Amazon biome (Moraes et al., 2021). However, it is important to acknowledge that this set of flux towers is not representative of all Amazonian ecosystems, like seasonally flooded, swamp or white sand forests.

115 **Table 1: Description of five different eddy covariance towers based on Amazon region (Restrepo-Coupe et al., 2021). LAI data is from ERA5 and Canopy Height data is from the Global Canopy Forest (Simardi et al., 2011).**

ID	Site location	Canopy height (m)	Year evaluated	Annual total rainfall (mm)	Average air temperature (°C)	LAI (m ² m ⁻²)
	Lat/Lon					
K34	2.614°S/60.12°W	27	2005	1964.81	25.98	4.79
K67	2.85°S/54.97°W	36	2003	1283.72	28.19	3.26
RJA	10.08°S/61.93°W	35	2001	2512.58	25.15	4.05
K83	3.01°S/54.88°W	28	2001	1658.29	26.37	3.78
ATTO	2.15°S/59.03°W	30	2018	2192.87	26.03	5.46



120

Figure 1: Eddy covariance towers across the Brazilian Amazon biome (red symbols) used to validate JULES simulation. Grided background colors denote the spatial distribution of leaf area index ($\text{m}^2 \text{m}^{-2}$) on the left panel and canopy height (m) on the right panel (refer to section 2.4). The black symbol indicates the tower used to validate the spatialization of JULES parameters. LAI data is from ERA5 and ^{canopy height} Canopy Height data is from the Global Canopy Forest (Simardi et al., 2011).

125

2.2. JULES model description

JULES is a land surface model that can simulate carbon fluxes punctually or in a grid with a temporal resolution of one hour. The JULES version utilized in this study was 7.0, based on nine plant functional types (PFT), including tropical forests (Harper et al., 2016). JULES requires hourly meteorological data as input, as described in section 2.3. Also, it requires an edaphic dataset, which is also described in section 2.3. JULES estimates GPP and Reco based on the limitation factor of three potential photosynthesis rates (Collatz et al., 1991, 1992). This topic presents the main equations to estimate GPP and Reco, defining the most relevant parameters for the calculation of carbon fluxes. A more detailed description of equations ^{used by JULES to} based ^{provided} on how JULES estimate carbon fluxes is demonstrated in the supplementary material S1.

135 The model considers three ^{potentially-limiting?} potential limiting photosynthesis rates: Light limitation rate (W_l); Rubisco ^{limitation} limited rate (W_c); and ^{transport} Transport of photosynthetic products for C3 and PEP Carboxylase limitation for C4 plants (W_e). W_l and W_e ^{arc} are depend on the maximum rate of carboxylation of Rubisco (V_{cmax}), which is calculated using an optimal temperature range for each plant functional type (T_{upp} and T_{low}), as described by Clark et al., (2011) (Equation 1):

140
$$V_{c \max} = \frac{V_{c \max 25} f_t(T_c)}{[1 + e^{0.3(T_c - T_{upp})}][1 + e^{0.3(T_{low} - T_c)}]} \quad (1)$$

where T_c is the canopy (leaf) temperature in ^{degrees Celsius} Celsius degrees, f_t is the standard Q_{10} temperature dependence (see equation 2 in the Supplementary material) and $V_{c \max}$ ^{at?} in 25°C is calculated based on leaf nitrogen content (kg N kg C⁻¹) in each canopy layer (i) (see equation 3 in the Supplementary material).

With $V_{c \max}$ it is possible to calculate two potential photosynthesis rates: W_c and W_e :

145
$$W_c = \begin{cases} V_{c \max} \left(\frac{c_i - \Gamma}{c_i + k_c \left(1 + \frac{O_a}{k_o} \right)} \right) & \text{for C3 plants} \\ V_{c \max} & \text{for C4 plants} \end{cases} \quad (2)$$

where $V_{c \max}$ (mol CO₂ m⁻² s⁻¹) is the maximum rate carboxylation of Rubisco, c_i is the leaf internal carbon dioxide partial pressure (Pa), Γ is the CO₂ compensation point in the absence of mitochondrial respiration (Pa), O_a is the partial pressure of atmospheric oxygen, and K_c and K_o are the Michaelis-Menten parameters for CO₂ and O₂, respectively.

150
$$W_e = \begin{cases} 0.5 V_{c \max} & \text{for C3 plants} \\ 2 \cdot 10^4 V_{c \max} \frac{c_i}{P^*} & \text{for C4 plants} \end{cases} \quad (3)$$

where P^* is the surface air pressure.

The light-limited rate (W_l) relies on the quantum efficiency for photosynthesis (α , in mol CO₂ mol⁻¹ PAR):

$$W_l = \begin{cases} \alpha(1 - \omega) I_{PAR} \left(\frac{c_i - \Gamma}{c_i + 2\Gamma} \right) & \text{for C3 plants} \\ \alpha(1 - \omega) I_{PAR} & \text{for C4 plants} \end{cases} \quad (4)$$

155 where ω is the leaf scattering coefficient for PAR, and I_{PAR} is the incident photosynthetically active radiation (PAR, mol m⁻² s⁻¹).

The three potentially-limiting rates are essential to calculate the rate of gross photosynthesis, ^{which is} being the smoothed minimum of the three limited rates previously calculated, as described in the Supplementary section (Equation 7). GPP is calculated based on the integration of leaf photosynthesis (AI, see Supplementary materials equation 11) taking into account
160 every canopy level adopted by Harper et al., (2016), assuming a multi-layer canopy with sunlit and shaded leaves in each layer.

The leaf CO₂ concentration on the surface or internal is defined based on the leaf humidity deficit estimated by the vapor deficit in the leaf surface (D) and ^{on} ~~in~~ two parameters related to specific plant function types (f_0 and D_{crit}) (Equation 5):

$$\frac{C_i - \Gamma}{C_s - \Gamma} = f_0 \left(1 - \frac{D}{D_{crit}} \right) \quad (5)$$

where C_s is the leaf surface CO₂ concentration.

165

To calculate Reco, first leaf dark respiration (R_d) is

To calculate ~~the~~ Reco the first aspect is to define leaf dark respiration (R_d), defined as a proportion of V_{cmax} . (Equation

6)

$$R_d = f_d V_{cmax} \quad (6)$$

where

~~being~~ f_d the dark respiration coefficient. To calculate the total plant respiration, JULES considers the sum of two processes:

170 maintenance and growth respiration (R_{pm} and R_{pg} , ^{Equations 7 and 12?} ~~Equations 7 and 8~~, respectively)

$$R_{pm} = 0.012 R_d \left(\beta + \frac{N_r + N_s}{N_l} \right) \quad (7)$$

where N_l , N_s and N_r are nitrogen contents of leaf, stem and root, respectively and β is the soil moisture stress factor based on Cox et al., 1998 (^{Consider naming Supplemental equations S1, S2, ... for clarity?} see equation 9 and 10 on Supplementary materials). To calculate the nitrogen contents of leaves, stem and roots, LAI and canopy height are important elements (Equations 8-10):

175 $N_l = n_m \sigma_l L \quad (8)$

$$N_s = \mu_{sl} n_m S \quad (9)$$

$$N_r = \mu_{rl} n_m R \quad (10)$$

present in roots and respiring

stems

where n_m is the mean leaf nitrogen concentration (kg N (kg C)^{-1}), R and S are the quantity of carbon ~~present root and respiring~~

180 ~~stem~~, L is the leaf area index and ^{should be subscript} σ_l (kg C m^{-2} per unit of LAI) is the specific leaf density. The nitrogen contents of roots and

~~stem~~ are assumed to be multiples, μ_{rl} and μ_{sl} , of the mean leaf nitrogen concentration, assuming: $\mu_{rl} = 1.0$ for all PFTs, $\mu_{sl} = 0.1$ for woody plants (trees and shrubs) and $\mu_{sl} = 1.0$ for grasses. To calculate the respiring stemwood the pipe model of Shinozaki et al (1964) was utilized taking into account canopy height and LAI (Equation 11):

$$S = n_{sl}hL \quad (11)$$

185 Where n_{sl} is a constant of proportionality from Friends et al (1993) and h is the canopy height.

To calculate the growth respiration, it is necessary to consider the maintenance respiration and also the estimated GPP (Equation 12)

$$R_{pg} = r_g(GPP - R_{pm}) \quad (12)$$

190 Where r_g is the growth respiration coefficient, set as 0.25 for all plant functional types (Clark et al., 2011 and Harper et al., 2016).

Finally, NEE is calculated by JULES as the difference between GPP and total ecosystem respiration (plant and soil respiration, R_{eco} , Equation 13):

$$NEE = R_{eco} - GPP \quad (13)$$

195 2.3. Ancillary environmental data

The JULES model requires the meteorological variables listed in Table 2 as input. In-situ meteorological forcing data from each flux tower (Restrepo-Coupe et al., 2021; Andreae et al., 2015) were used for model calibration (Section 2.4.2) and cross-validation using K83 tower data. For the spatialisation of carbon fluxes, meteorological data from reanalysis was applied, as will be described in Section 2.4.1. Soil information required by JULES was obtained from the EMBRAPA database (Reatto et al., 2004), which provides soil texture data (silt, sand, and clay content) at a 30 m of resolution down to a depth of 120 cm below surface. To convert soil texture into the parameters required to run JULES (Table 3) we applied equations from Marthews et al. (2014). The edaphological parameters in the model are static.

205 **Table 2: Meteorological variables required by JULES an their respective definitions and units.**

Variable	Definition
sw_down	Downward flux of short-wave radiation, $W m^{-2}$
lw_down	Downward flux of long-wave radiation, $W m^{-2}$
Precip	Rainfall, $kg m^{-2} s^{-1}$
T	Air temperature, $^{\circ}C$
Wind	Wind speed, $m s^{-1}$
Pstar	Air pressure, Pa

Q	Specific humidity, kg kg ⁻¹
---	----------------------------------------

Table 3: Soil physical parameters required for JULES with their respective definitions and units for five different sites in the Amazon region.

Parameter	Definition	ATTO	K67	RJA	K34	K83
b	Brooks-Corey exponential for hydraulic soil characteristics (dimensionless)	15.65	11.19	6.52	11.19	11.19
hcap	Dry heat capacity, J m ⁻³ k ⁻¹	1236203	1228469	1272748	1228469	1228469
sm_wilt	Soil moisture at the point of permanent wilt, m ³ m ⁻³	0.12	0.26	0.14	0.26	0.26
hcon	Dry thermal conductivity, W m ⁻¹ k ⁻¹	0.20	0.22	0.27	0.22	0.22
sm_crit	Soil moisture at the critical point, m ³ m ⁻³	0.21	0.37	0.25	0.37	0.37
satcon	Saturation hydraulic conductivity, kg m ⁻² s ⁻¹	0.00063	0.00152	0.0065	0.00152	0.00152
sathh	Soil matrix suction at saturation, m	0.39	0.32	0.14	0.32	0.32
sm_sat	Soil moisture at saturation, m ³ m ⁻³	0.39	0.46	0.42	0.46	0.46
albsoil	Soil albedo (dimensionless)	0.13	0.17	0.13	0.17	0.17

210 Concerning the carbon fluxes, the variables utilized to calibrate and evaluate JULES simulations were NEE, GPP and Reco. It is important to mention that the direct observation from Eddy-Covariance tower measurement is NEE. NEE was partitioned following Botía et al (2022), who followed a similar approach as Restrepo-Coupe et al., assuming that nighttime NEE corresponds to nighttime Reco. Nighttime Reco was used as the daytime respiration, while daytime GPP was calculated from the difference between GPP and NEE (NEE=Reco-GPP). NEE data was available every 60 minutes for all flux towers, 215 except for the ATTO tower, available every 30 minutes.

2.4. Gridded data

In addition to the in situ observational data, gridded datasets were used in JULES model simulations and as 220 benchmarks to the simulated carbon fluxes. Meteorological data from the ERA5 reanalysis (Hersbach et al., 2020) were used

to force the JULES model in spatialized runs (refer to Section 2.5.3). ERA5 has hourly temporal resolution and a spatial resolution of $0.25^{\circ} \times 0.25^{\circ}$, which was resampled to $1^{\circ} \times 1^{\circ}$, providing data for the variables listed in Table 2. This resolution was proposed in view of the computational limitation to run JULES for the Brazilian Amazon biome.

225 Gridded data of vegetation properties and land use were also used in the spatialized model runs, extrapolating model parameters across the Brazilian Amazon biome. Canopy height was collected in the Global Forest Canopy dataset (Simard et al., 2011). This dataset represents ^{canopy height} ~~the tree heights~~ with a resolution of 927 m based on a fusion of spaceborne-lidar data (2005) from the Geoscience Laser Altimeter System (GLAS) and ancillary geospatial data. Canopy heights retrieved from the gridded product were similar to local observations at the 5 tower fluxes considered in this study. LAI data from the ERA5 Land monthly reanalysis was used, with a resolution of 11132 m. In ERA5, LAI is calculated using the land surface model of the 230 European Centre for Medium-Range Weather Forecasts, known as CTESSEL (Boussetta et al., 2013), with the assimilation of a 9-year monthly climatology derived from satellite-based data from MODIS (Moderate Resolution Imaging Spectroradiometer). Therefore, the LAI product from ERA5 describes a fixed vegetation state. Land use and land cover data was provided by MapBiomas, collection 9, with a spatial resolution of 30 m (Souza Jr. et al., 2020). MapBiomas data was the reference to run JULES for each PFT represented in each grid (refer to supplementary material, Section 3.1, Table S3.1). All 235 data was resampled to ~~the~~ $1^{\circ} \times 1^{\circ}$ resolution and utilized in different versions of models approached in this study, as described in Section 2.5.3

Two gridded datasets on carbon fluxes were used as benchmarks for the simulations conducted in this study: FluxCom-X (Nelson et al., 2024) and the European Carbon Tracker CT 2022 (Jacobson et al., 2023). European Carbon Tracker provided hourly NEE at a resolution of 0.1° in latitude by 0.2° in longitude, ~~spatial and hourly temporal resolution~~, calculated 240 by the Simple Biosphere model Version 4 (SiB4) which is driven by meteorology variables from the European Centre for Medium-Range Weather Forecasts (ECMWF) Reanalysis 5th Generation (ERA5) dataset. To compare NEE with JULES simulation, the optimized biological flux was used (i.e., excluding Carbon flux from fuel and fire) and lateral fluxes from rivers were removed, following Friedlingstein et al. (2022). FluxCom-X, ^{providing estimates} ~~provided~~ with 0.05° spatial and hourly temporal resolution, is produced using a data-driven approach using an ensemble of machine-learning methods, combining local observations from 245 eddy covariance flux towers, satellite observations and meteorological reanalysis data. In the Brazilian Amazon biome, FluxCom-X assimilates data from only two flux towers: K67 and K83. The scarcity of flux data in the Amazon hinders the model training, resulting in a decreased model performance in this region when compared to other terrestrial ecosystems worldwide. Overestimation of the carbon sink (strongly negative NEE) in tropical regions is a well-known bias of the FluxCom-X dataset (Nelson et al., 2024).

250

2.5 JULES model procedures

In this section, we described the procedures necessary to optimize and spatialize NEE using JULES for the Brazilian Amazon biome. In the first topic we approach a local sensitivity analysis the first step to select the most sensitive parameters of JULES in a specific point in the Brazilian Amazon biome. The second topic will present the calibration and evaluation to improve the most sensitivity parameters selected in the sensitivity analysis. The third topic will describe the method utilized to spatialize JULES in the Brazilian Amazon biome. Attaining equilibrium between carbon stocks and humidity via the soil moisture spin-up procedure was a computationally expensive process. For this study, it was difficult to implement because of the large number of grid points required to simulate the Brazilian Amazon region. To initialize the JULES simulations, we I think I understand how this was done, from looking at the Moreira reference. To address Reviewer 2's comment, I think more details should be added adopted the strategy employed by Moreira et al. (2013). We ran JULES from the start to the end of the simulation period. The carbon pool was not altered during the simulation, and carbon levels varied in accordance with seasonal changes throughout the year. Also, we considered the soil texture obtained in the EMBRAPA database (described in the section 2.3) as a source that closely matches with the observed data and this can reduce the uncertainties in the water balance.

265

2.5.1. Sensitivity analysis

The first step in process-based model calibration and local sensitivity analysis is to understand how the modulation of GPP and Reco is influenced by the model parameters (with NEE calculated by the difference of GPP and Reco). This study initially assessed the sensitivity of the 21 core parameters of the JULES model by varying their values within the minimum and maximum expected ranges (Table S2.1). The underlying hypothesis was that the heterogeneity of the Amazon forest would lead to variation in these parameters. Understanding their impact on NEE helps identifying which parameters are critical for parameterization and should not be treated as fixed values, as it is done in the default JULES model PFT parameterization.

The local sensitivity analysis was developed for 2018 using the location of the ATTO tower as reference. Each JULES parameter was perturbed within its maximum and minimum expected range, as shown in Supplement Table S2.1. The effect of these changes on NEE calculations was quantified using the mean root sum of square deviation (RMSD, $\text{g C m}^{-2} \text{ day}^{-1}$) (Equation 14) and Δvar (%) (Equation 15). RMSD and Δvar depend on the difference of NEE computed using the maximum and minimum value of a specific parameter (all others are maintained fixed with the default value). The calculation is computed for the simulation of each day and averaged over the year. Δvar is computed as the sum of the square difference divided by the square root of the number of days analyzed which can generate spurious values with significantly higher magnitudes. To mitigate the impact of these spurious values, we treated them as outliers and applied the Grubbs' test (Grubbs, 1969) with a significance level of 95%, removing days with NEE considered outliers based on the absolute difference between maximum and minimum disturbed values, divided by the NEE before optimization (Harper et al., 2016). After this procedure, each parameter was classified by relevance level based on the largest Δvar values, identifying the most sensitive parameters.

Supplement Figures S2.1 present the NEE monthly simulations for 2018, considering the impact of changes in the most relevant parameters compared to observed data (retrieved from the eddy covariance towers). The simulations were performed by varying each relevant parameter individually, using different values within the specified minimum and maximum range.

290

$$\text{RMSD} = \sqrt{\frac{\sum_{i=1}^N (y_{\max_i} - y_{\min_i})^2}{N}} \quad \begin{array}{l} \text{I don't think this adequately addresses Reviewer 2's comment,} \\ \text{which was that this formula is a non-standard metric.} \\ \text{It is not RMSD (where dividing by N is under the radical).} \end{array} \quad (14)$$

$$\Delta\text{var} (\%) = \frac{100}{N} \cdot \sqrt{\sum_{i=1}^N \frac{(y_{\max_i} - y_{\min_i})^2}{(y_{\text{default}_i})^2}} \quad (15)$$

Where y_{\max} is the NEE daily value simulated with the maximum parameter; y_{\min} is NEE daily value simulated with the minimum parameter the minimum; y_{default} is the daily value simulated using the default version of JULES default (Figure S2.2) and N is the number of observations, removing days with outliers (352 days).

295




Figure 2: Variation in (%) (Δvar) of JULES parameters relative to the default version of JULES at the ATTO tower, representing the Amazon biome during 2018. The abbreviations were defined in Supplement Table S2.1

300

We considered the five most sensitive parameters (Figure 2): canopy height (canht); scale factor for dark respiration (fd), which is a coefficient between 0 and 1 associated with leaf dark respiration (Equation 6); quantum efficiency for

305 photosynthesis (α , mol CO₂ mol⁻¹ PAR) (Equation 4); the maximum ratio of internal to external CO₂ (f_0), necessary to simulate leaf CO₂ concentration based on leaf humidity deficit, and the upper-temperature threshold for photosynthesis (t_{upp} , Equation 1). The sensitivity analysis has shown that variations in canopy height between 19 m and 50 m can lead to variations of almost 200% in NEE. The variation of the dark respiration scaling factor, for potential values found in Amazonia, can also lead to differences in NEE of the order of 140%. The quantum efficiency, the maximum ratio of internal to external CO₂, and the upper temperature for photosynthesis can lead to variations in NEE of 45%, 16%, and 13%, respectively (refer to Table S2.2).

The set of parameters selected in the sensitivity analysis were similar compared to Raoult et al. (2016), which
310 calibrated JULES for different plant functional types using GPP to evaluate the new parameterization. The reason behind the high sensitivity of NEE towards the parameter **Canht** can be explained by its influence on calculating the Maintenance Respiration (Equation 11, section 2.2), **being this parameter** is necessary to estimate stem wood respiration (Clark et al., 2011). Another relevant aspect that explains the high sensitivity of Canht is the linear relation with roughness length (Best et al., 2011), which is important for carbon fluxes **estimated** by the mechanical turbulence and the capacity to enhance the mixing
315 of air **and** to facilitate the transfer of gases, including CO₂, between the land and the atmosphere (Khanna and Medvigy, 2014). The parameter f_d is also relevant to estimate the dark respiration coefficient (Equation 6, section 2.2) related to the Reco estimation. Alpha is a parameter that is related to estimating the **light**-limited **rate** (Equation 3, section 2.2), f_0 is a relevant parameter to estimate hydric stress and the stomata regulation (Equation 5, section 2.2) and t_{upp} is required to estimate V_{cmax} for different temperatures (Equation 1, section 2.2). The parameters α , t_{upp} and f_0 **are highly related to calculate GPP**
320 **being these three parameters also observed** by Raoult et al. (2016) and Li et al. (2016) **working on optimized GPP estimative** using JULES. Optimizing this set of parameters makes it possible to spatialize the carbon fluxes in the Brazilian Amazon biome and their vegetation heterogeneity.

2.5.2. Calibration and validation

325 After the local sensitivity analysis, which defined the most important parameters for GPP and Reco, JULES was optimized comparing simulations with observed data at each site described in section 2.2. For this attempt, we used the Nelder-Mead method (Nelder and Mead, 1965) for the optimization, using the SciPy implementation (Harris, et al., 2020) and NumPy to process data (Virtanen et al., 2020). The Nelder-Mead method is a numerical method used to find the minimum or maximum
330 of an objective function in a multidimensional space (Dakhlaoui, 2014). This method was successfully applied in studies of calibration and evaluation of different models as described by Jérôme et al., (2021). The JULES output utilized as a reference for calibration at each site was NEE, since it is directly retrieved from eddy covariance measurements without assumptions on flux partitioning. Canopy height was fixed as the average canopy height of each site, while the next four most sensitive parameters were concomitantly modified within the physiological limits, looking for the combination of values that minimized
335 the error between model and observation on a daily scale (Table S4.1). After that, **a leave-one-out cross-validation method** was

13 This LOO exercise was done using values predicted by the spatialization linear equations from canopy height and LAI, correct?
If so, it would be easier to follow if this was described after that process was presented.

The LOO exercise really only validates the calibration in one other site.

used to validate the calibration in different parts of the Brazilian Amazon biome (Wallach et al., 2018). The statistical index adopted to evaluate the error in this study was the root mean square error (RMSE) (Loague and Green, 1991, equation 16).

$$RMSE = \sqrt{\frac{1}{n} \sum_{i=1}^n (y_i - p_i)^2} \quad (16)$$

Where y_i is the predicted value of NEE; p_i the observed value of NEE and n the number of observations.

340 Another statistical matrix used to analyze the accuracy of the simulations during the year was the index of agreement (d) proposed by Wilmott et al. (2012), given by

$$d = 1 - \left| \frac{\sum_{i=1}^n (y_i - p_i)^2}{\sum_{i=1}^n (|y_i - P| + |p_i - P|)^2} \right| \quad (17)$$

where P is the average value of standard observations of NEE. When d is close to 1, this indicates a high accuracy level.

345 It was necessary to delimit maximum and minimum values for each parameter according to the physiological characteristics of tropical species (Table S4.1). Within the delimited values of reference, the optimization was developed from the default value of each JULES parameter adopted by Harper et al. (2016). It is important to mention that the Nelder-Mead method does not generate uncertainties for fitted parameters at a confidence level, being limited to one value in a physiological range that will be our reference to the calibration procedure

350 2.5.3. Spatializing JULES in the Amazon biome

The optimization of the JULES model parameters for different forest sites in Amazonia has shown significant differences, reflecting the heterogeneity of vegetation characteristics categorized in the PFT Broadleaf Evergreen Trees - tropical (BET-TR). This motivated the spatial extrapolation of JULES model parameters across the Amazon Basin using remote sensing data as predictors.

360 After the sensitive parameters were adjusted for each tower, it was possible to spatialize the parameter values across the Amazon biome. As such, we have developed a spatially dependent parameterization of the BET-TR PFT in JULES. The spatialization model was based on linear regressions, having each sensible parameter as the target variable, and two remote-sensed vegetation properties as predictors: canopy height and LAI. The reasons behind the choice of these variables include: data availability and the fact that they can be used as a proxy for the 5 most sensitive parameters (Li et al., 2018; Moudry et al., 2024). Also, canopy height and LAI can be considered constant in the short term, describing a fixed vegetation state. Moreover, these two variables are also required as input for JULES simulations, canopy height as plant functional type parameter and LAI as an required for initial condition for simulations.

365 With independent linear regressions on canopy height and LAI, it was possible to extrapolate the model parameters to the whole Brazilian Amazon biome. Different configurations for linear regression models were tested for each JULES parameter, following one of the general formats of Equation 18:

$$\begin{aligned} P(x, y, LAI) &= a + b \cdot LAI(x, y) \\ P(x, y, height) &= a + b \cdot height(x, y) \end{aligned} \quad \begin{array}{l} \text{Replace with a dot that is not at the} \\ \text{bottom of the text} \\ \text{to be clear about multiplication?} \end{array} \quad (18)$$

where P represents JULES model parameters (tupp, alpha, f0_io and fd); x, y are the coordinates of each model grid cell; a, b, are regression coefficients to be determined. The regression models were fit to the parameters optimized at four forest sites
370 described in section 2.1 (K34, ATTO, K67 and RJA), using the maximum likelihood method. The choice of the regression model configuration for each JULES parameter was based on a compromise between the regression model residuals and the physical consistency of the extrapolated values. Section 3 in the supplementary material shows the reasoning behind the choice of each regression model.

To represent variations in carbon fluxes throughout the year, simulations were performed with one-degree resolution
375 across the Brazilian Amazon biome during April and September 2022, representing a wet and a dry season month in the Amazon Region, respectively. The meteorological dataset required for JULES to simulate GPP, respiration, and NEE (Section 2.1, Table 2) was provided by ERA5 reanalysis data at an hourly scale with a 1°x1° resolution.

It is important to highlight that spatially dependent parameterization was used only for the BET-TR PFT, representing
380 71% of the Brazilian Amazon biome. For other PFTs present in the Amazon Basin, the default values were used for all parameters (Harper et al., 2016). The canopy height for BET-TR was provided by the Global Forest Canopy dataset (section 2.4), while for the other types of vegetation we used the default values by Clark et al. (2011) and Harper et al. (2016). In the case of C4 grass that has relevance in the arc of deforestation we utilized a canopy height of 15 cm which is typical for cattle farms in this region (Fernandes et al., 2015). In the case of soybean, a relevant crop cultivated in the northern region of the state of Mato Grosso, we considered the sowing date in September and the harvest in February, as described by Mato Grosso
385 Institution of Agricultural Economics (De Lima Filho, 2021). To assign a PFT for each model grid, a correspondence was established between JULES land functional types and land use data from MapBiomias collection 9 (Souza Jr et al., 2020) (see supplementary material, Section 3.1, Table S3.1). Since MapBiomias data have a resolution of 30 m, it was necessary to calculate the ^{percent} **percentual** contribution of each land use class present in each 1° model cell grid (Figure S3.1). To run the model, it was necessary to introduce the fraction of each land functional type as a tile to represent each vegetation present in the grid
390 for JULES simulations. A description of all procedures utilized to spatialize JULES is described in Figure S4.5 (see supplementary materials section S.4).^{^ type}

2.6 VPRM model

395 The Vegetation Photosynthesis and Respiration Model (VPRM) (Mahadevan et al., 2008) is a satellite-driven empirical model designed to estimate NEE by integrating GPP and ecosystem respiration. GPP is calculated using a light-use efficiency method that combines meteorological inputs (e.g., temperature and photosynthetically active radiation) with remote sensing indices such as the Enhanced Vegetation Index (EVI) and the Land Surface Water Index (LSWI). These indices are derived from the MODIS Surface Reflectance 8-Day L3 Global 500 m (MOD09A1) product, which is collected within a ±0.1°
400 area around each tower evaluated in this study (ATTO, K34, K67, K83, RJA; see Table 1 for descriptions). These data are interpolated to daily intervals using a curve smoothing technique (LOWESS filter). Ecosystem respiration is modeled using a

linear function of temperature to capture the temperature dependence of carbon release. VPRM's key parameters include λ_0 (maximum light-use efficiency), PAR_0 (light saturation constant), α and β (coefficients controlling temperature dependence), as well as the temperature thresholds T_{min} , T_{max} , T_{opt} , and T_{low} . In this study, the parameter values employed were those calibrated by Botía et al. (2022) for the Amazon forest.

3.Results

3.1. Calibration and evaluation of JULES

After the identification of the model parameters with highest sensitivity [in the Amazon](#), the JULES model was calibrated for each flux tower, following the methods described in Section 2.5.2. Table 4 shows the JULES default values for the BET-TR PFT parameters (Harper et al., 2016) along with the optimized values considering local measurements in the Amazon. The optimized values showed a strong variability, even among the equatorial forest sites. This explains the motivation for the spatialization of JULES parameters for the BET-TR plant functional type.

Table 4: New parameterization of JULES optimized by Nelder-Mead in each simulated site in this study. Four parameters were optimized: upper-temperature threshold for photosynthesis (tupp), quantum efficiency (alpha), scale factor for dark respiration (fd), maximum ratio of internal to external CO₂ (f0). Canopy height (canht) was retrieved from observations at each site.

Parameter	unit	Default	ATTO	K67	K34	RJA
tupp	°C	43	42.18	36	42.77	36
alpha	mol CO ₂ per mol PAR photons	0.08	0.05	0.066	0.061	0.05
fd	dimensionless	0.01	0.011	0.0066	0.01	0.007
f0	dimensionless	0.875	0.95	0.713	0.93	0.875
canht	m	30	30	36	27	35




Figure 3 shows the simulated fluxes for GPP, Reco and NEE using optimized JULES parameters, JULES default parameters, and simulations with the VPRM model. Observations are also depicted, as reference. The statistical metrics RMSE and d (Equations 16 and 17) were calculated in each case, to assess the performance of each model setup in reproducing the

observations. The new parameterization reduced RMSE for GPP and NEE in all flux towers, in comparison to the default parameter values and VPRM results. However, the optimized parameter values did not improve the Reco simulations. It is important to note that NEE was the control variable in the calibration process so that the GPP and Reco partitioned fluxes were indirectly optimized. NEE was used as the control variable because it is directly measured in the flux towers, without assumptions regarding to the partition into GPP and respirations.

The seasonality of the carbon fluxes was better represented by JULES optimized utilizing the Nelder-Mead method (Figure 3). Although JULES optimized did not capture the increase in GPP in the dry-to-wet season transition (Oct-Dec), the new version of JULES reduced the error in GPP in relation ^{to} of the default version and VPRM in each season of the year. The ^{difficulty in representing} ~~difficult to represent~~ the dry season effects by the models ^{was} ~~were~~ also described by Restrepo-Coupe et al. (2013) ^{who} ~~that~~ observed a different dynamic during the dry season in RJA tower, which is a region near to pasture and with a rainfall regime different from the equatorial region represented by ATTO, K67 and K34 ~~regions~~. In most process-based vegetation models, GPP is strongly associated with hydric stress, which may not be adequate for some Amazonian regions where leaf phenology and litter fall dynamics could play an important role (Restrepo-Coupe et al., 2017; Botia et al., 2022). JULES optimized was the version that better represented the observed carbon sink (NEE<0) between September and January at the K67 tower. Reco was overestimated in November and December, due to the direct relation between the dark respiration coefficient (fd) and $V_{C_{max}}$ (Clark et al., 2011, equation 1). Despite the limitations in the reproduction of the carbon ^{flux} ~~fluxes~~ seasonality, the optimization of JULES parameters resulted in improved estimates for annual means ~~in~~ NEE, reducing the bias in comparison to the default parameter values.

VPRM demonstrated weaknesses in simulating GPP seasonality, and the error magnitude in NEE was higher than in the optimized JULES and, in some regions (K67 and K34), even higher than its default version. Botia et al. (2022), comparing different models ^{at the} ^{^model} ~~in~~ ATTO tower, reported that VPRM demonstrated low efficiency in capturing carbon seasonality in this region. This was attributed to the lack of ^{model representation of} ~~methods for calculating~~ hydric stress, as the only water scaling source was the Water Scale Index, derived from remotely sensed Land Surface Water Index using MODIS reflectance data (Chandrasekar et al., 2010 and Gourdjji et al., 2022).

450







— JULES Optimized
 ● Observed
 — VPRM
 — JULES Default

455 **Figure 3: GPP, Reco, and NEE simulations using different model setups and observations at each flux tower in Amazonia. The observed data in the plots is the ^{aggregate value for} accumulated during each month of the year, and the RMSE error described is the daily average during the year in $\text{g C m}^{-2} \text{ day}^{-1}$.**

3.2. Spatialization of JULES parameters

460 Considering the variability of the optimized parameters for different sites of the Brazilian Amazon biome (Table 5), simple linear regression models were developed to extrapolate the parameter values for the whole Brazilian Amazon. As predictors, vegetation characteristics described in the Section 2.5.3, namely LAI and canopy height, were used. Table 5 shows the linear regression models developed for the JULES ^{parameters} parameter with the highest sensitivity. The reasoning behind each regression model is available in section 3 of the supplementary material, where maps showing the spatialized values for the JULES parameters and the relationship of each parameter with the respective vegetation index are also ^{provided} shown.

465 The relationship between each parameter and the selected predictor is shown in Figure 4. Canopy height was selected for tupp and alpha, while LAI was selected for f0 and fd. Tupp showed an inversely proportional relationship with the canopy height (Figure S.3.2.2), which is consistent with that fact that low-canopy plants like C4 grasses typically have higher temperature thresholds for photosynthesis. The parameter alpha did not show a clear relationship with any of the predictors, resulting in a rather constant behavior against canopy ^{height} height (Figure S.3.3.2). Canopy height was chosen as a predictor for alpha to obtain the expected lower quantum yields for C3 and C4 plants ($0.055 \text{ mol}^1 \text{ mol}^{-1}$, Skilman 2008) (Figure S3.3.1 The correlation of alpha with canopy height is small; however, as alpha in the Amazon has a small range of variation (between 0.05 and $0.06 \text{ mol mol}^{-1}$ for C₃ species, in line with Skilman, 2008), this low correlation has a small impact on the final result. Parameter f0 was positively associated with LAI (Figure S.3.4.2), consistent with the fact that f0 is expected to be lower in the arc of deforestation compared to forest sites. For ^{the} fd parameter, the selected predictor was LAI (Figure S.3.5.2), which is 475 expected to have a positive relationship with fd, given the greater photorespiration efficiency in C4 plants.



480 **Figure 4: Spatialization of the parameters tupp (upper-temperature threshold for photosynthesis), alpha (quantum efficiency), f0 (maximum ratio of internal to external CO₂), and fd (scale factor for dark respiration) for the Amazon biome using two different methods: based on canopy height and based on LAI.**


The regression equations were used to obtain the parameter values at the K83 tower site, which was left aside in the spatialization process. Using a canopy height of 28 m and an average LAI value of 3.78, as described in section 2.4, the parameter values obtained for K83 were used in a JULES simulation for the year of 2001, ^{parameterization} obtaining the GPP, Reco and NEE ^{predicting} fluxes depicted in Figure 5.

Table 5: Parameterization based on the spatialization in the Amazon region for four JULES parameters in Tower K83

Parameter	Equation	R ²	Value extrapolated to K83
Tupp (°C)	66.6212-0.85574*Height	0.94	42.66
alpha (mol mol ⁻¹)	0.04942 + 0.00022*Height	0.01	0.056
f0	0.40266 + 0.10577*LAI	0.87	0.802
fd	-0.00101+0.0022*LAI	0.91	0.0073

repetitive with previous sentence before the table?

490 **The parameterization proposed for JULES was used to simulate GPP, Reco, and NEE at the K83 tower, compared against observations in Figure 5.** The most relevant aspect was the improvement in GPP reducing the RMSE ^{by} 37% in comparison to the default version of JULES and 39 % in comparison to the VPRM model. Observations at the K83 tower showed a weak annual cycle in the carbon fluxes, which was satisfactorily reproduced by the models. Overall, this validation process indicates that the method used for the spatialization of JULES parameters provided satisfactory estimates in a forest site that was left out of the regression models.



495 **Figure 5:** GPP, Reco, and NEE fluxes in the independent **validation tower, K83,** for the year of 2001. The observed data in the plots is the **aggregated value for accumulated during** each month of the year, and the RMSE error described is the daily average during the year in $\text{g C m}^{-2} \text{ day}^{-1}$.


500 **3.3. Spatial variability of carbon fluxes in Amazonia**

After validation with an independent tower (K83), we were confident in using JULES to estimate carbon fluxes across the entire Brazilian Amazon biome for the year 2021. This year was chosen to allow comparison of the simulated carbon fluxes with recently released or updated global datasets. The simulations used the spatialized values of the 5 most sensitive parameters of the BET-TR JULES PFT (Fig. 4). Default parameter values were used for other PFTs in the Amazon Basin. Despite the fact that the JULES model was not able to reproduce precisely the carbon flux seasonal cycles (Fig. 3), it is important to assess the

estimated spatial variability of NEE in months with contrasting meteorological conditions, investigating the model responses. Figure 6 highlights the results from two representative months of the wet (April) and dry (September) seasons in Amazonia.

The mean GPP in April was $223 \text{ g C m}^{-2} \text{ month}^{-1}$, while the mean Reco was $170 \text{ g C m}^{-2} \text{ month}^{-1}$, characterizing a carbon sink (NEE) of $-53 \text{ g C m}^{-2} \text{ month}^{-1}$. During the dry season month (September), there was an increase in GPP, reaching a mean of $240 \text{ g C m}^{-2} \text{ month}^{-1}$, in Reco, with a mean of $182 \text{ g C m}^{-2} \text{ month}^{-1}$, increasing the carbon sink to $-58 \text{ g C m}^{-2} \text{ month}^{-1}$. The fact that GPP was not reduced by water limitation during the dry season also was observed by Restrepo-Coupe et al. (2013) who observed an increase in GPP during the dry season based on observations at the flux towers K34, K67 and K83.

The Reco value ^{estimated} ~~estimates~~ by JULES are underestimated in the wet season ^(April) ~~April~~ when compared to Botia et al. (2022), which reported a mean value of $350 \text{ g C m}^{-2} \text{ month}^{-1}$ for the wet season at the ATTO tower. In the dry season, however, Reco estimates were similar to the values reported by Botia et al. (2022) ($200 \text{ g C m}^{-2} \text{ month}^{-1}$) in the same region, which suggests that further improvements are needed to better reproduce the seasonality of ^{Reco, particularly, in the Amazon basin} ~~Reco in Amazonia, particularly in the Amazon basin~~.



520

Figure 6: Monthly accumulated GPP, Reco, and NEE for April and September, representing the wet and dry season in the Brazilian Amazon biome in 2021.

525 To further evaluate the spatialized model results, the simulated NEE fluxes for the year of 2021 were compared to the following estimates (Figure 7): i) European Carbon Tracker CT 2022 (Jacobson et al., 2023); ii) FluxCom-X (Nelson et al., 2024); iii) JULES simulation using fixed average values for the BET-TR parameters, considering the optimized values presented in Table 4; iv) JULES simulation using default parameter values (Harper et al., 2016).

530 Figure 7 clearly shows that the three different modelling approaches using JULES (optimized, default, and spatially fixed best adjusted parameters) result in an **overestimation of the carbon sink** in Amazonia (i. e., more negative NEE values) during both the wet and dry seasons, when compared to Carbon Tracker and FluxCom-X. The JULES run with spatialized vegetation parameters reveals spatial structures in the NEE fluxes, such as the less intense carbon sink observed in the far western Amazonian region (Acre state). There are no carbon flux measurements in this region to be used as ground truth, but the optimized Carbon Tracker estimates also indicate less intense carbon sink in this area, or even a carbon source (NEE>0) 535 in the wet season (Figure 7). Another spatial pattern revealed in the JULES simulation with spatialized vegetation parameters was a reduced carbon sink in northern Amazonia (Amapa state and northern Para state), where the Carbon Tracker and the FluxCom-X datasets also detected reduced carbon sinks or even carbon sources.

The regions of Acre and Amapa **regions** demonstrated a high carbon source. What these regions have in common are canopy heights above the average, with trees reaching above 35 m in Amapa (Figure 1). Compared to FluxCom-X, JULES 540 simulated a stronger carbon sink across the Brazilian Amazon biome during both the wet and dry months, except in forests located in the states of Amapa and Acre (Figure 7). This feature was also observed in the average JULES version and can be attributed to a modification of the tupp parameter in the BET-TR (43 °C). Restrepo-Coupe et al. (2017) simulated a reduction of GPP during the dry season, however the version used in this study was ~~the~~ 2.1, based on the parameterization of Clark et al. (2011), which considered a tupp of 36 °C in comparison ^{with} of our study that utilized a tupp between 36 ^{and} to 45°C as a limit in the 545 calibration procedure. Also, another relevant aspect that may have induced the GPP increases in JULES's simulations was the higher values of f0 observed in some regions calibrated in this study, such as ATTO and K34 (**0.95 and 0.93, respectively**). The modification of f0 led to a reduction in water stress, mainly in areas of the Amazon associated with the Amazon basin and the northern region of the State of Mato Grosso. Moreover, f0 may also help explain the carbon source in the states of Amapá and Acre, as the calibration procedure indicated an f0 value near 0.7 in regions with more sparsely spaced trees (LAI <4.0), 550 which can contribute to an increase of Reco, as shown in Figure 3.

Although JULES simulations highly overestimated the carbon sink, they showed a **similar trend** compared to the Carbon Tracker estimates, with an increase in magnitude of the carbon sink from April to September. The states of Acre and Amapa showed similar patterns to Carbon Tracker, both representing a reduced carbon sink in this areas (less than 50 g C m⁻² month⁻¹) (Figure 7). This similarity can be explained by the effects of the spatialization of JULES parameters mainly in regions 555 with tall trees as the case of forests of Amapa and Acre. During the wet month, Carbon Tracker showed a larger carbon source area across the Amazon biome compared to FluxCom-X, which represented a carbon source mainly in April in Amapá, in some regions of Amazon basin, the state of Acre, and the deforested areas of Roraima. (Figure 7). During September, Carbon Tracker was similar to FluxCom-X in representing a carbon sink across most of the Brazilian Amazon biome. However,

FluxCom-X showed a carbon source in the arc of deforestation, which was not indicated by either JULES or Carbon Tracker. Another important aspect was that the **spatialized JULES model** leads to a weaker sink of carbon in NEE in comparison to the default and mean versions (Figure 7).





Figure 7: Comparison of NEE fluxes for April (wet season) and September (dry season) of 2021 using different modeling approaches: JULES model with spatialized vegetation parameters (spatialized JULES); European Carbon Tracker, FluxCom-X, JULES model using the spatially constant mean values of optimized vegetation parameters (mean JULES), and JULES model using default vegetation parameter values (default JULES). Differences between spatialized JULES and the other estimates are also presented.

it would be helpful to say explicitly whether positive or negative “difference” values indicate a stronger carbon sink in the spatialized JULES model

After applying the spatialization procedure and comparing with different models, the JULES model was run for the entire year of 2021. Monthly accumulated NEE values were summed up from each $1^\circ \times 1^\circ$ pixel to estimate NEE for the Brazilian Amazon biome, resulting in $-1.34 \text{ Pg C year}^{-1}$. It is important to mention that this value represents the sum of different regions within the Amazon biome (Figure 8). The one-year accumulation revealed that the most concentrated carbon sources are located in the states of Amapa and Acre, with values exceeding $0.75 \text{ Kg C m}^{-2} \text{ year}^{-1}$ of carbon released to the atmosphere. Some regions stood out as strong carbon sinks (below $-1.0 \text{ Kg C m}^{-2} \text{ year}^{-1}$) as the forest in the north of the State of Mato Grosso (longitude 53°W and latitude 12°S) and the forest of São Gabriel da Cachoeira (longitude 74°W and latitude 0°N). The forests in the Amazon basin also demonstrated a high carbon sink (-0.25 to $1.0 \text{ Kg C m}^{-2} \text{ year}^{-1}$) during 2021.



580 **Figure 8: NEE accumulated in Kg C m^{-2} during 2021 in the Brazilian Amazon biome.**
[^]in the spatialized JULES model

4. **Discussion** I recommend starting the discussion with a clear statement of the most important parts of the results, instead of going through the order of the analyses strictly.

4.1. **JULES optimization**

585

The optimization of JULES for four parameters at the four flux tower sites in this study showed convergence in their values, consistent with the findings of Clark et al. (2011) for tupp value (36 °C) for Santarém and Jarú, and the f0 value for Jarú (0.875). Additionally, the f0 value calibrated for Santarém in this study was close to that reported by Raoult et al. (2016), which was 0.765. The tupp values for ATTO and K34 were similar to those reported by Harper et al. (2016), who increased tupp to 43 °C for tropical forests. The parameter fd was similar to the value reported by Harper et al. (2016) for ATTO and K34, however, it was lower than 0.01 for Santarém and Jarú, with values of 0.0066 and 0.007, respectively. The alpha parameter was lower than that in all previous JULES calibration studies for each of the towers. However, the results of this study for alpha parameter are in line with the values near 0.05 and 0.06 mol PAR mol CO₂⁻¹ reported by Skilman (2008), who analyzed different types of C₃ plants, including Broadleaf Evergreen Trees. This could be explained by the way that the default version overestimated GPP in comparison to the calibrated version (Figure 4).

I don't think "More variable" is what is meant to be communicated here, as the value doesn't vary much among sites (as stated next)

The cross-validation procedure also showed that the alpha parameter was more variable than the other parameters (Figure S4.2). This may be explained by the fact that the values for each tower were nearly constant, with a difference of only 0.0016 mol PAR mol CO₂⁻¹, while the other parameters exhibited greater variability between sites. The spatialized JULES also showed lower RMSE for NEE compared to VPRM model. This can be explained by the greater complexity of how JULES estimates GPP and, particularly, Reco. VPRM uses a simpler approach, relying on a linear regression in which air temperature is the sole independent variable (Gourdji et al., 2022). In contrast, JULES estimates GPP and Reco with more sophisticated equations that account for factors such as water stress, nitrogen content in different plant components (Best et al., 2011; Clark et al., 2011), photosynthesis light saturation (equation 3), and CO₂ leaf concentration (equation 5). The optimization of the parameters alpha, tupp, f0 and fd explain the improvement in the performance compared to the default version and to the VPRM model.

605

4.2. **NEE estimates using JULES spatialized**

The first relevant aspect that spatialized JULES was able to reproduce was the increase of GPP during the dry season, showing that water may not be a limitation for carbon assimilation in the Amazonian dry season (Figure 3 and Figure 6). Restrepo-Coupe et al. (2013) also observed the same feature by comparing different Eddy-Covariance towers spread in the Brazilian Amazon biome. The main driver for seasonality in this region is Canopy Photosynthetic Capacity and the leaf phenology (Restrepo-Coupe et al., 2013). The use of different parameterizations in different sites across the Amazon biome, how is this possible, if the parameters don't change in time? this seems more appropriate as a "future direction" to me with different LAI values, may have helped capture the effect of leaf phenology, particularly the emergence of new leaves, which tend to open their stomata for photosynthesis more frequently than older leaves approaching senescence (Wu et al.,

615 2016). The absence of phenology representation in some process-based models was noted by Restrepo-Coupe et al. (2017) and Botia et al. (2022), who observed a tendency for these models to underestimate GPP during the dry season. In contrast, the spatialization method used in this study, incorporating varying parameters based on LAI and canopy height, improved the model's ability to simulate GPP and Reco with greater diversity (Figure 6).

The spatialized JULES generated values of NEE between 0.75 and -1.25 Kg C m⁻² year⁻¹. This range ^{includes the mean value} ~~is according to the~~ ^{reported} ~~observed~~ by Lian et al. (2023), which estimated an average value of NEE in the South America Forest of -0.205 Kg C m⁻² year⁻¹ using a Random Forest Model applied in a global system. The spatialized JULES also demonstrated that the major focus of carbon sources was located in the states of Amapa and Acre (Figure 7). The forest of Amapa has ~~the characteristic of having~~ tall trees (> 35 m) and a low leaf area index (< 4.5 m² m⁻²) ~~even~~ ^{high} considering that this region has ~~the major~~ above-ground biomass ~~of the Amazon biome~~, reaching 518 Mg ha⁻¹ (Ometto et al., 2023). The spatialization reduced the tupp and f0, which ~~may lead to a reduction in GPP in relation to Reco, generating a carbon source in this region.~~ ~~A possible explanation is increased~~ ~~Reco in mature and tall forests, such as those found in the Amapa region.~~ ^{repetitive with previous sentence?} West (2020) observed in a review of studies with different tree species that the costs of respiration increase over the years while GPP remains constant, which could explain the net carbon source. The costs are based on adjustments in morphology and anatomy to construct new structures in the xylem, roots, and leaves to support the high amount of biomass. Concerning the state of Acre there is a climatic condition that can explain the carbon source in this region, since annual rainfall is lower than 2000 mm (Silva et al., 2020), which can increase the cost of maintenance and hence the respiration to avoid hydric stress. It is important to have eddy-covariance measurements in this region, to confirm the trend of carbon source.

The total NEE estimated for the Brazilian Amazon biome demonstrated a carbon sink (NEE) of -1.34 Pg C year⁻¹. The result obtained in this study is between the results obtained by Chen et al. (2024), which estimated the NEE in the Amazon ^{basis} region using the Trendy-v11 (-0.94 Pg C year⁻¹) and FluxCom-RS (-3.46 Pg C year⁻¹) ^{models} on an annual ~~average~~ between 2001-2015. It is important to mention that the FluxCom version utilized to analyze the NEE across the Brazilian Amazon biome (Figure 7) is a new version with the X-BASE database (Nelson et al., 2024) in comparison to the FluxCom-RS utilized by Chen et al. (2024). The new version of FluxCom reduced the global NEE in relation to ~~the~~ FluxCom-RS (-21 to -7 Pg C year⁻¹). Trendy v-11 is a dataset that provides global gridded carbon fluxes data from 16 different types of vegetation dynamics ^{sensitivity} models (Sitch et al., 2024). Our result was closer to ~~the~~ Trendy than to ~~the~~ FluxCom-RS, which can be favorable considering the uncertainties in the NEE partitioning in FluxCom-RS, ^{with} ~~being the~~ Reco partitioned by the NEE instead of subtracting GPP to get NEE (Jung et al., 2020). Due to this reason, FluxCom-RS underestimated Reco and tends to estimate a higher carbon sink. JULES is included in Trendy v-11, however, the version utilized to simulate carbon fluxes was JULES 5.1 (Wiltshire et al., 2021). In this version, JULES has only five Plant Function Types and the version we utilized to simulate carbon flux is ^{use} ~~have~~ the parametrization specific for ~~the~~ Tropical Evergreen Broadleaf ^{trees} ~~tree~~ (Harper et al., 2016). One ~~sensitivity~~ parameter modified in this version was ~~the~~ tupp (36°C in the Clark et al 2011 to 43°C in the Harper et al., 2016). This could be a reason that the carbon sink in the Brazilian Amazon biome is larger than the JULES version in TRENDY, ^{because} ~~being~~ this parameter relevant for GPP. Due to this reason, in ~~the~~ section S.5 of supplementary material, we compared the ^{is} ~~the~~ ^{the}

default with the spatialized version and the version utilized in Trendy v-11 based on Clark et al 2011 parametrization which demonstrates that the Harper et al., (2016) version tends to overestimate the carbon sink while and the spatialized JULES version agrees approximate with observed data in ATTO tower for 2018 (see Supplementary material, Figure S5.1).

In comparison with the annual value obtained by the mean and default versions of JULES (Harper et al., 2016), the default version obtained a carbon sink of -3.08 Pg C per year (see Supplementary Material, Figure S5.2), while the mean version obtained a carbon sink of -2.06 Pg C per year (see Supplementary Material, Figure S5.3). The default version of JULES presented a value similar to that obtained by FluxCom-RS (-3.46 Pg C per year), demonstrating that the calibration procedure adopted in this study improved the carbon simulations by JULES despite the lack of FluxCom-RS equations to simulate Reco. Another piece of evidence demonstrating the improvements made by the calibration procedure is that the mean value of the optimised parameters reduced the carbon sink in the Brazilian Amazon biome by 33.12% compared to the default value. The spatialised version of JULES reduced the carbon sink of the Brazilian Amazon biome by 56.49% compared to the default version and by 34.96% compared to the mean version, reaching a value closest to that provided by Trendy-v11 (-0.94 Pg C year⁻¹) by Chen et al. (2024). This reduction in the carbon sink can mainly be explained by the regions of Acre, as shown in Figures S5.2 and S5.3 for the default and mean versions, respectively. This can be considered the effect of the method of spatialising the sensitivity parameters f_0 and f_d , which are directly related to water stress (Clark et al., 2011), as characterised in this region. The same aspect can explain why the spatialised version of JULES demonstrated a high carbon source in the south of the Amazonian state (>0.50 kg C m⁻² year⁻¹), which the default and mean parametrizations did not capture (between 0 and 0.25 kg C m⁻² year⁻¹). However, it is worth noting that the state of Amapá demonstrates a carbon source in all three versions of JULES, reaching 0.75 kg C m⁻² year⁻¹. This suggests that the height of the tree canopy in this region contributes to the carbon source.

The result of -1.34 Pg C year⁻¹ was lower than found by other studies related to the Amazon region as Botia et al (2024) (-0.33 Pg C year⁻¹) and Rosan et al (2024) (-0.34 Pg C year⁻¹), however, some aspects need to be considered. The first aspect is related to the number of years evaluated in these studies in relation to our study. We have just evaluated the year 2021 instead of other studies that evaluated more than ten years, as the case of Chen et al (2024) and nine years as the case Botia et al (2024). In order to assess access uncertainties and the importance of interannual variability in NEE, future studies could perform simulations for additional years, using the spatialization of parameters developed here. The second aspect is that the carbon flux obtained by Botia et al (2024) (Net Land Flux) is the sum between river fluxes and NEE; in our simulation, we have just the NEE obtained by vegetation, similar than the paper by Chen et al (2024) which generated a NEE of -0.94 Pg C year⁻¹ using the Trendy-v11 and 3.46 Pg C year⁻¹. The third aspect is related to the fire emissions that can contribute to reducing the carbon sink, this value can vary 0.09 Pg C year⁻¹ (Rosan et al., 2024) to 0.41 Pg C year⁻¹ (Gatti et al., 2021).

Another important aspect to be mentioned and that can contribute to this distance between other models is that some process-based models can overestimate the carbon sink in tropical forests, as previously related by Restrepo-Coupe et al., (2017) and also by Botia et al. (2022) mainly when compared with inversion models as Carbon Tracker. The reason can be explained by the incorrect assumption of water limitation and the lack of leaf phenology in model formulations (Gonçalves et

al., 2020). Also, JULES demonstrated a higher sink in other types of vegetation presented in the Amazon biome as C4 grass (Harper et al., 2016) and C3 crops (Williams et al., 2017; Prudente Junior et al., 2022) in regions such as the states of Mato Grosso, Roraima, and east of Pará (Figure 8). In a region predominantly composed by C4 grass (longitude 49.5°W, latitude 7.5°S), with 84.5 % of C4 grass (see supplementary material, Figure S3.1.1), JULES simulated a carbon sink of $-250 \text{ g C m}^{-2} \text{ year}^{-1}$ (Figure 8). This value is higher (more negative) than that reported by Bezerra et al., (2022), which obtained in eddy-Covariance tower a NEE annual mean of $-215 \text{ g C m}^{-2} \text{ year}^{-1}$ in the Brazilian Northeast, working with *Urochloa brizantha cv Marandu*, the most relevant pasture used in the arc of deforestation. This indicates that tropical grassland can be considered a carbon sink mainly in regions with latitude near 15° S to 0° , with similar radiation levels during different seasons of the year. However, it is important to point out that the improvement of grassland parameterization is out of the scope of the current study. One step that can improve the estimate of NEE in the arc of deforestation can be the calibration and evaluation in agricultural crops, which can reduce the carbon sink in the regions of Mato Grosso and Roraima. Another area for improvement in future studies would be to use other canopy height databases, such as those based on airborne LIDAR observations, to improve the spatialisation of plant physiological parameters

The spatialized JULES demonstrated a higher carbon sink in comparison to FluxCom-X and the European Carbon Tracker in the Amazon basin, deforestation arc, and North of Mato Grosso, although it presented a higher carbon source in the states of Acre and Amapá. However, the new optimization and the spatialization approach showed improvements over the version used by Harper et al. (2016), which applied averaged optimized parameters. In addition to reducing the estimated carbon sink, it also highlighted the influence of vegetation heterogeneity on the spatial distribution of carbon budget across the Amazon biome, particularly in the states of Amapá and Acre.

5. Conclusions

This study presented a new method to estimate NEE from an adjusted land surface model, with parameters spatialized using the adjusted land surface model and spatialization considering two relevant vegetation properties: Canopy height and LAI. The first aspect presented in this study was to demonstrate the most sensitive parameters for NEE, which were canht, tupp, alpha, f0 and fd the most important parameters for the parameterization procedure. The optimization of selected JULES parameters for the PFT BET-TR led to a reduction in both RMSE and the d-index across all four analyzed towers, when compared to the default parameter values and the VPRM model. Our attempt of spatialization was validated in an independent tower, generating a better performance than VPRM and the default version of JULES. In general, the spatialized JULES model showed a stronger carbon sink in the northern Amazon region and across the Amazon basin compared to FluxCom-X and Carbon Tracker, particularly during the month of September. However, the spatialized version of JULES also indicated significant carbon source regions ($> 75 \text{ g C m}^{-2} \text{ month}^{-1}$) in Amapá and Acre. This highlights the importance of considering how forests with tall canopy height ($> 35\text{m}$), such as those in Amapá, and the influence of climate conditions, as observed in Acre, contribute to the overall carbon budget. The spatialized JULES

resulted in a NEE ^{estimate} ~~estimative~~ of -1.34 Pg C during 2021, which is a value that approaches those ^{of} ~~with~~ dynamic vegetation models for the Amazon biome.

720 Despite the advances presented in this study, some aspects still need more robust explanations. One of these aspects is related to the strong carbon source in the regions of Amapá and Acre, ^{awkward wording, I'm not sure what the intent is} ~~being the simulations obtained by JULES in 2021 a~~
725 ~~relevant aspect to better investigate the carbon balance in these regions~~. It is important to note that this study developed an optimization of JULES using a limited number of ~~eddy Covariance towers~~. While this approach improved model simulations, further improvements could be achieved by installing additional towers in different forest types across the Amazon region, ^{please make sure this is capitalized and hyphenated consistently throughout} especially in regions with tall canopy heights (> 35 m). Another aspect that could be improved is the simulation of regions dominated by agricultural land uses, such as soybean, maize, and pasture. These areas, particularly in northern Mato Grosso,
730 are relevant because the model currently simulates them as carbon sinks. Despite the development of JULES-crop, this model is not coupled in the most recent version of JULES, a feature that could improve simulations in agricultural zones. Additionally, calibration and evaluation using Eddy covariance towers in croplands and pastures could improve model performance in the deforestation arc. Despite these limitations, this study highlights the relevance of spatializing NEE using vegetation indices, demonstrating how this approach can improve the ^{estimation} ~~mapping~~ of carbon fluxes in the Brazilian Amazon biome by identifying source and sink regions in relation to forest height and density.

Funding Information

Funding sources include the support of the RCGI – Research Centre for Greenhouse Gas Innovation hosted by the University of São Paulo and sponsored by FAPESP – São Paulo Research Foundation (process number 2020/15230-5).
735 FAPESP also funds the projects 2023/06623-1, 2022/07974-0, 2023/04358-9 and 2024/12950-8. Also, the CNPq - National Council for Scientific and Technological Development to fund the project 304819/2022-0.

Data and code availability

The dataset covering all simulations described in this report is available at this
740 link:http://ftp.lfa.if.usp.br/ftp/public/LFA_Processed_Data/articles_database/Prudente_2025/.

Author contributions

ACPJ wrote the initial manuscript and ran the JULES model for the Brazilian Amazon biome. ACPJ, together with LATM, LVR, SB, and FSS, designed the methodology. DSM assisted in adapting JULES for the Amazon region. LPC ran VPRM
745 model for different sites across the Brazilian Amazon biome. CQDJ provided meteorological data measured in the ATTO tower. LATM, LVR, PEAN, TA and EF provided Amanan's computers to run JULES. LATM, CP, SB and PEAN consolidated funding for the postdoctoral position and an exchange period at the Max Planck Institute for Biogeochemistry in Jena. LATM, LVR, XX, SB helped with the data curation and the interpretation of the results. IMCT helped to improve observed carbon

fluxes at different sites in the Amazon region. FSS contributed to developing scripts to run JULES and to designed figures presented in the manuscript. LATM, LVRM, XX, SB, FSS, EF, CQDJ and IVCT contributed to review the manuscript.

Competing interests

The authors declare that they have no conflict to interest.

Acknowledgment

The authors acknowledge the use of the Amanan's Clusters, a collaborative facility supplied under the Institute of Astronomy, Geophysics and Atmosphere Science of the University of São Paulo. Also, the Max Planck Institute of Biogeochemistry for the ATTO towers data availability and the São Paulo Research Foundation to fund the project 2023/06623-1.

References

- Aguirre-Gutiérrez, J., Rifai, S. W., Deng, X., Ter Steege, H., Thomson, E., Corral-Rivas, J. J., ... & Malhi, Y.: Canopy functional trait variation across Earth's tropical forests. *Nature*, 1-8. <https://doi.org/10.5281/zenodo.14509493>, 2025.
- Andreae, M. O., Acevedo, O. C., Araújo, A., Artaxo, P., Barbosa, C. G. G., Barbosa, H. M. J., Brito, J., Carbone, S., Chi, X., Cintra, B. B. L., da Silva, N. F., Dias, N. L., Dias-Júnior, C. Q., Ditas, F., Ditz, R., Godoi, A. F. L., Godoi, R. H. M., Heimann, M., Hoffmann, T., Kesselmeier, J., Könemann, T., Krüger, M. L., Lavric, J. V., Manzi, A. O., Lopes, A. P., Martins, D. L., Mikhailov, E. F., Moran-Zuloaga, D., Nelson, B. W., Nölscher, A. C., Santos Nogueira, D., Piedade, M. T. F., Pöhlker, C., Pöschl, U., Quesada, C. A., Rizzo, L. V., Ro, C.-U., Ruckteschler, N., Sá, L. D. A., de Oliveira Sá, M., Sales, C. B., dos Santos, R. M. N., Saturno, J., Schöngart, J., Sörgel, M., de Souza, C. M., de Souza, R. A. F., Su, H., Targhetta, N., Tóta, J., Trebs, I., Trumbore, S., van Eijck, A., Walter, D., Wang, Z., Weber, B., Williams, J., Winderlich, J., Wittmann, F., Wolff, S., and Yáñez-Serrano, A. M.: The Amazon Tall Tower Observatory (ATTO): overview of pilot measurements on ecosystem ecology, meteorology, trace gases, and aerosols. *Atmospheric Chemistry and Physics*, 15(18), 10723-10776. <https://doi.org/10.5194/acp-15-10723-2015>, 2015.
- Best, M. J., Pryor, M., Clark, D. B., Rooney, G. G., Essery, R. L. H., Ménard, C. B., Edwards, J. M., Hendry, M. A., Porson, A., Gedney, N., Mercado, L. M., Sitch, S., Blyth, E., Boucher, O., Cox, P. M., Grimmond, C. S. B., and Harding, R. J. (2011). The Joint UK Land Environment Simulator (JULES), model description–Part 1: Energy and water fluxes. *Geoscientific Model Development*, 4(1), 677–699. <https://doi.org/10.5194/gmd-4-677-2011>, 2011.
- Bezerra, B. G., e Silva, C. M. S., Mendes, K. R., Mutti, P. R., Fernandes, L. S., Marques, T. V., and Lucio, P. S.: CO2 exchanges and evapotranspiration of a grazed pasture under tropical climate conditions. *Agricultural and Forest Meteorology*, 323, 109088. <https://doi.org/10.1016/j.agrformet.2022.109088>, 2022.

- Botía, S., Komiya, S., Marshall, J., Koch, T., Gałkowski, M., Lavric, J., and Gerbig, C.: The CO₂ record at the Amazon Tall Tower Observatory: A new opportunity to study processes on seasonal and inter-annual scales. *Global Change Biology*, 28(2), 588-611. <https://doi.org/10.1111/gcb.15905>, 2022.
- 785 Botía, S., Munassar, S., Koch, T., Custodio, D., Basso, L. S., Komiya, S., and Gerbig, C.: Combined CO₂ measurement record indicates decreased Amazon forest carbon uptake, offset by Savannah carbon release. *EGUsphere*, 2024, 1-55. <https://doi.org/10.5194/egusphere-2024-1735>, 2024.
- Boussetta, S., Balsamo, G., Beljaars, A., Kral, T., and Jarlan, L.: Impact of a satellite-derived leaf area index monthly climatology in a global numerical weather prediction model. *International journal of remote sensing*, 34(9-10), 3520-3542. <https://doi.org/10.1080/01431161.2012.716543>, 2013.
- 790 Brienen, R. J., Phillips, O. L., Feldpausch, T. R., Gloor, E., Baker, T. R., Lloyd, J., Lopes-Gonzalez, G., Monteagudo-Mendoza, A., Malhi, Y., Lewis, L.S., Vasques Martinez, R., Alexiades, M., Alvarez Davila, E., Alvares Loyaza, P., Andrade, A., Aragão, L.E.O.C., Muramaki, A.A., Arets, E.J.M.M., Arroyo, L., Aymard, C.G.A., Banki, O.S., Baraloto, C., Barroso, J., Donal, D., Zagt, R. J. (2015). Long-term decline of the Amazon carbon sink. *Nature*, 519(7543), 344-348. <https://doi.org/10.1038/nature14283>, 2015.
- 795 Caen, A., Smallman, T. L., de Castro, A. A., Robertson, E., von Randow, C., Cardoso, M., and Williams, M.: Evaluating two land surface models for Brazil using a full carbon cycle benchmark with uncertainties. *Climate Resilience and Sustainability*, 1(1), e10. <https://doi.org/10.1002/cli2.10>, 2022.
- Chandrasekar, K., Sessa Sai, M. V. R., Roy, P. S., and Dwevedi, R. S.: Land Surface Water Index (LSWI) response to rainfall and NDVI using the MODIS Vegetation Index product. *International Journal of Remote Sensing*, 31(15), 3987-4005. <https://doi.org/10.1080/01431160802575653>, 2010.
- 800 Chen, B., Xu, X., Wang, S., Yang, T., Liu, Z., and Falk, S.: Carbon dioxide fertilization enhanced carbon sink offset by climate change and land use in Amazonia on a centennial scale. *Science of The Total Environment*, 955, 176903. <https://doi.org/10.1016/j.scitotenv.2024.176903>, 2024.
- Clark, D. B., Mercado, L. M., Sitch, S., Jones, C. D., Gedney, N., Best, M. J., Pryor, M., Rooney, G. G., Essery, R. L. H., Blyth, E., Boucher, O., Harding, R. J., Huntingford, C., and Cox, P. M.: The Joint UK Land Environment Simulator (JULES), model description – Part 2: Carbon fluxes and vegetation dynamics, *Geosci. Model Dev.*, 4, 701–722, <https://doi.org/10.5194/gmd-4-701-2011>, 2011.
- Collatz, G. J., Ball, J. T., Grivet, C., & Berry, J. A.: Physiological and environmental regulation of stomatal conductance, photosynthesis and transpiration: a model that includes a laminar boundary layer. *Agricultural and Forest meteorology*, 54(2-4), 107-136. [https://doi.org/10.1016/0168-1923\(91\)90002-8](https://doi.org/10.1016/0168-1923(91)90002-8), (1991)
- 810 Collatz, G. J., Ribas-Carbo, M., & Berry, J. A. (1992). Coupled photosynthesis-stomatal conductance model for leaves of C₄ plants. *Functional Plant Biology*, 19(5), 519-538. <https://doi.org/10.1071/PP9920519>
- Dakhlaoui, H. (2014). Vers une procédure de calage automatique plus efficiente du modèle HBV (Doctoral dissertation, Thèse de Doctorat en Génie Hydraulique. Université de Tunis El Manar).

- 815 De Lima Filho, R. R. (2021). Produtor de soja deve ter um bom lucro na safra 2021/22. *AgroANALYSIS*, 41(9), 15-17.
- Fernandes, L. D. O., Reis, R. D. A., Paes, J. M. V., Teixeira, R. M. A., Queiroz, D. S., Paschoal, J. J., and PASCHOAL, J. J.: Desempenho de bovinos da raça Gir em pastagem de *Brachiaria brizantha* submetidos a diferentes manejos. *Revista Brasileira de Saúde e Produção Animal*, 16(1), 36-46. <https://doi.org/10.1590/S1519-99402015000100004>, 2015.
- Friedlingstein, P., O'Sullivan, M., Jones, M. W., Andrew, R. M., Gregor, L., Hauck, J., Le Quéré, C., Luijkx, I. T., Olsen, A.,
820 Peters, G. P., Peters, W., Pongratz, J., Schwingshackl, C., Sitch, S., Canadell, J. G., Ciais, P., Jackson, R. B., Alin, S. R.,
Alkama, R., Arneeth, A., Arora, V. K., Bates, N. R., Becker, M., Bellouin, N., Bittig, H. C., Bopp, L., Chevallier, F., Chini, L.
P., Cronin, M., Evans, W., Falk, S., Feely, R. A., Gasser, T., Gehlen, M., Gkritzalis, T., Gloege, L., Grassi, G., Gruber, N.,
Gürses, Ö., Harris, I., Hefner, M., Houghton, R. A., Hurtt, G. C., Iida, Y., Ilyina, T., Jain, A. K., Jersild, A., Kadono, K., Kato,
E., Kennedy, D., Klein Goldewijk, K., Knauer, J., Korsbakken, J. I., Landschützer, P., Lefèvre, N., Lindsay, K., Liu, J., Liu,
825 Z., Marland, G., Mayot, N., McGrath, M. J., Metzl, N., Monacci, N. M., Munro, D. R., Nakaoka, S.-I., Niwa, Y., O'Brien, K.,
Ono, T., Palmer, P. I., Pan, N., Pierrot, D., Pocock, K., Poulter, B., Resplandy, L., Robertson, E., Rödenbeck, C., Rodriguez,
C., Rosan, T. M., Schwinger, J., Séférian, R., Shutler, J. D., Skjelvan, I., Steinhoff, T., Sun, Q., Sutton, A. J., Sweeney, C.,
Takao, S., Tanhua, T., Tans, P. P., Tian, X., Tian, H., Tilbrook, B., Tsujino, H., Tubiello, F., van der Werf, G. R., Walker, A.
P., Wanninkhof, R., Whitehead, C., Willstrand Wranne, A., Wright, R., Yuan, W., Yue, C., Yue, X., Zaehle, S., Zeng, J., and
830 Zheng, B.: Global Carbon Budget 2022, *Earth Syst. Sci. Data*, 14, 4811–4900, <https://doi.org/10.5194/essd-14-4811-2022>,
2022.
- Gatti, L. V., Basso, L. S., Miller, J. B., Gloor, M., Gatti Domingues, L., Cassol, H. L. G., Tejada, G., Aragão, L. E. O. C.,
Nobre, C., Peters, W., Marani, L., Arai, E., Sanches, A. H., Corrêa, S. M., Anderson, L., Von Randow, C., Correia, C. S. C.,
Crispim, S. P., and Neves, R. A. L.: Amazonia as a carbon source linked to deforestation and climate change, *Nature*, 595,
835 388–393, <https://doi.org/10.1038/s41586-021-03629-6>, 2021, 2021.
- Gatti, L.V., Basso, L.S., Miller, J.B., Gloor, M., Gatti Domingues, L., Cassol, H.L.G., Tejada, G., Aragao, L.E.O.C., Nobre,
C., Peters, W., Marani, L., Arai, E., Sanches, A. H., Correa, S.M., Anderson, L., Von Randow, C., Correia, C.S.C., Crispim,
S.P., and Neves, R.A.L.: Amazonia as a carbon source linked to deforestation and climate change. *Nature* 595 (7867).
<https://doi.org/10.1038/s41586-021-03629-6>, 2021.
- 840 Gonçalves, N. B., Lopes, A. P., Dalagnol, R., Wu, J., Pinho, D. M., and Nelson, B. W.: Both near-surface and satellite remote
sensing con_rm drought legacy e_ect on tropical forest leaf phenology after 2015/2016 ENSO drought. *Remote Sensing of
Environment*, 237, 111489. <https://doi.org/10.1016/j.rse.2019.111489>, 2020.
- Gourdji, S. M., Karion, A., Lopez-Coto, I., Ghosh, S., Mueller, K. L., Zhou, Y., ... and Whetstone, J. R.: A modified Vegetation
Photosynthesis and Respiration Model (VPRM) for the eastern USA and Canada, evaluated with comparison to atmospheric
845 observations and other biospheric models. *Journal of Geophysical Research: Biogeosciences*, 127(1),
e2021JG006290. <https://doi.org/10.1029/2021JG006290>, 2022.
- Grubbs, F. E: Procedures for detecting outlying observations in samples. *Technometrics*, 11(1), 1-21.
<https://doi.org/10.1080/00401706.1969.10490657>, 1969.

- 850 Harper, A. B., Cox, P. M., Friedlingstein, P., Wiltshire, A. J., Jones, C. D., Sitch, S., and Bodegom, P. V.: Improved representation of plant functional types and physiology in the Joint UK Land Environment Simulator (JULES v4. 2) using plant trait information. *Geoscientific Model Development*, 9(7), 2415-2440. <https://doi.org/10.5194/gmd-9-2415-2016>, 2015.
- Harper, A. B., Wiltshire, A. J., Cox, P. M., Friedlingstein, P., Jones, C. D., Mercado, L. M., ... & Duran-Rojas, C. Vegetation distribution and terrestrial carbon cycle in a carbon cycle configuration of JULES4. 6 with new plant functional types. *Geoscientific Model Development*, 11(7), 2857-2873,2018. <https://doi.org/10.5194/gmd-11-2857-2018>
- 855 Harris, C. R., Millman, K. J., Van Der Walt, S. J., Gommers, R., Virtanen, P., Cournapeau, D., and Oliphant, T. E.:Array programming with NumPy. *Nature*, 585(7825), 357-362, <https://doi.org/10.1038/s41586-020-2649-2> , 2020.
- Hayek, M. N., Wehr, R., Longo, M., Hutyra, L. R., Wiedemann, K., Munger, J. W., Bonal, D., Saleska, S. R., Fitzjarrald, D. R., and Wofsy, S. C.: A novel correction for biases in forest eddy covariance carbon balance, *Agr. Forest Meteorol.*, 250–251, 90– 101, <https://doi.org/10.1016/j.agrformet.2017.12.186>, 2018.
- 860 Hersbach, H., Bell, B., Berrisford, P., Hirahara, S., Horányi, A., Muñoz-Sabater, J., ... & Thépaut, J. N.: The ERA5 global reanalysis. *Quarterly Journal of the Royal Meteorological Society*, 146(730), 1999-2049. <https://doi.org/10.1002/qj.3803> , 2020.
- Jacobson, A. R. et al. CarbonTracker CT2022. <https://doi.org/10.25925/z1gj-3254> (2023).
- Jérôme, Z. P., Eric, A. A., Ezéchiél, O., Eliézer, B. I., and Ezin, E. C.: An automatic optimization technique for the calibration of a physically based hydrological rainfall-runoff model. *Journal of Geoscience and Environment Protection*, 9(3), 1-20. <https://doi.org/10.4236/gep.2021.93001>, 2021.
- Jung, M., Schwalm, C., Migliavacca, M., Walther, S., Camps-Valls, G., Koirala, S., Anthoni, P., Besnard, S., Bodesheim, P., Carvalhais, N., Chevallier, F., Gans, F., S Goll, D., Haverd, V., Kohler, P., Ichii, K., K Jain, A., Liu, J and Lombardozzi, D.. Scaling carbon fluxes from eddy covariance sites to globe: synthesis and evaluation of the FLUXCOM approach. *Biogeosciences* 17 (5), 1343–1365. <https://doi.org/10.5194/bg-17-1343-2020>, 2020.
- 870 Khanna, J., & Medvigy, D. Strong control of surface roughness variations on the simulated dry season regional atmospheric response to contemporary deforestation in Rondônia, Brazil. *Journal of Geophysical Research: Atmospheres*, 119(23), 13-067, 2014. <https://doi.org/10.1002/2014JD022278>
- Li, J., Wang, Y. P., Duan, Q., Lu, X., Pak, B., Wiltshire, A., and Ziehn, T.: Quantification and attribution of errors in the simulated annual gross primary production and latent heat fluxes by two global land surface models. *Journal of Advances in Modeling Earth Systems*, 8(3), 1270-1288. <https://doi.org/10.1002/2015MS000583>, 2016.
- Li, L., Chen, S., Yang, C., Meng, F., and Sigrimis, N.: Prediction of plant transpiration from environmental parameters and relative leaf area index using the random forest regression algorithm. *Journal of Cleaner Production*, 261, 121136. <https://doi.org/10.1016/j.jclepro.2020.121136>, 2020.
- 880 Lian, Y., Li, H., Renyang, Q., Liu, L., Dong, J., Liu, X., and Zhang, H.: Mapping the net ecosystem exchange of CO₂ of global terrestrial systems. *International Journal of Applied Earth Observation and Geoinformation*, 116, 103176. <https://doi.org/10.1016/j.jag.2022.103176>, 2023.

Liu, J., Bowman, K.W., Schimel, D.S., Parazoo, N.C., Jiang, Z., Lee, M., Bloom, A.A., Wunch, D., Frankenberg, C., Sun, Y., O'Dell, C.W., Gurney, K.R., Menemenlis, D., Gierach, M., Crisp, D., and Eldering, A.: Contrasting carbon cycle responses of the tropical continents to the 2015–2016 El Niño. *Science* 358 (6360). <https://doi.org/10.1126/science.aam5690>, 2017.

Loague, K., and Green, R. E.: Statistical and graphical methods for evaluating solute transport models: overview and application. *Journal of contaminant hydrology*, 7(1-2), 51-73. [https://doi.org/10.1016/0169-7722\(91\)90038-3](https://doi.org/10.1016/0169-7722(91)90038-3), 1991.

Mahadevan, P., Wofsy, S. C., Matross, D. M., Xiao, X., Dunn, A. L., Lin, J. C., and Gottlieb, E. W. : A satellite-based biosphere parameterization for net ecosystem CO₂ exchange: Vegetation Photosynthesis and Respiration Model (VPRM). *Global Biogeochemical Cycles*, 22(2). <https://doi.org/10.1029/2006GB002735>, 2008.

Malhi, G. S., Kaur, M., and Kaushik, P.: Impact of climate change on agriculture and its mitigation strategies: A review. *Sustainability*, 13(3), 1318. <https://doi.org/10.3390/su13031318>, 2021.

Marthews, T. R., Quesada, C. A., Galbraith, D. R., Malhi, Y., Mullins, C. E., Hodnett, M. G., and Dharssi, I. : High-resolution hydraulic parameter maps for surface soils in tropical South America. *Geoscientific Model Development*, 7(3), 711-723. <https://doi.org/10.5194/gmd-7-711-2014>, 2014.

Meir, P., Metcalfe, D.B., Costa, A.C.L., and Fisher, R.A.: The fate of assimilated carbon during drought: impacts on respiration in Amazon rainforests. *Philos. Trans. R. Soc., B* 363 (1498). <https://doi.org/10.1098/rstb.2007.0021>, 2008.

Moraes, R. M., Correa, S. B., Doria, C. R. C., Duponchelle, F., Miranda, G., Montoya, M., ... and ter Steege, H. Amazonian ecosystems and their ecological functions. Amazon assessment report 2021, 1, 2018.

Moreira, D. S., Freitas, S. R., Bonatti, J. P., Mercado, L. M., Rosário, N. E., Longo, K. M., & Gatti, L. V. : Coupling between the JULES land-surface scheme and the CCATT-BRAMS atmospheric chemistry model (JULES-CCATT-BRAMS1. 0): applications to numerical weather forecasting and the CO₂ budget in South America. *Geoscientific Model Development*, 6(4), 1243-1259. <https://doi.org/10.5194/gmd-6-1243-2013>, 2013.

Moudrý, V., Gábor, L., Marselis, S., Pracná, P., Barták, V., Prošek, J., and Wild, J.: Comparison of three global canopy height maps and their applicability to biodiversity modeling: Accuracy issues revealed. *Ecosphere*, 15(10), e70026, 2024.

Nelder, J. A., and Mead, R.: A simplex method for function minimization. *The computer journal*, 7(4), 308-313. <https://doi.org/10.1093/comjnl/7.4.308>, 1965.

Nelson, J. A., Walther, S., Gans, F., Kraft, B., Weber, U., Novick, K., and Jung, M.: X-BASE: the first terrestrial carbon and water flux products from an extended data-driven scaling framework, FLUXCOM-X. *Biogeosciences*, 21(22), 5079-5115. <https://doi.org/10.5194/bg-21-5079-2024>, 2024.

Nelson, J. A., Walther, S., Gans, F., Kraft, B., Weber, U., Novick, K., Buchmann, N., Migliavacca, M., Wohlfahrt, G., Šigut, L., Ibrom, A., Papale, D., Göckede, M., Duveiller, G., Knohl, A., Hörtnagl, L., Scott, R. L., Zhang, W., Hamdi, Z. M., Reichstein, M., Aranda-Barranco, S., Ardö, J., Op de Beeck, M., Billesbach, D., Bowling, D., Bracho, R., Brümmer, C., Camps-Valls, G., Chen, S., Cleverly, J. R., Desai, A., Dong, G., El-Madany, T. S., Euskirchen, E. S., Feigenwinter, I., Galvagno, M., Gerosa, G. A., Gielen, B., Goded, I., Goslee, S., Gough, C. M., Heinesch, B., Ichii, K., Jackowicz-Korczynski, M. A., Klosterhalfen, A., Knox, S., Kobayashi, H., Kohonen, K.-M., Korkiakoski, M., Mammarella, I., Gharun, M., Marzuoli,

R., Matamala, R., Metzger, S., Montagnani, L., Nicolini, G., O'Halloran, T., Ourcival, J.-M., Peichl, M., Pendall, E., Ruiz Reverter, B., Roland, M., Sabbatini, S., Sachs, T., Schmidt, M., Schwalm, C. R., Shekhar, A., Silberstein, R., Silveira, M. L., Spano, D., Tagesson, T., Tramontana, G., Trotta, C., Turco, F., Vesala, T., Vincke, C., Vitale, D., Vivoni, E. R., Wang, Y., Woodgate, W., Yopez, E. A., Zhang, J., Zona, D., and Jung, M.: X-BASE: the first terrestrial carbon and water flux products from an extended data-driven scaling framework, *FLUXCOM-X. Biogeosciences*, 21(22), 5079-5115. <https://doi.org/10.5194/bg-21-5079-2024>, 2024.

Ometto, J. P., Gorgens, E. B., de Souza Pereira, F. R., Sato, L., de Assis, M. L. R., Cantinho, R., and Keller, M.: A biomass map of the Brazilian Amazon from multisource remote sensing. *Scientific Data*, 10(1), 668. <https://doi.org/10.1038/s41597-023-02575-4>, 2023.

Osborne, T., Gornall, J., Hooker, J., Williams, K., Wiltshire, A., Betts, R., & Wheeler, T.: JULES-crop: a parametrisation of crops in the Joint UK Land Environment Simulator. *Geoscientific Model Development Discussions*, 7(5), 6773-6809. <https://doi.org/10.5194/gmd-8-1139-2015>, 2015.

Peel, M. C., Finlayson, B. L., and McMahon, T. A. (2007). Updated world map of the Köppen-Geiger climate classification. *Hydrology and earth system sciences*, 11(5), 1633-1644. <https://doi.org/10.5194/hess-11-1633-2007>, 2007

Prudente Junior, A. C., Vianna, M. S., Williams, K., Galdos, M. V., & Marin, F. R.: Calibration and evaluation of JULES-crop for maize in Brazil. *Agronomy Journal*, 114(3), 1680-1693. <https://doi.org/10.1002/agj2.21066>, 2022.

Raoult, N. M., Jupp, T. E., Cox, P. M., and Luke, C. M.: Land-surface parameter optimisation using data assimilation techniques: the adJULES system V1. 0. *Geoscientific Model Development*, 9(8), 2833-2852. <https://doi.org/10.5194/gmd-9-2833-2016>, 2016.

Reatto, A., Martins, É. D. S., Farias, M. F. R., Silva, A. V. D., & Carvalho Júnior, O. A. D.: Mapa pedológico digital-SIG atualizado do Distrito Federal escala 1: 100.000 e uma síntese do texto explicativo, 2004.

Restrepo-Coupe, N., da Rocha, H. R., Hutyrá, L. R., da Araujo, A. C., Borma, L. S., Christoffersen, B., and Saleska, S. R.: What drives the seasonality of photosynthesis across the Amazon basin? A cross-site analysis of eddy flux tower measurements from the Brasil flux network. *Agricultural and Forest Meteorology*, 182, 128-144. <https://doi.org/10.1016/j.agrformet.2013.04.031>, 2013.

Restrepo-Coupe, N., da Rocha, H. R., Hutyrá, L. R., de Araujo, A. C., Borma, L. S., Christoffersen, B., and Saleska, S.: LBA-ECO CD-32 Flux Tower Network Data Compilation, Brazilian Amazon: 1999-2006, V2. ORNL DAAC. <https://doi.org/10.3334/ORNLDAAC/1842>, 2021

Restrepo-Coupe, N., Levine, N. M., Christoffersen, B. O., Albert, L. P., Wu, J., Costa, M. H., and Saleska, S. R.: Do dynamic global vegetation models capture the seasonality of carbon fluxes in the Amazon basin? A data-model intercomparison. *Global change biology*, 23(1), 191-208. <https://doi.org/10.1111/gcb.13442>, 2017.

Rosan, T. M., Sitch, S., O'sullivan, M., Basso, L. S., Wilson, C., Silva, C., ... and Aragão, L. E.: Synthesis of the land carbon fluxes of the Amazon region between 2010 and 2020. *Communications Earth & Environment*, 5(1), 46. <https://doi.org/10.5281/zenodo.10423522>, 2024.

- Saatchi, S.S., Harris, N.L., Brown, S., Lefsky, M., Mitchard, E.T.A., Salas, W., Zutta, B.R., Buermann, W., Lewis, S.L., Hagen, S., Petrova, S., White, L., Silman, M., Morel, A.: Benchmark map of forest carbon stocks in tropical regions across three continents. *Proc. Natl. Acad. Sci.* 108 (24), 9899–9904. <https://doi.org/10.1073/pnas.1019576108>, 2011.
- Shinozaki, K., Yoda, K., Hozumi, K., and Kira, T.: A quantitative analysis of plant form – the pipe model theory, I. Basic Analyses, *Japanese Journal of Ecology*, 14, 97–105, 1964
- 955 Silva, D. S., Blanco, C. J. C., dos Santos Junior, C. S., & Martins, W. L. D.: Modeling of the spatial and temporal dynamics of erosivity in the Amazon. *Modeling Earth Systems and Environment*, 6, 513-523. <https://doi.org/10.1007/s40808-019-00697-6>, 2020.
- Simard, M., Pinto, N., Fisher, J. B., and Baccini, A.: Mapping forest canopy height globally with spaceborne lidar. *Journal of Geophysical Research: Biogeosciences*, 116(G4). <https://doi.org/10.1029/2011JG001708>, 2011
- 960 Sitch, S., O’sullivan, M., Robertson, E., Friedlingstein, P., Albergel, C., Anthoni, P., ... & Zaehle, S. (2024). Trends and drivers of terrestrial sources and sinks of carbon dioxide: An overview of the TRENDY project. *Global Biogeochemical Cycles*, 38(7). <https://doi.org/10.1029/2024GB008102>
- Skillman, J. B.: Quantum yield variation across the three pathways of photosynthesis: not yet out of the dark. *Journal of experimental botany*, 59(7), 1647-1661. <https://doi.org/10.1093/jxb/ern029>, 2008.
- 965 Souza Jr, C. M., Z. Shimbo, J., Rosa, M. R., Parente, L. L., A. Alencar, A., Rudorff, B. F., and Azevedo, T. (2020). Reconstructing three decades of land use and land cover changes in brazilian biomes with landsat archive and earth engine. *Remote Sensing*, 12(17), 2735. <https://doi.org/10.3390/rs12172735>
- Verbeeck, H., Peylin, P., Bacour, C., Bonal, D., Steppe, K., and Ciais, P.: Seasonal patterns of CO₂ fluxes in Amazon forests: Fusion of eddy covariance data and the ORCHIDEE model. *Journal of Geophysical Research: Biogeosciences*, 116(G2). <https://doi.org/10.1029/2010JG001544>, 2011.
- 970 Virtanen, P., Gommers, R., Oliphant, T. E., Haberland, M., Reddy, T., Cournapeau, D., and Van Mulbregt, P.: SciPy 1.0: fundamental algorithms for scientific computing in Python. *Nature methods*, 17(3), 261-272, <https://doi.org/10.1038/s41592-019-0686-2>, 2020.
- 975 Wallach, D., Makowski, D., Jones, J. W., & Brun, F.: Working with dynamic crop models: Methods, tools and examples for agriculture and environment. Academic Press, 2018.
- West, P. W.: Do increasing respiratory costs explain the decline with age of forest growth rate?. *Journal of Forestry Research*, 31(3), 693-712. <https://doi.org/10.1007/s11676-019-01020-w>, 2020.
- Williams, K., Gornall, J., Harper, A., Wiltshire, A., Hemming, D., Quafe, T., and Scoby, D.: Evaluation of JULES-crop performance against site observations of irrigated maize from Mead, Nebraska. *Geoscientific Model Development*, 10(3), 1291-1320. <https://doi.org/10.5194/gmd-10-1291-2017>, 2017.
- 980 Willmott, C. J., Robeson, S. M., and Matsuura, K.: A refined index of model performance. *International Journal of climatology*, 32(13), 2088-2094. <https://doi.org/10.1002/joc.2419>, 2012.

985 Wiltshire, A. J., Burke, E. J., Chadburn, S. E., Jones, C. D., Cox, P. M., Davies-Barnard, T., and Zaehle, S.: JULES-CN: a
coupled terrestrial carbon–nitrogen scheme (JULES vn5. 1). *Geoscientific Model Development*, 14(4), 2161-2186.
<https://doi.org/10.5194/gmd-14-2161-2021>, 2021.

Wu, J., Albert, L. P., Lopes, A. P., Restrepo-Coupe, N., Hayek, M., Wiedemann, K. T., .and Saleska, S. R.: Leaf development
and demography explain photosynthetic seasonality in Amazon evergreen forests. *Science*, 351(6276), 972-976. <https://doi.org/10.1126/science.aad5068>, 2016.

990 Wutzler, T., Antje, L M., Migliavacca M., Knauer, J., Sickel, K., Šigut, L., Menzer, O and Reichstein, M.: Basic and extensible
post-processing of eddy covariance flux data with REddyProc. *Biogeosciences*, 15(16), 5015-5030. .
<https://doi.org/10.5194/bg-15-5015-2018>, 2018.

995

1000