Constraints on the Lithospheric Structure and Rheology of Northern Chile from 8-year Post-Seismic Deformation following the $M_w8.1$ Iquique Earthquake

Juliette Cresseaux[1], Mathilde Radiguet[1], Marie Pierre Doin[1], Marcos Moreno[2], Flora Huiban[1,6], Mathilde Marchandon[3], Juan Carlos Baez[4], Aubin Tsapong Tsague[1], Gaël Janex[1], Andres Tassara[5], and Anne Socquet[1]

[1]University Grenoble Alpes, University Savoie Mont Blanc, CNRS, IRD, University Gustave Eiffel, ISTerre, 38000 Grenoble, France
[2]Departamento de Ingeniería Estructural y Geotécnica, Pontificia Universidad Católica, Santiago, Chile
[3]Department of Earth and Environmental Sciences, LMU Munich, Germany
[4]Centro Sismológico Nacional, Santiago, Chile
[5]Departamento de Ciencias de la Tierra, Facultad de Ciencias Químicas, Universidad de Concepción, Concepción, Chile
[6]Current address, Department of Geosciences and Natural Resources Management, University of Copenhagen, 1350, Copenhagen, Denmark

Correspondence: Anne Socquet (anne.socquet@univ-grenoble-alpes.fr)

Abstract.

Understanding and modeling the deformation following large ~~earthquake~~ earthquakes is essential for characterizing the rheological structure and processes that release post-seismic stress. Here, we measured postseismic deformation over an 8-year period following the 2014 $M_w8.1$ Iquique earthquake using Sentinel-1 InSAR and GNSS time series in northern Chile and Bolivia. We jointly modeled the surface displacements caused by afterslip and viscoelastic relaxation using a two-dimensional finite element model. The combination of GNSS and InSAR data allows us to continuously map the temporal and spatial variations of the displacement field, especially in the vertical component, providing valuable constraints for modeling the rheological structure of the continental plate from the slab to the Altiplano. The amplitude of the uplift pattern ~~claims~~ pleads for a weak zone below the western part of the Altiplano, where the volcanic arc is fed by partial melting. To reproduce the temporal evolution of post-seismic uplift, this weak zone must be governed by a Burgers rheology, combining a transient Kelvin body with a viscosity $\eta_{Kwz} = 2 \times 10^{18} Pa.s$ and a Maxwell body with a viscosity $\eta_{Mwz} = 2 \times 10^{19} Pa.s$. To the west, our preferred model includes a cold nose rooting into the slab at a slab-mantle decoupling depth of $d_{CN} = 84$ km. This near-trench elastic wedge, predicted by thermal models, drives mantle flow and generates surface uplift during post-seismic relaxation. By characterizing the post-seismic deformation field following the Iquique earthquake, our results refine the rheological structure below the Central Andes and define its response to stress changes down to short time scales.

1 Introduction

The aftermath of large earthquakes often entails prolonged visco-elastic relaxation, resulting in regional-scale deformation that can persist for several decades (Wang, 2007; Hu et al., 2004; Suito and Freymueller, 2009; Wang et al., 2012). Exploration of post-seismic deformation following megathrust earthquakes has proven pivotal in refining our understanding of mantle viscosity for both oceanic and continental regions ~~?e.g.>[] pollitz2006post, panet2010upper, suito2017importance, Li2017PostseismicRheology, boulze2022post~~(Pollitz et al., 2006; Panet et al., 2010; Suito, 2017; Li et al., 2017; Boulze et al., 2022) . Many previous studies have shown that using transient viscosity rheology more effectively captures the time evolution of post-earthquake deformation (Sun et al., 2014; Hu et al., 2016; Klein et al., 2016). Furthermore, the analysis of post-seismic deformation offers valuable insights into the rheological structure of the overriding plate (Pollitz et al., 2008; Li et al., 2018; Muto et al., 2019, e.g.). For example, Luo and Wang (2021) demonstrated that the rigid cold forearc mantle (commonly known as the cold nose), shaped by the thermal structure of subduction zones (Wada et al., 2008; Wada and Wang, 2009), significantly influences modeled vertical surface displacements resulting from post-seismic mantle corner flow. Other studies have shown that a weak (i.e. low viscosity) zone within the overriding plate modifies the post-seismic response by localizing the deformation in this area (Rousset et al., 2012; Itoh et al., 2021).

In the Central Andes, large-scale structural features are well-constrained by geophysical studies, revealing that the rigid ~~Brazilian~~ South American lithosphere, approximately 130 km thick, is substantially thinned to 70-80 km beneath the Altiplano. This region also has a thick crust (60-70 km) characterized by a thin elastic layer ($\sim$ 20 km) atop a weak lower crust (Tassara et al., 2006; Tassara and Echaurren, 2012; Giambiagi et al., 2022). The weakened zone is consistent with predictions from numerical simulations of small-scale flow within the hydrated subduction mantle wedge, which suggest reduced rock strength and thermal erosion in the upper plate (Arcay et al., 2005; Babeyko et al., 2002; Sobolev and Babeyko, 2005; Pons et al., 2022; Wang et al., 2021). Despite these insights, the precise extent and rheology of this weak zone remain poorly characterized. Fundamental questions persist: How wide is the weak zone? How does it relate to the topography? How low is its viscosity? Does its rheology evolve with time during the post-seismic relaxation? How does it affect the deformation during the seismic cycle?

The post-seismic deformation following the 2014 Iquique earthquake offers an excellent opportunity to explore the rheological structure of the overriding continental plate. Existing studies on post-seismic deformation after the Iquique earthquake have primarily focused on the afterslip process (Shrivastava et al., 2019; Itoh et al., 2023). Only two studies (Hu et al., 2021; Hoffmann et al., 2018) have addressed the influence of visco-elasticity on the surface displacement field, but these are limited by the short observation period (2 or 4 years) and show a suboptimal fit, particularly with respect to vertical displacements. In this study, we ~~take advantage of the monitoring of the deformation by permanently installed GPS stations~~ use GNSS (Global Navigation Satellite System) data in northern Chile and Bolivia, and combine ~~it~~ them with Sentinel-1 InSAR (Synthetic Aperture Radar Interferometry) time series to delineate the spatial pattern of the post-seismic deformation and its temporal evolution over an 8-year period following the earthquake. InSAR shows a strongly deformed area, extending from the forearc to the arc, ~~that is~~ resulting from viscoelastic relaxation in the weak zone. We model the surface displacement generated

by afterslip and visco-elastic relaxation following the co-seismic rupture using a Finite Element Model in two dimensions. Our objective is to perform a parametric exploration of the geometry ~~in order to constrain the geometry~~ of the cold nose and of the weak zone, and to explore its rheology. The use of a simple 2D model, rather than a 3D model, allows us to test various configurations ~~against the data. The spatial continuity of the deformation~~ and trade-offs between parameters, which would not be possible in such an exhaustive manner with a 3D model. We do not aim at inverting jointly all parameters, but instead evaluate the sensitivity of the modelled deformation to the explored parameters, which is something that is rarely done in viscoelastic modelling. The continuous deformation field provides excellent constraints on the localization of the deformation, enabling us to refine our understanding of the rheological structure of the continental plate from the subduction zone to the Altiplano.

2 Seismotectonic Setting of the 2014 Iquique Earthquake

Stretching over 8000 km, the Peru-Chile trench delineates the boundary between the Nazca and South American plates and has played a crucial role in the formation and seismic activity of the ~~Andes~~ Andean Cordillera. This subduction zone is segmented along strike and ruptures ~~into~~ during large earthquakes (Métois et al., 2016; Molina et al., 2021). The 1960 $M_w 9.5$ Valdivia earthquake was the largest earthquake instrumentally recorded worldwide (Kanamori, 1977). It ruptured a 920 km-long ~~section~~ segment of the subduction zone (Cifuentes, 1989), and was followed by prolonged visco-elastic relaxation and seismic quiescence that lasted for several decades (Hu et al., 2004; Moreno et al., 2011; Ruiz et al., 2017).

More recently, three mega-earthquakes ruptured the Chilean subduction zone: Maule, 2010, $M_w 8.8$ (Moreno et al., 2010; Lin et al., 2013); Iquique, 2014 $M_w 8.1$ (Ruiz et al., 2014; Schurr et al., 2014; Duputel et al., 2015) and Illapel, 2015 $M_w 8.3$ (Tilmann et al., 2016; Heidarzadeh et al., 2016). The post-seismic visco-elastic relaxation that followed the 2010 $M_w 8.8$ Maule earthquake has been investigated in various studies. Klein et al. (2016) suggest that a weak mantle (with a viscosity of ~~$4.75.10^{18}$~~ $4.75 * 10^{18}$ Pa.s) and a viscous channel along the slab interface to model the afterslip are required to explain the GNSS observations. To model the uplift observed at 300 km distance from the trench, Li et al. (2017) incorporated a mantle with a low viscosity beneath the Main Cordillera that increases toward the Argentinian craton. At 700 km from the trench, a remarkably high viscosity of 10^{30} Pa.s ~~is~~ was required to account for the observed subsidence in the far-field, which, over the time scale considered, is equivalent to an elastic behaviour. Additionally, Li et al. (2018) emphasized that viscosity increases not only with the distance from the trench but also with time after the earthquake. Studies focusing on the aftermath of the 2015 $M_w 8.3$ Illapel earthquake have predominantly delved into afterslip and aftershock seismicity (Poli et al., 2017; Twardzik et al., 2021; Shrivastava et al., 2016; Tissandier et al., 2023; Hormazábal et al., 2023). Nevertheless, a comparative analysis of post-seismic visco-elastic relaxation following the three most recent megathrust earthquakes in Chile pleads for a linear, Newtonian, viscosity in the asthenosphere (Boulze et al., 2022). Additionally, the continuous geodetic monitoring over the years since these earthquakes offers data to evaluate the rheological impact on the observed post-seismic deformation.

The $M_w 8.1$ Iquique earthquake occurred on ~~the~~ April 1^{st} ~~of April~~, 2014, with its epicenter located -70.79° East and -19.62° North (see Figure 1). It ruptured the central part of a mature seismic gap that had last ~~been~~ ruptured in 1877 by a $M_w 8.6+$ event (Comte and Pardo, 1991; Métois et al., 2013; Béjar-Pizarro et al., 2013; Vigny and Klein, 2022). However, smaller magnitude

earthquakes have also struck the gap, such as the 2005 M_w7.8 Tarapacá intraslab intermediate-depth earthquake (Peyrat et al., 2006; Jara et al., 2017) and the 2007 M_w7.7 Tocopilla deep subduction earthquake (Béjar-Pizarro et al., 2010). This earthquake was also preceded by a slow slip event and a foreshock sequence (Socquet et al., 2017; Ruiz et al., 2014; Schurr et al., 2014).

The Iquique earthquake ruptured the subduction interface between depths of 15 and 55 km over a $\sim$ 50 km wide area, with a peak slip of 9 meters (Duputel et al., 2015; Jara et al., 2018). Following the mainshock, a significant aftershock of magnitude 7.7 occurred about 120 km further south (Duputel et al., 2015; Jara et al., 2018) (Figure 1). Itoh et al. (2023) focused on the early afterslip occurring during the 27 hours separating the mainshock from its largest aftershock using high-rate GNSS data. Given the notably high magnitude of this aftershock compared to the mainshock, its contribution should be considered in any post-seismic relaxation model. Subsequent post-seismic deformation was investigated using GNSS time series until the end of 2014 (Shrivastava et al., 2019), and during the first two years, reaching a maximum of $\sim$ 89 cm of afterslip on the slab interface at depths of 40-50 km (Hoffmann et al., 2018). However, a two-year time-frame is insufficient to distinguish between afterslip and visco-elastic relaxation. Hu et al. (2021) modeled viscoelastic relaxation and proposed the presence of a 110 km thick low-viscosity layer (~~2.10^{18}~~ $2 * 10^{18}$ Pa.s) beneath the slab, along with oceanic and continental mantle viscosities of ~~1.10^{20} and 3.10^{19}~~ $1 * 10^{20}$ and $3 * 10^{19}$ Pa·s, respectively. They also included a weak shear zone to model afterslip. However, this study is limited by the availability of GNSS time series and shows a suboptimal fit, especially for vertical displacements. Therefore, the temporal evolution of deformation after the Iquique earthquake and the role of the rheological structure in viscoelastic relaxation remain poorly understood.

3 Data

3.1 InSAR velocity maps

The arid climate in South Peru and North Chile makes it the ideal area to process SAR interferometric data. This region is covered by two Sentinel-1 tracks, ascending (A149) and descending (D054). We processed all available acquisitions from October 2014 to December 2019, thus covering a duration of slightly over 5 years, with 183 dates for track A149 and 145 dates for track D054. We used the small baseline subset method with the NSBAS processing chain ~~that goes~~ which spans the entire workflow from raw data processing to time series analysis, and includes image coregistration, spectral diversity correction, mitigation of atmospheric delays, filtering and unwrapping, as described in Doin et al. (2011). It is partly based on the ROIPAC software (Rosen et al., 2004) and adapted to Sentinel-1 data processing following Grandin (2017). More processing details can be found in Thollard et al. (2021). The network of interferograms is defined and calculated with temporal and perpendicular baseline constraints. Interferometric pairs were computed with n/n+1 (an acquisition n with the following acquisitions (n+1)), then the pairs n/n+2, n/n+4, plus interferometric pairs with both a temporal baseline around 12 months and a perpendicular baseline smaller than 100 meters. This strategy results in 514 (710, respectively) interferograms for track A149 (D054, respectively). The contribution of the stratified atmosphere is corrected using the ERA-5 global atmospheric reanalysis produced by ECMWF (European Centre for Medium-Range Weather Forecast) (Doin et al., 2009; Jolivet et al., 2011). Unwrapped interferograms are flattened with linear ramps in range and azimuth, as explained in Thollard et al. (2021),




Figure 1. Seismo-tectonic context of the Iquique earthquake. The red and green stars display the USGS locations of the epicenter of the Iquique earthquake and that of the major aftershock of magnitude 7.7, respectively, whereas the red and green contours represent their respective co-seismic slips from Jara et al. (2018). The circles represent the location of the GNSS stations. The white line and dotted lines show the studied cross-section ±100 km. The black bold arrow shows the convergence direction of the subduction (Kendrick et al., 2003). The blue lines describe the slab isodepth contours. The color of the inner (outer, respectively) circles represent the vertical displacements of the GNSS stations during the period between 2 days to 7 months (7 months to 5.7 years, respectively) after the earthquake. The purple (blue, respectively) arrows represent the horizontal displacements of the GNSS stations during the period between 2 days to 7 months (7 months to 5.7 years, respectively) after the earthquake.

that removes the effects of solid earth tides, of rigid plate ~~movement in ITRF reference frame~~movements, and some ramps associated with the ionosphere (Lemrabet et al., 2023; Marconato et al., 2024). The interferometric network is then inverted into displacement time series (López-Quiroz et al., 2009; Ho Tong Minh et al., 2022). The interferometric network misclosure (i.e. the phase difference within equivalent interferogram pairs, e.g. AC-AB-BC) is very low for the two time series, showing the absence of residual unwrapping errors and a low phase noise due to temporal decorrelation.

The phase delay time-series is affected by large residual tropospheric delays, especially during the austral summer and, to a lesser extent, by ionospheric ~~phase screens~~signal. To extract the ground displacement, the InSAR time series ~~is~~ are fitted using a simple trajectory model (Bevis and Brown, 2014) consisting of a linear term representing the interseismic loading, a logarithm decay representing post-seismic relaxation, and a seasonal term, using the equation:

$$\Phi(t) = \underbrace{v \times t}_{\text{interseismic loading}} + \underbrace{A \times log(1 + (t - t_{Iq})/\tau)}_{\text{post-seismic relaxation}} + \underbrace{B \times \cos(2\pi t) + C \times \sin(2\pi t)}_{\text{seasonal term}} \quad (1)$$

where v, A, B and C are parameters, t is the acquisition time, t_{Iq} is the Iquique earthquake time and τ is the relaxation time. Each time step in equation 1 is inversely weighted by the atmospheric phase screen amplitude to decrease the influence of summer acquisitions and of outliers, as detailed in Lemrabet et al. (2023). We found that we cannot constrain the relaxation time with InSAR data, as the time series starts seven months after the earthquake, moreover during a noisy summer season. Therefore, we fixed τ to 45 days.

The estimations of the secular loading rate v and the amplitude of the post-seismic relaxation A are anticorrelated as the variables t and $log(1 + (t - t_{Iq})/\tau)$ are positively correlated over the time series duration. Because of this, and because of the large tropospheric noise during the summer seasons, we keep both, the interseismic loading and the post-seismic relaxation to correct from the seasonal variations. Then we extract from InSAR the cumulated displacement, d_{cumul}, using:

$$d_{cumul} = v \times (t_{end} - t_{start}) + A \times log(1 + (t_{end} - t_{Iq})/\tau) - A \times log(1 + (t_{start} - t_{Iq})/\tau)$$

We correct the ~~cumulated displacement from~~ cumulative displacement for the interseismic loading effect using the predictions of coupling model of Jolivet et al. (2020), projected into the Line Of Sight (LOS) and obtain ~~LOS cumulated~~ cumulative LOS displacement maps of the post-seismic deformation. For track D054, we ~~miss~~ lack far-field InSAR information~~, where we could assume a zeroing~~. We therefore assume that far-field displacement is unaffected by a post-seismic signal (Figure 2). We ~~choose to reference the cumulated~~ reference the cumulative post-seismic InSAR maps using GNSS data available within the tracks. As will be shown in section 3.2, we computed the east, north and up components of the post-seismic GNSS time series between t_{start} and t_{end}, and project them in LOS (Figure 2). The differences between GNSS and InSAR ~~cumulated~~ cumulative post-seismic displacements is fitted by a linear ~~function of~~ plane in range and azimuth, that is then added to InSAR post-seismic maps.

The obtained cumulative displacement maps of the ascending and descending tracks are presented in Figure 2. On the ascending track (A149) on the left, a deformation pattern towards the LOS is clearly seen affecting the entire width of Chile.




Figure 2. Maps of the InSAR cumulative displacements between October 2014 and December 2019, corrected from interseismic displacement and referenced using GNSS data. Colored dots show the GNSS cumulative displacements during the InSAR-period, projected in the LOS. Left: ascending track A149. Right: descending track D054. The red star shows the location of the epicenter of the Iquique earthquake and the red lines the associated slip contours from Jara et al. (2018). The green star denotes the epicenter of the aftershock. The solid white line shows the location of the section and the dotted white lines the section ±100 km.

On the descending track (D054) on the right, a pattern away from the LOS is seen, it has less amplitude and the general pattern is less clear than the track A149. To obtain the trench perpendicular evolution of the cumulative displacement, the displacement is extracted along a section by computing the mean value every 10 km, over 125 km on each side of the section.

3.2 GNSS time series

The GNSS ~~time series~~ data used in this study ~~consist of~~ were acquired by 25 stations from different networks located in Chile (CSN, IPOC) and Bolivia (UNAVCO) (Foster et al., 2014). ~~Data processing is similar to Lovery et al. (2024) and position time series are available through Socquet et al. (2023).~~ The location of the stations is presented in Figure 1 and a map with the associated names can be found in ~~the~~ Figure A1. Data processing is similar to Lovery et al. (2024) and position time series are available through Socquet et al. (2023). Rinex data were processed using the GipsyX software version 1.5 from the Jet Propulsion Laboratory (JPL) (Bertiger et al., 2020). The phase ambiguity was resolved using wide-lane phase bias constraints provided by JPL. JPL's final orbit and clock products and NNR (No Net Rotation) orbits are used. ~~Bi-frequency~~ Dual-frequency observables are used to cancel ionospheric delays . The vertical tropospheric zenith delays are ~~inverted~~ estimated every 5

minutes and two horizontal gradients are accounted for per session of 24 hours, using the VMF1 mapping functions (Boehm et al., 2006). Multi-path and phase center stability corrections are obtained with antenna calibration tables and by averaging the GNSS positions to ~~keep~~ estimate one position per 24h. The FES 2014b model is used to correct from ocean tide loading (Lyard et al., 2021). We then apply a Helmert transform to map the loose NNR solution in the IGS2014 (Altamimi et al., 2016), using the scaling, rotation and translation factors provided by JPL.

We analyze the time series between 2010 and 2022. Beginning in 2010~~allows us to avoid the important contribution of the~~ , we assume that the remaining post-seismic signal that followed the M_w7.7 2007 Tocopilla and the M_w8 1995 Antofagasta earthquakes are insignificant for the current study. We are mostly interested in the 8 years of post-seismic data following the Iquique earthquake in 2014, which allows us to study the post-seismic deformation process over a long time scale. For the eight stations listed in Appendix A, the time series ~~does~~ do not have sufficient data before the Iquique earthquake to make a robust estimate of a linear interseismic trend. In that case, we use the interseismic trends predicted by the interseismic model from Jolivet et al. (2020). To be in the same reference frame as the interseismic model from Jolivet et al. (2020), we rotated the time series in the South America stable reference (SOAM) using the rotation between NNR-Nuvel-1A to SOAM (defined by the following Euler pole rotation with lat/lon/angular rate: -25.4°N, -124.6°E, 0.11°/yr) and then account for a sliver modeled as a translation with a velocity of 5.4mm/yr to the North and 10.2mm/yr to the East (Jolivet et al., 2020).

To isolate the contribution of the post-seismic signal of interest in the GNSS time-series, and correct from other sources of deformation (interseismic, co-seismic, antenna jumps, seasonal variations), we use a trajectory model ~~inspired by Bevis and Brown (2014) and developped~~ following Bevis and Brown (2014) and developed by Marill et al. (2021). The position time series $x(t)$ is modeled, for each station, with the following relation:

$$
\begin{aligned}
x(t) = & x_R + \underbrace{v(t-t_R)}_{\text{interseismic}} + \underbrace{\sum_{k=1}^{2}[s_k sin(2k\pi(t-t_R)) + c_k cos(2k\pi(t-t_R))]}_{\text{seasonal variations}} \\
& + \underbrace{\sum_{a=1}^{n_A} b_a H(t-t_a)}_{\text{antenna changes}} + \underbrace{\sum_{j=1}^{n_J} c_J H(t-t_J)}_{\text{co-seismic}} + \underbrace{m_{Iq} H(t-t_{Iq}) \times log10(1+\frac{t-t_{Iq}}{\tau})}_{\text{post-seismic}}
\end{aligned}
\tag{2}
$$

with x_R the initial position, t_R the reference time, s_k and c_k seasonal variations amplitudes, n_A the number of antenna jumps and t_a the time of the antenna jumps, b_a the amplitude of the antenna jumps, n_J the number of co-seismic jumps, t_J the time of the co-seismic jumps, c_J the amplitude of the co-seismic jumps, t_{Iq} the Iquique earthquake time, τ the relaxation time of the Iquique earthquake, m_{Iq} the amplitude of the post-seismic relaxation of the Iquique earthquake and H the Heaviside function. The influence radius of an earthquake has been adapted from the Nevada Geodetic Laboratory and is given by: $r(M_W) = 10^{(0.5M_W - 0.8)/1.28} km$ with M_W, the moment magnitude of the earthquake. The parameters are inverted using a multi-step iteration procedure (see Marill et al. (2021)). The fit of the trajectory model to the data is shown in the Figures A2 to A26 for each station. For the initial fit, we consider a constant value of $\tau_R = 45$ days, which might not be optimal for all the time series but does not significantly impact the estimates of other parameters. Mismodeled signals will be preserved in

the residuals time series. Our post-processed time series consists of the original data corrected from a linear interseismic term, seasonal terms (annual and semi-annual), co-seismic offsets and antenna jumps, thus keeping only the displacements due to the post-seismic relaxation and noise.

We then further analyze the post-Iquique time series, starting on the 4^{th} of April, one day after the April 3^{rd} $M_w 7.7$ aftershock, so that our results are not affected by the co-seismic displacements of this aftershock. We select 25 stations located around a profile of 100 km width, centered on the co-seismic patch (See Figure 1). The time series from those stations is further modeled to estimate the spatial variability in the amplitude (m_i) and temporal evolution (τ_i) of the post-seismic signal between the near-field (close to the trench) and the far-field. To do so, we fit the GNSS time series with a logarithmic model and a variable ~~time constant τ_i~~ relaxation time for each station ~~i, using the equation:~~

~~$$x_i(t) = A_i + m_i * log10(1 + \frac{t - t_{Iq}}{\tau_i})$$~~

~~where m_i is the amplitude, τ_i is a time constant characterizing the relaxation and A_i is a constant corresponding to an offset if the pre or co-seismic is poorly inverted~~. The GNSS time series contains considerable data gaps, in particular missing data right after the earthquake for several stations, or missing data for the more recent time (see Figure 3). Our strategy to model the post-seismic signal ~~using equation ?? will thus vary~~ therefore varies depending on the completeness of the time series.

When the time series ~~has data just~~ contains only data shortly after the earthquake, we fix the constant A_i so that the model and data equal 0 for the first data point. In that case, we invert for the amplitude m_i and the time constant τ_i for the East component time series, as it has the strongest signal amplitude. For the North and Vertical components, we only invert for the amplitude m_i, with τ_i equal to the value inferred for the East component. A grid search between the amplitude and the relaxation time is then done to estimate the trade-off between the parameters, and obtain uncertainties for our time-series modeling (see Figure A27 for an example of the grid search and uncertainty estimation). The time series is resampled using a logarithmic sampling to give more weight to the short-term data with respect to long-term trends in the model fit. ~~The Root Mean Square (RMS) is calculated with the following formula: $RMS_i = \sqrt{(\sum_t^{n_t} (d_{obs}^{log}(t) - x_i^{log}(t))^2 / n_t)}$ where d_{obs}^{log} are the resampled data, x_i^{log} the logarithmic model and n_t the number of resampled data. The~~ The grid search gives the best combination of amplitude and relaxation time for the time series. The data and best model fit are plotted in Figure 3. The uncertainty associated with a modeled time series is computed using three times the ~~RMS~~ nRMS of the best model.

~~For the stations without data for~~ If the time-series only begins several months after the earthquake or with a post-seismic signal of very low amplitude (SCRZ and URUS) (in grey on the Figure 3), we cannot constrain the relaxation time τ_i so we fix τ_i to the value inverted for the closest ~~station with enough reliable data: for the stations in Bolivia, in far-field, we imposed the one of COLC and for HMBS, we imposed the relaxation time of CGTC. For these stations, we invert for the offset A_i in addition to the amplitude m_i. We also perform a grid search on the amplitude m and offset A to search for the best parameters and estimate uncertainties (see Figure A28). As for the stations with data just after the earthquake, the time series is resampled logarithmically.~~ well-constrained station. The best models for different stations are plotted in Figure 3. We consider as acceptable the parameter range for which ~~$RMS \leq 1.5 \times RMS_{best}$, RMS_{best}~~ $nRMS \leq 1.5 \times nRMS_{best}$,




Figure 3. East components of time series depicting post-seismic displacements for the selected 25 stations ordered by distance to the trench. We can notice three subsets of stations as a function of the distance to the trench: the coastal stations from AEDA to HMBS ($\leq$ 150 km from the trench), the intermediate-field stations, from FBAQ to PB08 (between 150 and 250 km from the trench) and finally the far-field stations from COLC to SCRZ ($\geq$ 250 km from the trench). The stations are color-coded by the relaxation time inverted to fit each time series as in Figure A1. The stations colored in grey are those with not enough data to constrain the relaxation time, then the relaxation time of the nearest station is used to model the time series. The black curves are the modeled displacements using post-seismic relaxation equation~~??~~. The vertical grey line ~~delineates~~ separates the two studied periods: the short-term period (P1) from 3 days to 7 months after the mainshock and the long-term period (P2) from 7 months to 5.7 years after the mainshock. The map of the location of these stations can be found in Figure A1.

220 $nRMS_{best}$ being the RMS of the best-fit model (see ellipse in Figure S27). We consider the highest and lowest amplitude models from this range of acceptable models to build a lower and upper bound on the displacements for each time series, and estimate the uncertainties on our time series.

In the following, the data are presented either as time series to investigate the temporal evolution (Figures 5 and 11) or spatially along a cross-section perpendicular to the trench (Figures 6 to 10, 12 and 13). In the cross sections, we plot the cumulative displacements for two different periods: the short-term period from 3 days to 7 months after the mainshock, and the long-term period from 7 months to 5.7 years after the mainshock. This second period corresponds to the acquisition period of InSAR data. For the GNSS time series, if data are present for a given station and a given date, we use a mean position over 10 days at that date. If the data are missing, we use the modeled time series (from equation ~~??~~2) to extrapolate the position and estimate the displacement offset. ~~Such extrapolated displacements are plotted in cyan on the cross-section, while if data are available for the beginning and the end of the period, they are plotted in dark blue.~~

3.3 Complementarity and Correspondence between InSAR and GNSS observations

Both datasets ~~bring~~ produce complementary spatial and temporal information. GNSS time series provides continuous evolution of the position at precise points between the earthquake and 2022. Although the temporal sampling in InSAR is only 6 to 24 days, and the time series is noisier than GNSS, a post-seismic signal is clearly visible in the InSAR time series, and its amplitude can be extracted with great spatial coherency. InSAR data thus allow characterizing precisely the pattern of deformation and better locating the main features of the signal. Because the Sentinel-1 satellite was launched 7 months after the earthquake, the early stage of the post-seismic deformation cannot be assessed by InSAR. For GNSS, the period of observation varies depending on the stations and goes from the earthquake until 2022 for the most complete stations. Over the period covered by the InSAR time series (27 October 2014 to 31 December 2019), we compare the cumulative deformation obtained by InSAR and GNSS, with the GNSS displacements projected in the InSAR LOS. ~~The~~ Figure 2 shows that the same pattern is observed with both datasets, with ~~a global coherency in the~~ coherent amplitude despite a few outliers (see also Figure A28 for further comparison of the amplitudes).

4 Modeling Strategy

We model the post-seismic deformation accounting for both afterslip and visco-elastic relaxation, using finite element model. Our objective is mainly to test the existence of a weak zone below the volcanic arc (located on the Western Cordillera) and to explore its geometry and rheology. Additional parameters are also explored, and results are shown in the supplementary material.

To keep the paper simple enough to read, we describe our best model, then we vary each parameter around their best value to evaluate their effect on the resulting deformation and fit to the observations.

4.1 Structure of the Model

~~To explore and model the trench perpendicular~~

To investigate and model trench-perpendicular post-seismic displacements, we ~~used a 2-dimensional Finite Element Model. We constructed the mesh with~~ developed a two-dimensional finite-element model. The mesh was generated using the soft-

ware Coreform Cubit (2023)~~and computed the~~ , and post-seismic relaxation and associated surface deformation ~~with the~~ were computed with Pylith 2.2.2 ~~software (Aagaard et al., 2013, 2017)published under the MIT license. To align our~~ (Aagaard et al., 2013, 2017) .

To align the 2D cross-section with the direction of maximum displacement, ~~it is oriented with an angle of~~ the model is oriented 9~~° with respect to the East which represents a medium~~ ° clockwise from the East direction. This orientation represents an intermediate angle between the East-West direction and the ~~trench perpendicular~~ trench-perpendicular direction. The section ~~passes by the maximum of the mainshock~~ crosses the region of maximum co-seismic slip during the mainshock (Figure 1).

~~To avoid edge effectsin the finite-element model, the section is~~ To minimize boundary effects, the model extends over 4000 km ~~long:~~ horizontally, with 1900 km on the oceanic side and 2100 km on the continental side~~and the depth is~~ , and reaches a depth of 1000 km. ~~We use triangles to mesh the structure. Their size is increasing~~ The mesh is composed of triangular elements whose size increases progressively away from the fault plane~~with a cell size of~~ , from 5 km ~~on~~ near the fault to 100 km ~~on the model edges. The obtained model is composed of 13525 cells~~at the model boundaries. The final mesh contains 13,525 elements. The lateral ~~sides are constrained with no displacementin the horizontal direction. The bottom has no~~ boundaries are constrained to prevent horizontal displacement, while the bottom boundary prevents vertical displacement. The surface is free to ~~move~~deform.

The Central Andes ~~exhibit~~ display a topographic variation of approximately 13 km ~~from the trench to~~ between the trench and the Western Cordillera (Armijo et al., 2015). Further ~~inland~~east, the Altiplano ~~is characterized by a sustained~~ forms a high-elevation plateau ~~of approximately 4000m. The Altiplano extends until it meets~~ reaching about 4000 m, extending to the Eastern Cordillera ~~, where the topography gradually descends towards the~~ where elevation progressively decreases toward the Amazon basin. ~~Our model includes topography ; we use the topography and the bathymetry of~~ The model incorporates both topography and bathymetry from the global digital elevation model SRTM15+ (Tozer et al., 2019) (Figure 4A and C). The ~~delimitation of the surface of the slab is taken from~~ slab geometry is defined using the Slab2 model from Hayes et al. (2018).

The model is ~~composed of 5~~ divided into five domains (Figure 4):

(1) ~~An~~ an oceanic elastic layer,

(2) an oceanic visco-elastic layer,

(3) a continental elastic layer~~(including a~~ , including the cold nose and the craton~~),~~ ,

(4) a weak zone~~and~~ , and

(5) a continental visco-elastic layer.

~~In the following the structure of the different domains is detailed. The structural parameter explored are indicated~~ The structural parameters investigated in this study are highlighted in red in Figure 4~~(Cold nose border~~ : the cold nose boundary depth (d_{CN}~~,~~), the Altiplano elastic thickness (h~~, position of craton 's border~~), and the craton boundary position (x_{craton}). The values ~~given in the paragraph~~ described below correspond to the ~~structure of our~~ preferred model, ~~and the range explored (if relevant) can be found~~ while the explored ranges are summarized in Table 1 and ~~is detailed in section 4.3. Other~~ discussed in Section 4.3. All other structural parameters are ~~fixed.~~ kept constant.

~~Exploration of the parameters Parameter Name Explored range Optimal value Afterslip depth A_d 30 - 50 km 36 km Afterslip width A_w 16-28 km 24 km Afterslip amplitude A_a 0.3-0.5 m 0.4 m Altiplano elastic thickness h 10-35 km 25 km Cold nose border d_{CN} 80-95 km 84 km Position of craton's border x_{craton} 250-400 km 300 km Oceanic viscosity η_{oc} 1.10^{20}-5.10^{21} Pa.s 1.10^{21} Pa.s Continental viscosity η_{cont} 8.10^{18}-5.10^{20} Pa.s 3.10^{19} Pa.s Maxwell weak zone viscosity $\eta_{M_{wz}}$ 8.10^{18}-5.10^{20} Pa.s 2.10^{19} Pa.s Kelvin weak zone viscosity $\eta_{K_{wz}}$ 8.10^{17}-5.10^{18} Pa.s 2.10^{18} Pa.s~~

The oceanic elastic layer has a constant thickness of 60 km. The continental elastic layer ~~has a variable thickness, with a maximum of 130 km. The continental elastic layer contains~~ includes the cold nose~~(see section 1)~~ , which extends from the trench ~~until a vertical limit intercepting with~~ to a vertical boundary intersecting the slab at a depth of $d_{CN} = 84$ km in ~~our best model. Wada and Wang (2009) explore the location of the decoupling depth between the cold nose, the slab and the mantle for several subduction zones with thermal modeling . They found a decoupling depth of~~ the preferred model. This value is consistent with the ~80 ~~km~~ km decoupling depth estimated from thermal modeling in northern Chile at ~~about~~ approximately 23.5~~°S of latitude. Our result is consistent with the value proposed by Wada and Wang (2009).~~ °S (Wada and Wang, 2009).

Further inland, beneath the Altiplano, the ~~elastic layer is thin (~~continental elastic layer thins to $h = 25$ km ~~, see section~~ in the best model (see Section 2) and ~~is underlaid by a region characterized by a low viscosity (weak zone)~~overlies a low-viscosity weak zone. From $x_{craton} = 300$ km to 600 km from the trench, ~~there is a linear transition towards the thick craton (see section 2) which has a depth of~~ the elastic thickness increases linearly toward the 130 ~~km. These two elastic layers have~~ km-thick craton. The oceanic and continental elastic layers share the same elastic ~~parameters, given~~ properties, which are listed in Table 2. ~~The~~

The geometry of the weak zone, which strongly ~~controls~~ influences the post-seismic response of ~~our models, is delimited by 3 geometrical parameters that are explored (see Figure 4and~~ the model, is controlled by three parameters explored in this study (Figure 4; Table 1): the ~~border with the cold nose with the best value of $d_{CN} = 84$ km on one side, the Altiplano elastic thickness with the best value of $h = 25$ km~~cold nose boundary (d_{CN}), the continental elastic thickness below the Altiplano (h), and the ~~border with the craton that is a taper between $x_{craton} = 300$ km and 600 km from the trench (for the best values). Below, the continental visco-elastic mantle is set at 130 km depth. The limits with the oceanic and continental visco-elastic mantles are respectively located below 60 km and 130 km.~~ location of transition toward the craton (x_{craton}).

The model ~~contains~~ includes three visco-elastic domains. ~~For the~~ The oceanic and continental visco-elastic layers ~~we consider~~ are modeled using a Maxwell rheology~~while for~~ . In contrast, the weak zone ~~, the data require~~ requires a transient relaxation ~~time and we consider~~ timescale and is therefore represented using a Burgers rheology (see ~~section~~ Section 1). ~~We transposed the~~ The Burgers viscosity and rigidity parameters were converted into the generalized Maxwell formulation ~~, which is~~ implemented in Pylith (code ~~available in the~~ provided in Appendix B1). ~~The elastic parameters are given~~ Elastic parameters are reported in Table 2~~and the viscosities are~~ , and rheological parameters are summarized in Table 3.

Table 1. Exploration of the parameters

Parameter	Name	Explored range	Optimal value
Afterslip depth	A_d	30 - 50 km	36 km
Afterslip width	A_w	16-28 km	24 km
Afterslip amplitude	A_a	0.3-0.5 m	0.4 m
Altiplano elastic thickness	h	10-35 km	25 km
Cold nose border	d_{CN}	80-95 km	84 km
Position of craton's border	x_{craton}	250-400 km	300 km
Oceanic viscosity	η_{oc}	$1*10^{20}$-$5*10^{21}$ Pa.s	$1*10^{21}$ Pa.s
Continental viscosity	η_{cont}	$8*10^{18}$-$5*10^{20}$ Pa.s	$3*10^{19}$ Pa.s
Maxwell weak zone viscosity	$\eta_{M_{wz}}$	$8*10^{18}$-$5*10^{20}$ Pa.s	$2*10^{19}$ Pa.s
Kelvin weak zone viscosity	$\eta_{K_{wz}}$	$8*10^{17}$-$5*10^{18}$ Pa.s	$2*10^{18}$ Pa.s




Figure 4. (A) Elevation along the cross section ~~with~~ showing the ~~name~~ locations of the ~~different~~ stations whose data are used in this study. The ~~delimitation~~ boundaries between the coastal, mid-field, and far-field stations ~~is shown~~are indicated. (B) Co-seismic and afterslip ~~amplitude along~~ amplitudes as a function of depth are shown in green and red, respectively. The ~~explored parameters of the~~ afterslip parameters explored in this study are ~~shown~~also indicated: the afterslip depth (A_d), ~~the~~ afterslip amplitude (A_a), and ~~the~~ afterslip width (A_w). (C) ~~Structure~~ Schematic representation of the model structure, showing the ~~5~~ five domains considered: the oceanic slab ~~in~~ (light blue), the oceanic mantle ~~in~~ (blue), the continental elastic layer ~~in~~ (green), the weak zone ~~in~~ (yellow), and the continental mantle ~~in~~ (orange). The parameters ~~written~~ shown in red are ~~the ones that vary~~ those varied during this study. Along the slab, the green and red lines indicate the ~~respective~~ locations of the imposed co-seismic and post-seismic slips~~imposed in our model~~, respectively (see also ~~detailed in~~ (panel B)~~)~~.

Table 2. Elastic parameters ~~for~~ used in the ~~elastic and visco-elastic layers~~model. ρ ~~,~~ designates the density, ~~Vs~~ V_s the S-wave velocity, ~~Vp~~ V_p the P-wave velocity, E the Young modulus, μ the rigidity and ν the Poisson's coefficient.

Layer	$\rho\ (kg.m^{-3})$	~~Vs~~ V_s $(km.s^{-1})$	~~Vp~~ V_p $(km.s^{-1})$	$E\ (GPa)$	$\mu\ (GPa)$	ν
Elastic	3320	4.2	8.0	150	59	0.3
Visco-elastic	3450	4.5	8.3	180	70	0.29

Table 3. Rheological properties of the different layers. η_M designates the Maxwell viscosity, η_K, the Kelvin viscosity and μ_K the Kelvin rigidity.

Layer	Rheology	$\eta_M\ (Pa.s)$	$\eta_K\ (Pa.s)$	$\mu_K\ (GPa)$
oceanic elastic	elastic	-	-	-
oceanic mantle	visco-elastic	~~1.10^{21}~~ $1*10^{21}$	-	-
continental elastic	elastic	-	-	-
weak zone	visco-elastic	~~2.10^{19}~~ $2*10^{19}$	~~2.10^{18}~~ $2*10^{18}$	136
continental mantle	visco-elastic	~~3.10^{19}~~ $3*10^{19}$	-	-

4.2 Modeling of the Displacement

We separate the modeling into two independent simulations: in the first one we model the co-seismic displacement field, stress, and consequent visco-elastic relaxation, and in the second one we model the afterslip with a kinematic approach. The final model and associated displacements correspond to the sum of the outputs from both models.

We first impose the co-seismic slip on the slab interface. Having an appropriate co-seismic model is crucial to model the subsequent post-seismic signal. Given the limited temporal resolution of our data, the co-seismic slip considered contains both the mainshock (M_w8.1) and its largest aftershock (M_w7.7) two days later. The slip distribution considered (see Figure 4B) is based on Jara et al. (2018). For the first simulation (co-seismic / visco-elastic), the co-seismic slip is imposed at the first time step. It induces a stress change in the medium that is relaxed over time. The modeled post-seismic deformation, extracted at the surface at the location of GNSS and/or InSAR points, is considered over the observation period of the data (from 3 days up to 5 years after the mainshock).

To model the afterslip, we ~~use a simple approach and~~ impose the spatio-temporal ~~kinematic~~ kinematics of the slip on the slab. The afterslip distribution as a function of depth $A(z)$ has a Gaussian shape ~~$A(z) = \frac{G(z)}{max(G(z))} \times A_a$ with $G(z) = \frac{\exp(-(\frac{(z-A_d)}{A_w})^2/2)}{\sqrt{2\pi}\times A_w}$~~ : $A(z) = A_a \times G(z)/max(G(z))$, with $G(z) = \exp(-(\frac{(z-A_d)}{A_w})^2/2)/A_w\sqrt{2\pi}$ (see Figure 4B) where the afterslip amplitude A_a, its depth A_d, and the width of the afterslip zone A_w are among the parameters tested (Table 1). The temporal evolution of the afterslip is controlled by a logarithmic function: $A(t,z) = A(z) \times log(1 + \frac{t}{\tau_a})$. The time constant τ_a for the afterslip is set to 17 days, which corresponds to the time constant found when using equation ~~(2)~~ 2 to model the time series for the stations closest to the trench, for which the afterslip can be considered as the dominant mechanism in the post-seismic phase.

4.3 Explored Parameters

Our modeling explores ten parameters (Table 1), which are detailed below. ~~3~~ Three parameters are associated with the afterslip~~, 3 with the structure of the weak zone and 4 parameters control the rheology of the visco-elastic regions.~~

~~We vary~~ : (1) the depth of maximum slip A_d ~~between~~ from 30 to 50 km, (2) the width of the Gaussian A_w between 16 and 28 km, and (3) the amplitude of the slip A_a between 0.3 and 0.5 meters (see Figure 4B and Table 1). The amplitude A_a corresponds to the maximum displacement after 7 months. The total displacement (after 6 years) is about twice the slip over the first 7 months. We initially set the afterslip values from the afterslip distribution of Hoffmann et al. (2018).

~~Three parameters correspond to~~ Three additional parameters are associated with the structure of the ~~low-viscosity layer.~~ weak zone: (4) ~~The~~ the thickness of the elastic layer under the altiplano h ~~is varied~~ from 10 to 35 km~~.~~ , (5) ~~The~~ the position of the border between the elastic cold nose and the weak zone d_{CN} ~~. It is~~ between 80 km and 95 km depth and often constrained by the decoupling depth ~~on the interface. d_{CN} is varied between 80 km and 95 km depth. The last structural parameter is~~ along the interface, and (6) the border between the weak zone and the elastic craton, which is controlled by the position of the point x_{craton} ~~, which~~ and is varied between 250 to 400 km from the Trench. x_{craton} marks the end of the flat upper limit of the weak zone. For $x > x_{craton}$, the depth of the weak zone increases with a constant slope, and the elastic ~~craton becomes thicker. The weak zone terminates at~~ layer thickens progressively until a depth of 130 km ~~, and a distance $x_{craton} = 300$ km~~ at a distance of $300km$ from the Trench.

~~The Maxwell viscosity of the oceanic~~ The last four parameters control the rheology of the visco-elastic ~~layer~~ regions: (7) the Maxwell viscosity of the oceanic visco-elastic mantle η_{oc} ~~is explored between 1×10^{20} and 5×10^{21} $Pa.s$, the continental mantle~~ between 10^{20} and $5 \times 10^{21} Pa.s$, (8) the Maxwell viscosities of the continental mantle η_{cont} ~~and the Maxwell weak zone~~ , and (9) of the weak zone η_{Mwz} ~~viscosities are tested~~ between 8×10^{18} and 5×10^{20} $Pa.s$~~. On the low viscosity layer,~~ , and (10) ~~the~~ in the weak zone, the Kelvin viscosity of the Burgers rheology η_{Kwz} ~~is also varied~~ between 8×10^{17} and 5×10^{18} $Pa.s$.

4.4 Comparing Data and Models

To evaluate the range of model parameters that can adequately explain the observed surface displacements, we evaluate the misfit ~~between our datasets and the model predictions~~(χ^2) between the observed and predicted surface displacements for all different data sets (GNSS horizontal, vertical, InSAR ascending and descending), and chose the preferred model as being the best compromise, explaining most of the observations. We then ~~determine our preferred model and~~ investigate the influence of each model parameter by varying the parameter ranges around the best model.

The evaluation of the agreement between observed surface displacement and model prediction is performed separately for GNSS and InSAR ~~data~~observations. We first make visual comparisons between data and model over two observation periods: the short-term period (P1, from 3 days to 7.3 months), where only GNSS data are available, and the long-term period (P2, from 7.3 months to 5.72 years after the earthquake), where both GNSS and InSAR are available. The amplitudes of surface displacements along the profile for GNSS (horizontal and vertical, periods P1 and P2) and InSAR (Ascending and descending

track, period P2), are shown in Figures 6 to 10, 12 and 13. These figures allow us to examine the spatial pattern of the model and the influence of the tested parameters on the modeled surface displacements.

We ~~also~~ make a quantitative evaluation of the fit between surface observations and models by computing the reduced Chi-Square for all datasets. For the GNSS data, the χ^2_{GNSS} is computed from the displacement time series. For each time series i, the $\chi^2_{i_{GNSS}}$ is defined as

$$\chi^2_{i_{GNSS}} = \sum_{t=1}^{n_t} \frac{(d^{log}_{i_{GNSS}}(t) - m^{log}_{i_{GNSS}}(t))^2}{\sigma^2_{i_{GNSS}}} \tag{3}$$

The global horizontal and vertical Chi squares are then computed by summing the estimations from individual stations with $\chi^2_{H_{GNSS}} = \sum_{n=1}^{N_H} \chi^2_{iH_{GNSS}}$ and $\chi^2_{V_{GNSS}} = \sum_{i=1}^{N_V} \chi^2_{iV_{GNSS}}$ where N_H and N_V are the number of horizontal and vertical time series. The uncertainties for each station i are estimated based on the dispersion (RMS) of the data around the post-seismic time series fit ~~from equation ??~~: $\sigma_{i_{GNSS}} = 3 \times RMS_{i_{best}}$.

For the InSAR data, since the time series is noisy, the comparison between data and model is made directly on the estimation of the amplitude over the observation period. The cumulative InSAR displacement (in the radar LOS) over the observation period (Figure 2) is estimated for each pixel from the trajectory model of equation 1. We then subsample the InSAR displacement map, considering N_I InSAR points located every 10 km along the cross-section. The subsampled displacements $d_{i_{InSAR}}$ are the median values across the 100 km wide section~~, and $\sigma_{i_{InSAR}}$ is 1.4826 times the median absolute deviation (see~~. We define $\sigma_{i_{InSAR}} = 1.4826 \times MAD$, as this factor makes the scaled MAD comparable to the standard deviation under a normal distribution (grey dots and shaded grey region in the profiles E and F in Figures 6 to 13).

For each InSAR track, we evaluate the adjustment between the data $d_{i_{InSAR}}$ and the model $m_{i_{InSAR}}$ (modeled surface displacements projected in the radar LOS) by:

$$\chi^2_{InSAR} = \frac{1}{N_I} \frac{\sum_{i=1}^{N_I} (d_{i_{InSAR}} - m_{i_{InSAR}})^2}{\sigma^2_{InSAR}} \tag{4}$$

The influence of the horizontal and the vertical on the InSAR displacements depends on the LOS of the acquisition. The InSAR is more sensitive to the vertical component bringing then another way to measure vertical displacements. For the horizontal component, it is more sensitive to the East-West displacements~~almost ignoring the~~, ignoring the component along North-South~~one~~.

5 Results

In the following, we evaluate the influence of the different model parameters. We first start by describing the different processes at stake (i.e. afterslip versus viscoelastic) and their relative contribution to explain the observations. Then we focus on how our observations constrain the geometrical structure (geometry of the weak zone and decoupling depth) and rheology (viscosity, Maxwell versus Burgers) of the continental plate (continental mantle and weak zone). In Figures 7 to 13, we compare observed

~~surface displacements to model predictions~~ and predicted surface displacements along cross-sections at a short time scale (subplots A and B, GNSS data only), and a longer time scale (subplots C and D for GNSS, F and G for InSAR), and also by evaluating the variation in χ^2 with model parameters (subplots E) for horizontal ($\chi^2_{H_{GNSS}}$) and vertical ($\chi^2_{V_{GNSS}}$) GNSS and ascending ($\chi^2_{A_{InSAR}}$) and descending ($\chi^2_{D_{InSAR}}$) InSAR tracks. Similar figures for less critical parameters are shown in the electronic supplement.

6 ~~Results~~

5.1 Evidence ~~of for~~ Supporting the Need for Both ~~Processes:~~ Afterslip and ~~Visco-elastic~~ Visco-Elastic Relaxation

The GNSS time series (Figure 3) ~~shows that~~show that, on average, the time constant associated with the post-seismic deformation tends to increase with increasing distance from the trench: the mean time constant, when estimated over the complete 8-year time series, is 17 days for coastal stations and up to 31 days in Bolivia. These variations indicate that different processes are combined at different spatial and temporal scales in the post-seismic signal. To decipher between these processes, we consider that at a short time scale, and close to the earthquake rupture, afterslip must be the dominant mechanism and thus explain most of the observed signal. ~~The afterslip~~ Afterslip is a relaxation phenomenon ~~of~~ on the fault plane that surrounds the co-seismic slip. It mostly impacts the coastal stations that are the nearest to the fault interface. Instead, the visco-elastic relaxation is happening in the mantle and in the weak zone and has a spatial signature with a large wavelength. That is why at the trench, the displacement observed is mainly due to the afterslip (see section B2 for details on the parameters controlling the afterslip). We use the average time constant of the observations at the coastal stations (AEDA to HMBS) $\tau_{afterslip} = 17$ days to constrain the evolution of the afterslip.

The respective ~~contribution~~ contributions of afterslip and visco-elastic deformation ~~for~~ to our best model (see below for the justification of model parameters) ~~is~~ are shown in Figure 5 for the temporal evolution along with GNSS time series, and in Figure 6 for the spatial signal along a cross-section. We see that afterslip (green curve) is the dominant process at a short time scale during the months following the earthquake (Figure 6A and B) and that its contribution is dominant mostly at coastal stations (e.g. PSGA and ATJN in Figure 5). Over a longer time scale (Figure 6 C, D, E, F), and in the far-field (e.g. COLC and BDJC in Figure 5), visco-elastic relaxation (blue curve) becomes significant. ~~We can observe that although~~ Although the contribution of afterslip and visco-elastic deformation add ~~up~~ constructively on the horizontal component (Figure 6 A and C), they can produce deformation of opposite signs on the vertical (Figure 6 B and D). Thus visco-elastic deformation is needed to explain the observed uplift pattern. Due to the differences in acquisition geometry, the ascending track is more sensitive to the visco-elastic deformation than the descending track which is more sensitive to afterslip (Figure 6 E and F). InSAR ~~data computed on~~ displacement maps from both ascending and descending ~~tracks~~ track are therefore useful to help discriminate between the different processes.

5.2 ~~Afterslip~~




Figure 5. Temporal evolution of the post-seismic displacements and predictions of the best model for coastal stations (PSGA and ATJN), intermediate-field stations (FBAQ and PCHA) and far-field stations (COLC and BDJC). For each station, the top subplot shows the horizontal displacement and the bottom one, the vertical displacement. Grey dots with error bars show the GNSS data with the associated uncertainties. The colored lines are the modeled displacements: the blue curve is the visco-elastic contribution and the green curve is the afterslip contribution. The red curve is the total modeled displacement, combining afterslip and visco-elastic displacements. The best model parameters are presented in the table 1.




Figure 6. ~~Cross~~ Trench-perpendicular cross section of the best model along with GNSS and InSAR data for different periods.~~On all plots, the x-axis is the distance from the trench along the section.~~ The green, blue and red curves represent respectively the afterslip, visco-elastic and total displacement predicted by the best model. Subplots A and B represent respectively the horizontal and vertical cumulative displacement in millimeters from 3 days to 7.3 months. Subplots C, D, E and F represent respectively the horizontal, vertical, LOS of the InSAR track A149 and LOS of the InSAR track D054 cumulative displacement in millimeters from 7.3 months to 5.72 years. Dark blue points represent the displacement extracted from the data with the associated error bars. Cyan points represent the displacement extrapolated from the trajectory model fit for the time series with missing data (Figure 3). ~~Subplots E and F are the cumulative InSAR displacement from 7.3 months to 5.72 years after the earthquake, in the Radar LOS for the tracks A149 and D054 respectively.~~ The grey curve represents the median value of the InSAR and the grey envelope, 1.4826 times the median absolute deviation.

~~In section 5.1, we show that the afterslip is predominant at short time scales (a few months), and we have set its temporal evolution (logarithmic decay with a time constant of 17 days) so that it reproduces the observed displacement at the coastal stations. The depth of the afterslip (A_d) mostly induces a horizontal offset of the modelled curve in near field (Figure B2). The width of the afterslip pulse (A_w) (Figure B3) as well as the maximum slip value (A_a) (Figure B4) control the amplitude of the surface displacements associated with afterslip. Best fitting parameters are $A_w = 24$ km and $A_a = 0.4$ m, more results are detailed in the Appendix B. Our optimal afterslip model, presented in Figure 4B, gives a maximum slip at a depth $A_d = 36$ km, it is located below the co-seismic slip (which extends between 22 and 34 km depth). Some afterslip overlaps up-dip with the co-seismic slip, and it extends downdip down to 60 km depth.~~




Figure 7. Exploration of the elastic layer thickness h in km. The subfigures A, B, C, D, E and F show the same organization as in figure 6. (G) draws the evolution of the different χ^2 with the tested parameter. The pink curve corresponds to the horizontal χ^2, the blue curve to the vertical χ^2 ~~and~~, the green curve to the χ^2 of the InSAR A149, and the brown curve to the χ^2 of the InSAR D054. The scale changes following the component. An elastic layer thickness $h = 25km$, marked by a bright red vertical line, best fits the pattern observed in the data.

5.2 Structure

We then investigate how our data bring constraints on the structure and rheology of the crust and upper mantle, and more precisely on the weak zone beneath the Altiplano. Here, we explore how the geometry of this weak zone influences the modeled displacements at the surface. The rheological parameters correspond to our best model and are not varied. Their influence is discussed in the next section. Geophysical studies and thermo-mechanical models give some constraints on the thickness of the elastic layer h beneath the Altiplano. In our models, we varied h between 10 and 35 km, and as expected, we observe that a thicker elastic crust produces surface ~~displacement~~ displacements of longer wavelength and lower amplitudes. We find an optimal value for $h = 25$ km (Figure 7) which gives the best compromise in fitting the GNSS components together with both InSAR tracks. This thickness is compatible with the values found in the literature for thermo-mechanical models (Araya Vargas et al., 2021; Springer, 1999).

We then studied the lateral extension of the weak zone across the Altiplano: we vary the position of its limit trenchward which is ~~constraints~~ constrained by its depth (d_{CN}, marking the downdip end of the elastic cold nose). Its inland limit gradually deepens over 300 km, and we varied the position x_{craton} that marks the beginning of the thickening of the elastic crust at the transition with the Brasilian craton. The cold nose limit controls the position of the maximum uplift pattern seen in the vertical




Figure 8. Variation of the decoupling depth d_{CN} in km, materialized by the intersection between the slab and cold nose border~~d_{CN}~~. The subfigures A, B, C, D, E and F show the same organization as in figure 6. (G) shows the same organization as in figure 7. The limit between the cold nose and the weak zone at $d_{CN} = 84km$ depth, marked by a bright red vertical line, best fits the pattern observed in the vertical displacements and on the track A149.

component (Figure 8). The ascending InSAR track brings the strongest constraint on the optimal location of the cold nose limit ($d_{CN} = 84$ km). Note that a model without any cold nose does not produce vertical uplift, as already discussed by Luo and Wang (2021), and would thus not fit the data. Varying the landward limit of the low-viscosity zone will affect the amplitude and shape of the post-seismic relaxation in the intermediate and far-field, a shorter weak zone inducing smaller displacements (Figure B5). We find an optimal position of $x_{craton} = 300$ km, which makes the shallow section of the weak zone 90 km wide below the Altiplano before it starts to deepen.

~~Exploration of the craton border x_{craton}. The subfigures A, B, C, D, E and F show the same organization as in figure 6. (G) shows the same organization as in figure 7. A limit between the craton and the weak zone at $x_{craton} = 300km$ from the trench along the x-axis fits the best the pattern observed in the data.~~

5.3 Rheology

We ~~finally~~ investigate the influence of rheological parameters ~~,~~ in the weak zone, as well as in the ~~oceanic and continental mantles. The tests made with variable viscosity in the oceanic mantleshow its influence on the modeled displacements near the trench. They show that no significant visco-elastic relaxation in the oceanic mantle during the observation period is required~~

to fit the data. We select $\eta_{oc} = 10^{21}$Pa.s (i.e. quasi-elastic behaviour during the observation period, with a relaxation time of 450 years), lower viscosity values inducing a significant misfit to the coastal stations and near-field ascending InSAR track (Figure B6). continental mantle. The viscosity of the continental mantle influences controls the amplitude of the intermediate intermediate- and far-field displacements over the period P2 (Figure 9). We set $\eta_{cont} = 3 \times 10^{19}$, a value that captures Pa.s, which reproduces the amplitude of the both horizontal and vertical deformation in the intermediate-field, while also intermediate field while providing a reasonable fit to the far-field dataobservations.

The rheological properties in of the weak zone are tested investigated in Figures 10 to 13. First, we tested the rheological law that controls the propagation of the deformation in the medium . We tried the Maxwell and the test the influence of the rheological law controlling deformation propagation within the medium by comparing Maxwell and Burgers rheologies. The Burgers rheology is the combination of combines a Maxwell body and a Kelvin body. It allows for a transient relaxation at smaller characteristic times. In , allowing transient relaxation over shorter characteristic timescales. As shown in Figure 11, we see that the Maxwell rheology underestimates the displacements during the first year, there is a lack of displacements using the Maxwell rheology while the Burgers rheology fits the temporal evolution for whereas the Burgers rheology reproduces the GNSS time series both during the first year and in the longer term. Spatially, at short-time scales over longer timescales.

At short timescales, the spatial distribution of deformation (Figure 10A and B) , we see more effects due to the visco-elasticity. It highlights a stronger influence of visco-elastic relaxation. The Burgers rheology improves the fit on the vertical because the afterslip leads to too much to the vertical GNSS observations because afterslip alone produces excessive subsidence between 150 and 300 km , the from the trench. The additional uplift generated by visco-elastic relaxation produces uplift, then it compensates the afterslip and the data are well fitted using a Burgers rheology. compensates for this subsidence, resulting in a better agreement between the model and the observations.

The data fit is thus fit to the first period of GNSS observations is therefore significantly improved by considering introducing a Burgers rheology instead of a Maxwell rheology in the weak zone. The parameters of controlling this Burgers rheology have been investigated in Figure 12 (viscosity $\eta_{M_{wz}}$ are investigated in Figures 12 and 13: the viscosity of the Maxwell component in the Burgers rheology) , and Figure 13 (viscosity $\eta_{K_{wz}}$ ($\eta_{M_{wz}}$) is tested in Figure 12, while the viscosity of the Kelvin component of the Burgers rheology) . Varying ($\eta_{K_{wz}}$) is explored in Figure 13. Variations in the Maxwell viscosity will mostly mainly control the amplitude of the visco-elastic deformation pattern over the period P2 (long time scaletimescales). We find identify an optimal value of $\eta_{M_{wz}} = 2 \times 10^{19}$ $\eta_{M_{wz}} = 2 \times 10^{19}$ Pa.sthat , which provides the best fit to the vertical GNSS data and InSAR Ascending observations and the ascending InSAR track (Figure 12D and E). Changing the viscosity of the Kelvin element will

Changes in the Kelvin viscosity affect both periods (P1 and P2) , and mostly vary the and primarily modify the deformation amplitude (Figure 13). We select $\eta_{K_{wz}} = 2 \times 10^{18}$ $\eta_{K_{wz}} = 2 \times 10^{18}$ Pa.s, 10 times smaller which is ten times lower than the Maxwell viscositywhich is typical for . This ratio is consistent with values commonly used in visco-elastic simulations incorporated incorporating Burgers rheologies (Luo and Wang, 2021).

Exploration of the oceanic viscosity η_{oc}. The subfigures A, B, C, D, E and F show the same organization as in figure 6. (G) shows the same organization as in figure 7. An oceanic viscosity $\eta_{oc} = 1.10^{21} Pa.s$ best fits the pattern observed in the data.




Figure 9. Exploration of the continental viscosity η_{cont} in Pa.s. The subfigures A, B, C, D, E and F show the same organization as in figure 6. (G) shows the same organization as in figure 7. A continental viscosity of ~~$\eta_{cont} = 3.10^{19} Pa.s$~~ $\eta_{cont} = 3 * 10^{19} Pa.s$, marked by a bright red vertical line, best fits the pattern observed in the data.

6 Discussion

6.1 Limitations of the model and trade-off between parameters

Models are simplifications of natural processes. Our models involve important limitations. First, we exclude gravitational body forces in our viscoelastic simulations. Including gravity often prevents the system from reaching a stable initial state, as the model continues to relax under its own weight (Aagaard et al., 2017). To avoid this numerical instability and ensure consistency across all simulations, gravity is omitted. Second, we make a 2D simplification of a 3D process and we use a simplified structure below the Andes. This was done on purpose to meet the objective of the study : assess the geometry of the weak zone and its rheology over the decadal time scale by performing a parametric exploration. Like in any parametric model, it is necessary to limit the amount of variables to be explored, and a simplified geometry avoids having to explore too many trade-offs. A model meant to reproduce the full 3D displacement field would definitely require a 3D geometry. However previous studies have shown that to assess the trench perpendicular structure, such as the cold nose or the transition between the weak zone and the craton, a 2D assumption provides reasonable results, comparable to 3D simulations at the first order ~~(?Luo and Wang, 2022)~~ (Luo and Wang, 2021, 2022). The other important result from our study is the necessity of using a Burgers rheology in the weak zone to explain the temporal evolution of afterslip versus visco-elastic in near field versus far field. As this is mostly




Figure 10. Comparison between Maxwell and Burgers rheologies in the weak zone. The organization of the figure follow the one of the 6. Here the curves are color-coded the same way as in the figure 11. The red curve is the best model and the green curve represents a model with a Maxwell instead of a Burgers rheology in the weak zone.

constrained by the relative amplitude of the measured signal, using a 2D model should not introduce a strong bias. A 3D model would likely improve the fit to the far field deformation, that is anyway very poorly constrained with sparse and noisy GNSS observations.

Some trade-offs exist between model parameters. The parameters that are most affected by these trade-offs are the crustal thickness and the Maxwell viscosity of the weak zone. Variations in crustal thickness primarily modify the wavelength and amplitude of the elastic deformation signal, whereas changes in the Maxwell viscosity of the weak zone mainly affect the amplitude of the long-term deformation associated with viscous relaxation, particularly in the vertical component. Although a trade-off between these two parameters may exist, it remains limited because the elastic thickness has only a minor influence on the overall deformation pattern.

Other parameters have a significant impact on the model predictions but show no major trade-offs. The position of the cold nose boundary controls the location of the maximum uplift and is therefore a key geometrical parameter. The continental viscosity does not significantly affect the short-term deformation, but it controls the amplitude of the long-term viscoelastic response, especially in the far field. The Kelvin viscosity of the weak zone strongly influences both the short- and long-term deformation associated with transient viscoelastic relaxation. A limited trade-off exists between this parameter and the prescribed afterslip contribution; however, reproducing the observed short-term vertical deformation requires a significant contribution from transient Kelvin relaxation within the weak zone.




Figure 11. Temporal evolution of the post-seismic displacements at coastal stations (PSGA and ATJN), intermediate-field stations (FBAQ and PCHA) and far-field stations (COLC and BDJC). For each station, the top subplot shows the horizontal displacements and the bottom one, the vertical displacements. Grey dots with lines show the GNSS data with the associated uncertainties. The red curve shows the best model with a Burgers rheology in the weak zone. The green curve shows the model with a Maxwell rheology instead of a Burgers in the weak zone.




Figure 12. Exploration of the Maxwell viscosity $\eta_{M_{wz}}$ ~~in~~ of the weak zone in Pa.s. A lower viscosity induces more displacement. It impacts mainly the long-term period. The subfigures A, B, C, D, E and F show the same organization as in figure 6. (G) shows the same organization as in figure 7. A Maxwell viscosity for the weak zone of ~~$\eta_{M_{wz}} = 2.10^{19} Pa.s$~~ $\eta_{M_{wz}} = 2 * 10^{19} Pa.s$, marked by a bright red vertical line, best fits the pattern observed in the data.

Finally, some parameters have a comparatively minor influence on the model results and do not exhibit significant trade-offs. Sensitivity tests for these parameters are available in the electronic supplement. The craton boundary only slightly modifies the far-field deformation amplitude and is not a critical parameter for this model. Similarly, the oceanic viscosity has no significant effect on the short-term deformation but influences the amplitude of the long-term vertical deformation in the forearc region.

6.2 Influence of Rheological Discontinuities in the Vertical Displacement Field

Previous studies on the post-seismic deformation following the Iquique earthquake exhibit a significantly larger misfit in the vertical component compared to the horizontal component (Hoffmann et al., 2018; Hu et al., 2021). The vertical component presents higher uncertainties and is then generally less well reproduced for the benefit of the horizontal component. Therefore, vertical displacements are better defined when multi-year time windows are analyzed, as in this work. The visco-elastic relaxation has a strong influence on the vertical component (Li et al., 2017; Luo and Wang, 2021) and some of the parameters we have explored can only be assessed by looking at the vertical deformation (the decoupling depth d_{CN} ~~,~~ inferred by the position of the cold nose border, the oceanic viscosity η_{oc}, and the Maxwell viscosity of the weak zone $\eta_{M_{wz}}$). In particular, the inclusion of InSAR data in this study allows us to better constrain the vertical deformation, as InSAR data are highly sensitive




Figure 13. Exploration of the Kelvin viscosity $\eta_{K_{wz}}$ ~~in~~ of the weak zone in Pa.s. The subfigures A, B, C, D and E show the same organization as in figure 6. (G) shows the same organization as in figure 7. A Kelvin viscosity for the weak zone of ~~$\eta_{K_{wz}} = 2.10^{18} Pa.s$~~ $\eta_{K_{wz}} = 2 * 10^{18} Pa.s$, marked by a bright red vertical line, best fits the pattern observed in the data.

to the vertical component. The data used therefore enable us to better explore these processes. The evolution of the misfit on the horizontal and the vertical for a given parameter is often opposed. But it is possible to reconcile them. Notably, the addition of a cold nose together with a weak zone is necessary to reproduce the observed vertical displacement field. The addition of a Burgers rheology allows to predict a different pattern at short time scale and allows to fit the early uplift on the Altiplano (Figures 10 and 11).

6.3 Far-field Subsidence

The post-seismic deformation following large subduction earthquakes shows far-field subsidence and was already described for the M_w8.8 Maule earthquake (Li et al., 2017) or the M_w9.1 Tohoku Oki earthquake (Li et al., 2020). This pattern is of low amplitude and long spatial wavelength. In this study, it is not clear if a far-field subsidence is seen or not. The Bolivian far-field data are affected by high uncertainties due to the lack of data before the Iquique earthquake and several data gaps. Indeed, most GNSS stations in Bolivia start to register only ∼6 months after the earthquake, and only 2 or 3 years of data are available. We therefore have to extrapolate the post-seismic displacements using a model assuming a given interseismic velocity, that likely propagates uncertainties. Since the InSAR time series ~~is~~ are flattened on the GNSS displacements, any reference issue in the ~~GPS~~ GNSS will propagate in the InSAR flattening (a ramp correction that does not affect the pattern of deformation).

These large uncertainties in the eastern side of our data set, make it difficult to decipher between zero displacement and small subsidence. If a subsidence exists, its amplitude is very low. The amplitude of the far-field subsidence may be linked with the magnitude of the earthquake. As the magnitude of the Iquique earthquake is lower ($M_w 8.1$) than the Maule or Tohoku earthquakes, it may imply an amplitude of subsidence that is small and close to the limit of detection.

6.4 Structure of the Weak Zone

The final model obtained contains a weak zone below the Western ~~cordillera~~ Cordillera between 210 km and 300 km from the trench, which progressively deepens under the Altiplano. The extent of the weak zone corresponds to the high topography of the Andes and the associated crustal root that is particularly deep in this region. The boundary between the cold nose and the weak zone represents the depth of decoupling between the slab and the overriding plate. Above, the plates are decoupled, below plates are viscously coupled and the the slab drags the continental plate at depth. It creates a flow and this region is hot enough for partial melting. This is not the case above the decoupling depth where there is no flow and the region is then colder. The depth of decoupling has been studied by Wada et al. (2008) and Wada and Wang (2009). They found a depth of $\sim$ 80 km. Our preferred model shows a decoupling depth of 84 km which is close to the one found by Wada and Wang (2009). The heat flow from the thermo-mechanical model is not well constrained in northern Chile because of few measurements in that region. At depth, this weak zone extends from 25 km depth (corresponding to the thickness of the elastic Altiplano) down to 130 km depth. At greater depths, the visco-elastic continental mantle takes over. The weak zone is located downdip the volcanic arc (Western Cordillera). A weak viscosity in this area is expected due to increased temperature and hydration causing partial melting below the arc. This weak zone indeed corresponds to a hotter area following temperature models (Araya Vargas et al., 2021; Springer, 1999) from 210 km from the trench and diminishing progressively from 300 km. It is also confirmed by the presence of hydrated phases imaged by magneto-telluric data (Araya Vargas et al., 2019) and seismic tomography (Gao et al., 2021; Yuan et al., 2000). In our model, the border between the low-viscosity area and the craton is modeled by a slope. This is a way to represent the variation of the viscosity. As shown by the temperature models by Araya Vargas et al. (2021) and Springer (1999), the temperature slowly diminishes, implying that the viscosity may also slowly increase in the eastern part of the Altiplano. The two limits of the taper may therefore rather represent the viscosity gradient than an actual geometry.

6.5 Potential contribution of poroelasticity

Recent studies have suggested that pore-pressure diffusion following large earthquakes may play an important role in post-seismic deformation (Peña et al., 2025). In particular, poroelastic deformation has been shown to contribute significantly during the first 3–4 months after an earthquake. Because our geodetic observations span six years following the earthquake, the long-term deformation cannot be explained by poroelastic processes alone. Instead, viscoelastic relaxation is required to account for the observed long-term signal, which provides robust constraints on both the geometry and Maxwell viscosity of the weak zone.

Nevertheless, incorporating poroelastic deformation could provide an alternative explanation for part of the transient response that we currently attribute to a low transient viscosity in the first few months after the earthquake. Assessing this possibility,

however, is beyond the scope of the present study, as it would require jointly quantifying the respective contributions of poroelastic deformation and transient viscoelastic relaxation to the early post-seismic observations.

7 Conclusions

To fit the post-seismic surface displacements of the 2014 $M_w 8.1$ Iquique earthquake, we use a model that includes a weak zone beneath the Altiplano. In the corner of the continental mantle, elastic behavior of the cold nose is required to produce the uplift seen at the surface. Further east, the weak zone, extends from 210 km from the trench at a depth of 25 km and deepens at 300 km. This region behaves as a Burgers rheology with a Maxwell viscosity of ~~2.10^{19}~~ $2 * 10^{19}$ Pa.s and a transient Kelvin viscosity of ~~2.10^{18}~~ $2 * 10^{18}$ Pa.s. The exploration of the viscosities shows that the viscosity of the continental mantle is lower than that of the oceanic mantle, the latter being so high that it does not relax in the 8-year period considered.

InSAR data brings spatial continuity to the dataset. While GNSS data are available at some points only, InSAR continuously covers a region and brings consistency to the displacement pattern. It allows us to better define the pattern observed: what is the shape, the extent and the location of the post-seismic deformation, which is in direct link with the underlying structure. In addition, it provides useful constraints on the vertical component with lower uncertainties than the GNSS data. The InSAR tracks cover the Altiplano above the weak zone and all the uplift area, which allows to point the location of the maximum uplift and how it diminishes.

Our preferred model incorporates a cold nose, this near trench elastic area predicted by thermal models (Wada and Wang, 2009) governs the displacements observed above that region because it drives the mantle flow at the border with the weak zone. The transition from elastic to visco-elastic with a low viscosity creates an uplift above the boundary. Without this cold nose we would be unable to reproduce the observed uplift pattern with the model. The modeling performed here shows that surface displacements can only be matched with the presence of this rheological contrast, confirming the need for a cold nose derived from thermo-mechanical behaviour. The cold nose ends with the decoupling depth which allows the mantle below to flow and react visco-elastically.

We show that below the western part of the Altiplano, the viscosity should be low (~~$\eta_{M_{wz}} = 2.10^{19} Pa.s$~~ $\eta_{M_{wz}} = 2 * 10^{19} Pa.s$). This is required by the amplitude of the uplift pattern over this area. The location is well resolved thanks to the InSAR data. The location is in good agreement with the Andean structure. The western boundary correlates with the ~~western cordillera~~ Western Cordillera hosting the volcanic arc. This weak zone therefore correlates with the place of melting of the magma, which should be characterized by a lower viscosity due to partial melting.

Another key point demonstrated by this study is the need to use a Burgers rheology instead of a Maxwell rheology within the weak zone. Our data require the need for a transient viscosity to fit the vertical pattern observed at short time scales, i.e. during the months following the earthquake. During this period, we need a combination of afterslip on the fault plane and visco-elastic relaxation at short time scales to explain the pattern and amplitude of the vertical displacements. Also, we can see in the time series, but also by comparing the early and late periods on the sections, that by fitting the long-term displacements with a Maxwell rheology, there is a lack of amplitude due to the visco-elasticity in the early stage. The continental mantle is too

deep (below the weak zone) to affect the surface data or is further east where the data quality is lower. The viscosity required in the oceanic mantle is high enough that the characteristic time is higher than the time span of this study. That is why, the use of a Burgers rheology will not affect the results. The temporal evolution of the deformation therefore requires a Burgers rheology rather than a Maxwell rheology in the weak zone below the Altiplano.

Code and data availability. All time series used in this manuscript is available at https://doi.osug.fr/public/GNSS_products/GNSS.products.SouthAmerica_GIPSYX.daily.html. RINEX data from CSN network are available at http://gps.csn.uchile.cl RINEX data from Bolivia are available from UNAVCO at https://www.unavco.org/data/doi/10.7283/T5DJ5D0X RINEX data from RBMC are available at https://www.ibge.gov.br/en/geosciences/geodetic-positioning/geodetic-networks/19213-brazilian-network-for-continuous-monitoring-of-the-gnss-systems.html?=&t=downloads. The trajectory model software (ITSA) is available at https://gricad-gitlab.univ-grenoble-alpes.fr/isterre-cycle/itsa. SAR Sentinel-1 data are available at https://peps.cnes.fr/rocket/#/home or https://scihub.copernicus.eu/. Pylith software is available at https://geodynamics.org/resources/pylith.

Acknowledgements. This work was supported by funding from the European Research Council (ERC) CoG 865963 DEEP-trigger. Most computing was made on the CIMENT/GRICAD infrastructure (https://gricad.univ-grenoble-alpes.fr). TEXT

Author contributions. JC analysed the GNSS and InSAR time series, did the modelling and wrote the first draft of the manuscript, MR supervised the work and participated in the modelling, MPD did the InSAR processing and supervised the work, MM MM participated in the modelling, FH participated in the InSAR analysis, ATT and GJ processed the GNSS data, JCB acquired the GNSS data, AT participated in the discussion and structural interpretation, AS obtained the funding, conceptualized and supervised the work, participated in GNSS data acquisition and processing, all authors participated in the discussion and in the writing of the manuscript

Competing interests. The authors declare no competing interests.

References

Aagaard, B., Knepley, M., and Williams, C.: A domain decomposition approach to implementing fault slip in finite-element models of quasi-static and dynamic crustal deformation, Journal of Geophysical Research: Solid Earth, 118, 3059–3079, https://doi.org/10.1002/jgrb.50217, 2013.

Aagaard, B., Knepley, M., and Williams, C.: PyLith v2.2.2 [Computer software], Computational Infrastructure for Geodynamics, https://doi.org/10.5281/zenodo.438705, 2017.

Altamimi, Z., Rebischung, P., Métivier, L., and Collilieux, X.: ITRF2014: A new release of the International Terrestrial Reference Frame modeling nonlinear station motions, Journal of Geophysical Research: Solid Earth, 121, 6109–6131, https://doi.org/10.1002/2016JB013098, 2016.

Araya Vargas, J., Meqbel, N. M., Ritter, O., Brasse, H., Weckmann, U., Yáñez, G., and Godoy, B.: Fluid Distribution in the Central Andes Subduction Zone Imaged With Magnetotellurics, Journal of Geophysical Research: Solid Earth, 124, 4017–4034, https://doi.org/10.1029/2018JB016933, 2019.

Araya Vargas, J., Sanhueza, J., and Yáñez, G.: The Role of Temperature in the Along-Margin Distribution of Volcanism and Seismicity in Subduction Zones: Insights From 3-D Thermomechanical Modeling of the Central Andean Margin, Tectonics, 40, 1–20, https://doi.org/10.1029/2021TC006879, 2021.

Arcay, D., Tric, E., and Doin, M.-P.: Numerical simulations of subduction zones: Effect of slab dehydration on the mantle wedge dynamics, Physics of the Earth and Planetary Interiors, 149, 133–153, 2005.

Armijo, R., Lacassin, R., Coudurier-Curveur, A., and Carrizo, D.: Coupled tectonic evolution of Andean orogeny and global climate, Earth-Science Reviews, 143, 1–35, https://doi.org/10.1016/j.earscirev.2015.01.005, 2015.

Babeyko, A. Y., Sobolev, S. V., Trumbull, R. B., Oncken, O., and Lavier, L. L.: Numerical models of crustal scale convection and partial melting beneath the Altiplano-Puna plateau, Earth and Planetary Science Letters, 199, 373–388, https://doi.org/10.1016/S0012-821X(02)00597-6, 2002.

Béjar-Pizarro, M., Carrizo, D., Socquet, A., Armijo, R., Barrientos, S., Bondoux, F., Bonvalot, S., Campos, J., Comte, D., De Chabalier, J., et al.: Asperities and barriers on the seismogenic zone in North Chile: state-of-the-art after the 2007 M w 7.7 Tocopilla earthquake inferred by GPS and InSAR data, Geophysical Journal International, 183, 390–406, 2010.

Béjar-Pizarro, M., Socquet, A., Armijo, R., Carrizo, D., Genrich, J., and Simons, M.: Andean structural control on interseismic coupling in the North Chile subduction zone, Nature Geoscience, 6, 462–467, 2013.

Bertiger, W., Bar-Sever, Y., Dorsey, A., Haines, B., Harvey, N., Hemberger, D., Heflin, M., Lu, W., Miller, M., Moore, A. W., Murphy, D., Ries, P., Romans, L., Sibois, A., Sibthorpe, A., Szilagyi, B., Vallisneri, M., and Willis, P.: GipsyX/RTGx, a new tool set for space geodetic operations and research, Advances in Space Research, 66, 469–489, https://doi.org/10.1016/j.asr.2020.04.015, 2020.

Bevis, M. and Brown, A.: Trajectory models and reference frames for crustal motion geodesy, Journal of Geodesy, 88, 283–311, https://doi.org/10.1007/s00190-013-0685-5, 2014.

Boehm, J., Werl, B., and Schuh, H.: Troposphere mapping functions for GPS and very long baseline interferometry from European Centre for Medium-Range Weather Forecasts operational analysis data, Journal of Geophysical Research: Solid Earth, 111, 1–9, https://doi.org/10.1029/2005JB003629, 2006.

Boulze, H., Fleitout, L., Klein, E., and Vigny, C.: Post-seismic motion after 3 Chilean megathrust earthquakes: a clue for a linear asthenospheric viscosity, Geophysical Journal International, 231, 1471–1478, 2022.

Cifuentes, I. L.: The 1960 chilean earthquakes, Journal of Geophysical Research: Solid Earth, 94, 665–680, 1989.

Comte, D. and Pardo, M.: Reappraisal of great historical earthquakes in the northern Chile and southern Peru seismic gaps, Natural hazards, 4, 23–44, 1991.

Coreform Cubit: [Computer software]. Orem, UT: Coreform LLC., http://coreform.com, 2023.

Doin, M. P., Lasserre, C., Peltzer, G., Cavalié, O., and Doubre, C.: Corrections of stratified tropospheric delays in SAR interferometry: Validation with global atmospheric models, Journal of Applied Geophysics, 69, 35–50, https://doi.org/10.1016/j.jappgeo.2009.03.010, 2009.

Doin, M.-P., Lodge, F., Guillaso, S., Jolivet, R., Lasserre, C., Ducret, G., Grandin, R., Pathier, E., and Pinel, V.: Presentation of the small baseline NSBAS processing chain on a case example: the Etna deformation monitoring from 2003 to 2010 using Envisat data, Proceedings of the ESA 'Fringe 2011 Workshop', Frascati, Italy, (19-23 September 2011), 2011, 19–23, http://www.geologie.ens.fr/~grandin/upload/Doin_2012_NSBAS.pdf%5Cnhttp://www.gps.caltech.edu/~jolivetr/jolivetr/Publications_files/Proceedings_of_the_Fringe_symposium_2011_Doin.pdf, 2011.

Duputel, Z., Jiang, J., Jolivet, R., Simons, M., Rivera, L., Ampuero, J.-P., Riel, B., Owen, S. E., Moore, A. W., Samsonov, S. V., Ortega Culaciati, F., and Minson, S. E.: The Iquique earthquake sequence of April 2014: Bayesian modeling accounting for prediction uncertainty, Geophysical Research Letters, 42, 7949–7957, https://doi.org/10.1002/2015GL065402, 2015.

Foster, James, Bevis, and Michael: Pisagua Megathrust Bolivia RAPID Response GPS Network, The GAGE Facility operated by EarthScope Consortium, GPS/GNSS Observations (Aggregation of Multiple Datasets), https://doi.org/10.7283/T5DJ5D0X, 2014.

Gao, Y., Tilmann, F., van Herwaarden, D. P., Thrastarson, S., Fichtner, A., Heit, B., Yuan, X., and Schurr, B.: Full Waveform Inversion Beneath the Central Andes: Insight Into the Dehydration of the Nazca Slab and Delamination of the Back-Arc Lithosphere, Journal of Geophysical Research: Solid Earth, 126, https://doi.org/10.1029/2021JB021984, 2021.

Giambiagi, L., Tassara, A., Echaurren, A., Julve, J., Quiroga, R., Barrionuevo, M., Liu, S., Echeverría, I., Mardónez, D., Suriano, J., Mescua, J., Lossada, A. C., Spagnotto, S., Bertoa, M., and Lothari, L.: Crustal anatomy and evolution of a subduction-related orogenic system: Insights from the Southern Central Andes (22-35°S), Earth-Science Reviews, 232, https://doi.org/10.1016/j.earscirev.2022.104138, 2022.

Grandin, R.: Interferometric Processing of SLC Sentinel-1 TOPS Data, 2017.

Hayes, G. P., Moore, G. L., Portner, D. E., Hearne, M., Flamme, H., Furtney, M., and Smoczyk, G. M.: Zone Geometry Model, Science, 362, 58–61, 2018.

Heidarzadeh, M., Murotani, S., Satake, K., Ishibe, T., and Gusman, A. R.: Source model of the 16 September 2015 Illapel, Chile, Mw 8.4 earthquake based on teleseismic and tsunami data, Geophysical Research Letters, 43, 643–650, https://doi.org/10.1002/2015GL067297, 2016.

Ho Tong Minh, D., Hanssen, R., Doin, M., and Pathier, E.: Advanced Methods for Timex2010;series InSAR, pp. 125–153, https://doi.org/10.1002/9781119986843.ch5, 2022.

Hoffmann, F., Metzger, S., Moreno, M., Deng, Z., Sippl, C., Ortega-Culaciati, F., and Oncken, O.: Characterizing Afterslip and Ground Displacement Rate Increase Following the 2014 Iquique-Pisagua Mw 8.1 Earthquake, Northern Chile, Journal of Geophysical Research: Solid Earth, 123, 4171–4192, https://doi.org/10.1002/2017JB014970, 2018.

Hormazábal, J., Moreno, M., Ortega-Culaciati, F., Báez, J. C., Peña, C., Sippl, C., González-Vidal, D., Ruiz, J., Metzger, S., and Yoshioka, S.: Fast relocking and afterslip-seismicity evolution following the 2015 Mw 8.3 Illapel earthquake in Chile, Scientific Reports, 13, 19 511, 2023.

Hu, Y., Wang, K., He, J., Klotz, J., and Khazaradze, G.: Three-dimensional viscoelastic finite element model for postseismic deformation of the great 1960 Chile earthquake, Journal of Geophysical Research: Solid Earth, 109, 2004.

Hu, Y., Bürgmann, R., Uchida, N., Banerjee, P., and Freymueller, J. T.: Stress-driven relaxation of heterogeneous upper mantle and time-dependent afterslip following the 2011 Tohoku earthquake, Journal of Geophysical Research: Solid Earth, 121, 385–411, 2016.

Hu, Z., Hu, Y., and Bodunde, S. S.: Viscoelastic relaxation of the upper mantle and afterslip following the 2014 MW8.1 Iquique earthquake, Earthquake Research Advances, 1, 100 002, https://doi.org/10.1016/J.EQREA.2021.100002, 2021.

Itoh, Y., Nishimura, T., Wang, K., and He, J.: New megathrust locking model for the southern kurile subduction zone incorporating viscoelastic relaxation and non-uniform compliance of upper plate, Journal of Geophysical Research: Solid Earth, 126, e2020JB019 981, 2021.

Itoh, Y., Socquet, A., and Radiguet, M.: Largest aftershock nucleation driven by afterslip during the 2014 Iquique sequence, Geophysical Research Letters, 50, e2023GL104 852, 2023.

Jara, J., Socquet, A., Marsan, D., and Bouchon, M.: Long-Term Interactions Between Intermediate Depth and Shallow Seismicity in North Chile Subduction Zone, Geophysical Research Letters, 44, 9283–9292, https://doi.org/10.1002/2017GL075029, 2017.

Jara, J., Sánchez-Reyes, H., Socquet, A., Cotton, F., Virieux, J., Maksymowicz, A., Díaz-Mojica, J., Walpersdorf, A., Ruiz, J., Cotte, N., and Norabuena, E.: Kinematic study of Iquique 2014 Mw 8.1 earthquake: Understanding the segmentation of the seismogenic zone, Earth and Planetary Science Letters, 503, 131–143, https://doi.org/10.1016/j.epsl.2018.09.025, 2018.

Jolivet, R., Grandin, R., Lasserre, C., Doin, M. P., and Peltzer, G.: Systematic InSAR tropospheric phase delay corrections from global meteorological reanalysis data, Geophysical Research Letters, 38, 1–6, https://doi.org/10.1029/2011GL048757, 2011.

Jolivet, R., Simons, M., Duputel, Z., Olive, J. A., Bhat, H. S., and Bletery, Q.: Interseismic Loading of Subduction Megathrust Drives Long-Term Uplift in Northern Chile, Geophysical Research Letters, 47, 1–11, https://doi.org/10.1029/≠, 2020.

Kanamori, H.: The Energy Release in Great Earthquakes, Journal of Geophysical Research, 82, 1977.

Kendrick, E., Bevis, M., Smalley, R., Brooks, B., Vargas, R. B., Lauría, E., and Fortes, L. P. S.: The Nazca–South America Euler vector and its rate of change, Journal of South American Earth Sciences, 16, 125–131, https://doi.org/10.1016/S0895-9811(03)00028-2, 2003.

Klein, E., Fleitout, L., Vigny, C., and Garaud, J. D.: Afterslip and viscoelastic relaxation model inferred from the large-scale post-seismic deformation following the 2010 Mw 8.8 Maule earthquake (Chile), Geophysical Journal International, 205, 1455–1472, https://doi.org/10.1093/gji/ggw086, 2016.

Lemrabet, L., Doin, M. P., Lasserre, C., and Durand, P.: Referencing of Continental-Scale InSAR-Derived Velocity Fields: Case Study of the Eastern Tibetan Plateau, Journal of Geophysical Research: Solid Earth, 128, 1–28, https://doi.org/10.1029/2022JB026251, 2023.

Li, S., Moreno, M., Bedford, J., Rosenau, M., Heidbach, O., Melnick, D., and Oncken, O.: Postseismic uplift of the Andes following the 2010 Maule earthquake: Implications for mantle rheology, Geophysical Research Letters, 44, 1768–1776, https://doi.org/10.1002/2016GL071995, 2017.

Li, S., Bedford, J., Moreno, M., Barnhart, W. D., Rosenau, M., and Oncken, O.: Spatiotemporal Variation of Mantle Viscosity and the Presence of Cratonic Mantle Inferred From 8 Years of Postseismic Deformation Following the 2010 Maule, Chile, Earthquake, Geochemistry, Geophysics, Geosystems, 19, 3272–3285, https://doi.org/10.1029/2018GC007645, 2018.

Li, S., Fukuda, J., and Oncken, O.: Geodetic Evidence of Time-Dependent Viscoelastic Interseismic Deformation Driven by Megathrust Locking in the Southwest Japan Subduction Zone, Geophysical Research Letters, 47, 1–10, https://doi.org/10.1029/2019GL085551, 2020.

Lin, Y. N. N., Sladen, A., Ortega-Culaciati, F., Simons, M., Avouac, J. P., Fielding, E. J., Brooks, B. A., Bevis, M., Genrich, J., Rietbrock, A., Vigny, C., Smalley, R., and Socquet, A.: Coseismic and postseismic slip associated with the 2010 Maule Earthquake, Chile: Characterizing

the Arauco Peninsula barrier effect, Journal of Geophysical Research: Solid Earth, 118, 3142–3159, https://doi.org/10.1002/jgrb.50207, 2013.

López-Quiroz, P., Doin, M. P., Tupin, F., Briole, P., and Nicolas, J. M.: Time series analysis of Mexico City subsidence constrained by radar interferometry, Journal of Applied Geophysics, 69, 1–15, https://doi.org/10.1016/j.jappgeo.2009.02.006, 2009.

Lovery, B., Chlieh, M., Norabuena, E., Villegas-Lanza, J., Radiguet, M., Cotte, N., Tsapong-Tsague, A., Quiroz, W., Sierra Farfán, C., Simons, M., et al.: Heterogeneous locking and earthquake potential on the South Peru megathrust from dense GNSS network, Journal of Geophysical Research: Solid Earth, 129, e2023JB027 114, 2024.

Luo, H. and Wang, K.: Postseismic geodetic signature of cold forearc mantle in subduction zones, Nature Geoscience, 14, 104–109, https://doi.org/10.1038/s41561-020-00679-9, 2021.

Luo, H. and Wang, K.: Finding simplicity in the complexity of postseismic coastal uplift and subsidence following great subduction earthquakes, Journal of Geophysical Research: Solid Earth, 127, e2022JB024 471, 2022.

Lyard, F. H., Allain, D. J., Cancet, M., Carrère, L., and Picot, N.: FES2014 global ocean tide atlas: Design and performance, Ocean Science, 17, 615–649, https://doi.org/10.5194/os-17-615-2021, 2021.

Marconato, L., Doin, M. P., Audin, L., and Pathier, E.: Ionospheric compensation in L-band InSAR time-series: Performance evaluation for slow deformation contexts in equatorial regions, Science of Remote Sensing, 9, https://doi.org/10.1016/j.srs.2023.100113, 2024.

Marill, L., Marsan, D., Socquet, A., Radiguet, M., Cotte, N., and Rousset, B.: Fourteen-Year Acceleration Along the Japan Trench, Journal of Geophysical Research: Solid Earth, 126, https://doi.org/10.1029/2020JB021226, 2021.

Métois, M., Socquet, A., Vigny, C., Carrizo, D., Peyrat, S., Delorme, A., Maureira, E., Valderas-Bermejo, M.-C., and Ortega, I.: Revisiting the North Chile seismic gap segmentation using GPS-derived interseismic coupling, Geophysical Journal International, 194, 1283–1294, 2013.

Métois, M., Vigny, C., and Socquet, A.: Interseismic Coupling, Megathrust Earthquakes and Seismic Swarms Along the Chilean Subduction Zone (38°–18°S), Pure and Applied Geophysics, 173, 1431–1449, https://doi.org/10.1007/s00024-016-1280-5, 2016.

Molina, D., Tassara, A., Abarca, R., Melnick, D., and Madella, A.: Frictional Segmentation of the Chilean Megathrust From a Multivariate Analysis of Geophysical, Geological, and Geodetic Data, Journal of Geophysical Research: Solid Earth, 126, https://doi.org/10.1029/2020JB020647, 2021.

Moreno, M., Rosenau, M., and Oncken, O.: 2010 Maule earthquake slip correlates with pre-seismic locking of Andean subduction zone, Nature, 467, 198–202, https://doi.org/10.1038/nature09349, 2010.

Moreno, M., Melnick, D., Rosenau, M., Bolte, J., Klotz, J., Echtler, H., Baez, J., Bataille, K., Chen, J., Bevis, M., Hase, H., and Oncken, O.: Heterogeneous plate locking in the South-Central Chile subduction zone: Building up the next great earthquake, Earth and Planetary Science Letters, 305, 413–424, https://doi.org/10.1016/j.epsl.2011.03.025, 2011.

Muto, J., Moore, J., Barbot, S., Iinuma, T., Ohta, Y., and Iwamori, H.: Coupled afterslip and transient mantle flow after the 2011 Tohoku earthquake, Science Advances, 5, eaaw1164, 2019.

Panet, I., Pollitz, F., Mikhailov, V., Diament, M., Banerjee, P., and Grijalva, K.: Upper mantle rheology from GRACE and GPS postseismic deformation after the 2004 Sumatra-Andaman earthquake, Geochemistry, Geophysics, Geosystems, 11, 2010.

Peña, C., Heidbach, O., Metzger, S., Schurr, B., Moreno, M., Bedford, J., Oncken, O., and Faccenna, C.: Pore-pressure diffusion controls upper-plate aftershocks of the 2014 Iquique earthquake, Nature Communications, 16, 9474, 2025.

Peyrat, S., Campos, J., de Chabalier, J.-B., Perez, A., Bonvalot, S., Bouin, M.-P., Legrand, D., Nercessian, A., Charade, O., Patau, G., et al.: Tarapacá intermediate-depth earthquake (Mw 7.7, 2005, northern Chile): A slab-pull event with horizontal fault plane constrained from seismologic and geodetic observations, Geophysical Research Letters, 33, 2006.

Poli, P., Maksymowicz, A., and Ruiz, S.: The Mw 8.3 Illapel earthquake (Chile): Preseismic and postseismic activity associated with hydrated slab structures, Geology, 45, 247–250, 2017.

Pollitz, F., Banerjee, P., Grijalva, K., Nagarajan, B., and Bürgmann, R.: Effect of 3-D viscoelastic structure on post-seismic relaxation from the 2004 M= 9.2 Sumatra earthquake, Geophysical Journal International, 173, 189–204, 2008.

Pollitz, F. F., Bürgmann, R., and Banerjee, P.: Post-seismic relaxation following the great 2004 Sumatra-Andaman earthquake on a compressible self-gravitating Earth, Geophysical Journal International, 167, 397–420, 2006.

Pons, M., Sobolev, S. V., Liu, S., and Neuharth, D.: Hindered Trench Migration Due To Slab Steepening Controls the Formation of the Central Andes, Journal of Geophysical Research: Solid Earth, 127, 1–21, https://doi.org/10.1029/2022JB025229, 2022.

Rosen, P. A., Hensley, S., Peltzer, G., and Simons, M.: Updated repeat orbit interferometry package released, Eos, 85, 47, https://doi.org/10.1029/2004EO050004, 2004.

Rousset, B., Barbot, S., Avouac, J.-P., and Hsu, Y.-J.: Postseismic deformation following the 1999 Chi-Chi earthquake, Taiwan: Implication for lower-crust rheology, Journal of Geophysical Research: Solid Earth, 117, 2012.

Ruiz, S., Metois, M., Fuenzalida, A., Ruiz, J., Leyton, F., Grandin, R., Vigny, C., Madariaga, R., and Campos, J.: Intense foreshocks and a slow slip event preceded the 2014 Iquique Mw8.1 earthquake, Science, pp. 1165–1169, https://doi.org/10.1126/science.1256074, 2014.

Ruiz, S., Moreno, M., Melnick, D., Del Campo, F., Poli, P., Báez, J. C., Leyton, F., and Madariaga, R.: Reawakening of large earthquakes in south central Chile: The 2016 Mw 7.6 Chiloé event, Geophysical Research Letters, 44, 6633–6640, 2017.

Schurr, B., Asch, G., Hainzl, S., Bedford, J., Hoechner, A., Palo, M., Wang, R., Moreno, M., Bartsch, M., Zhang, Y., Oncken, O., Tilmann, F., Dahm, T., Victor, P., Barrientos, S., and Vilotte, J. P.: Gradual unlocking of plate boundary controlled initiation of the 2014 Iquique earthquake, Nature, 512, 299–302, https://doi.org/10.1038/nature13681, 2014.

Shrivastava, M. N., González, G., Moreno, M., Chlieh, M., Salazar, P., Reddy, C., Báez, J. C., Yáñez, G., González, J., and de La Llera, J. C.: Coseismic slip and afterslip of the 2015 Mw 8.3 Illapel (Chile) earthquake determined from continuous GPS data, Geophysical Research Letters, 43, 10–710, 2016.

Shrivastava, M. N., González, G., Moreno, M., Soto, H., Schurr, B., Salazar, P., and Báez, J. C.: Earthquake segmentation in northern Chile correlates with curved plate geometry, Scientific reports, 9, 4403, 2019.

Sobolev, S. V. and Babeyko, A. Y.: What drives orogeny in the Andes?, Geology, 33, 617–620, https://doi.org/10.1130/G21557.1, 2005.

Socquet, A., Valdes, J. P., Jara, J., Cotton, F., Walpersdorf, A., Cotte, N., Specht, S., Ortega-Culaciati, F., Carrizo, D., and Norabuena, E.: An 8 month slow slip event triggers progressive nucleation of the 2014 Chile megathrust, Geophysical Research Letters, 44, 4046–4053, https://doi.org/10.1002/2017GL073023, 2017.

Socquet, A., Tsapong-Tsague, A., Lovery, B., Janex, G., and Radiguet, M.: Metadata and GNSS daily position solutions for permanent GNSS stations in South America., https://doi.org/10.17178/GNSS.products.SouthAmerica_GIPSYX.daily, 2023.

Springer, M.: Interpretation of heat-flow density in the Central Andes, Tectonophysics, 306, 377–395, https://doi.org/10.1016/S0040-1951(99)00067-0, 1999.

Suito, H.: Importance of rheological heterogeneity for interpreting viscoelastic relaxation caused by the 2011 Tohoku-Oki earthquake, Earth, Planets and Space, 69, 1–12, 2017.

Suito, H. and Freymueller, J. T.: A viscoelastic and afterslip postseismic deformation model for the 1964 Alaska earthquake, Journal of Geophysical Research: Solid Earth, 114, 2009.

Sun, T., Wang, K., Iinuma, T., Hino, R., He, J., Fujimoto, H., Kido, M., Osada, Y., Miura, S., Ohta, Y., et al.: Prevalence of viscoelastic relaxation after the 2011 Tohoku-oki earthquake, Nature, 514, 84–87, 2014.

Tassara, A. and Echaurren, A.: Anatomy of the Andean subduction zone: Three-dimensional density model upgraded and compared against global-scale models, Geophysical Journal International, 189, 161–168, https://doi.org/10.1111/j.1365-246X.2012.05397.x, 2012.

Tassara, A., Götze, H. J., Schmidt, S., and Hackney, R.: Three-dimensional density model of the Nazca plate and the Andean continental margin, Journal of Geophysical Research: Solid Earth, 111, 1–26, https://doi.org/10.1029/2005JB003976, 2006.

Thollard, F., Clesse, D., Doin, M.-p., Donadieu, J., Durand, P., Grandin, R., Lasserre, C., Laurent, C., Deschamps-ostanciaux, E., Pathier, E., Thollard, F., Clesse, D., Doin, M.-p., Donadieu, J., Durand, P., Thollard, F., Clesse, D., Doin, M.-p., Donadieu, J., Durand, P., Grandin, R., Lasserre, C., Laurent, C., and Deschamps-ostanciaux, E.: FLATSIM : The ForM @ Ter LArge-Scale Multi-Temporal Sentinel-1 InterferoMetry Service To cite this version : HAL Id : hal-03397350 FLATSIM : the ForM @ Ter LArge-scale multi-Temporal Sentinel-1 InterferoMetry service, 2021.

Tilmann, F., Zhang, Y., Moreno, M., Saul, J., Eckelmann, F., Palo, M., Deng, Z., Babeyko, A., Chen, K., Baez, J. C., Schurr, B., Wang, R., and Dahm, T.: The 2015 Illapel earthquake, central Chile: A type case for a characteristic earthquake?, Geophysical Research Letters, 43, 574–583, https://doi.org/10.1002/2015GL066963, 2016.

Tissandier, R., Nocquet, J.-M., Klein, E., Vigny, C., Ojeda, J., and Ruiz, S.: Afterslip of the Mw 8.3 2015 Illapel Earthquake Imaged Through a Time-Dependent Inversion of Continuous and Survey GNSS Data, Journal of Geophysical Research: Solid Earth, 128, e2022JB024 778, 2023.

Tozer, B., Sandwell, D. T., Smith, W. H., Olson, C., Beale, J. R., and Wessel, P.: Global Bathymetry and Topography at 15 Arc Sec: SRTM15+, Earth and Space Science, 6, 1847–1864, https://doi.org/10.1029/2019EA000658, 2019.

Twardzik, C., Vergnolle, M., Sladen, A., and Tsang, L. L.: Very early identification of a bimodal frictional behavior during the post-seismic phase of the 2015 M w 8.3 Illapel, Chile, earthquake, Solid Earth, 12, 2523–2537, 2021.

Vigny, C. and Klein, E.: The 1877 megathrust earthquake of North Chile two times smaller than thought? A review of ancient articles, Journal of South American Earth Sciences, 117, https://doi.org/10.1016/j.jsames.2022.103878, 2022.

Wada, I. and Wang, K.: Common depth of slab-mantle decoupling: Reconciling diversity and uniformity of subduction zones, Geochemistry, Geophysics, Geosystems, 10, https://doi.org/10.1029/2009GC002570, 2009.

Wada, I., Wang, K., He, J., and Hyndman, R. D.: Weakening of the subduction interface and its effects on surface heat flow, slab dehydration, and mantle wedge serpentinization, Journal of Geophysical Research: Solid Earth, 113, 1–15, https://doi.org/10.1029/2007JB005190, 2008.

Wang, K.: Elastic and viscoelastic models of crustal deformation in subduction earthquake cycles, in: The seismogenic zone of subduction thrust faults, pp. 540–575, Columbia University Press, 2007.

Wang, K., Hu, Y., and He, J.: Deformation cycles of subduction earthquakes in a viscoelastic Earth, Nature, 484, 327–332, 2012.

Wang, M., Shen, Z. K., Wang, Y. Z., Bürgmann, R., Wang, F., Zhang, P. Z., Liao, H., Zhang, R., Wang, Q., Jiang, Z. S., Chen, W. T., Hao, M., Li, Y., Gu, T., Tao, W., Wang, K., and Xue, L.: Postseismic Deformation of the 2008 Wenchuan Earthquake Illuminates Lithospheric Rheological Structure and Dynamics of Eastern Tibet, Journal of Geophysical Research: Solid Earth, 126, 1–18, https://doi.org/10.1029/2021JB022399, 2021.

Yuan, X., Sobolev, S. V., Kind, R., Oncken, O., Bock, G., Asch, G., Schurr, B., Graeber, F., Rudloff, A., Hanka, W., Wylegalla, K., Tibi, R., Haberland, C., Rietbrock, A., Giese, P., Wigger, P., Röwer, P., Zandt, G., Beck, S., Wallace, T., Pardo, M., and Comte, D.: Subduction and collision processes in the Central Andes constrained by converted seismic phases, Nature, 408, 958–961, https://doi.org/10.1038/35050073, 2000.

Appendix A: Relaxation times and trajectory models

Figure A1 shows the relaxation time estimated at each station. Figures A2 to A26 show the trajectory model estimated for each station and its fit to the position time series. The stations are ordered by distance to the trench.

Eight stations have not enough data to constrain the interseismic and we use the interseismic from Jolivet et al. (2020) instead of the one inverted from the data. Ordered by distance to the trench, these stations are: PB11, BDEC, BWSZ, BLOV, BRDQ, AMDE, BDJC, RDEO.

Figure A27 shows an example of grid search exploration for estimating the amplitude and the relaxation time. Figure A28 shows the agreement between InSAR and GNSS.




Figure A1. Map of the studied area presented the location and the name of the GNSS stations. Triangles are color-coded by the relaxation time. The grey colour stands for stations which does not have enough early data to constrain the relaxation time.




Figure A2. Trajectory model for the station AEDA. The three subplots present the three component of the displacement against the time. The blue dots present the data and the red curve the trajectory model inverted for each component. Pink lines present the dates of antenna changes. Yellow lines co-seismic jumps for earthquakes without modeled post-seismic and the orange line present the date of the co-seismic jump of the Iquique earthquake for which the post-seismic relaxation is modeled.




Figure A3. Trajectory model for the station BN01.




Figure A4. Trajectory model for the station UAPE.




Figure A5. Trajectory model for the station ATJN.




Figure A6. Trajectory model for the station IQQE.




Figure A7. Trajectory model for the station PSGA.




Figure A8. Trajectory model for the station CGTC.




Figure A9. Trajectory model for the station HMBS.




Figure A10. Trajectory model for the station FBAQ.




Figure A11. Trajectory model for the station PB11.




Figure A12. Trajectory model for the station MNMI.




Figure A13. Trajectory model for the station PCHA.




Figure A14. Trajectory model for the station PICC.




Figure A15. Trajectory model for the station CHM2.




Figure A16. Trajectory model for the station PB08.




Figure A17. Trajectory model for the station COLC.




Figure A18. Trajectory model for the station BDEC.




Figure A19. Trajectory model for the station BWSZ.




Figure A20. Trajectory model for the station BLOV.




Figure A21. Trajectory model for the station BRDQ.




Figure A22. Trajectory model for the station AMDE.




Figure A23. Trajectory model for the station BDJC.




Figure A24. Trajectory model for the station URUS.




Figure A25. Trajectory model for the station RDEO.




Figure A26. Trajectory model for the station SCRZ.




Figure A27. Example of a grid search of the exploration of the accepted values for the amplitude and the relaxation time (Tau) for the East component of the station MNMI. (A) Grid search for the fit of the times series between the amplitude and the relaxation time. The color shows the misfit computed with the L2 norm with the time as a logarithmic scale. The red cross is the best model found. The green and blue ones represent respectively the models with the minimum and maximum amplitude inside $3 \times RMS_{best_model}$. The orange star corresponds to the simple model inverted with the time in a non-logarithmic scale. (B) Time series of the data represented with grey points and the different models which correspond to the ones described in the subfigure A.




Figure A28. Comparison of the post-seismic displacement amplitudes measured from GNSS and InSAR. GNSS displacements are projected in the Line Of Sight (LOS). The InSAR data are extracted from the displacement map. Points on the line x=y indicate that the amplitude measured from GNSS and InSAR are the same. Red and blue points are the LOS displacements of track A149 and D054, respectively.

Station	Relaxation time (days)
AEDA	14.5
BN01	23.0
UAPE	19.5
ATJN	13.0
IQQE	12.0
PSGA	19.0
CGTC	18.5
HMBS	same as CGTC
FBAQ	21.5
PB11	11.5
MNMI	25.8
PCHA	16.5
PICC	30.4
CHM2	14.5
PB08	23.0
COLC	21.5
BDEC, BWSZ, BLOV, BRDQ, AMDE, BDJC, URUS, RDEO, SCRZ	same as COLC

Table A1. Relaxation times for the selected stations

Appendix B: Further details on the modeling

B1 Python's code to transpose from Burgers formulation to generalized Maxwell

```
def Burgers4PyLith(shear_modulus_Kelvin,viscosity_Kelvin,shear_modulus_Maxwell,
viscosity_Maxwell):
    # calculate the four parameters p_1, p_2, q_1 and q_2
    p_1 = viscosity_Maxwell/shear_modulus_Maxwell
    + viscosity_Maxwell/shear_modulus_Kelvin + viscosity_Kelvin/shear_modulus_Kelvin
    p_2 = viscosity_Maxwell/shear_modulus_Maxwell
    * viscosity_Kelvin/shear_modulus_Kelvin
    q_1 = viscosity_Maxwell
    q_2 = viscosity_Maxwell*viscosity_Kelvin/shear_modulus_Kelvin
    # calculate the constant A
    A = np.sqrt(p_1**(2)-4*p_2)#
    # calculate hat_mu_1 and hat_mu_2
    hat_mu_1 = (q_1-q_2*(p_1-A)/(2*p_2))/A
    hat_mu_2 =(q_2*(p_1+A)/(2*p_2)-q_1)/A
    # calculate the relaxation times tau
    tau_1 = (2*p_2)/(p_1-A)
    tau_2 = (2*p_2)/(p_1+A)
    # calculate the total shear modulus
    total_shear_modulus = hat_mu_1+hat_mu_2
    # calculate the shear modulus
    mu_1 = hat_mu_1/total_shear_modulus
    mu_2 = hat_mu_2/total_shear_modulus
    # calculate the viscosities
    viscosity1 = hat_mu_1 * tau_1
    viscosity2 = hat_mu_2 * tau_2
    return(mu_1,viscosity1,mu_2,viscosity2,total_shear_modulus)
```

B2 Results of the afterslip exploration

Here, we discuss the location and amplitude of the afterslip patch in our 2D model.

In section 5.1, we showed that afterslip is predominant at short time scales (a few months), and we have set its temporal evolution (logarithmic decay with a time constant of 17 days) so that it reproduces the observed displacement at the coastal stations.

We vary the depth of the afterslip patch, which also changes its distance to the trench (Figure B2). Varying the depth mostly induces a horizontal offset of the model curve, the strongest constraint here being the fit to the vertical displacements at the coastal stations (Figure B2 B and D). Our optimal model is selected with an afterslip mean depth of 36 km (i.e. 90 km from the Trench).

The width of the afterslip pulse (Figure B3) as well as the maximum slip value (Figure B4) control the amplitude of the afterslip surface displacement. We perform a grid search over amplitude A_a and width A_w (see Figure B1)~~to assess the best fit to the coastal stations and find~~ . Best fitting parameters are $A_w = 24$ km and $A_a = 0.4$ m~~. These values predict the minimum horizontal misfit for all stations in Figures B3 and B4.~~ , more results are detailed in the Appendix B.

Our optimal afterslip model, presented in Figure 4B, gives a maximum slip at a depth $A_d = 36$ km, it is located below the co-seismic slip (which extends between 22 and 34 km depth). Some afterslip overlaps up-dip with the co-seismic slip, and it extends downdip down to 60 km depth.




Figure B1. Grid search between afterslip amplitude A_a (cm) and the afterslip width A_w (km) for the coastal stations where these parameters have the most influence. The preferred model parameters are highlighted by a red square.




Figure B2. Test of the afterslip ~~position~~ depth A_d in km. The subfigures A, B, C, D, E and F show the same organization as in Figure 6 in the main paper. (G) shows the same organization as in Figure 7 in the main paper. Here the value of the position of the afterslip along the interface is tested. From this figure, we can conclude that an afterslip centred around ~~90~~ 36 km ~~from the trench~~ depth, marked by a bright red vertical line, fits the best the pattern observed in the data.




Figure B3. Exploration of the afterslip width A_w in km. The subfigures A, B, C, D, E and F show the same organization as in Figure 6 in the main paper. (G) shows the same organization as in Figure 7 in the main paper. From this figure, we can conclude that an afterslip width $A_w = 24km$, marked by a bright red vertical line, best fits the pattern observed in the data.




Figure B4. Exploration of the afterslip amplitude A_a in cm. The subfigures A, B, C, D, E and F show the same organization as in Figure 6 in the main paper. (G) shows the same organization as in Figure 7 in the main paper. An afterslip amplitude $A_a = 40cm$ after 6 months best fits the pattern observed in the data.

B3 Results of the exploration of less impactful structural and rheological parameters

The craton border slightly modifies the amplitude in far field, and that is not critical in this model as shown by figure B5. The oceanic viscosity does not infer any change at short time scale, but changes the amplitude of the vertical in the forearc at long time-scale as shown in figure B6. Tests with variable oceanic mantle viscosities indicate that significant visco-elastic relaxation in the oceanic mantle is not required over the observation period to reproduce the data. We therefore select $\eta_{oc} = 10^{21}$ Pa.s, corresponding to a quasi-elastic behavior during the observation period (relaxation time of 450 years). Lower viscosity values induce significant misfits at the coastal stations and along the near-field ascending InSAR track (Figure B6).




Figure B5. Exploration of the craton border x_{craton}. The subfigures A, B, C, D, E and F show the same organization as in figure 6. (G) shows the same organization as in figure 7. A limit between the craton and the weak zone at $x_{craton} = 300km$ from the trench along the x-axis fits the best the pattern observed in the data.




Figure B6. Exploration of the oceanic viscosity η_{oc}. The subfigures A, B, C, D, E and F show the same organization as in figure 6. (G) shows the same organization as in figure 7. An oceanic viscosity $\eta_{oc} = 1 * 10^{21} Pa.s$ best fits the pattern observed in the data.